

WITH KENTUCKY SUPPLEMENT

ESSENTIALS *of* GEOGRAPHY

BRIGHAM AND MCFARLANE
SECOND BOOK





REVISED EDITION

AMERICAN BOOK COMPANY

Mark & Amos
66 Peach Tree Lane
Elmwood, Kentucky

10 years / 10 years / 10 years
years at Caywood 3




11/6

[Scribbled out text in blue ink]

25 West 1st St
Coalington, Calif.
Please

Kind Johnson
666 Peach Tree Lane
Elmanger Hwy.

grade 5
Miss Jasper room



Miss Loretta Meyer.
1219 Highway ave.
west Covington Ky.
Phone South 23282.

delininations

~~cabin~~

~~local~~

~~Miss Loretta Myers~~

~~1279 Highway Ave.~~

~~West Covington Ky.~~

~~Phone South 2328~~

baleful

Ruth Bolser.

The Richard &
Yust.

delininations




Fig. 1. Irrigation dam and canal in the dry western part of the United States. The Truckee-Carson storage dam, Nevada

ESSENTIALS *of* GEOGRAPHY SECOND BOOK

BY

ALBERT PERRY BRIGHAM, A.M., Sc.D., L.H.D.

PROFESSOR OF GEOLOGY, COLGATE UNIVERSITY
HAMILTON, N. Y.

AND

CHARLES T. McFARLANE, Ph.D.

PROFESSOR OF GEOGRAPHY, TEACHERS COLLEGE
COLUMBIA UNIVERSITY, NEW YORK



REVISED EDITION

AMERICAN BOOK COMPANY

NEW YORK

CINCINNATI

CHICAGO

BOSTON

ATLANTA

COPYRIGHT, 1916, 1920, BY
ALBERT PERRY BRIGHAM AND CHARLES T. MCFARLANE.

ALL RIGHTS RESERVED

ESSENTIALS OF GEOGRAPHY, SECOND BOOK.

E. P. 74

PREFACE

IN this series of texts it is recognized that the physical and the human are coördinate branches of geography.

Every important phase of physical geography is sufficiently covered, but care has been taken not to give it the emphasis which is suited only to the high school or the college.

In pursuance of emphasis on the human side of geography, the materials and modes of life, industry, and trade are given more than the usual proportion of attention. Moreover, industries and the growth of trade centers furnish out-door material for teaching in every locality; while routes of transportation and the contribution of the whole world to the needs of a single community can be so studied as to give the pupil inspiring ideas of the unity of the world and its people.

The derangement of industry caused by the recent war, great though it is, must be regarded as a temporary interruption of normal conditions. It is therefore thought best, in describing the industries of each country, to emphasize conditions as they are in normal times. The aim is to present matters of permanent importance rather than those of passing interest.

The map is the central feature in geographic instruction. Hence great care has been taken to reach excellence in the maps of this series. Essential features are shown, but minor features are omitted to avoid vagueness of impression. For this reason it is necessary to omit the smaller cities and towns of each state or region, although some of the omitted cities in densely populated states may be places of considerable size. The contour maps of the United States Geological Survey now cover wide areas and are of such general interest that they have been given special explanation.

In the text, the causal relation is central and vital, but emphasis is also placed upon the study of location, as in the map questions that precede leading divisions of this book, and in the reviews that follow. Location should also be pressed home in the study of industrial, commercial, and other phases.

The principles and forces with which physical geography deals are brought in at appropriate points of application in the regional

treatment. Thus rivers and valleys are studied in a passage that leads to the account of the drainage of North America; and volcanoes are explained in connection with the study of a well-known volcano, Vesuvius.

In the handling of all great topics, concentration and unity are sought, so that the reader will not have to depend on diffused and scattered notices. Wheat, for example, is described as fully as possible in the account of the region where it first appears in a large way, that is, the North Central States. In like manner iron is treated with Pittsburgh, and irrigation with the Plateau States.

Because of the difficulty of the subject, a progressive treatment has been adopted in the study of the atmosphere, and the student is led by simple steps to a knowledge of the main facts. Under North America, climate is studied as to range of temperature, the westerly winds, and the northeast trades. Under the United States the subject is expanded by a study of rainfall and by an explanation of cyclonic movements and storms. The theme is further advanced under the several state groups. The southeast trades and the westerly winds of the Southern Hemisphere are taken up under South America. Following the treatment of the ocean, the various facts about winds are brought together and amplified, and a view of world winds is presented.

The earth as a whole and its astronomical relations are treated in a simple manner in the First Book of the series, and the fuller study is then postponed to the end of the Second Book, when the pupil is best prepared to understand the facts presented.

The authors gratefully acknowledge the helpful suggestions of many expert teachers of geography. For assistance in illustration, they are greatly indebted to several departments of the United States Government, to many American Consuls in foreign countries, to a large number of industrial establishments, to boards of trade both at home and abroad, and to the personal kindness of many geographers in America and Europe.

ALBERT PERRY BRIGHAM
CHARLES T. MCFARLANE

TABLE OF CONTENTS

	PAGE		PAGE
MAIN IDEAS IN GEOGRAPHY		OUTLYING POSSESSIONS OF THE UNITED STATES	
The Earth Shapes Man's Ways of Living	I	Alaska	185
Man is a Trader	4	Porto Rico	192
Man Changes the Earth	5	Panama Canal Zone	190
What Geography Is	5	Hawaiian Islands	193
NORTH AMERICA		The Philippine Islands, Guam, and Samoa	195
The Land	7	NORTHERN COUNTRIES OF NORTH AMERICA	
Rivers and Valleys	11	The Dominion of Canada	199
Climate of North America	16	Newfoundland, Greenland	209
Glaciers	19	SOUTHERN COUNTRIES OF NORTH AMERICA	
Discovery and Settlement	21	Mexico	211
Political Divisions	24	Central America	215
THE UNITED STATES		The West Indies	216
Ways of Showing the Forms of the Land	28	SOUTH AMERICA	
Surface Features	31	Physical Features	219
Climate of the United States	41	Plants and Animals	223
Growth of the United States	46	People and Industries	225
THE NEW ENGLAND STATES		Coffee and Rubber	227
Land and People	53	Brazil	231
Agriculture and Manufacture	59	Countries of the Plata Basin	233
Other Industries	64	Countries of the Andes	235
Cities and Routes of Trade	69	Countries of the North Coast	238
THE MIDDLE ATLANTIC STATES		Islands	239
Physical Features	71	OCEANS, POLAR REGIONS, AND WORLD WINDS	
Soils	77	The Ocean	242
Climate and Agriculture	78	Waves, Currents, and Tides	244
Valuable Minerals	81	Uses of the Ocean	249
Principal Cities and Industries	85	World Winds	255
Resorts	96	The Polar Regions	251
THE SOUTH ATLANTIC STATES		Causes of Winds	258
Physical Features	99	EUROPE	
Mineral Wealth and Forests	103	Physical Features	261
Agriculture and Other Industries	104	History and People	268
Cities and Routes of Trade	109	Occupations and Industries	271
The National Capital	111	British Isles	275
THE SOUTH CENTRAL STATES		Germany	287
Physical Features	116	Belgium	292
Agriculture	120	The Netherlands	293
Lumber and Mineral Wealth	124	Denmark	295
Cities and Routes of Trade	126	Norway	296
THE NORTH CENTRAL STATES		Sweden	297
Physical Features	132	Poland	298
Wheat, Corn, and Other Crops	136	Baltic States	299
Stock Raising and Meat Packing	140	ASIA	
Mining and Lumbering	143	Physical Geography	335
Cities	146	Plants and Animals	339
Transportation	151	People and Industries	340
THE PLATEAU STATES		Southwestern Asia	345
Description of the Region	155	India	351
Grazing	163	Southeastern Asia	354
Irrigation and Crops	164	China	357
Mining	168	Empire of Japan	363
Routes and Cities	171	Asiatic Russia	366
THE PACIFIC STATES		AFRICA	
Description of the Region	173	Physical Geography	369
Industries	178	People and History	374
Manufacturing and Commerce	182	Countries of Africa	377
		AUSTRALIA AND PACIFIC ISLANDS	
		The Earth as a Whole	392
		APPENDIX	
		Review of Important Products	403
		Books for Reference Reading	411
		Tables of Area, Population, etc.	412
		Index and Pronunciations	419

MAIN IDEAS IN GEOGRAPHY

THE EARTH SHAPES MAN'S WAYS OF LIVING

1. Life in the Far North.—On the distant Arctic shores of North America live a few scattered tribes of Eskimos. There are no forests or fields to give them nuts, grain, vegetables, or cultivated fruits. They get most of their food from the flesh of the seal, walrus, sea birds, and fish, and therefore must live near the sea. Their clothing is made of furs and skins, because these are the only materials at hand and because such clothing is warm. In their search for food they use canoes and sleds made of bone and skin, and many of their tools are made of bone. In the short summer they live in tents of skin, and in the winter their permanent homes, if they have any, are made of stones, sod, and earth, partly underground; but they often camp in huts quickly built out of blocks of snow (Fig. 2). The blubber of the seal gives them not only food, but also light and heat. Their manner of life is very different from that of many Eskimos who live farther south.

2. In Tropical Forests.—The lands near the Equator are hot, except on high moun-

tains, and usually have heavy rains. In such regions trees and other plants grow very rapidly. Hence there are dense forests, with a rank undergrowth. With little labor the savage in these hot lands may live upon bananas, breadfruit, sago, or coconuts. He needs but little clothing, and such as he has is made of grasses, bark of trees, and fibers of other plants. Of poles and grasses he builds such shelter as he needs to protect himself from the burning sun and beating rains (Fig. 3).

For the Eskimos life is hard, for the savages in the tropics it is easy; but in each case the life of the people is shaped by the physical condition of the country in which they live.

3. On Dry Plains.
—In Asia, from Manchuria in the east to Arabia in the south-

west, are found dry grasslands, or *steppes*, which support the flocks and herds of many wandering tribes. Horses, cattle, and sheep form the wealth of these people, and the milk and flesh, wool and skins, supply food, clothing, and shelter. The animals are pastured on the open steppe, near springs where they can be watered. When the flocks and herds have eaten the grass of one place, they are driven to other springs and to fresh pastures.



Fig. 2. Snow hut built by Eskimos



Fig. 3. Hut of tropical savages




Fig. 4. Iron furnaces near Pittsburgh

The people gain skill and courage in their wanderings, and have no desire to live in one place and till the soil. The men who tend the great herds and flocks on the grassy plains of Argentina and Australia live with their herds much as do these wandering tribes of central and western Asia.

4. Life in a New Country.—The influence of the earth upon the way men live is shown also among pioneers in new countries, and even among the older civilized peoples. The pioneers of our own country lived almost as simply as the red men among whom they came. Like the savages, they fished and hunted, and sometimes wore garments of skin; but they cut down trees and built log huts for their houses and barns, cleared the fields as fast as they could, and cultivated more corn, fruits, and vegetables than the Indian ever thought of growing. The farmer was his own blacksmith and tool maker. The housewife and her daughters spun and wove the wool and flax and made the garments for the family. With tallow candles for light, wood for fuel, and food grown on the clearing, each family supplied its own needs.

Like the wanderer of the grasslands, the pioneer used the things that were about him.

5. In a Region of Coal and Iron.—If you were to visit the neighborhood of Pittsburgh,

you would find iron furnaces (Fig. 4) and coal mines, coal barges on the river, trainloads of coke and iron ore, and piles of steel rails and girders, and you would hear the noise of industry everywhere. Men by tens of thousands work in the mines and furnaces, man the railroad trains and river boats, and tend the smoking coke ovens.

Other thousands keep shops to supply food and clothing for the workers, and care for the schools, churches, and hospitals, while smaller numbers practice law and medicine, conduct banks and boards of trade, and attend to the government of the great city. The lives of all these people depend more upon the making of iron than upon any other work.



Fig. 5. Making steel, near Pittsburgh

Because there is much coal in the hills, water in the rivers, and good transportation for iron ore and for the finished products of iron, the people of Pittsburgh live mainly by the iron industry. The land, the water, and the minerals influence them, as the Arctic climate influences the Eskimos, and as the steppe shapes the habits of the wandering herdsmen.

6. Influence of Mountains, Seas, and Plains.

The Swiss mountaineer dwells in a narrow valley between high mountains, and usually lives in a small village by a stream. He builds his house with overhanging roof (Fig. 6), out of wood from the forests on the mountain side. He has a little land by the stream for garden and grain, but cuts his hay and pastures his cattle on the slopes as far up among the rocks as grass will grow. He makes butter and cheese for home use and for sale, and may spend the winter evenings in carving wooden trinkets to sell to the summer traveler.

Norway is a mountainous country with a long seacoast. Like the Swiss, the Norwegian pastures his cows on the high slopes and brings down hay for winter use; but much of the year he is out in the fishing fleet (Fig. 7), or as a sailor he goes over all seas to the ports of every nation, helping to carry the world's goods.

On the prairies of our own country there is neither mountain nor sea, but a wide stretch of fertile soil. Here man tills the fields, raises crops of corn and oats, fattens stock, and sells grain, cattle, and hogs to pay for the things



Fig. 6. Swiss farmhouse

he needs. Like the Swiss, the Norwegian, and other people, the prairie farmer is under the influence of the land in which he lives.

7. How the Earth Influences Man; Summary.—In the far north there is little heat and much ice and snow. On the steppes there is moisture enough for grass, but not enough for forests or grain. In most tropical regions there is much heat and much rain. Such differences in the amount of *heat* and of *moisture* determine, to a very large extent, the way in which men live.

Among high mountains much land is waste and much is good only for pasture. On the prairie there is little waste land, and many modern machines can be used in the fields. Hence the *forms of the land* help to shape the life of man.

Life on the prairies, or in the Swiss mountains, is very different from life on the sea border in Norway. In many countries the *presence or absence of the sea* is important.

In Pittsburgh and similar regions the *minerals* and the *facilities for transportation* by roads and rivers control the destiny of the people.

Everywhere the earth influences man.




Fig. 7. Fishing boats in a harbor, Norway

MAN IS A TRADER

8. Commerce.—Influenced thus in different ways, men become different from one another. In the ground and in the rocks they find various things, and out of minerals, plants, and animals they make different things. The Eskimo of the farthest north has little to sell and cannot buy much, but he would give a valuable skin for a piece of wood or a bright trinket. The savage in tropical forests may collect rubber or the material for useful drugs which he himself cannot use. The Swiss makes more cheese than he can use, or he makes toys or embroidery or silks or watches for the markets of the world. The Norwegian sells fish and buys flour from over the sea, because his small fields do not produce grain enough to furnish him with bread. The iron of Pittsburgh is exchanged for meat and flour from the West, and even the herdsman of the steppes will buy a little grain of the farmer whom he meets in his wanderings.

The more men have of their own and the more they travel, the more they want of what others find or make; so they exchange, or *trade*, with one another, and thus establish commerce. In a single town, the dry-goods



Fig. 9. Loading cotton at Galveston, a Texas seaport

merchant, the grocer, the baker, the druggist, the hardware man, and the printer sell their goods and buy others that they need. The townsman trades with the farmer, and both with all the world.

The silver or copper or timber of the mountains is exchanged for the wheat, corn, and meat of the plains. The hot lands send us their rubber, coffee, rice, and fruits; the cold lands send us their furs; and from different nations we buy such a variety of things as Persian rugs, Japanese vases, Swiss embroidery, British woolen goods, and French silks. We send, in return, cotton, wheat, steel rails, typewriters, sewing machines, locomotives, agricultural implements, and automobiles.

Wherever men live, there is opportunity to gain by exchanging their surplus goods for other kinds of goods produced in different parts of the world. All men are traders.



Fig. 8. Market place in Nuremberg, a German city

MAN CHANGES THE EARTH

9. **Altering the Earth's Surface.**—In doing so many things men make great changes upon the surface of the earth. In many countries vast forests have been cut away, and replaced with roads, houses, and fields. Great cities stand where the pioneer found the stillness of the woodland. Under the city, the soil and rocks are honeycombed with basements, tunnels, drains, and sewers. In the country, excavations are made for roads, drains, wells, quarries, and mines. Harbors are dredged, canals are dug, swamps are drained, and dikes are built to keep out the sea. Everywhere the farmer, the gardener, and the landscape artist are covering the earth's surface with plants of their own choice.

Man destroys many animals that he does not want, and teaches others to do his work. He not only harnesses the beasts, but he compels the waters, steam, electricity, and the winds to carry him from place to place, and to aid him in tilling the soil, in making what he wants, and in sending his messages.

Where the city of New York now stands Henry Hudson saw only some wooded islands when he sailed by them a little more than three hundred years ago. The city of Chicago has been built on a low, swampy plain which less than a hundred years ago bore only a small military post. On the prairies one now sees great cities, railroads, roadways, farm buildings, fields, and factories where once there were only vast grasslands over which roamed herds of buffalo.

Describe the changes which men have made in the region where you live.

WHAT GEOGRAPHY IS

10. **Geography.**—We have seen that the earth influences man, and that man makes changes in the earth. The plants, animals, and men of one region are very different from those of many other regions. Geography tells what some of the differences are, and

how men live together, influenced by the earth and by one another.

Geography is the study of the earth and its products, of man and his industries, and of their influence upon each other.

Review.—1. Where do some Eskimos live? Describe their homes, food, and clothing. 2. What is the food of the tropical savage? 3. How do people live on the steppes of Asia? 4. Name other parts of the world in which men live in the same way. 5. What did the American pioneer make for himself? 6. What is the chief industry of Pittsburgh? 7. Compare the lives of the Norwegian and the Swiss mountaineer. 8. When a Norwegian moves to a farm on the prairies of Iowa, how does his manner of life change?

9. Why do men exchange things with one another? 10. What products of the western prairies are needed in Pittsburgh? 11. Why cannot all countries make the same things?

12. What changes does man make in the surface of the earth? 13. How did your home region look before the white man came to it?

14. How do the climate and natural products of your region influence the life of your family and of your neighbors? 15. Without using the words of the book, define geography.



Fig. 10. A street corner in Chicago





Fig. 12. Wheat field, Canada, after the reapers have finished their work

NORTH AMERICA

Map Study.—1. What country is crossed by the Tropic of Cancer? 2. What countries are crossed by the Arctic Circle?

3. What waters separate Greenland from the Dominion of Canada? 4. Using the scale of miles, find the width of Hudson Bay from east to west. 5. By what ways may a ship go from the Gulf of Mexico to the Atlantic Ocean? 6. Name and locate three peninsulas belonging to North America. 7. Locate each of these islands: Newfoundland, Cape Breton, Cuba, Jamaica, Vancouver Island. 8. Name the Great Lakes. 9. What large lakes lie wholly in the Dominion of Canada? 10. Name at least two large rivers that are partly in the United States and partly in Canada. 11. What is the chief river of Alaska? 12. What are the main tributaries of the Mississippi River? 13. Locate the Rocky Mountains, Sierra Madre, and Appalachian Mountains.

14. What river forms part of the boundary between the United States and Mexico? 15. What countries are north of the United States? 16. Name the seven countries of Central America.

17. Using the scale of miles, find the distance between New York and San Francisco; between New Orleans and Duluth.

18. What cities in the United States are directly north of the Isthmus of Panama?

THE LAND

II. Position.—North America lies in all three zones of the Northern Hemisphere. On the south it extends within 490 miles of the Equator. On the north the continent and adjacent islands extend far within the Arctic Circle, to a point about 450 miles from the North Pole.

The southern part of North America is a land of coffee, cotton, sugar cane, bananas, and rubber; a tropical country, where the forests are luxuriant, the weather is hot, and the midday sun is always high in the heavens.

In the middle part of the continent is the belt of wheat (Fig. 12), corn, oats, apples, and potatoes. The forests abound in oak, chestnut, maple, ash, walnut, and birch; in spruce, cedar, pine, and hemlock. Here a winter covering of snow melts with the approach of summer and is soon replaced by the springing green of crop and forest.



In the far north is the country of stunted forest and of open grassland, or *tundra*, whose surface thaws a little during the few weeks of a short summer. The shores of this region are the land of the Eskimo and the polar bear, with the seal and the walrus in the adjacent waters. Here, even in midsummer, the sun at midday is low in the southern sky.

North America lies between two great oceans, the Atlantic and the Pacific. The oceans are wide in the temperate belt, in which most of the people live. It takes five or six days for fast ships to go from New York to the ports of England, France, or Germany, and two or three weeks are occupied by the voyage from San Francisco or Vancouver to Japan, China, or the Philippine Islands.

In the far north, Seward Peninsula in Alaska is within 40 miles of Asia, a distance so short that the canoes of native savages have carried them across from one continent to the other. The Atlantic Ocean also narrows at the north, so that Norse sailors were able to pass across a few hundred miles of open sea, from Scandinavia to Iceland, from Iceland to Greenland, and thence to the mainland of North America.

12. Size.—North America contains nearly one sixth of all the land of the globe. Asia and Africa are the only continents that are larger. Canada alone is almost as large as Europe, while the United States, including Alaska, is nearly as large as Canada. North America extends about 5000 miles from north to south, or one fifth of the distance around the globe. We think of the Yukon River (Fig. 14) as confined to a corner of the continent, and yet it is

nearly 1900 miles long. As seen on the map, Hudson Bay does not seem very large, yet it is 900 miles long. Travelers on the Great Lakes may make a voyage for several hours out of sight of land.

13. Coast Line.—Our continent has an irregular coast line. It is less broken than that of Europe, but much more broken than the sea border of Africa or of South America.

The Gulf of Mexico is the largest indentation in the coast line of North America. It is important as a trade route, because of the commerce of the Mississippi Valley and of the thriving cities along the shores of the Gulf. Hudson Bay is the great northern indentation, reaching to the heart of Canada, but the passage to the Atlantic is blocked with ice during the long winter. The Gulf of St. Lawrence and the St. Lawrence River, with the Great Lakes, allow navigation, during most of the year, to reach the fertile plains and several of the large cities of two great countries. Smaller, but very important because of their use as harbors, are the Chesapeake, Delaware, New York, and Massachusetts bays (Fig. 58). Inlets at Savannah and Charleston form other important harbors, but the south Atlantic shore is less irregular than that of the north Atlantic.

At the north of the continent is the group of barren islands that form the Arctic Archipelago. In spite of their great size, their position makes them far less valuable than the smaller islands of the east coast.

The western coast, especially that of Alaska and Canada, has many deep bays, and is bordered by bold headlands and rocky islands. Of the western bays the




Fig. 14. Yukon River. Drying fish




Fig. 15. Rocky Mountains, Colorado, — part of the Cordilleras. Longs Peak, elevation 14,271 feet


largest is the Gulf of California, but the most important for commerce are Puget Sound and other protected waters behind Vancouver Island, the mouth of the Columbia River, and San Francisco Bay. South of San Francisco Bay, to Panama, there are few natural harbors.

14. Surface.—Two systems of highlands extend lengthwise of the continent. The greater is the *Cordilleran* system, which is on the west side. It is long, for it extends from Alaska to Panama. It is broad, for it reaches from San Francisco almost to Denver. It is also high; a large part of its surface is more than a mile above sea level. In Colorado and other states its higher peaks are nearly three miles in altitude (Fig. 15). In Alaska it includes Mt. St. Elias, and Mt. McKinley, which is the highest peak known in North America, rising 20,464 feet above sea level. The highest point of the Mexican Cordilleras is the summit of Mt. Orizaba. Its altitude is 18,314 feet.

The other system of

highlands is the *Appalachian*, in the east. Its direction is nearly northeast and southwest, and it extends from central Alabama through eastern Canada. Its ridges and peaks are lower than those of the western highlands, and most of them are covered with forest to their summits (Fig. 16), while the higher Cordilleras rise to the region of bare rocks or perpetual snow. In the northern Appalachians, the highest point is the summit of Mt. Washington, in New Hampshire, 6279 feet above sea level. In the south the highest peak is Mt. Mitchell, in western North Carolina. Its altitude is 6711 feet, which is the highest point in the eastern half of the United States (Fig. 155).

Between the Appalachians and the Cordilleras, a broad *central plain* extends from the Gulf of Mexico to the Arctic Ocean. From the Gulf of Mexico one can go up the Mississippi and Minnesota rivers, down the Red River (of the North) and Lake Winnipeg, and pass west of Hudson Bay to the



U. S. Geological Survey
Fig. 16. Appalachian Mountains, North Carolina




Fig. 17. East and west profile of North America, across the United States on the parallel of 39° north

Arctic Ocean, and never be as much as 1000 feet above sea level. Near the mountains, east or west, some parts of the central plain are much higher than this.

This plain is vastly wider than an ordinary valley, as it reaches from the Appalachians to the Cordilleras, a distance of many hundred miles. Figure 17 shows the curvature of the earth and the great width of the valley as compared with the height of the eastern and western mountains.

The western system of mountains reaches to the Pacific Ocean, and, excepting a few lowland valleys, the slopes of the mountains descend into the sea. East of the Appalachians, however, there is the *Atlantic Lowland*, sloping gently from the eastern foot of the mountains to the sea border.

It will be seen, therefore, that the surface of North America includes two systems of highland and two regions of lowland. The greater highland is in the west, the greater lowland is in the center, and the lesser highland and the smaller lowland are in the east.

Review.—1. How far from the Equator is the most southern part of North America? 2. Compare the products of the southern part of the continent with those of the middle part. 3. How long would it take to go from England or France across North America to China?

4. Compare this with other continents in size. 5. What is the largest country in North America? The second in size?

6. Compare North America with Europe and with Africa and South America as regards their coast lines. 7. What are the advantages of a

broken coast line? 8. Compare the east and west coasts of the United States as regards the number of good harbors.

9. Locate and describe the Cordilleran highlands. 10. Where is the southern end of the Appalachian Mountains? 11. Give the location of Mt. Mitchell. 12. Compare the Appalachian highland with the Cordilleran in length; in breadth; in height. 13. Where are the high parts of the great central plain? The low parts? 14. How does the slope of the Atlantic borderland differ from that of the Pacific border?

RIVERS AND VALLEYS

15. Rivers.—Drops of rain falling on the forests and fields may soak into the ground, or they may form rills and run down the slopes to the nearest brook. Brooks and creeks, running together as they descend, form rivers. Much of the water that sinks below the surface moves slowly through the soil and rocks and comes out at some lower point as a spring that feeds a rivulet. If the water falls in the form of snow, the snow melts in due time and swells the rivers, perhaps to flood levels.

When water is exposed to the air, some of it mixes with air as an invisible vapor. This process is called *evaporation*. Most of the moisture in the air has evaporated from the surface of the ocean. The invisible vapor moves with the winds over the lands. When chilled, it condenses and forms clouds, composed either of very small drops of water or of minute snow crystals. These particles may unite and form larger drops or crystals, which fall to the earth as rain or snow.

The moisture that falls on the land finally gathers into rivers and flows to the ocean. Thus water is always journeying from the ocean to the land and back again to the ocean.

Rivers are so important in the geography of North America and of all other continents that we should understand how they act and what work they do. Running water, whether in stream or in roadside gutter, has power to pick up and carry or roll along with it fragments of earth or stone. The larger and swifter the stream, the larger the particles that it can transport. In mountainous or hilly regions, such *rock waste* is plentifully supplied to the streams. On the steep sides of the valleys rocks are broken up by water, which, in cold regions, freezes and expands in the crevices. Pieces of rock are often wedged off from ledges by the growing roots of trees. These fragments fall from cliffs or slide down the slopes and come within the reach of the current. Rivers that flow through plains carry away, at many places, the gravel, sand, and earth of which the banks are composed.

Some mineral substances, such as common salt, lime, iron, sulphur, and many others, are gradually dissolved by the water in the ground, and go with it into the rivers and the sea. These *dissolved* substances,

which we cannot see, together with the mud, sand, gravel, and boulders, which we can see, make up the *load* which the stream moves. When the stream flows swiftly, it carries or pushes the entire load, including the pebbles and boulders. When it moves gently, it carries only the mud and the minerals that the water has dissolved.

The waste of the land, therefore, as well as the water, is always on its way to the sea.

16. The Formation of Valleys.—A stream makes a trough, at the bottom of which it flows. This trough is the *valley* of the stream. The stream wears the rocks and makes the valley deeper.* The wasting of the rocks and the falling and sliding of the rocks and soil from the valley sides constantly make the valley wider.

Where a stream has not worked long, but has worked vigorously and cut down rapidly, its valley is a gully or gorge. Spanish explorers used the word *cañon* for such a narrow valley, and as they were the first to explore much of our western country, the gorges there are called *cañons*, or *canyons*. A gorge or canyon is a *young* valley (Figs. 18, 19, 239).

Where the stream has worked a long time at its task, so that the sides of the valley have wasted until the valley has become wide, and the slopes are no longer




Fig. 18. Young valley



Fig. 20. Mature valley



Fig. 19. Young valley



Fig. 21. Mature valley in Vermont

steep, we call the valley *mature* (Figs. 20, 21). Where the side slopes are almost worn away and the country nearly flat, we call the valley *old* (Fig. 92).

As these processes are going on all the time, the surface of the land is slowly changing its shape. In the course of long periods of time, narrow valleys widen and the separating hills are reduced to gentle slopes. Even mountains may be worn down to the level of plains.

17. Waterfalls.—Young streams have many uneven places in their beds, because they have not had time to wear away the rocks. They may flow gently and smoothly for some distance and then flow more swiftly in *rapids*, or plunge over a cliff, making a *waterfall*. The Niagara Falls have been formed where a hard layer of rock crosses the bed of the stream (Figs. 22, 119). Below the falls the river flows through a deep gorge (Fig. 43) formed by the wearing away of the softer layers below and the breaking off of the hard layer thus left unsupported.




Fig. 22. Section of Niagara Falls

Waterfalls and rapids are of great use to man, because they supply power not only for mills at the falls, but also for the development of electricity used in moving cars, lighting houses, and running machinery even at a long distance (Fig. 23).

18. Floods.—Usually streams flow within their channels, that is, between banks. But after heavy rains or the melting of snows the waters rise, and may flow over the

banks and flood the lowlands, or *river bottoms*, on either side. Floods undermine railways, wash out roads, carry off fences, and may bury good soil under a mass of gravel. But their work is not all bad. The water of most floods carries fine mud, or *silt*, which it brings from the higher lands and deposits on the flooded lowland. In this way the river has built the flat lands, or *flood plains*, bordering the river (Fig. 24). On these fertile bottom lands rich crops of grain, fruit, and vegetables are grown, and such lands furnish an easy grade along which to lay railway tracks.



Fig. 23. Power plant at a waterfall



Fig. 24. Flood plain, Missouri




Fig. 25. Meanders in the Tennessee River, Tenn.



Fig. 27. Delta at the head of a mountain lake

19. Meanders.—If we observe a stream as it flows along its flood plain, we shall see that it has a winding course. It bends back and forth, sometimes doubling on itself in close, sharp curves. These are the *meanders* of the stream (Figs. 25, 26).

A very little cause may prevent a stream from flowing straight. If a farmer dumps a load of stones over the bank, or if the earth on one bank is held fast by the roots of a tree, the water will cut out a curve in the opposite bank. The water flows against this curve and is thrown back against the other bank a little downstream. So the water wears heavily first on one side and then on the other, and the curves increase from year to year until the stream may form a series of *oxbow loops*.

On the inside of each curve the water is shallow and the bank sloping. On the outside the current is swifter, the water is deeper, and the bank is steep. Here is the "swimming hole," or, if the stream is a great river like the Mississippi, here runs the steamer track, here the landings are made and towns arise.

In flood time the river often breaks across the neck of an oxbow loop, leaving the loop full of still water, to become a lake. Many such lakes are found along the Mississippi River and its branches (Fig. 26).

20. Deltas.—A river is able to carry its load of rocky or earthy waste because its water is moving. When the motion slackens, the heavier parts of the load drop to the bottom. When the river enters a lake or the ocean, the current is lost and all the load is dropped, except the mineral substances that have been dissolved by the water, and are thus carried in an invisible state. In many cases the stream deposits so great a mass of earth that it builds up a broad, flat addition to the land, called a *delta* (Figs. 27, 28). The river may divide near its mouth, and enter the sea by several streams called *distributaries* (Fig. 28).

We do not need to see the Mississippi or the Nile or any other large river in order to see a delta. Deltas may be seen along many lake shores, or in the border of almost any roadside pool after a heavy shower.




Fig. 26. Meanders in the Mississippi River

21. Uses of Rivers.

—What has here been said about the work of rivers will help us to understand the ways of streams when we see them, and will prepare us to study the great rivers of North America. Rivers are interesting because man uses them in so many ways. They supply water for domestic use, for manufactures, for fire protection, and for irrigation. They furnish the most economical form of power for every kind of industry. When deep and long, they may become highways of travel and transportation, and along their valleys are many of the greatest cities, richest farms, and finest roadways of the world.

22. River Systems, Basins, and Divides.

When several rivers unite, the main stream and all its branches, great and small, make a *river system* (Fig. 29). All the surface that is drained by a river and its tributaries is called its *basin*. The higher ground that separates one basin from another is a *divide*. If formed by a high range of mountains, the divide is narrow and has a sharp crest. But low hills often form divides, and the boundary between river basins may even ex-




Fig. 28. Delta of the Nile

system drains into the Gulf of Mexico. This system includes the Ohio River and its tributaries on the east, and the Missouri, Arkansas, and Red rivers on the west. The distance from the head of the Missouri to the

tend across plains and marshes.

23. Rivers of North America.

—In North America there are seven great river systems.

The *St. Lawrence* system includes the Great Lakes and the rivers that flow into them, or into the St. Lawrence, from the United States and Canada. It discharges its waters into the Atlantic Ocean.

In the central lowland the *Mississippi* system drains into the Gulf of Mexico. This system includes the Ohio River and its tributaries on the east, and the Missouri, Arkansas, and Red rivers on the west. The distance from the head of the Missouri to the mouth of the Mississippi is 4200 miles. No other river in the world is so long as this. Northward, mainly in Canada, is the *Nelson* system, discharging into Hudson Bay. It includes Lake Winnipeg, the Saskatchewan River, and the Red River (of the North), a part of which is in the United States. Farther north, the *MacKenzie* system sends its waters into the Arctic Ocean. Its river basin is larger than any other in North America except that of the Mississippi.



Fig. 29. A small river system—that of the Illinois River

Three systems discharge into the Pacific Ocean. The *Yukon* has its sources in north-western Canada, crosses Alaska, and pours its waters into Bering Sea. The *Columbia* system belongs partly to the United States and partly to Canada. It drains the central portions of the Cordilleran region. The *Colorado* drains much of the western highlands of the United States, and flows into the Gulf of California.

Of these systems, the St. Lawrence and the Mississippi are of great importance for navigation. The lower part of the Columbia River also has considerable shipping. The Nelson, Mackenzie, and Yukon systems are used for navigation, but are icebound during much of the year. The Colorado flows for a large part of its course in deep canyons, and is of little use for navigation.

The Rio Grande is a long river with few branches. Many shorter rivers of North America are important because their lower courses are deep enough for ships, and because they supply water, ice, and power to dense populations. Numerous examples are found on the Atlantic Lowland, as the James, Potomac, Susquehanna, Delaware, Hudson, and Connecticut rivers.

Review.—1. Trace the progress of a drop of water from the ocean to the land and back to the ocean. 2. What is the *load* of a stream?

3. What is a gorge and how is it made? 4. What word is used for gorge in the western part of our country?

5. What harm is done by floods? 6. What are the uses of valleys and flood plains? 7. In a stream that winds in sharp curves, where would a swimming hole or a steamer landing be found?

8. What is a delta? A river basin? A divide? 9. Mention several important uses of rivers.

10. Name and locate the great river systems of North America. 11. Which are the most important for navigation?

CLIMATE OF NORTH AMERICA

24. Factors of Climate.—The air about us is a mixture of several gases. It surrounds the whole earth, and extends many miles above the surface. We speak of it as the *atmosphere*. The air at any place may be hot or cold, moist or dry, at rest or in motion. We refer to its heat as the *temperature*; to the moisture, if it falls to the earth, as *rainfall*; and to movements of air that are nearly horizontal, as *winds*. Temperature, rainfall, and the winds are the conditions or factors that make the *climate* of a region.

25. Effect of Latitude.—In the southern part of North America, the sun at midday is always high in the sky, the rays fall directly upon the surface, and the region is hot. Except in the mountains, frosts do not occur.

In much of the United States and southern Canada, the cold and warm seasons are about equal in length. The midday sun is low in the sky in winter and high in summer. In these northern regions, snows cover the ground during much or all of the winter.



Fig. 30. Winter in northern United States



Fig. 31. Winter in southern North America



Fig. 32. Rocky Mountains, southern Canada, in summer

The Hudson Bay region, the Mackenzie River basin, and Alaska have short summers and long winters. Still farther north, in northern Canada and Greenland, are regions of perpetual frost, ice, and snow.

Thus the temperature of North America changes from the equatorial to the polar regions; that is, it varies with latitude. Low latitudes have in general high temperatures the year round, and high latitudes have low temperatures for most of the year.

26. Effect of Altitude.—Not all places in the same latitude, however, have the same climate. The states along the Mississippi River have hot summers. The states along the Rocky Mountains, such as Colorado and Wyoming, in the same latitudes, but situated at high altitudes, have rather cool summers. In like manner the valley of California has a mild climate, while parts of the Sierra Nevada and the Rocky Mountains bear snow and ice throughout the year (Fig. 32). Thus climate becomes cooler as *altitude* increases.

27. Oceanic and Continental Climates.—The waters of the ocean, except in shallow or quiet bays, or in polar regions, never freeze. Ocean water is deep and absorbs much heat from the sun. The land is warmed more quickly than the water in summer, but loses its heat more quickly in winter. Hence the ocean is usually colder than the neighboring lands in the summer and warmer than they are in the winter.

On the west coast of Canada and the United States the prevailing winds are westerly; that is, they blow from the Pacific Ocean. This part of the coast is therefore warmed by the winds from the ocean in the winter and cooled by them in the summer. The climate is even, with no great extremes of heat or cold.

In contrast with the Pacific coast region we may study the northern part of the Mississippi basin. This becomes very warm in the summer. Hot winds blow from the still more heated plains of the southern Mississippi Valley, and there is no bordering ocean from which cooling winds can come. In the winter the ground soon loses the heat absorbed in summer, and the prevailing winds reach the region from the west after passing many hundred miles over the chilled surfaces of mountains and high plateaus. Hence this region has great yearly extremes. Yet it is in the same latitude as much of the Pacific border, which has an even climate. The one has an *oceanic* climate, the other a *continental* climate.

The north Atlantic coast region has a colder climate than the north Pacific coast. The west coast of Canada, with mild winters, is on the north Pacific. Here the prevailing winds come from the ocean and are never very cold. The coast of Labrador, with its bitterly cold winters, is in the same latitude on the north Atlantic. On this shore icy winds come from the cold lands of the interior.

The south Atlantic coast, from Florida to New York, has a milder climate, both because it is farther south and because southerly winds often blow over it from the warm waters of the Caribbean Sea and the Gulf Stream.

28. Summary.—In North America the temperature in the southern part of the continent is tropical, in the central part temperate, and in the northern part Arctic,—due to differences in latitude. It is true, however, that places in the same latitude often differ much in climate because one place is low and another is high, or because one is near the ocean and the other far from it. It is also true that the climate of two places in the same latitude and both on the ocean may differ on account of the direction of the winds and ocean currents. A continental climate is one of extremes, while an oceanic climate is more nearly uniform. As a rule more rain falls near the ocean and less in the interior.

29. Prevailing Winds.—Before leaving our study of the climate of North America, we must learn more about its winds. We have already learned that in much of the United States the more common, or prevailing, winds are from the west (Sec. 27). This is true of nearly the entire temperate belt of the continent. These *prevailing westerly winds* are part of a great system of world winds which are to be taken up later when we come to the study of the ocean.

In the tropical parts of the continent the prevailing winds are from the northeast. They move along the tropical parts of the Atlantic Ocean north of the Equator, cross the West Indies, the Caribbean Sea, and the Gulf of Mexico, and sweep over Mexico and Central America. These are called *trade winds*, and should be fixed firmly in mind because they, like the prevailing westerlies, are parts of the great world winds (Fig. 33).



Fig. 33. Prevailing westerlies and trade winds



U. S. Geological Survey

Fig. 34. Glacier entering the sea, Alaska



Fig. 35. Valley glacier, Alps

Review.—1. What are the factors that make climate? 2. Give examples of places in the same latitude that have different climates. Explain.

3. Why is the ocean warmer in winter and cooler in summer than the lands on its shores?

4. Explain the difference between the climate of Labrador and that of the west Canadian coast.

5. What is the direction of the prevailing winds in the temperate latitudes of North America?

6. What is the direction of the prevailing winds in the West Indies and Central America? What are they called?

GLACIERS

30. Glaciers of the Present Time.—

Greenland is the largest of all islands. It is about three times as large as the state of Texas. Nearly seven eighths of its surface, or over 700,000 square miles, are covered with ice. In the past more snow has fallen during the long winters than could melt away during the short summers. Hence the snow has accumulated. Snowflakes consist of crystals of ice, and, when packed together, become solid and blue like other ice. An old snow-bank, as seen in the spring, has been packed down, partly melted, and frozen again, and is much like ordinary ice. This has happened on a large scale in Greenland, until most of the island is covered with a thick blanket of ice called an *ice sheet*, or *glacier*.

The ice, brittle as it is, moves slowly out toward the coast, and some of it creeps down

the deeper valleys into the sea. There the front masses of ice break off and float away and drift southward through the north Atlantic Ocean as *icebergs*.

It is not easy to understand how ice can move in great sheets or streams, but there is no doubt that it does so. The Greenland ice is, in many places, several thousand feet thick, and moves gently outward to the edge of the island, somewhat as molasses candy spreads out toward the edge of a plate.

In southern Alaska, by the sea, is a range of high mountains, with deep and narrow valleys. Much water vapor comes to them with the mild winds from the Pacific Ocean. This cools and falls as snow on the high slopes of the mountains. The snows pack, creep down the slopes, and form glaciers in the valleys. As in Greenland, some of the glaciers push out into the bays or gulfs of the sea border. In Greenland there is a great central ice sheet with tongues, or streams, reaching out from the edge. In Alaska there are no glaciers except in the mountains, and most of them are narrow streams of ice in mountain valleys.

In high valleys and near the summits of high peaks in western Canada, western United States, and Mexico, small glaciers are found. Hundreds of small glaciers occur in the Alps (Fig. 35) and in the mountains of Scandinavia, and there are many among the high mountains of Asia, Africa, South

America, and New Zealand. Some of the glaciers in Africa and South America are in the equatorial region, showing that if we go high enough, even in the hottest parts of the world, we shall find an Arctic climate.

Most of the Antarctic Continent is buried under an ice sheet much larger than that which covers Greenland. The vast ice mass is always pushing slowly outward into the sea, and the icebergs broken from it are of immense size.

31. Wearing by Glaciers.—Glaciers are heavy because they are hundreds or thousands of feet thick. When they move over the land, even a few inches or a few feet a day, they scrape up loose material and act on the firm rocks as a file or gouge. The stones in the bottom of the ice grind over the rocks, tear them up, or scratch and polish them. We may think of the glacier as a scraper or rude harrow, tearing up earth and rocks and moving them forward. A glacier moving across the hills and valleys of a rugged region will make it smoother. Where a glacier plows




Fig. 37. Moraines

through a valley for a long time, it may scrape out the bottom and make the valley deeper. Sometimes the glacier gouges out the valley floor in places and thus digs basins that are filled by lakes when the glacier melts away.

32. Glacial Period.—In a former period, in most of Canada and northern United States the climate was colder than now, and there was much greater snowfall. Glaciers formed around Hudson Bay, among the highlands of Canada, and also in the mountains of New York and New England. As the snows increased, ice sheets formed and grew larger, until there were great movements southward, southeastward, and southwestward. This *ice invasion* extended as far as the islands south of New England, into northern Pennsylvania, to the Ohio River where Cincinnati now is, and into Kansas and Nebraska (Fig. 36). Much of the northeastern United States was covered by ice for a long time.

The moving mass of ice tore pieces from the rock surface over which it moved, and carried them along or ground them into *rock flour*. Such *land waste* was scattered over wide regions. In some places it covered the land rather evenly, like a sheet or veneer. In other places it was left in irregular hills, knolls, and ridges, making what are called *moraines* (Fig. 37). In certain regions, as in eastern Massachusetts, western New York, and southeastern Wisconsin, there are hundreds of oval hills, called *drumlins*, which got their shape from the glacier's pushing over them.



Fig. 36. North American ice sheet



Fig. 38. Stream flowing from a glacier, Alberta

Water is constantly produced by the melting of glaciers. This water sinks through cracks in the ice and flows out from beneath the glacier at its lower end (Fig. 38). Such water is often white with pulverized rock ground up by the glacier. When an ice sheet spreads over plains, the waters come out at many points along the edge and flow over the land. Many of the prairie plains of the Mississippi basin are covered with sands, clays, and loams brought by such streams from beneath the ancient ice sheet.

Review.—1. What part of North America has a great ice sheet? 2. What are icebergs? 3. What other northern region has many glaciers? 4. What other parts of North America have glaciers?

5. How thick may glaciers be? 6. What effect does their moving have on the ground and rocks beneath?

7. What parts of our continent were formerly invaded by the ice and covered, as much of Greenland is to-day? 8. What deposits were left by the glacier?

DISCOVERY AND SETTLEMENT

33. The Early People of North America.—The Bible and books of Oriental history describe people who lived about the east end of the Mediterranean Sea and along the Nile and Euphrates rivers several thousand years ago. The poets and historians of Greece and Rome tell the story of civilized life in southern Europe, from 2000 to 3000 years ago. Even Great Britain, France, and

Germany were visited by civilized men about the time of Christ. But North America had no history of importance, so far as white men are concerned, until 1492, the year of its discovery by Columbus. Norse sailors, indeed, about five hundred years earlier, had come to Greenland by way of Iceland, and made large settlements which lasted several hundred years. It is believed, from their stories, that some of them even discovered the North American mainland, but where they landed is not known.

Columbus, supposing that he had reached the “Indies,” or southeastern Asia, called the savages who met him *Indians*. They are often called *red men*, although the real color of their skin is reddish brown. Some of the tribes used red paint on their bodies, and this may explain the name.

As they lived chiefly by hunting and fishing, they required much land to supply food even for a few. North of the Gulf of Mexico, North America was almost an empty continent, waiting for the white man to come and fill it with people. East of the Mississippi River there were perhaps as many Indians as there are people now in the city of Rochester, New York, or in the city of St. Paul, Minnesota.

Through some parts of the forest the Indian made trails, but in the untracked forest he found his way just as well, for he was keen to see and hear, and to remember all that he saw and heard. Before the white man came, he had, in most of our continent, no domestic animal but the dog, hence he traveled afoot when he went out to hunt for food or to engage in war. On streams and lakes, however, he used a light birchbark canoe which he could easily carry across country from the headwaters of one stream to those of another.

Most of the time the Indians in the eastern part of our country lived a settled life in their villages. Like other peoples of the world, they built their homes out of what was near at hand. Some had shelters of brush,



Fig. 39. Indian tents



Fig. 41. Indians decorating pottery

bark, and skins. Some had tents of rush mats supported by poles. Others built houses of wood, often showing much skill; they used posts and rafters, with thatch and siding of split poles and bark. Some of the houses were built 50 or 60 feet long, and were divided into rooms.

The Pueblo tribes of the Southwest, who lived by farming, were more advanced in skill. Because they had little wood, they used bricks of dried mud, or *adobe*. A single *pueblo* held many inhabitants, and was a kind of village, built several stories high, the rooms being reached by ladders (Fig. 40). In Mexico, the Aztecs were a semicivilized people, and built splendid monuments and temples.

In the East most of the Indians cultivated patches of ground near their villages, raising beans, squashes, and especially Indian corn. Wild berries were gathered, and in some parts of the country wild rice, acorns, sunflower seeds, and potatoes were used. Corn and the potato were unknown to the rest of the world before America was discovered, but they have now become important food crops in many other countries.

Wild animals of many kinds were trapped, or killed with bow

and arrow, to supply food and clothing. Oysters and clams were found along the shores, and fish were caught in all waters. On the Pacific coast, from Oregon to Alaska, the salmon of the rivers were the chief food of the tribes in that region.

Many Indians had learned more about getting the good things of the earth than we commonly suppose. They made good arrowheads, knives, and hammers of stone, and even quarried the native copper about Lake Superior and hammered it into utensils. They made pottery (Fig. 41), wove garments, blankets, and baskets of many kinds of fibers, and fashioned elaborate ornaments. They had many kinds of dances and games. There



Fig. 40. A pueblo, New Mexico. The doors and windows are modern

were various games of ball; there were contests in throwing and shooting; foot races were common; and "hunt the button" games were played by both men and women. The boys played with tops, slings, and stilts, and the girls played "house" and had dolls of buckskin.

Hominy, samp, and succotash are names derived from Indian speech. States, cities, islands, lakes, and rivers that the white man has called after Indian names are found in all parts of the continent. The following are examples: Mexico, Ottawa, Connecticut, Manhattan, Chicago, Michigan, Dakota, Wyoming, Spokane, Chattanooga, and Tallahassee. The student may add to this list names from his own region.

34. Spanish Explorers. — Columbus was an Italian, but he sailed under the patronage of the king and queen of Spain. His aim was to find a new route from Spain to southeastern Asia, and he believed he had succeeded when he reached the Bahama Islands and Cuba. He made three later voyages to the same region, and other Spaniards followed him. The result was that Spain took possession of the lands about the Caribbean Sea and the Gulf of Mexico, including Florida, Mexico, Central America, and most of South America (Fig. 42). Spanish explorers and settlers went to the region now occupied by our southwestern states, from Texas to California, and this part of our country still bears many Spanish

names. El Paso, Santa Fe, Colorado, Los Angeles, and San Francisco are examples.

35. French Explorers. — French fishermen began to catch fish near Newfoundland in 1504. French explorers discovered the St. Lawrence River and the Great Lakes. Quebec, the first permanent French settlement, was founded by the explorer Champlain; for whom the lake between the Adirondacks and the Green Mountains is named. The French missionary Father Marquette went from Lake Michigan far down the Mississippi River, and the great explorer and fur trader La Salle followed the river to its mouth. They were two

of the many traders and missionaries who went through the forests of Canada and over the prairies of the Mississippi Valley and took possession of the central parts of North America for the French king. Detroit, Duluth, Des Moines, St. Louis, and New Orleans are examples of French names that remain. Many people in Canada and in the city of New Orleans still use the French language.

36. English Explorers. — The first English explorer who came to this continent was John Cabot. He landed on the coast of Nova Scotia or of Labrador. But the great English settlements in America were made more than a century later, on the middle Atlantic coast. The first successful settlement was at Jamestown, in Virginia, in 1607. The *Mayflower* Pilgrims came to Plymouth in 1620. The Dutch took possession of Manhattan Island and named



Fig. 42. Early divisions of North America



Fig. 43. A river boundary — the Niagara Gorge



Fig. 44. Boundary marker, Rocky Mountains

the place New Amsterdam; but later they were obliged to give it up to the English, who called it New York.

The English settlers built up thirteen colonies, but they were confined to the narrow Atlantic Lowland (Fig. 42). The French held the St. Lawrence and the great interior lowland. The Spanish held Florida and the Southwest. But the French and Spanish generally cared more for furs and gold than they did to make homes, though many noble French missionaries sought to turn the natives to Christianity. Only the Englishmen came across the sea in large numbers with their families to make homes. They pressed across the mountains, defeated the French in war, and won the central part of North America.

POLITICAL DIVISIONS

In studying the mountains, plains, coast line, rivers, glaciers, or soils, we are dealing with *physical geography*. Look at the map of our continent to see what countries occupy its various parts. The study of the location and extent of countries belongs to *political geography*.

37. The United States. — After England had made its great conquest over the French, the English colonies separated from the mother country as a result of the American Revolution. In 1783 the land was ceded to the United States, from the southern border of

Canada to Florida, and from the Atlantic Ocean to the Mississippi River. At length the United States gained Florida and also Texas and other lands west of the Mississippi, until, in 1853, our borders on the Gulf of Mexico and the Pacific were the same as now. In 1867 the United States bought Alaska from Russia, and as a result of the war with Spain in 1898, Porto Rico came into our possession. These are the lands in North America that belong to the United States.

The Atlantic and Pacific oceans are the natural boundaries of the United States on the east and west. On the north the Great Lakes form a natural boundary, but north-eastern New York, most of New England, and the border states of the northwest, are not separated from Canada by any river, lake, or mountain range. The boundary runs across plains and mountains, mainly in regular lines as fixed by treaty between governments. On the south the Rio Grande in part separates the United States from Mexico.

38. Countries North of the United States. — The Dominion of Canada includes all of the mainland north of the United States, except Alaska, and embraces many islands north of Hudson Bay and lying on the borders of the Arctic Ocean. There are also many small islands bordering the Pacific coast of Canada, and others in the Gulf of St. Lawrence. Canada is the largest country in North America. It is part of the British Empire.

The large island of Newfoundland also belongs to the British Empire, but it is a colony distinct from Canada.

Greenland is under the rule of the kingdom of Denmark.

St. Pierre and Miquelon are two small islands south of Newfoundland, which still belong to France, and are important as stations for the French fishermen in those waters. They contain only 93 square miles, have a population of but a few thousand, and are all that is left of the French empire in North America, except a few small islands in the West Indies.

39. Countries South of the United States.—The republic of Mexico extends from the United States on the north to Central America on the southeast. It includes the peninsula of Lower California, and its southern and narrower part curves to the east and north and embraces the peninsula of Yucatan. It has long shore lines on the Pacific Ocean and on the Gulf of Mexico. Mexico was a Spanish possession for about three hundred years, but became independent in 1821.

Central America is a group of seven small countries. British Honduras is a colony belonging to Great Britain, and the other six countries are republics. Guatemala, Salvador, Honduras, Nicaragua, and Costa Rica gained their independence from Spain about the same time as Mexico. Panama became independent of the South American republic of Colombia in 1903, and at once sold to the United States the right to use forever a strip ten miles wide for the Panama Canal. This is known as the Canal Zone.

The West Indies, like the mainland of North America, are divided among a number of different countries. Cuba has been an independent republic since its release from Spain in 1898. The island of Haiti is divided between the republic of Haiti and the Dominican Republic. Porto Rico belongs to the United States. The Bahamas, Trinidad, Jamaica, and several other islands belong to Great Britain, and other small islands are the property of Holland and of France.

No European nation except Great Britain has important possessions in North America.



Fig. 45. Statue of Champlain, founder of French America

Review.—1. How does the white man's stay in North America compare in length of time with the history of older lands? 2. Are *Indians* and *red men* good names for the ancient people of America? 3. What materials did the Indians use for houses? 4. To what extent did the Indians till the soil? 5. What were some of the amusements of the Indians? 6. What names of food do we get from Indian

speech? 7. Give examples of Indian names of rivers, states, and cities. 8. Make as full a list of such names as you can from your own state.

9. What was Columbus seeking, in his voyage of 1492? 10. What parts of our continent were occupied by the Spaniards?

11. What first brought the French to the American coast? 12. What parts of the continent did they occupy?

13. Who was the first English explorer to come to America? 14. When was Jamestown settled? 15. How did France lose the great Mississippi Valley? 16. Why were the English successful in winning the continent?

17. When did Spain lose her last possession in North America? 18. What foreign powers have possessions in North America? 19. Name the independent countries of this continent. ✕



THE UNITED STATES

Map Study (Fig. 46).—1. How many degrees of longitude are covered by the United States? How many degrees of latitude? 2. What rivers and lakes form part of the northern boundary of the United States? 3. What parallel of latitude does part of this boundary follow? 4. Describe the boundary between this country and Mexico.

5. Which is the longer, the Atlantic or the Pacific coast line of the United States? 6. What states touch the Pacific Ocean? 7. Between what states is Delaware Bay? In what states is Chesapeake Bay? In what state is San Francisco Bay? 8. How do the Atlantic and Pacific coast lines differ?

9. Make a list of the states that touch the Ohio River or some of its branches. 10. Is any state drained wholly by the Ohio River system? 11. What rivers flow into the Mississippi from the east? From the west? 12. What

river systems share in the drainage of Minnesota? 13. What important branches has the Missouri River? 14. Describe the course of the Arkansas River.

15. Name a river and a lake that have no outlet to the ocean. 16. Describe the course of the Columbia River. 17. What great rivers have some of their headwaters in Colorado? 18. What states touch one or more of the Great Lakes?

WAYS OF SHOWING THE FORMS OF THE LAND

40. Relief.—The term *relief* is used in geography to mean the elevations and de-

pressions of the land surface. To show the relief is to represent the plains, slopes, mountains, peaks, and valleys as they are in nature. We may do this by pictures, but a picture can include only a small region. We may do it by models made of paper, plaster, sand, or clay, but the most convenient way is by

maps. In these we can show a river basin, a state, a country, or a continent on a single page. If the map has a scale, we can learn from it the size of the region shown.

There are four common ways of showing the forms or relief of the land on a map; these are illustrated by maps of parts of the United States in Figures 47, 48, 51-57, and 58.

41. Showing Relief by Hachures.

The first is by the use of short, nearly parallel lines called *hachures* (Fig. 47). In order to represent heights, such as mountains, or the border slopes of a plateau, hachures are so drawn as to give the effect of shading. Thus the map shows where the Sierra Nevada and the Coast Ranges are, and in what directions they trend, but does not tell *how high* they are.

42. Showing Relief by Shading.—The second method of showing relief is by *shading* (Fig. 48). The effect of such a map is like that of shadows cast by the higher lands, and the map gives a kind of bird's-eye view of the forms of the region or country.




Fig. 47. Relief shown by hachures

43. Showing Relief by Contours.

—The third method is by *contours*. In this method a system of lines is used, and all points on any one line have the same altitude. If the student will start at any point on the side of some hill

that stands out by itself and walk around the hill, never going up or down, but keeping his feet always at the same level, it will help him to understand the meaning of a contour.

If the hill is near the sea (or near a lake or large pond), it will be easy to find a point on its side that is 20 feet higher than the water level. Beginning at this point, walk around the hill as above directed. Your path will be a contour line of 20 feet (Fig. 49, line *a*).

Then climb the slope until you are 40 feet above the water and walk around again to the second starting point. This is the contour line of 40 feet (line *b*). Every point on this line is 40 feet above sea level. All points




Fig. 49. A simple contour map

between line *a* and line *b* are between 20 and 40 feet in altitude.

Go up 20 feet more, and walk around, and you will trace the 60-foot contour. If the hill is but 70 feet high, you cannot go up another 20 feet.

The map (Fig. 49) shows that the hill is more than 60, and less than 80 feet high.

Study now Figure 50. It shows a shore line and a hill drawn on the same scale as before. The hill is longer than the other. It is not only wider, but much wider at one end than at the other. Notice also that the wider end is higher than the other. It requires six lines to represent the higher end. The hill at the wide end is therefore more than 120 feet, but less than 140 feet high. At the narrow end the height is more than 80, but less than 100 feet. The low place between the summits is between 60 and 80 feet high. The map also shows that the wide end of the hill has a steeper slope on the side toward the water than on the side away from it.



Fig. 48. Relief shown by shading



Fig. 50. Profile view and contour map



Fig. 51. A flat plain — part of the basin of the Red River




Fig. 52. Drumlins, — oval hills composed of glacial waste, — New York




Fig. 53. Land made rough by the work of streams, Virginia




Fig. 54. Water gap cut across a mountain range by the Delaware River



Fig. 55. Mt. Shasta, California, a volcanic mountain peak (see Fig. 69)




Fig. 56. Crater Lake, Oregon, in an extinct volcano (see Fig. 265)

It is plain that the contour map gives us more definite information about a region than we get from the hachures or from the shading.

In the maps already described the *contour interval* is 20 feet. We might use a contour interval of 5, 10, 50, 100, 500, or 1000 feet as well as of 20 feet. The choice depends on the nature of the country and the scale of the map; a 500 or 1000 foot interval is about as small as can be used on the large maps in this book. If the region shown is almost flat, we must use a small interval to show its shape. If we wish to show very high mountains with steep slopes, we can represent their general shape with contours 500 or 1000 feet apart. In Figure 57 the contour interval is 1000 feet.

Figures 51-56 are copied from maps published by the government through the Geological Survey at Washington. Such maps have already been made for many parts of our country and will ultimately be made for all parts. These maps are sold by the government for a small price. Find out if the

map for the region in which you live has been published.

The following statements apply to all these maps. All water is shown in blue. This applies to the ocean, to lakes, ponds, rivers, and canals. Every feature due to man, except canals and artificial ponds, is shown in black. This applies to roads, towns, tunnels, bridges, boundary lines, wharves, lighthouses, and many other things. The contour lines are in brown. The maps chosen here show different kinds of country, varying from flat to hilly and mountainous.

44. Showing Relief by Colors.—A fourth way of showing relief is by the use of *colors* (Fig. 58). Lands of a certain range of altitude are shown by a single color. Thus in the map of the United States every area whose surface is between sea level and 500 feet is shown in dark green. It is common to use green shades for the lower lands and brown or red for the higher. This method does not show particular heights except on the line where one color borders another. Such a map is a variety of the contour map.

SURFACE FEATURES

45. The Formation of Rock Layers.—If we visit a sand or clay pit, which has been opened for the purpose of making mortar or brick, we find that the material lies in layers or beds. If we wait until the water has dried away from a pool after a storm, and dig up the mud at the bottom, we find it also in the form of one or more layers. In the same way, on the bottom of every lake, and of the ocean, muds are accumulating. They are made of the land waste that the rivers bring in. Layers of mud are always forming on the bottom of the Gulf of Mexico, for example, on account of the earthy matter brought in by the Mississippi River and other streams. Near the mouth of the Mississippi River, in the region of the delta, the muds accumulate very rapidly.



Fig. 57. Relief shown by contours. Compare with Figs. 47 and 48, of the same region.





Some of the finer matter carried by the Mississippi is moved out to sea hundreds of miles before it settles to the bottom. If the sands of the sand bank, the clays of the clay pit, or the muds of the pool or ocean were hardened, they would make rocks.

The large flat stones often used in making sidewalks were once parts of beds of mud that were in time hardened into rock. The blocks in the walls of many stone buildings are parts of beds of ancient rock. In many quarries the rocks are in horizontal layers. They may be a few inches in thickness, or several feet. Such rocks were once beds of mud or sand, laid down in seas which no longer exist. The particles of clay or sand have been bound firmly together by various substances which serve as a cement.

The rocks that underlie the surface of the United States are mainly of this kind (Fig. 59). When we dig down through the soil or stony clay, or other loose material, we find firm rock. Sometimes the rock is near the surface, and sometimes it requires a deep well or mine shaft to reach it. The thickness of the rock layers, taken all together, is often many thousand feet.

In many regions the rock layers are nearly or quite horizontal. This is true in the Atlantic coastal plain, from New Jersey

southward to Florida. It is also true in the greater part of the Mississippi basin.

46. Folded Rocks.—If the student will lay several sheets of paper or cloth together and push them inward from opposite sides, the paper or cloth will wrinkle or fold. Some of the folds will turn up and some

will turn down. In many mountain regions something like this on a large scale has happened to the rocks. They were once nearly horizontal, but the earth has shrunk a little, and the rock beds have been wrinkled or folded in places, somewhat as the skin of an apple wrinkles or shrivels when the apple is baked. They have been pushed and crumpled, and the sidewise pushing has made the rocks rise in some folds and sink in others (Fig. 60).

It seems as strange that brittle rocks will bend as it does that the brittle ice in glaciers will move, but both are true. The folding of rocks, however, is sometimes so great that they are

broken and crushed. Many mountains are formed of folded or broken rock layers, carved and worn by the work of streams and glaciers.

47. The Atlantic Lowland.—The lowland between the Atlantic Ocean and the Appalachian Mountains varies greatly in character in different parts. South of New York, the



Fig. 59. Rock beds that are nearly horizontal



Fig. 60. Folded rock layers



Fig. 61. Atlantic coastal plain in North Carolina. The ditches are in a rice field

belt of lowland bordering the ocean is known as the *Atlantic coastal plain*. It is nowhere more than a few hundred feet above sea level, and slopes gently to the shore of the sea. It is so nearly flat (Fig. 61) that the rivers flow sluggishly, and railroads run from New York, Philadelphia, and Baltimore to Florida almost on a level. The rock layers not only lie nearly horizontal, but many of them are loose and soft, somewhat like the muds and sands of the seashore. In them are found shells that are much like those found on the seashore.

These facts show clearly that these lands were at one time a part of the sea bottom and that they have slowly risen above the sea. When free from water, the surface was soon covered with grasses and forest and was crossed by rivers flowing from the higher lands on the west. The rocks of the higher lands are harder and older than

those of the coastal plain, and the streams have cut into them more slowly.

Where a river flows from the harder, higher lands to the western edge of the belt of soft rocks, there is usually a rapid or a waterfall. There is such a waterfall in the Potomac River above Washington (Fig. 62), and there is such a rapid in the James River at Richmond (Fig. 63). The line marking the boundary between the higher lands and the western edge of the coastal plain, where these and other rivers have falls and rapids, is called the *Fall Line*. There is water power where the rivers cross the line. On the seaward side of the Fall Line some of the rivers are deep enough for navigation. For these reasons many cities, such as Richmond, Columbia, and Macon, have grown up, and are known as the cities of the Fall Line.

The tides of the ocean flow far up these rivers, and hence the coastal plain is often



Fig. 62. Waterfall in the Potomac River



Fig. 63. Rapids in the James River at Richmond




Fig. 64. Blue Ridge, North Carolina. These mountains are covered with forests

called the *Tidewater country*. In early days, when ocean ships were small, the farmer by such a river often had his own wharf, and the ships came up, took his crop of tobacco on board, and carried it across the sea to be sold in London.

East and north of the city of New York, along the coast of New England, there is a lowland also, but it is in many places rough, hilly, and rocky, and the beds of rock lie at almost every angle. The hills were once much higher than they are now, and have been worn away until they are nearly as low as the coastal plain south of New York, but the region is much less even and smooth.

Between the coastal plain and the Appalachian Mountains is a hilly region much like the lowland of New England. From New York to Maryland, this region of harder and older rocks is low and rather narrow; farther south it becomes a wide, rolling upland. It is often called the *Piedmont* (foot of the mountain) *Plateau*.

48. Appalachian Mountains.—The Appalachian Mountains (Sec. 14) are made up of folded rock layers, unevenly worn away. Several groups of these mountains have special or local names. In New Hampshire there is a group of peaks called the White Mountains. In Vermont are the Green Mountains. They extend southward across Massachusetts into Connecticut as the Berkshire Hills. In New York are the Adirondacks and the Highlands of the Hudson, the latter continuing into New Jersey. In Pennsylvania, north of Harris-

burg and Reading, is the Blue Mountain, a long, high ridge running northeast and southwest. Parallel to it on the northwest are several other ridges, all belonging to the Appalachians.

In the southern states, the highest part of the Appalachians is the Blue Ridge (Fig. 64). It crosses Maryland and Virginia, and in North Carolina grows higher and broadens into a great series of ridges and peaks, known generally on the eastern side as the Blue Ridge, but often in Tennessee as the Great Smoky Mountains.

West of the Blue Ridge in Virginia, Kentucky, and Tennessee are other long mountain ridges and valleys, all belonging to the same system. One very wide and important valley is called the *Great Appalachian Valley*. It extends through Maryland, Virginia, eastern Tennessee, and northern Alabama. In Virginia, the Shenandoah and the upper parts of the James River and other rivers flow through this valley; in Tennessee, the Tennessee River. In this valley are many beautiful farms, long lines of railroad, and important cities, including Knoxville and Chattanooga in Tennessee, and Birmingham in Alabama.

The Appalachian Mountains vary from less than 2000 feet to a little over a mile in altitude. They are low as compared with the Rocky Mountains or with the Alps, and are for the most part covered with forest. Only a few of the peaks are rocky; they have no glaciers and no snows that remain through the summer.

49. Appalachian Plateau.—West of the mountains is another highland, about as high as the mountains, but made in a different way. The rock layers were not folded, but have been lifted high above the sea and left flat. Originally the surface was nearly level, but the streams have carved it into a region of hills and deep valleys (Fig. 65).

This upland or plateau bears different names in different states. In New York it includes the Catskills, and extends to Lake Erie. In Pennsylvania it is called the Allegheny Plateau, and in Kentucky and Tennessee it is called the Cumberland Plateau. The plateau slopes to the north and west through Ohio and Kentucky. On the north it leads down to the flat ground along the Great Lakes. On the west it descends to the uplands of southern Indiana and the prairie plains in Illinois and other states along the Mississippi River. Most of the plateau is drained by the Ohio River and its branches.

50. The Great Lakes and the Lake Plains.—The Great Lakes are five in number. Four form part of the boundary between the United States and Canada, and one, Lake Michigan, is wholly within the United States. They all belong to the St. Lawrence River system. In their deepest parts they vary from about 200 to 1000 feet deep. Their water is warmed by the sun during the summer. The heat is slowly given off during the autumn and winter and relieves the severity of the climate about the lakes. These lakes are so large, and reach so far into the interior of a fertile country, that they are great highways of commerce, and many cities have grown up on their shores. Around Lake Superior is a rugged upland with much forest and many

mines of iron and copper, but all the other lakes are surrounded by flat or rolling lands which are fertile and produce rich crops of grain and fruit.

The St. Marys River, leading from Lake Superior to Lake Huron, descends about 20 feet in rapids. Around these, both the United States and Canada have made canals with locks to carry large ships from one lake to the other. The Niagara River flows from Lake Erie to Lake Ontario, and here are the Niagara Falls, well known in all lands for their grandeur. Ships passing between the two lakes make use of the Welland Canal. There are rapids also in the St. Lawrence River between Lake Ontario and tide-water at Montreal. At these places other canals have been dug, so that ships of good size can pass from Lake Superior to the Atlantic Ocean.



Fig. 65. Valley in the Appalachian Plateau

51. Plains of the Mississippi Valley.—Westward from the Great Lake region and the Appalachian Plateau are wide lowlands lying on both sides of the Mississippi River. They are very gently rolling, and nowhere more than a few hundred feet above the level of the sea. Much of the region is called *prairie*, from a French word meaning "meadow,"—that is, open grassland, with little forest. When the white man first saw the country, thousands of square miles were covered with tall grasses and other wild plants. The decaying roots and tops of these plants had been gathering on the ground and below the surface for a very long time. As a result, the soil was a black loam, in some places more than ten feet deep. In most regions, however, this layer of dark-colored soil does not extend much below the furrow made by the plow. The surface soil was filled with a tangle of



Fig. 66. A windbreak on a prairie farm, Nebraska

weeds and was hard to break up at first. But when once subdued, the soil was found to be very fertile and has since produced large crops of grain. In the early days fierce prairie fires sometimes ran over these grasslands with the speed of the wind, burning the thick carpet of dried grasses and weeds.

The prairies are not entirely without forests, for woodlands are found along the bluffs bordering the shallow valleys. Now that many people live on the prairies, trees have been planted along the roads and in the towns for shade and windbreaks (Fig. 66), so that, with houses, cultivated fields, roads, and trees, the country has a different appearance from that of one hundred years ago.

Illinois and Iowa are the great prairie states, and the prairies reach northward into Wisconsin and Minnesota, and southward into Kentucky and Missouri.

Southern Missouri and northern Arkansas are uplands, known as the *Ozark Plateau*, and there are mountain ridges south of the Arkansas River.

Farther to the south are plains again, stretching along the Gulf of Mexico from Texas to Florida. They include the delta of the Mississippi. Excepting the delta, they are like the Atlantic coastal plain from New Jersey to Florida, and are known as the *Gulf Plains*. Parts of these plains

drain into the Mississippi River, and other parts into smaller rivers flowing to the Gulf of Mexico.

The prairies, that is, the open grasslands, reach westward into the Dakotas, Nebraska, Kansas, Oklahoma, and Texas. Toward the west the rainfall is less and the prairie merges into a drier region called the *Great Plains*. The Great Plains slope smoothly and gently upward to the foot of the Rocky Mountains, in Montana, Wyoming, Colorado, and New Mexico (Fig. 67). In these states the plains are about a mile above the sea, but the ascent from the Mississippi River is made so gradually that the traveler on the railway does not notice it. Thus there is a vast plain slightly inclined from west to east (Fig. 17).

A cluster of mountains rising out of the Great Plains in South Dakota and Wyoming is known as the Black Hills.

52. Cordilleran Region, or Western Highlands.—The eastern part of the Cordilleran region is the Rocky Mountain system. It consists of many ranges and peaks and extends from New Mexico through Colorado, Wyoming, and Montana. It thus crosses the country from the southern part toward the northwest, and continues northward into Canada, where it is called the Canadian Rockies. The higher peaks and ridges are from 10,000 to 14,000 feet in altitude. Hence they rise as much as 8000 feet above the Great Plains on the east.



Fig. 67. Threshing wheat on the Great Plains, Colorado

In these mountains trees do not grow at a greater altitude than about 10,000 feet. Above this height the slopes and tops are either of bare rock, or are covered with rock waste which bears grasses or alpine flowers. The belt along the slopes where the trees thin out and finally cease is known in these and all mountains as the *timber line* (Fig. 68). In warmer regions the timber line may be higher than 10,000 feet, and in colder lands it is lower.

Between the ridges of the Rocky Mountains in Colorado, at altitudes of 7000 or 8000 feet, are wide basins of grassland. They are good for pasturage in the summer, but are too high and cold for agriculture. Although they have few trees, these basins, bordered by mountains, are called *parks*.

Many great rivers have their sources in the Rocky Mountains. Flowing to the east and south are the Missouri and Arkansas rivers and the Rio Grande. On the west are the Snake River and several branches of the Colorado River.

53. Plateaus.—West of the Rocky Mountains are vast plateaus, or table-lands, from 2000 to 10,000 feet in altitude.

In southern Idaho and eastern Oregon and Washington are the plateaus of the Snake and the Columbia rivers. They are mainly fields of lava poured out in former ages and spread widely over the country. Most of the active volcanoes of the present time build up mountains, or *cones*, of the lava and fragments of rock which come up through their craters. But in former periods great floods of very liquid lava sometimes rose through many openings or through long cracks in the earth. Most of the lavas of these plateaus originated in this way, and in some places they are as much as 4000 feet thick. They break up into a very fertile soil. The Snake River has cut deep canyons through the southern parts of these plateaus. Since the Snake River is a part of the Columbia river system, the entire region is often called the *Columbia Plateaus*.



Fig. 68. Timber line in the Rocky Mountains

To the south are the *Colorado Plateaus*. They are the lands drained by the Colorado River and its branches. They lie in western Colorado and New Mexico, in eastern Utah, and in Arizona. Both the Colorado and its tributaries have cut deep gorges into the plateau. The greatest of these is the Grand Canyon of the Colorado, in northern Arizona, 200 miles long and in some parts more than a mile deep. It is one of the most wonderful natural features of the world.

54. Great Basin.—West of the Colorado Plateaus is the lofty range of the Wasatch Mountains, running north and south through Utah. At the western base of the Wasatch range is the Great Basin, which includes western Utah, nearly all of Nevada, and small parts of other states. It is called the Great Basin because it is bordered on the east and on the west by high mountains, and because its rivers do not reach the sea.

Streams from the Wasatch Mountains discharge into Great Salt Lake. This lake has no outlet. Evaporation from its surface removes as much water as the rivers bring.

The streams flowing into the lake bring with them salts and other substances dissolved from the rocks, and these are left as the water is evaporated. Hence the water of Great Salt Lake is a brine, so dense and heavy that a person cannot sink in it. Similar conditions exist in the Dead Sea of Palestine and in many other lakes in dry regions.

55. Pacific Ranges.—West of the Great Basin is the lofty mountain range called Sierra Nevada, and west of the lava plateaus of the Columbia River is the Cascade Range. Rising above the wooded parts of the Cascade Range are several high volcanic peaks. Among them are Mt. Baker, Mt. Rainier, Mt. St. Helens, Mt. Adams, and Mt. Hood. Mt. Shasta is another great volcanic peak, close to the Sierra Nevada, in northern California (Fig. 69). Several of the volcanic cones, and parts of the Sierra Nevada, have small glaciers near their summits.

On the coast, close to the Pacific Ocean, are rugged mountains which are not so high as the Sierra Nevada. They are the Coast Ranges in California and Oregon, and the Olympic Mountains in Washington. They are separated from the Cascade Range and the Sierra Nevada by the wide valleys of Puget Sound and the Willamette, Sacramento, and San Joaquin rivers.

56. Summary.—The chief regions of the United States, studied according to their surface, are as follows: the Atlantic Lowland, the Appalachian Mountains, the Appalachian Plateau, the Great Lake region, the plains of the Mississippi Valley, the Gulf Plains, the Rocky Mountains, the Columbia and Colorado plateaus, the Great Basin, and the Pacific

ranges and valleys. The student should now be able to draw a map, showing these regions as they are shown on the physical map (Fig. 58).

Review.—1. What is meant by the relief of the land? 2. In what ways may we show relief by a map? 3. Explain the meaning of a contour map. 4. In what way is it superior to other relief maps? 5. What is a bed of rock? 6. In what condition are the rock beds when first formed? 7. What is the position of the beds in much of this country? 8. In what other shapes or positions are beds of rock sometimes found?

9. How does the Atlantic Lowland northeast of the city of New York differ from the lowland south of that city? 10. What is the Fall Line? What regions does it separate? 11. Why is the Atlantic coastal plain called the Tidewater country?

12. What names are borne by different parts of the Appalachian Mountains? 13. In what states is the Blue Ridge? 14. What is the Great Appalachian Valley? 15. Name rivers whose courses are wholly or partly in this valley.

16. How does the Appalachian Plateau compare in height with the Appalachian Mountains? 17. Is the position of the rocks alike in both?

18. What name does this plateau have in eastern New York? In Kentucky and Tennessee?

19. What does the St. Lawrence River system include? 20. How do the Great Lakes affect the climate of the regions about them? 21. In what other ways are the lakes useful? 22. Where is the Welland Canal? 23. What other canals are used by a boat sailing from Lake Superior to the ocean?

24. What is a prairie? Which are the prairie states? 25. Where is the Ozark Plateau?

26. Where are the Gulf Plains, and what other plains in the United States do they resemble? 27. Where are the Great Plains? 28. What is their altitude on their western edge?

29. In what states are the Rocky Mountains? 30. What are the parks in these mountains? 31. Describe the Columbia Plateaus. 32. Where is the Grand Canyon of the Colorado? 33. What mountain ranges are east and what are west of the Great Basin? 34. Why are some lakes salt? 35. Name the volcanic peaks of the Cascade Range. 36. What range of mountains is on the coast in Washington?



U. S. Geological Survey

Fig. 69. Mt. Shasta, an ancient volcanic peak




Fig. 70. Rocky Mountains, Glacier National Park, Montana, in summer

CLIMATE OF THE UNITED STATES

57. Weather and Climate.—There is a difference between *weather* and *climate*. When we speak of the weather, we refer to the conditions of dryness or rainfall, of heat or cold, for a day or two, or to the changes of sunshine and storm, or of wind or temperature within a few days. When we speak of climate, we mean the prevailing conditions of the atmosphere for several seasons or years, or for a long period of years. The climate of a region is sometimes called its *average weather conditions*.

In our study of the climate of North America we saw that climate depends mainly on four conditions: (1) latitude, which determines whether the sun's rays strike vertically or slantingly; (2) altitude, which may give an Arctic climate even near the Equator; (3) nearness to the sea, on the windward side of the continent, giving an even, oceanic climate, or remoteness from the sea, giving a continental climate, marked by extremes; (4) the direction of the prevailing winds. The moisture which has evaporated from the surface of water bodies moves with the winds.

58. Temperature.—In southern Florida the Atlantic Lowland has a warm climate, but as we go north the temperature gradually becomes lower until we reach New England. In the coastal lowland of New England the winters are moderately cold and the summers are warm. The Appalachian Mountain belt varies from mild winters in North Carolina to

severe winters in the Adirondacks and in the mountains of northern New England. Sometimes the temperature is 40° or more below zero during the winters in the Adirondack region.

In Louisiana the Mississippi Valley has hot summers, but is liable to frosts from November to March. As we go north we find greater extremes of heat and cold, and in some parts of Minnesota the temperature ranges from 102° above to 45° below zero.

The Pacific coast usually has mild summers, with warm, pleasant winters in southern California, and mild winters in western Oregon and western Washington. This is because the winds that blow from the ocean over the lands are warmer than the land in winter and cooler than the land in summer.

In the interior, the temperature of the Cordilleran highlands varies according to latitude and altitude. Thus the lowlands in the southern part of the Great Basin and in the southern part of Arizona are among the warmest regions in the United States, sometimes reaching a temperature of 125° on the hottest days. The high plateaus in Utah and other states to the north are much cooler. The higher parts of the Rocky Mountains, of the Wasatch Mountains, of the Cascade Range, and of the Sierra Nevada have snow or ice in some places throughout the year. There is often a very great difference between the day and night temperatures of dry regions, the temperature frequently falling so low at night as to cause frosts in summer.



Fig. 71. Average length of crop-growing season in the United States—number of days without killing frost

U.S. Dept. of Ag.




Fig. 72. Average annual rainfall in the United States

59. Growing Period.—Figure 71 tells the conditions of heat and cold in the United States by the number of days during the year in which crops can grow in the different parts of the country. Each line passes through places that have about the same number of crop-growing days.

In the far south, along the Gulf of Mexico, are lands in which growth takes place for 260 days or more; that is, about nine months or longer each year.

Trace the line of 200 days. South of this are nearly all the southern states, where crops can grow for about seven months or more.

Trace the lines that mark 150 days. See what effect the Great Lakes have in lengthening the growing season about them. Compare Lake Ontario shores, with 170 days of growth, with a small region on the boundary of New York and Pennsylvania, with only 130 days. This region is away from water and on high ground. Part of northern Michigan has 100 days, while to the north, on the shore of Lake Superior, there are 140 days.

Find the regions in which frosts are rare and the regions where the possible crop-growing season is less than 90 days.

60. Rainfall.—The rainfall is to be carefully studied in connection with the map (Fig. 72). Rainfall is measured by catching the rain in a vessel with vertical sides and measuring the depth of the water. If the moisture falls in the form of snow, the snow is melted and the measure of the water thus obtained is added to that of the ordinary rainfall. By adding the amounts for each storm the number of *inches of rainfall* for a year is found. The figures and shadings of the map show the annual rainfall in inches.

Where the annual rainfall is more than 50 inches a year, it is considered large. If it is more than 20 inches, it is nearly always enough for good crops. Where it is less than 20 inches, most crops need to be irrigated or to be cultivated in special ways. Where

it is less than 10 inches, the region is *arid*, and such regions are usually called deserts.

In Figure 72 observe the line running through Texas, western Kansas, and the eastern half of the Dakotas. All the country east of this line has more than 20 inches. The moisture that produces this rain comes mainly from the Gulf of Mexico and from the Atlantic Ocean. The lands near the ocean have the most rain, and a region far inland has the least. The places that have more than 60 inches are on the Gulf Coast and in the highest parts of the Appalachian Mountains in North Carolina and adjoining states. The large rainfall helps to explain the heavy forest in these regions. The belt of more than 50 inches reaches from eastern Texas to Virginia. Trace on the map the rainfall belts as follows: 40–50 inches, 30–40 inches, 20–30 inches.

In the western United States the heavy rainfall is along the coast and more to the north. There is a region of heavy rainfall extending from central California to Canada along the Coast Ranges, and a larger region extending through the Sierra Nevada and the Cascade Range. The moist, warm air of the Pacific Ocean moves in the westerly winds up into the mountains, where it is chilled as it rises, so that the vapor condenses and falls as rain or snow. In these mountains there are heavy forests and the largest trees in the world. East of the Sierra Nevada and the Cascade Range most of the country has less than 20 inches, until we come to the line running through Texas, Kansas, and the Dakotas. The winds that have crossed the mountains are warmed as they descend and are prepared to take up moisture. A large area in the Great Basin and in southern Arizona has less than 10 inches, and is a true desert (Figs. 72 and 73). As the winds rise again in crossing the high mountains farther inland some of their moisture is condensed, so that there are regions in the Wasatch and Rocky Mountains having more than 20 inches.



Fig. 73. Desert in Arizona, nearly 300 miles from the Pacific Ocean

At the same time the air is sultry or muggy. It is not only hot, but *humid*; that is, full of moisture. The winds, when they spring up, may come from the south, southeast, or southwest. Clouds may overspread the sky and rain begin to fall. Often the rain comes in a thunderstorm. Cloud masses or "thunderheads" rise, and then the storm bursts with vivid lightning and long peals of thunder. The succession of thunderstorms or the quiet rains may cover an area hundreds of miles across.

The eastern part of the country receives its moisture from the Atlantic Ocean and the Gulf of Mexico; the western part receives moisture from the Pacific Ocean; and both in the east and in the west we find less rain as we go from the coast to the interior.

61. Storms of the Westerly Winds.—In all the northern parts of the United States, and in much of Canada, the winds, while they frequently vary, blow more often from the west, northwest, or southwest than from other directions. Many trees in open fields incline eastward, and we must usually look to the winds for an explanation.

If we watch a vane upon a church spire or upon a barn for a number of weeks and record its direction once or twice each day, we shall see that the wind blows from the west or southwest more often than from any other direction.

Most of the storms in the temperate zone in North America come in connection with these prevailing westerly winds. As such a storm approaches a place the air grows warmer, and in summer sometimes becomes very hot. The thermometer may stand at 90° , 100° , or even higher. A temperature of 100° is 2° warmer than our bodies, and makes us very uncomfortable from the heat.


As the storm or the succession of storms, which may last a day or more, passes by, the wind changes to the northwest, the air becomes cooler, the clouds disappear, and a period of clear weather follows. We say that a *hot wave* has been followed by a *cool wave*.

Similar changes come in the winter. A south wind blows, the air grows warmer, and the sky becomes cloudy. In the northern states at this time snow usually falls instead of rain, though sometimes there is a "break-up" and rain falls even in midwinter. People in some sections look for what they call the "January thaw." In the winter, as in the summer, the storm passes by, the wind changes to the northwest, the skies clear, and cooler weather follows. It is the "cold snap," or "cold wave," and the thermometer in some regions may indicate many degrees below the zero point.

62. The Cyclone.—All this the student can observe for himself, and he is now ready to learn a little more fully the meaning of what he has observed. In the temperate parts of the United States and of Canada the atmosphere is like a sea of air moving eastward over the land. In this moving sea of air there is often a large region in which the air is warmer and lighter than the sur-

rounding colder air. The result is that the colder air pushes in from all sides along the ground, and pushes up the lighter, warmer air. This pushing in from all sides means that winds blow toward the center from all directions, making a kind of whirl in the general eastward movement. Such an area is known as a *cyclonic area* (central part of Fig. 74). It usually appears in the northwestern states and western Canada, moves eastward through the northern states, along the Great Lakes, and passes on across the Atlantic Ocean.


The warm, moist air of the cyclonic area cools as it rises, and the moisture is condensed and falls as rain or snow.



The direction of the winds in the forward-moving cyclone does not change (Fig. 74, A). As the cyclone approaches and passes the place where we are living, we notice changes in the direction of the winds because we are, from time to time, in different parts of the cyclonic area. Around

the central part of the storm area the winds may be changeable and violent. When the center of the area passes to the east, the winds are from the northwest or west, the clouds pass off, and the weather is clear and cool.

These are the storms of the westerly winds, and they are frequent. They nearly always pass eastward over about the same regions, and the line of their movement is



called a storm track. Telegraphic reports show where the cyclonic winds and rains are at a given time, and how fast they are moving eastward. It is therefore possible to tell when a storm now in North Dakota is likely to arrive in the region of Lake Erie or over New England.

63. Weather Bureau.—It is often very important that farmers, sailors, and others should know about the approach of storms and about the changes in temperature and rainfall that may come. For this purpose the United States Weather Bureau has been formed. It has a central office in Washington, and there are local offices at many other places, as well as many observers scattered over the country.

Each day each observer records the temperature, the pressure of the air as told by the barometer, the rainfall, the direction of the winds, and the condition of the sky, and he reports these facts to one of the offices of the Weather Bureau by telegraph. In these offices expert students compare the facts from all parts of the country, plot them on a map, tell where the storm areas are, and send out to the newspapers and to many public institutions the weather report for the day. It is the movement of the storm areas that enables the weather observer to forecast what the weather is likely to be for a day, or two or three days, in advance. People who profess to foretell the weather for a long time ahead are not to be trusted.

64. Summary.—Three important subjects have now been studied concerning the climate of the United States. The first is temperature, depending on latitude, altitude, and relation to the sea, and showing great differences in the length of the crop-growing period in various parts of the United States. The second is the rainfall, which in most regions is enough for crops, but in some is so light that the land is a desert (Figs. 72 and 73). The third is the prevailing movement of the atmosphere in the temperate regions, from west

to east, broken by the great whirls of wind and rain or snow, known as cyclonic storms. As we study the different parts of the United States, we shall learn other facts about climate.

Review. 1. Give definitions of *weather* and *climate*. 2. What conditions control climate?

3. What region has a growing period of 300 days in each year? A period of 150 days? Of 100 days? 4. How many degrees of latitude between the first region and the last? 5. Why does the temperature of these two regions differ?

6. How is rainfall measured? 7. What would be called a large rainfall? 8. Compare the rainfall along the Atlantic coast with the rainfall east of the Rocky Mountains and give the reason for the difference. 9. Where are the areas of the largest rainfall in the United States? 10. What is the rainfall of your own state?

11. Describe a "storm of the westerly winds." 12. What is a "cyclonic area"? What is the usual course or track of such storms in the United States? 13. Explain the work of the United States Weather Bureau. 14. From what station of the Weather Bureau does your town receive the daily weather map?

GROWTH OF THE UNITED STATES

65. The Original Colonies.—The original thirteen colonies lay along the Atlantic Lowland, but they claimed lands extending westward across the Appalachians. After the American Revolution, Great Britain gave up to the United States all the land lying east of the Mississippi River, from Canada to the Spanish colony of Florida (Fig. 76). Most of the people were east of the Appalachians. To the west of the Appalachians there were few settlements, and most of the unoccupied land was given to the United States by the states that had claimed it.

66. Louisiana Territory.—In 1803 the Louisiana Territory was bought from France. The present state of Louisiana is but a small part of this territory, which extended northward to Canada and northwest from the Mississippi River to the Rocky Mountains. What states are wholly or partly included in the "Louisiana Purchase" (Fig. 76)?




Fig. 76. Acquisitions of territory, 1783 to 1853

67. Spanish Territory on the Gulf of Mexico.—In 1819 Florida was bought from Spain. This gave the United States the Gulf and Atlantic coast line from the east border of Texas to the east border of Maine. In 1836 Texas separated from Mexico and became an independent republic. In 1845 it was annexed to the United States, and the Rio Grande became part of our southern boundary.

68. Oregon Territory.—For a long time the land of the present states of Idaho, Washington, and Oregon was part of the "Oregon Country" claimed by Great Britain; but in 1846 this region became the property of the United States. Then for the first time the United States reached from the Atlantic to the Pacific and had harbors and outlets for foreign trade on two oceans.

69. California.—The lands west of Texas and south of Oregon, including California, the Great Basin, and the Colorado Plateaus, were acquired from Mexico in 1848, and a small tract on the

control of the Canal Zone was acquired from Panama. Three of the Virgin Islands were purchased from Denmark in 1916.

The original United States in 1783 contained 892,135 square miles. The lands which are now under the American flag make a total of about 3,800,000 square miles.

71. The Westward Movement.—In 1790, or seven years after the treaty of peace was made with Great Britain, the first *census* of the United States was taken. This counting of population, and of the products of industry, has been made by the government every

ten years since that time. The first census showed that there were 3,929,214 persons in the United States. Most of them lived within 200 miles of the Atlantic coast, and mainly on the Atlantic lowlands. A few had pushed into the valleys among the mountains. West of the mountains, the largest settlements were in the region of Pittsburgh, and in Tennessee and Kentucky along the Cumberland and Ohio rivers (Fig. 77).




Fig. 77. Where the people lived in 1790



Fig. 78. A prairie schooner on the dry plains

As the population of the Atlantic states increased, many left their old homes and sought larger opportunities for themselves and their children in the unoccupied lands farther west. They went on foot or with wagons, carrying a few household treasures to start new homes in the "West." Many went by the Mohawk Valley and along the plains south of Lake Ontario and Lake Erie. Others went from Philadelphia to the Ohio River at Pittsburgh, and there built rude houseboats and floated down the river to take up land and make a home.

72. New States.—So many people settled west of the Appalachians that new states were formed and admitted to the Union, joining the thirteen original states. In this way Kentucky was admitted in 1792, Tennessee in 1796, Ohio in 1803, five other western states in 1812–1819, and Missouri, the first new state entirely west of the Mississippi, in 1821. Iowa, just north of Missouri, did not become a state until 1846. This is within the memory of men still living, and shows how young some of the states are; for nineteen are younger than Iowa.

Up to this time there were few white men in the far West. In 1848 gold was found in California, and there was great excitement in the East. People went west by thousands. Some traveled by wagons, called

prairie schooners, across the dry plains and through the mountain passes (Fig. 78). Others went by way of Panama, or sailed around Cape Horn, in the great rush for gold. At the end of 1849 California had more than 100,000 people, and in 1850 it was admitted to the Union as a state,—the first one in the Cordilleran region.

73. Immigration.—Many of the people who have spread over our country within the past one hundred years are the descendants of the pioneers of the Atlantic coast. They are therefore of English, Scotch, Irish, Dutch, or German blood. Millions of people, mostly in the last fifty years, have come directly from Europe,—from Great Britain, Norway, Sweden, and Germany in the north, from Russia in the east, and from Italy, Hungary, and other nations in the south.

More than ten million of our people are descendants of negroes brought from Africa.




Fig. 79. Distribution of population in 1850

74. Where the People Now Are.—By *density of population* we mean the number of people living on a square mile of land surface. When we speak of the density of population of a country or state, we mean the average number of people per square mile. For example, there are parts of Chicago or New York where tens of thousands of people occupy a square mile, and there are square miles in the Adirondacks or in the Rocky Mountains, or on the dry plains, where not a single person lives.

The map (Fig. 80) gives the average density, by counties and by states. The density for the whole country is 35. Study the explanation of the different shadings and of the numbers. Rhode Island has the greatest density, 566. Nevada has the least density, or 1. Observe that all states having more than 100 persons to the square mile are east of the Mississippi River and north of the Ohio and Potomac rivers. Pick out, in their order, the five states that have the greatest density of population. What states east of the Mississippi River have fewer than 50 people per square mile? Divide the country into three sections, of which one has great density, another has medium density, and the third a scattered population.

States may have few people because they are young and have lately been settled. Thus some states of small density west of the Mississippi River will have many more people as they grow older and the water, soils, and minerals are more fully used.

75. Industries of the United States.—The growth of our country's industries has been no less marvelous than the growth of its territory and its population.

To-day the United States ranks first among the countries of the world in the production of corn, wheat, cotton, and tobacco. Fig-





Fig. 80. Distribution of population in 1920

ure 81 shows in what parts of the country each of these crops is chiefly grown. Many other crops are grown, and the United States is a large producer of apples, peaches, lemons, oranges, and other orchard and smaller fruits.

Our country also produces more coal, iron ore, petroleum, copper, and silver than any other country in the world, and stands second only to South Africa in the production of gold. Figure 81 shows the location of the different mineral regions in our country.

In the animal industries the United States is next to China as a producer of swine, ranks second to India in the number of cattle, and is exceeded only by Australia and Argentina in the number of sheep. In its fishing industries its annual catch is nearly equal to that of Great Britain, which ranks second to Japan.

The raw materials above mentioned, with others imported for the purpose, have led to the development of great manufacturing industries, especially in the northeastern section of the country. The growth of manufacturing has led to the concentration of laborers and the development of cities and villages. More than half of the population of the United States is in cities or villages of more than 2500 inhabitants.



REFERENCES

- Corn
- Wheat
- Cotton
- Tobacco
- Coal
- Petroleum
- Iron Mines
- Gold
- Copper
- Silver
- Zinc
- Lead
- Manufactures
- Railroads
- Steamship Lines
- Fisheries




Fig. 81
Industrial
UNITED STATES
Showing
PRINCIPAL PRODUCTS, RAILROADS
AND STEAMSHIP LINES

Capitals of Countries thus: ☉

Capitals of States thus: ⦿

Scale of Statute Miles

0 50 100 200 300

252 MILES TO ONE INCH

COPYRIGHT, BY AMERICAN BOOK COMPANY.

THE MATTHEWS-NORTHUP WORKS, BUFFALO, N. Y.




Fig. 82. Railroads of the United States

The cities are connected by a network of railroad lines which make easy the trade between the various parts of the country, and the United States now has a far greater railroad mileage than any other country in the world (Fig. 82).

76. Foreign Trade.—The United States is to-day the chief trading nation of the world.

In the early days the ships that left our ports were laden with food supplies and raw materials needed by the industrial population of Europe. In recent years, however, in spite of a constant and rapid increase of foreign commerce, most of our food supplies are consumed at home and our raw materials are largely manufactured in our own factories. Cotton is the only raw material that is still exported in very large quantities, but we export also much coal, tobacco, petroleum, and timber. At the same time the exportation of manufactured goods ready for use has enormously increased.

In imports similar changes may be noted. The importation of foodstuffs has remained about the same for many years, but the importation of manufactured goods has greatly

decreased, while the importation of raw materials for use in our own factories has greatly increased. Our imports include coffee, sugar, rubber, silk, and a great variety of other products. The American nation is no longer selling merely its raw materials. It is, instead, using them to give employment to labor in its factories, and the products of these factories find a ready

sale in foreign as well as in domestic markets.

The recent war in Europe caused an enormous increase in the manufactures, ship-building, and commerce of the United States, especially the trade with European countries.

Review.—1. What was the extent of our territory at the close of the American Revolution? 2. Give an account of the Louisiana Territory and its purchase. 3. Give the date of the annexation of Texas. 4. When was the Oregon region acquired? 5. What lands were bought in 1848? 6. What was the population of the country at the first census? 7. Give the date of this census. 8. What were the first states formed west of the Appalachian Mountains? 9. When was gold first found in California?

10. What is meant by *density of population*? 11. What is the density in Rhode Island? In Iowa? In Nevada? In your own state?

12. In what crops does the United States rank first among the countries of the world? 13. Which parts of the country produce corn? Cotton? 14. What regions yield gold? Silver? Coal? Iron ore? Petroleum? Copper?

15. Which part of the country has the most railroads? On the railroad map point out the location of the Appalachian Mountains; the Rocky Mountains; the Sierra Nevada; the Coast Ranges




Fig. 83. On the coast of New England

© Detroit Photographic Co.

THE NEW ENGLAND STATES

77. Early Settlement.—It was not long after the voyages of Columbus (Sec. 34) that several of the nations of Europe became interested in the exploration and settlement of the New World that he had discovered. Expeditions were sent out from France, England, the Netherlands, and Spain, and soon the governments of these countries began to claim as their own those parts of North America that their seamen had explored.

That portion of our country now called New England was one of the parts of the continent claimed and settled by people from England, as its name suggests. They had left their homes beyond the sea because they wished to worship in the way they thought right. This they had not been permitted to do in their old homes. To enjoy this right they were ready to endure any hardship and to work with all their strength in the new land, and they had need of all their courage.

The coast of this part of our continent is, for the most part, exceedingly rugged, and to those first settlers it must have been very forbidding. The land was covered with dense forests. The climate they found to be much more severe than that of the mother country, and there was a native population that soon became unfriendly. It was only after many years of toil and suffering that the people finally won safety and comfort.

In the years that have passed since then, the population has increased enormously, especially in the southern states of the group, and New England is now one of the richest and most populous parts of our country. The chief industry of the first settlers was agriculture, and most of the manufactured articles needed were made at home or brought from across the sea. Now the chief industry is manufacturing, and agriculture is of secondary importance.

N




Fig. 84

Physical and Political NEW ENGLAND STATES

Scale of Statute Miles
0 10 20 30 40 50 60 70 80 90 100
58 MILES TO ONE INCH

Capitals of States thus: ●

ELEVATIONS IN FEET

- OVER 5000
- 2000 TO 5000
- 1000 TO 2000
- 500 TO 1000
- SEA LEVEL TO 500

THE MATTHEWS-NORTHROP WORKS, BUFFALO, N.Y.

COPYRIGHT, BY AMERICAN BOOK COMPANY

Longitude West 70° from Greenwich.



Fig. 85. In the Berkshire Hills

THE NEW ENGLAND STATES

	AREA, Sq. Mi.	POPULATION, 1920	CAPITAL
Maine	33,040	768,014	Augusta
New Hampshire	9,341	443,083	Concord
Vermont	9,564	352,428	Montpelier
Massachusetts	8,266	3,852,356	Boston
Rhode Island	1,248	604,397	Providence
Connecticut	4,965	1,380,631	Hartford

city on each of them. 19. Make from memory a sketch map of this group, showing state boundaries, chief rivers, and state capitals.

LAND AND PEOPLE

78. Surface.—New England has a hilly lowland near the sea and a hilly upland in the interior, with mountains in the north and west.¹ Some of the hills of the lowland are rocky, but many consist of glacial waste piled into hills and ridges of various forms.²

The upland in central and western Massachusetts and northern Connecticut is a plateau varying from 900 to about 2000 feet in altitude, and having a hilly surface. The streams have cut deep valleys into the plateau. A good example is the Connecticut Valley, which in Connecticut and Massachusetts is not far above sea level.

The upland in western Massachusetts, known as the Berkshire Hills, is in some places quite mountainous (Fig. 85).

Farther north, in Vermont, are the Green Mountains, a range extending north and south, with many ridges and peaks.

In New Hampshire are the White Mountains (Fig. 86), some of whose peaks are named after former presidents of the United States. The highest point is Mt. Washington. A cog railroad ascends to its rocky summit, which stands out above the timber line. From it, one can see the ocean and look far into Maine and Vermont.



Fig. 86. White Mountains; Mt. Washington

Map Study.—1. Which of the New England states border the Atlantic Ocean? 2. Which border New York? 3. Name the largest state and the smallest of the group. 4. What lake lies between Vermont and New York? 5. Trace the course of its outlet.

6. Locate Cape Cod. 7. Where is Narragansett Bay? Cape Cod Bay? Massachusetts Bay? Casco Bay? 8. Give the position of Marthas Vineyard, Nantucket, and Mt. Desert islands, and indicate to what state each belongs. 9. What body of water is south of Connecticut?

10. Where are the Berkshire Hills? The Green Mountains? The White Mountains? 11. Locate Mt. Washington and give its altitude. 12. Name and locate the largest lake in New Hampshire; in Maine.

13. Trace the course of the Connecticut River. 14. Use the scale of miles and give the length of this river. 15. Have you heard of any of the cities or towns on its banks? 16. What river is partly in New Hampshire and partly in Massachusetts? 17. Name the three chief rivers of southern Maine and trace their courses. 18. Name an important




Fig. 87. Lakes in southern Maine

79. Lakes and Swamps. ¹Lakes are common in New England; in fact, there are several thousand. ²Some are small ponds across which one could throw a stone, while Moosehead Lake, in Maine, is 35 miles long, and Lake Winnepesaukee, in New Hampshire, is 20 miles in length. ³There are also many lakes in most of the northern states and in Canada, — and indeed throughout the world in regions that were covered by ancient ice sheets. On the other hand, there are few lakes in the southern states, which were beyond the southern border of the ice sheet.

The glacial waste was often spread very unevenly, leaving basins that would hold water. Some of the old valleys, made by rivers long before the ice invasion, were blocked by piles of waste, called *moraines*. Behind these moraines, which served as dams, water gathered and formed lakes. In some places the ice rasped the solid rock so hard that it dug basins which are now occupied by lakes.

Many lakes are shallow on their edges, if not over their whole area. Mud is deposited on the lake bottom, and grasses, weeds, and mosses grow in the shallow places, thus gradually changing the lake into

swamp lands. Some swamps, however, have never been lakes, but are in low or flat places from which the surface streams cannot drain off the water. In many swamps in New England, *peat* is found. ⁴Peat is formed from mosses, leaves, and trees that grow or lodge in swampy places, where the moisture keeps them from decay. ⁵If there is not enough water to preserve the vegetation from decay, it may form a deep layer of black soil, or *muck*, such as is found in many swamps.

80. Uses of Lakes. ¹The facts about the lakes of New England are true of the greater number of lakes in various parts of the world. ²Such bodies of water are useful in many ways. They serve as reservoirs to hold back the rain waters and prevent floods. ³Rivers with a steady flow are much more useful for water supply, for water power, and for navigation. ⁴The larger lakes are especially important for navigation and for supplies of fish. Along lake shores also there are attractive places where the people of city and country can find rest and amusement.

81. Rivers. ¹In general, the rivers of New England flow southward. ²The following, which are the most important, should be traced on the map (Fig. 84): the Connecticut, Merrimack, Androscoggin, Kennebec, and Penobscot. Three facts should be noted about New England rivers: ³

(1) They are in a region of rains and snows, and they are fed by many lakes. Hence there is a constant supply of water.

(2) Many of the rivers have rapids and waterfalls formed where they descend to a lower level or where glacial waste has choked their ancient channels. This makes them useful in the manufacturing industries, because dams can be built and the waters taken out

in raceways for turning water wheels. The falls at Holyoke on the Connecticut River, and at Manchester and Lowell (Fig. 88) on the Merrimack River, are examples.

(3) On the shore the ocean waters slowly rise and fall twice in each period of about twenty-five hours. These changes of the water level are known as *tides*. Several of the larger rivers of New England are affected in their lower courses by this rise and fall of the tides.¹⁰ Such parts of rivers are said to be *tidal*. The Connecticut River is tidal for 40 miles inland, to the city of Hartford.¹¹ Since the water is deep and flows quietly, ships can sail in the lower river below Hartford; but above that city the river is not navigable.¹² Therefore Hartford is said to be at the *head of navigation*. Several of the larger rivers of Maine have falls at the head of their tidal channels. At these places cities have grown up, having the double advantage of water power and navigation. Bangor is an example.

82. Shore Line.¹³ Much of the New England shore line is very uneven and rugged.¹⁴ There are long and rocky headlands, or *prom-*



Fig. 88. Dam on the Merrimack River at Lowell

ontories, with deep, narrow bays between. In a direct line it is a little over 200 miles along the coast of Maine from the New Hampshire boundary to Eastport, but the actual shore line of Maine, including all the windings and the shores of the islands, is about 2000 miles long.

From Boston southward, toward Cape Cod, the shores are rocky in places; but along the cape there are long stretches of sandy beach. Most of the cape is built of glacial waste, and some of the hills are of sand, blown and heaped up by strong winds.¹⁵ Such sand hills, or *dunes*, are found on the shores of many seas and lakes.¹⁶ At the tip of Cape Cod, where the sand is sometimes blown into the fields and gardens, the government has planted grasses (Fig. 89) and trees on the dunes to keep the sand in place.¹⁷ Such *sand binding* is done in many countries where the shores have drifting sands.¹⁸

The southern shores of New England are irregular. Note the branches of Narragansett Bay in Rhode Island, and the bays and tidal river channels of Connecticut (Fig. 84).




Fig. 89. Grass planted on Cape Cod to keep the sand from blowing away

Marthas Vineyard and Nantucket, islands off the south shore of Massachusetts, are built of sands, gravels, and clays, and their surface and materials are much like those of Cape Cod.

The deep, narrow bays and tidal river channels were carved out by the rivers when this part of our continent was higher above sea level than it is now. Later the land slowly sank, and the sea water flowed into the lower ends of the valleys and between the hills along the shore. It flowed completely around some hills and turned them into islands. River valleys that have been filled with sea water in this way are called *drowned valleys*.

83. Climate.—The early settlers in New England were surprised and disappointed by the severity of the climate. They were about 600 miles farther south than at their old homes in England, but instead of finding a mild and even climate in the new home, they found greater cold in winter and greater heat in summer. They did not know that in New England the prevailing westerly winds make the climate continental (Sec. 27), while in England the west winds make the climate oceanic, with cooler summers and warmer winters.

Northern New England is colder than southern New England because of differences in altitude, in latitude, and in nearness to the sea. In the woods of Maine and in the uplands of New Hampshire and Vermont the winters are long, and there is a heavy cover of snow. Thick ice is formed on lakes and streams, and is cut and stored for summer use. The snow in the woods makes excellent roads for the lumbermen who cut logs and haul them to the streams. In the spring

the snows melt and cause floods which float the logs down to the mills and to market. Along the coast, especially in the south, there is far less snow, and there is little sleighing. When the winds blow from the southeast in winter, they come from the warmer sea, and there is usually much moisture. A "northeaster" is dreaded because it comes from colder seas and is therefore intensely cold. The winds of such a storm are often violent and cause many shipwrecks.

Climate is even more important than soils in determining what crops will grow. The latest killing frost in spring, in New England, is likely to come late in April along the southern shores, and late in May in the north. The earliest killing frost in autumn varies from the middle of September in the north to the middle of November in the south. The average length of the crop-growing season is six months in the south

and four months in the north, along the Canadian border. Thus New England has great variety in its climate.

84. Population.—The six states of New England are small in comparison with most other states. They are together about one and one half times as large as New York, and one fourth as large as Texas (Fig. 90). Their population at the time of the Fourteenth Census, in 1920, was nearly seven and one half millions. The three states of southern New England are much more thickly populated than the three states to the north, and more of their people live in cities and engage in manufacture and trade. The density of population for the several states is shown in Figure 80. For a long time most of the people of New England were descendants




Fig. 90. Comparison of areas

of Englishmen, but in recent years many people from other lands have gone there to make their homes and engage in business.²⁴

Review. 1. Where are the lowlands of New England? The highlands? 2. What is the character of the hills in the lowlands?

3. Why has New England many lakes? 4. What do we find in place of some lakes of former times? 5. What is peat? 6. In what ways are lakes useful?

7. Why is the flow of New England rivers constant? 8. What is the cause of the rapids and falls in the rivers? 9. Name cities at which the falls are used for power. 10. What is a tidal river? 11. Name some New England rivers that are tidal in their lower courses. 12. What is the head of navigation on a river?

13. What is the general character of the New England shore line? 14. How does the shore of Cape Cod differ from that of Maine? 15. What are dunes? 16. What is sand binding? 17. What has made the southern shore line of New England so irregular? 18. Where an irregular shore line is formed in this way, what happens to the lower ends of river valleys?

19. How did the climate of New England bring disappointment to the first colonists? 20. What are the coldest parts of New England? For what reasons? 21. Describe the winters in northern New England. 22. What are the usual limits of the growing season in southern New England?

23. What is the density of population in Maine? In Rhode Island? Massachusetts? Connecticut? 24. Why should there be more people in southern than in northern New England?



Fig. 91. Boulders left by the glacier



Fig. 92. The Connecticut Valley

AGRICULTURE AND MANUFACTURE

85. Soils.—The ancient ice sheet spread over all of New England (Sec. 32). The ice stirred up the ancient soils that covered the land before the glacial time, and mixed with them much crushed rock and many stones (Sec. 31). On some hilltops and mountain summits nothing was left but bare rock. As New England has so many hills and mountains, the soil is thin over much of the country. Many of the stones brought by the glacier were large boulders, which were left on the surface (Fig. 91). The steep slopes, thin soils, and boulders are not favorable to the growth of crops nor to the use of many improved farming implements such as gang plows, grain drills, and harvesting machines.

Much of the good land is along the rivers and in the lowlands near the seashore. In Vermont and New Hampshire, the Connecticut Valley is narrow and has little farm land. But in Massachusetts and Connecticut the river flows through a broad lowland which has a good soil and a surface favorable for agriculture (Fig. 92).

86. Agriculture.—In the early days, New England was chiefly a farming region, and produced its own grain and meat. But when the rich soil of the states farther west was




Fig. 93. Milk wagons and trucks, Boston

brought under cultivation, general farming in New England became less profitable and began to decline. Some stony or steep fields have been allowed to grow up again to forest.

This does not mean that there is little agriculture in these states. Much land is tilled, and it is cultivated with great care. The towns and cities need vegetables. Hence market gardening is a flourishing industry. All the common hardy small fruits are raised, and many farms and small plots are used for dairying and poultry raising.

Railroad trains bring milk every day to Boston and many other large cities from nearly all parts of New England. The milk is then distributed by wagons and automobiles (Fig. 93). Hay, oats, and corn are grown in large quantities because forage crops are needed for horses and for herds of cattle.

Besides meeting these home needs, some special crops are raised where soil and climate are suited to them. Tobacco raising is an important industry in the southern part of the Connecticut Valley. The broad leaves of the plant as it grows in the fields, and the large barns for drying the crop, are a common sight in that region. Cranberries need swampy ground, and are raised on Cape Cod and in the adjoining region. The raising and canning of green corn and the growing of potatoes are extensive industries in Maine.

87. Manufacturing.—Several causes have made New England a manufacturing region. (1) There is much water power, the cheapest kind of power man uses. When the mill site has been bought, the dam built, and the water wheels put in place, the water of the stream from year to year costs nothing. When steam is used, the coal must be mined and usually must be carried long distances, which is expensive. In many cities of New England there is so much manufacturing that more power is required than the rivers can furnish. Coal is used for power, and comes by railroad from Pennsylvania and other states to Atlantic ports, where it can be loaded into barges (Fig. 94). These barges are towed by powerful tugs to Providence, Fall River, New Bedford, Boston, and other seaports of New England.

(2) New England is on the sea border, and has good harbors and extensive railroad systems. It can readily get the raw materials it needs, such as cotton, leather, and iron, and can readily send its goods to market.

(3) The invention of machinery accounts for the growth of manufactures, not only in New England, but also in other regions. In the early days, spinning and weaving were done by the women of each household, and the village cobbler made shoes by hand. But labor-saving machinery has been invented, most of it during the last hundred years, so




Fig. 94. Loading coal barges by machinery

that now one man can accomplish more than many men in the days of our ancestors.

This is true in agriculture and transportation as well as in manufacture. Ninety years ago it took 160 hours of one man's work to raise 50 bushels of wheat. Now not more than 8 hours of labor are required, because of the great plows, drills, and harvesters that are used. In 1865 it took 222 hours of work to make 10 pairs of men's high-grade calfskin shoes. With modern machinery, only 30 hours of work are needed to make the same number.

The chief manufactures of New England are cotton and woolen goods, leather goods, and a great variety of things made from the metals. Goods woven from cotton, wool, or other fibers are often spoken of as *textiles*.

88. The Cotton Industry.—More than one hundred years ago skillful men in England had invented machinery for spinning and weaving cotton. England did not allow any of these machines, or even any patterns of them, to be taken out of the country, because she wished to keep the business for herself. In 1789 Samuel Slater came to this country and settled in Rhode Island. Remembering how the English machines were made, he built some new ones, and in 1790 began to make cotton goods in Pawtucket, Rhode Island, a town which now has great cotton




Fig. 96. Machinery used in a textile school

mills. In this way cotton manufacture began in this country.

Most of the cotton used in New England is raised in the southern states. It is pressed into bales of about 500 pounds each and comes by ship from Savannah, Mobile, New Orleans, and Galveston to the New England ports. Some of these ports, as New Bedford and Fall River, have cotton mills, so that many of the bales are unloaded close to the mills, while others must be carried inland a short distance by rail.

Many people are engaged in the cotton industry. A single mill may employ several thousand workers. French people from Canada and people from various European countries have come in large numbers to work in the mills. Textile schools have been established in New Bedford, Fall River, and Lowell, to prepare skilled workers for the industry (Fig. 96).

Calicoes, ginghams, and other cotton fabrics are made; also knit underwear, stockings, towels, handkerchiefs, and thread. From the mill the finished goods are sent to the wholesale and retail merchants in all parts of the United States, and to many foreign countries.

The great cotton-manufacturing centers of New England are New Bedford, Fall River, and Lowell in Massachusetts, Manchester in New Hampshire, and Pawtucket in Rhode



Fig. 95. Weaving cotton cloth, Lowell, Mass.

Island. There are large mills also in Taunton, Massachusetts; in Nashua, New Hampshire; in Lewiston, Maine; and in many other cities and towns.

89. The Woolen Industry.—Woolen manufacture in New England began long ago on the home farms. Later small mills were built in villages along the streams, and now much of

of Pennsylvania and Wisconsin. Boston is the principal market for hides and leather. The hides come from the western states and from many countries in Europe, Asia, and South America.

Many common articles, such as traveling bags, pocketbooks, and harnesses, are made from leather, but its greatest use is for boots

and shoes. In early days these were all made by hand, but now they are turned out very rapidly by machinery (Sec. 87). The region around Boston is the largest center for the manufacture of boots and shoes in the United States, and there are also factories in southern New Hampshire, especially in Manchester. The more important seats of the shoe industry in Massachusetts are Brockton, Lynn, Ha-

verhill, and Boston. More than three fourths of all the business in Brockton and Haverhill is of this kind. Many shoes are now made in New York, St. Louis, Rochester, Cincinnati, Milwaukee, and Philadelphia. American shoes are known for their excellence, and are sold all over the world.

91. Metal Manufactures.—No coal and not much iron is mined in New England, but large quantities of both are needed in the manufacture of steel rails, steel bridges, or the steel frames for tall buildings. Hence such things are not largely made in New England, but in places like Pittsburgh, where coal and iron are easily brought together. But firearms and other smaller articles that do not require very much iron are made in great quantities both in Massachusetts and in Connecticut.



Fig. 97. Examining cloth in a woolen mill



Fig. 98. One room in a large watch factory, Waltham, Massachusetts

the industry is concentrated in great mills in a few cities. At first the wool came from the New England farms, but now most of it is brought from the western states and from Argentina and Australia.

Lawrence in Massachusetts, and Providence and Woonsocket in Rhode Island, are centers of woolen manufacture, but many of the cities that make cotton goods make woolen goods also. The weaving of carpets is an important branch of the woolen industry, and especial attention is given to making the finer kinds, such as Brussels, Axminster, and Wilton.

90. Boots and Shoes.—The tanning of skins is an old industry in eastern Massachusetts. Men who knew how to make leather were among the first comers from England. Tanning is still done in towns near Boston, but more is done in the states

The watchmakers in the factories at Waltham (Fig. 98), in Massachusetts, turn a small piece of steel into so many small screws or fine watch springs that it becomes worth thousands of dollars. With the steel they use brass and silver or gold, and turn out, ready for use, several thousand watches each day. In Providence, Rhode Island, and in Attleboro and other places in Massachusetts, much jewelry is made (Fig. 99). In many New England cities, particularly in Worcester, looms and other cotton and woolen machinery are manufactured. Wire making also is one of the industries of Worcester. In all these examples, — the watches, the jewelry, and the textile machines, — the amount of material used is small, but the time and skill required are very great.

The state of Connecticut has many factories in which small but valuable things are made of metals. Waterbury is a center for brass work, and for watches and clocks. Cutlery and silverware are manufactured in Meriden, and almost all kinds of hardware are made in various cities of the state, especially in New Haven, Bridgeport, Hartford, and New Britain.

92. Wood Pulp and Paper.—In the old days paper was made from rags gathered from homes and factories. For more than forty



Fig. 99. Jewelry factory in Providence




Fig. 100. A pulp and paper mill, Maine

years, however, much paper has been made from wood, and now all newspapers and most books and magazines are printed on such paper. So much printing is done that rags can supply only a small part of the paper needed. The softer kinds of wood are used, particularly spruce. Maine, New Hampshire, Vermont, and New York have much spruce, and these states have become important in the wood-pulp industries. Much wood pulp is also imported from Canada.

The trees are felled, the bark removed, and the trunks cut into blocks about two feet long. The mills (Fig. 100), which often make both the pulp and the paper, are in or near the forests, usually where a waterfall supplies power. All the large rivers of New England float the logs and supply the power for pulp mills. The pieces of wood are ground by heavy machinery or boiled in acid to separate the fibers and make the pulp. The acid process leaves the fibers longer and makes the paper stronger than the method of grinding the wood. One mill in Maine makes 350 tons of paper from wood every twenty-four hours.

We can follow the process from the woodman's ax to the pulp factory, the paper making machines, and to the printing establishments in great cities where the paper is used for books, magazines, and newspapers.



Fig. 101. A lake in the forests of Maine

Holyoke, on the Connecticut River in Massachusetts, has great paper mills and other industries, as the river here provides the largest water power in New England. The city is not near the forests, but the paper mills can thrive because the best grades of Holyoke paper are made from rags. Some of the rags come from New England mills, and some are imported.

All the paper used by the government for printing bank notes is made at Dalton in western Massachusetts.

We have now studied five kinds of New England manufactures, namely, cotton, woolen, boots and shoes, metals, and paper. Of these, paper is the only one for which the manufacturer finds much of the raw material at hand.

Review.—1. How did the ice invasion affect the soils? 2. Why is much of New England unfavorable to farming?

3. Compare the farming of former days with that of the present time. 4. How do towns and cities affect the work of the farmer? 5. What special crop is raised in the Connecticut Valley? 6. What crop is raised on Cape Cod?

7. Give the causes that have made New England a center of manufactures.

8. Who established the cotton industry in Rhode Island? 9. Where is most of the cotton raised? 10. Through what southern and what northern ports is it likely to come on its way from the plantation to the New England factory?

11. Where are textile schools established, and what is their purpose? 12. What is done with the cotton cloths, ginghams, and other fabrics after they are finished?

13. Name some of the centers of woolen manufacture. 14. What regions furnish most of the wool? 15. Name two kinds of woolen manufactures.

16. What is the chief market for hides and leather? 17. How has the making of boots and shoes changed? 18. What are the principal boot and shoe centers in New England? In other parts of the country?

19. What kind of manufactures of metals prevails in New England? Why? 20. What is the great industry at Waltham? 21. What metal industry is centered in Providence? 22. Name five Connecticut cities which have metal manufactures.

23. Give an account of wood pulp, the wood used, the process of manufacture, and the use of much of the paper. 24. Tell about paper making at Holyoke. 25. Where is the bank note paper of the government made?

OTHER INDUSTRIES

93. The Forests.—The early settlers found forests almost everywhere. Naturally they cleared the lowlands, the smoother and gentler slopes, and the lower hilltops. The rougher and higher ground was left in forest, and forms the "wood lots" of to-day. In northern New England in the Green and the White mountains, and stretching across Maine, there are still large forests (Figs. 101, 102).



Fig. 102. A hardwood forest in Maine

The leaves, mosses, and black soil of the woodlands hold much of the rain water and allow it to flow gradually into the lakes and streams. If the trees were all cut away, the rains and melting snows would rush down the steep slopes, making floods in the lower river valleys, and leaving the rivers with little water in the dry seasons.

The people are now learning the value of the forests, not only for lumber, but also for preserving the water powers and preventing floods. Our government is purchasing some of the White Mountain forest for a *reservation*.

Pine, spruce, and hemlock are important kinds of soft wood found in northern New England, and among the hardwoods are oak,



Fig. 103. Hauling sap from the trees to the camp

ash, maple, and birch. Lumbering is much less extensive than in former times, but is still an important industry in Maine and in parts of New Hampshire and Vermont. Much more lumber is now cut in the South and West than in New England, but, with proper care, the New England forests will always produce lumber for local use and supplies of firewood and pulp wood.

The forests furnish material for many manufactures. Among these are bobbins, spools, and crates and boxes for shipping to market the products of the mills. Pails, rakes, clothespins, toys, and many other common objects and novelties are made, and large amounts of lumber are used for building or are made into furniture.

Maple sugar is an important product of



Fig. 104. A lumber camp, New Hampshire

the forests in Vermont, which has first place in this industry. The sap of the sugar maple, in its first days or weeks of flow in early spring, is caught in buckets, and boiled in large kettles or pans until it forms sirup or sugar. The tapping of the trees in the "sugar bush," the gathering of the sap among the lingering snows (Fig. 103), the boiling and "sugaring-off" of the sugar camp, make an interesting chapter in the life of many Vermont farmers.

The forests affect the life of country and city in many ways. The lumber camp in the deep snows of winter is a place of hard toil and rough and ready fun (Fig. 104). The "driving" of the logs in the flooded streams of spring is a work of much hardship and danger (Fig. 105). Down the stream at some convenient point the logs are collected in a pond, and wait to be pulled into a mill and cut into lumber or made into wood pulp.

By a waterfall on some small stream a factory may be built to make spools or clothespins. Or, in some large town or city at tide-



U. S. Dept. of Ag., Forest Service

Fig. 105. Rafting logs in the Penobscot River

water, the lumber is not only sawed, but much of it is worked up into moldings, window frames, doors, or flooring, to be shipped to Boston or some other port. Bangor and Augusta in Maine are downstream from great forests and have water power for sawmills and factories; and they can ship lumber and its products directly by water.

94. Quarrying.—Many of the rocks of New England are so hard and so compact that they can be cut into blocks and slabs and used for building and other purposes. The most widespread and important rock in this region is granite, which is hard and enduring, and is used for buildings, for monuments and tombstones, and for paving and curbing. New England granites are usually of a gray color. There are large granite quarries in Milford and Quincy, Massachusetts; Westerly, Rhode Island; Barre, Vermont; and Concord, New Hampshire. There are many fine granite quarries in Maine.

Marble is quarried in the Green Mountains in Vermont, in the Berkshire Hills in western Massachusetts, and in Connecticut. The industry is largest in Vermont, which ranks first among the states in this product. Rutland and Proctor are the chief centers. Here enormous pits have been made by the removal of marble (Fig. 106), and great



Fig. 106. At the bottom of a marble quarry

yards and sheds are filled with the blocks to be dressed and made ready for shipment (Fig. 107). Marble is used for the walls of buildings, for interior decoration, and for tombstones. Being softer than granite, it is more easily shaped, and hence, from ancient times until now, has been much used by sculptors, especially to represent the human form.

Slate is a rather hard, fine-grained rock that splits into thin sheets or slabs, and is useful for roofing, for school slates and blackboards, and for mantels and other furnishings. Slate is quarried in western Vermont and in Maine. Red and brown sandstones are found in the Connecticut Valley, and were formerly used in the brownstone fronts of city houses, and for various building purposes.

Stone of all these kinds is shipped not only to towns and cities in New England, but also to other states. Many of the granites are quarried near the sea and go by ship. This is usually the cheapest way for any freight that is as heavy and bulky as stone. Nearness to large markets and good transportation facilities make quarrying a large industry in New England.




Fig. 107. Marble blocks ready for shipment, Proctor, Vt.



Fig. 108. Drying codfish at Gloucester

95. The Fishing Industry.—⁶The New England coast waters abound in fish, and a few hundred miles to the east are the shallows called the Banks of Newfoundland. Europeans have fished there for more than four hundred years. The region is crossed by steamers plying between America and Europe, and fogs and icebergs are dangerously common there.

Although fishing is still an important New England industry, some shore towns have changed their business from catching and packing fish to manufacturing. Sailors from New Bedford and Nantucket at one time went out on sailing voyages of three or four years to distant oceans to catch whales, but New Bedford is now best known for cotton mills, and Nantucket as a summer resort.

Boston and Gloucester are the great fishing centers of New England, and are among the greatest in the world. Several hundred schooners sail from New England ports to the Banks of Newfoundland, where cod and halibut are found. The fishing is done by means of dories, small boats that put off from the schooner,

each with one or two men. The fish are dressed on board and packed in ice, or salted, and the schooner, when loaded, returns to Boston, Gloucester, or it may be, to Portland or some other fishing center.

Cod and halibut live in waters of some depth and must be caught with hooks. Mackerel swim in schools through the surface waters and are caught with huge nets. Lobsters are caught in traps near the shore, especially along the coast of Maine. Oysters are common on the south shores, and many are shipped from shore towns. Along

the shores of Maine many small herring are canned and sold as sardines. The canning of fish and other sea foods is an important industry in eastern Maine.

96. Scenery and Summer Resorts.—In summer the sea is cooler than the land (Sec. 27). New England has many rocky coast cliffs and smooth sandy beaches, and many thousand people seek the sea border in the heat of summer, because it is cool and because of the good bathing and fishing and boating. Newport in Rhode Island is one of the best known seaside resorts. It has an excellent harbor frequently visited by ships of the United States Navy. Bar Harbor on Mt. Desert Island is also well known (Fig. 109).



Fig. 109. Bar Harbor, Maine

Mountains are cooler than lowlands (Sec. 26), and the New England mountains have forests and clear air far above the smoke of towns; they also offer noble views of woods, fields, lakes, and sky. Hence, in summer, thousands of people go to these mountains, seeking rest.

In the wide forests of Maine are many lakes, joined by streams. Here the tourist can canoe for long distances, and can camp, hunt, and fish. The New England shores, mountains, streams, lakes, and forests attract many, not only from the cities and towns near at hand, but also from cities far to the westward.

A great number of New Englanders find occupation in managing hotels and boarding houses, building and renting cottages, raising the needed vegetables and fruit, making and sailing pleasure boats, and carrying the tourists in wagons, cars, and automobiles. In these ways the natural scenery helps some of the New England people to earn their living.

97. Education.—Universities, colleges, academies, and public and private schools flourish in New England. The people from early days have had the advantage of education and have been influential in the affairs of the nation. They were prompt to resist the unjust taxes that led to the Revolution, and to fight when it became necessary. From New England many sturdy men and women migrated to New York and to the states of the

Mississippi Valley, and have been influential in shaping the life of some of the greatest states and cities in the Union.

In Massachusetts, at Cambridge, is Harvard, the oldest of American universities (Fig. 110). It was founded in 1636, and was endowed by John Harvard, a graduate of the University of Cambridge in England. Also in the same state are the Massachusetts Institute of Technology,

a number of colleges for men, and several of the best known colleges for women. Yale University, at New Haven, Connecticut (Fig. 111), was founded in 1701; and there are in the various New England states many other well-known colleges.

Review.—1. Where are the principal forests of New England? 2. Why should they be preserved? 3. What are some of the useful things made from New England trees? 4. What special product is made in some of the forests in Vermont? 5. What cities in Maine have a large lumber business? Why is their location favorable?

6. What are the chief kinds of useful rock in New England?

7. Give an account of the Banks of Newfoundland. 8. Name the chief New England fishing centers. 9. How does cod fishing differ from mackerel fishing?

10. What kinds of scenery are found in New England? 11. How does the dense population of the eastern states affect summer resorts? 12. Of what practical value is this to many people of New England?

13. What is the principal university in Massachusetts? In Connecticut?



Fig. 110. Yard of Harvard University



Fig. 111. Campus at Yale University

CITIES AND ROUTES OF TRADE

98. Boston.—The largest of New England cities is Boston. Many other large places are within a few miles of Boston, and "greater Boston," or the Metropolitan District, as the region is sometimes called, has far more than a million people. Cambridge has over 100,000 inhabitants; Lynn, the shoe town, has about 100,000. The Metropolitan District includes also Somerville, Malden, Newton, Everett, Quincy, Chelsea, Waltham, Brookline, and other cities and towns (Fig. 112). Some of the cities are places of residence for the business men of Boston.

Boston is one of the most important seaports of the United States. Coasting steamers run to all points on the New England coast, to the ports of Canada, and to New York, the West Indies, and the Gulf of Mexico. Several lines have regular sailings to Great Britain and other foreign countries. Cotton from the southern states, fruit from the tropics, and hides from many countries are among the commodities landed on Boston wharves. From Boston are sent many of the



Fig. 113. State House, Boston. The dome is gilded

manufactured products of New England. The city is also a shipping point for grain from the western states.

Salem, like Boston, is an old seaport, and many years ago ships from all parts of the world brought rich cargoes to its wharves. Boston grew faster and gained the shipping trade partly because it has a better and more commodious harbor than Salem, more suitable for modern ocean steamships. Boston is also at the most western point on Massachusetts Bay, and from Boston rail-

roads were built across the Berkshire Hills to Albany and the West. After Boston secured the advantage in size and business, other railroads were built leading to it, so that now roads run from Boston to the city of New York, to the West, and to all points in northern New England and eastern Canada. Southern New England is covered by a close network of railroads. One of the roads passes through the Hoosac Mountain by a tunnel about five miles long, —the longest railroad tunnel in this country.

The canal across Cape Cod from Buzzards Bay to Cape




Fig. 112. Boston and vicinity

Cod Bay shortens by several hours the sea route from Boston to southern points.

Boston is the financial or banking center of New England. The companies that operate mills and factories in the smaller cities have their main offices in Boston. Through these offices they buy their raw materials, such as wool, cotton, or leather, and also make sales of cotton cloth, worsteds, shoes, and other finished products. Boston has many dealers in wool, and only London is greater as a wool market.

Boston is a place of much interest to Americans, for it was the scene of many events in the Revolution. Bunker Hill is in the city, and Lexington and Concord are near it. The Old South Church, the State House (Fig. 113), and Faneuil Hall are among the historic buildings of America.

99. Other Cities.—Westward from Boston is Worcester, the second city in the state and the third in New England, with many manufactures besides those named in Section 91. Springfield is the principal city of the Connecticut Valley in Massachusetts, and is the banking and trade center for many smaller cities and towns in the neighborhood. Here the Boston and Albany Railroad is crossed by the railroad lines of the Connecticut Valley. Pittsfield, with large factories, is the chief city of the Berkshire region. Fitchburg in central Massachusetts is a place of many kinds of manufacture.

Portland is the chief city of Maine. It is a trade center for the manufacturing cities of the state, has an excellent harbor, and sends steamships to Boston, to other American ports, and to Liverpool. The Grand Trunk Railway of Canada reaches the sea at Portland, and thus has an outlet in the winter months, when most of the Canadian ports are closed by ice. New Hampshire has one good harbor, at Portsmouth. Vermont has no seacoast, but Burlington is a port on Lake Champlain.

Providence, in Rhode Island, the second city

of New England, has railroad connections with Boston and New York, and a large coasting trade. Fall River in Massachusetts, and New Haven, Bridgeport, and Hartford, all in Connecticut, are ports engaged in coastwise trade.

Review by States.—Maine. 1. How does Maine compare with your state in area? In density of population (Fig. 80)? 2. What kind of coast line has Maine? 3. Which city is the capital? 4. Name three other cities of Maine and mention their important industries. 5. Which is the largest city? 6. Where do its steamships go? 7. What great railroad connections has it? 8. In what way is it important to the other cities of Maine? 9. What kinds of fishing prevail along the coast? 10. What well-known summer resort is on Mt. Desert Island?

New Hampshire (N. H.). 11. What seaport has New Hampshire? 12. How long is its seacoast (see Fig. 84)? 13. What is the principal river? 14. Give name and location of the capital. 15. What city is farther south on the same river? What are its two chief industries? 16. What mountains are to the northward?

Vermont (Vt.). 17. Name a river and a lake on the boundaries of Vermont. 18. What mountains are in Vermont? 19. At what place is granite quarried? 20. Where is marble found? 21. What other useful stone is found in Vermont? 22. Name the capital; the chief lake port.

Massachusetts (Mass.). 23. What are the great industries of Massachusetts? 24. Name the principal cities for each of the greater industries. 25. Give an account of the foreign trade of Boston; of its railroad connections. 26. Make a sketch map of the state, showing the location of Worcester, Springfield, Lowell, Lynn, Waltham, Gloucester, and Fall River. 27. What are the industries of each of these cities? 28. Where is the Hoosac tunnel?

Rhode Island (R. I.). 29. What is the density of population of Rhode Island? 30. What bay runs far inland? 31. What is the rank of Providence among the cities of New England? 32. What seaport and summer resort is on an island in the southern part of the state? 33. Where is granite quarried? 34. What important city in Massachusetts is approached through Narragansett Bay?

Connecticut (Conn.). 35. What is the capital of Connecticut? 36. What is the character of the Connecticut River up to this point? 37. Name the chief seaports.



Fig. 114. The *Half Moon*,—photograph of a replica of the ship in which Henry Hudson crossed the Atlantic Ocean

THE MIDDLE ATLANTIC STATES

100. Early Settlements.—As has already been pointed out, the real reason why Columbus undertook his voyage across the terrifying sea that stretched for an unknown distance west of Europe, was to try to reach Asia by sailing west.

Long before his time, the people of Europe had carried on an overland trade, by caravan, with some of the people of Asia. The fine silks and metal goods, the gold and silver ornaments, the jewels, the spices, perfumes, and dyes which came from these eastern countries were highly valued in European markets.

Practically all of the caravan routes crossed territory under the control of the Turks. When these people decided upon a war against those of their neighbors who did not believe as they did, trade could no longer be carried on across their territory. The closing of these routes of trade made it necessary for the merchants of Europe to find other routes to these eastern countries, and the voyage of Columbus was one of the attempts to find a water route. He found

a New World instead, but he died without knowing that he had done so.

After the voyage of Columbus many other such attempts were made. Several of them were made by Henry Hudson, an Englishman in the service of the Dutch. On one of his trips, Hudson reached the coast of the New World, entered the river which now bears his name, and sailed for a long distance up the stream. As a result of this expedition the Dutch laid claim to the surrounding territory and made several settlements. One of these was at New Amsterdam, a name that was changed to New York when the country finally came into English hands. This settlement has now come to be the second largest city in the world. The early settlements in Pennsylvania and New Jersey, however, were made by the people of Great Britain and Germany.

In the Middle Atlantic States, as in New England, agriculture is still an important industry, but the leading industry, and the one which gives employment to the greater part of the vast population, is manufacture.



THE MIDDLE ATLANTIC STATES

	AREA, Sq. Mi.	POPULATION, 1920	CAPITAL
New York . . .	49,204	10,385,227	Albany
New Jersey . . .	8,224	3,155,900	Trenton
Pennsylvania . . .	45,126	8,720,017	Harrisburg

Map Study.—1. What are the states of the Middle Atlantic group? 2. Name the rivers and lakes that form parts of the boundary of New York. 3. What natural boundaries has Pennsylvania? New Jersey?

4. What three rivers flow southward to the Atlantic Ocean? 5. By what stream does New York send waters to the Gulf of Mexico? 6. What river rises in Pennsylvania, crosses New York, and flows into Lake Ontario? 7. What important city is on this river?

8. Trace the Delaware River from its source to the ocean. 9. Describe the Susquehanna River in the same way. 10. What state capital is on this river? 11. What state capital is on the Delaware River? 12. What other large cities are on this river? 13. What state capital and other large cities are on the Hudson River? 14. What canal connects Lake Erie and the Hudson River? Name seven important cities on or near it. 15. What great city is at the head of the Ohio River?

16. What mountains are north of the Mohawk River? What highland is south of it? 17. How long is Long Island? 18. Name the four largest lakes within New York state.

PHYSICAL FEATURES

101. Size and Position.—The three states, New York, New Jersey, and Pennsylvania, together contain a little more than 100,000 square miles, and are therefore smaller than the single state of Colorado. They have, however, more than 22,000,000 people, while Colorado has less than 1,000,000.

On their southeastern border is the Atlantic Ocean, with the great and safe harbors of New York and Philadelphia. On the northwest this group of states is bounded by Lake Erie, Lake Ontario, and the St. Lawrence River. Here are Buffalo and Erie, ports of Lake Erie. In the west are the headwaters of the Ohio River, and here is Pittsburgh.

These states have the advantage of three vast systems of waterways, namely, (1) the Great Lakes, leading to Chicago and Duluth; (2) the Ohio River, connecting with the whole Mississippi system and the Gulf of Mexico; and (3) the ocean, the highway to all the world. In addition New York and Philadelphia are the eastern terminals of some of the greatest American railroad systems.

All three states were among the original thirteen colonies, and as they were settled at an early time, they have the advantage of long growth. They are like New England in having many cities, great markets, special crops on the farms, and extensive manufactures.

102. Surface.—There are four physical regions in this group of states.

The first of these regions borders the ocean and is called the *Atlantic Lowland* (Sec. 47). Part of it is hilly lowland, which was once much higher than now and has been worn down to its present form. This hilly region includes the southern corner of New York state, with Manhattan Island; also north-

eastern New Jersey and southeastern Pennsylvania. Southern New Jersey is low and flat, its rocks are clays and sands and marl beds, and it is a part of the uplifted sea bottom that now forms the Atlantic coastal plain (Sec. 47). New Jersey is mainly lowland.



Fig. 116. The hilly lowland of northeastern New Jersey



Fig. 117. Bathing beach at Atlantic City

© Detroit Publishing Co.

Long Island is a part of the state of New York. It is more than 100 miles long. It is mainly flat, but in some places it is hilly with glacial moraines, for the glacier reached across the region where Long Island Sound now is. Long Island, however, is like the coastal plain rather than the hilly lowland.

Nearly all the sea border of this group of states is low and sandy. Great cities are near, and there are many resorts and bathing beaches, such as Atlantic City (Fig. 117) and Long Branch in New Jersey, and Coney Island and Rockaway Beach on Long Island. There are thousands of summer homes on the shores of Long Island.

The second physical region in this group of states is a part of the *Appalachian Mountains* (Sec. 48), and contains several groups of highlands. The Adirondacks are a forested region in northern New York, with beautiful lakes and many peaks from 3000 to 5000 feet in altitude. The highest is Mt. Marcy, whose top is 5344 feet above the sea. A large part of this region is a state forest preserve.

East of the Hudson are the foothills of the Berkshires, and farther south are the Highlands of the Hudson, through which the river has cut a gorge from Cornwall to Peekskill.

West of the Highlands are the Shawangunk (pronounced shon'gum) Mountains. Northwestern New Jersey is a region of wooded highlands, with forests and iron mines. Having few people and no large towns, these uplands furnish pure water for the cities of northern New Jersey.

Through Pennsylvania, from the Delaware River on the northeast, a number of long, even-topped mountain ridges extend across the state southwest into

Maryland and West Virginia. The Susquehanna River cuts through the whole series of ridges north of the city of Harrisburg. Within this mountain belt are beds of hard coal, or anthracite.

The third region is the northern part of the *Appalachian Plateau* (Sec. 49). In eastern New York it is called the Catskill Mountains. Their steep cliffs look down on the Hudson Valley. The higher slopes of the Catskills are a region of bold forest-covered hills, some of the higher peaks rising to 3000 or 4000 feet above the sea. Being high, cool, and near large cities, these hills are the sites of many summer homes and hotels.

Westward from the Catskills the hills are about 2000 feet above the sea, and extend through central and southern New York almost to Lake Erie. Deep valleys run among the hills, and in some of them there are beautiful lakes. One of these, Otsego Lake, is the source of the Susquehanna River. At the foot of the lake is Cooperstown, once the home of James Fenimore Cooper, the novelist. In west-central New York are some long, narrow lakes occupying valleys which were much changed by the great glacier that once swept over this region (Sec. 31). The largest of these lakes are Oneida, Seneca, and Cayuga.

In Pennsylvania the plateau occupies all of the state north-west of the mountain belt. As in New York, there are many deep valleys. The largest of these are the valleys of the Allegheny and Monongahela rivers, which unite at Pittsburgh to form the Ohio. This plateau in Pennsylvania is often called the Allegheny Plateau (Fig. 118). In this region there are great beds of soft coal, and much petroleum and natural gas.

The fourth region is the lowland bordering the Great Lakes, often called the *Lake Plains* of New York. Lake Ontario and Lake Erie were once much larger than now, and overflowed all the lowlands that now border the lake shores. On these lowlands mud gathered, forming a level deposit which, when the waters went down and plants grew, became good soil. The fruit and grain farms on the Lake Plains are among the richest in New York state.

103. Drainage.—The principal streams of the Middle Atlantic States are:

(1) The St. Lawrence river system, including Lake Erie, Lake Ontario, and many streams from northern and western New York. It also includes the Niagara River, between New York and Canada. This river is very

short, but has the great falls which are the wonder of all nations (Figs. 22, 119).

(2) The Ohio, with headwaters in West Virginia, Pennsylvania, and New York.

(3) The Susquehanna. Its main source is in Otsego Lake, but it has many sources in the plateau regions of New York and Pennsylvania. The river passes through the mountains, crosses the Atlantic Lowland, and enters the Chesapeake Bay.

(4) The Delaware. This stream rises in the Catskills, and flows between Pennsylvania and New Jersey (Figs. 54, 120), into Delaware Bay.

(5) The Hudson and its large branch the Mohawk. The Hudson is a tidal stream,



Fig. 119. Niagara Falls, seen from the New York side



Fig. 118. A valley (Allegheny River) in the Allegheny Plateau; Oil City, Pennsylvania




Fig. 120. The Delaware River above the Water Gap



Fig. 121. Looking up the Hudson River from West Point

and is navigable as far as Albany and Troy, 150 miles from the sea (Fig. 121). The Mohawk Valley is an open highway leading westward between the Adirondacks and the Appalachian Plateau.

Review. 1. What great systems of waterways are partly in these states? 2. Trace the journey by water from Buffalo to the Atlantic Ocean by two routes. (On questions 2, 3, and 4 use the maps of North America and the United States.) 3. Describe the water route from Pittsburgh to the Gulf of Mexico. 4. Outline the water route from Buffalo to Duluth. 5. How do the Middle Atlantic States resemble New England?

6. Name the regions as classified by surface, beginning on the Atlantic side. 7. Describe Long Island. 8. Where are the Highlands of the Hudson? 9. What is the character of north-western New Jersey? 10. In what way is this region useful to many people? 11. Describe the course of the mountain belt across Pennsylvania. 12. What is the Appalachian Plateau called in eastern New York? 13. What streams drain the plateau in Pennsylvania? 14. What is meant by the Lake Plains in New York?

SOILS

104. Kinds of Soil.—There are several kinds of soil in different parts of the Middle Atlantic States. In order to understand them, let us first consider what soils are and how they are made. A soil is fine, earthy matter in which plants will grow. It may be mixed with coarse or even stony materials, or it may be entirely fine and free from stones. If the soil is sandy, the farmer calls it a light soil. Water readily drains out of such soils, and plants growing in them often suffer from lack of moisture. Sandy soils are in many cases less fertile than others. If the soil is clayey, the farmer calls it heavy. Sometimes it holds too much water, and care must be taken not to work it when it is wet, or it may bake under the sun's heat into hard lumps. If the soil is a mixture of sand and clay, it is a loam. Many of the soils that are the most productive are loams.

105. Origin of Soils.—All rocks, when exposed to the air, to water, or to heat and frost, slowly break into small pieces. Such breaking up is called *weathering*. Also the wear of rivers, glaciers, and waves makes much rock waste. The surface parts of the crushed and decayed rocks become covered with trees, grasses, and other plants. Then the roots and tops decay and mingle with the rock waste. Such a mixture of rock and plant matter is a soil. When a ditch or a cellar is dug, the material found at the top, which is dark in color and is filled with roots, is the soil layer. It may be several inches in thickness, or several feet, as is true of some prairie soils in the Mississippi Valley.

The ice of the glacial invasion (Sec. 32) covered nearly all of New York, all of northern New Jersey, and part of northern Pennsylvania. Wherever the ice moved, it mixed the soils that were already there with rock waste which it had gathered in its progress. Hence glacial soils are a mixture of what might be called home and foreign material. Indeed some of the soil material in New York was brought from Canada by the ice as it came southward.

Where there has been no glacial invasion the home rock weathers and decays in its place. The fragments may slip down hill, but they do not go far. Soils in such regions are made from the rocks which lie below the surface. There are exceptions to this rule; rivers and winds carry soil materials long distances from the rock formations from which they were made.

Soils made by decay in place are found in central and southern Pennsylvania and in southern New Jersey, as well as in many other parts of the world.

There are many special kinds of soil, as mucky, volcanic, or silty. Mucky soils consist mainly of decayed vegetation. Most lavas break up quickly into volcanic soils. In some regions the winds work over the fine rock waste left by rivers and glaciers or

formed by the decay of rock in place, and make a silty or *loess* soil such as is found on some of our prairies and in other parts of the world.

106. Management of Soils.—The soil on which most crops are raised needs to be cultivated during the growing season. This stirring of the soil not only kills weeds, but helps to keep the ground moist, as the ground water will not evaporate quickly through the layer of loose soil.

To be most successful with crops, the farmer must know how to manage soils. If the ground is too wet, he must drain it. If it is too dry, he must keep the soil under constant cultivation, plant crops that require less moisture, or irrigate the ground. He must understand the rotation of crops; that is, he must not plant the same crop on the same ground year after year, for this will always take the same kinds of plant food out of the soil and may exhaust the land. He must also use the right kind of fertilizers.

The wise farmer leaves forests, or grass for pasture, on the higher lands and steeper slopes, for these are harder to work, and if the soil is turned with the plow and made fine with the harrow, the rains wash away the best of it and ruin the surface with gullies (Fig. 122). When he plows a sidehill, he works around or across it so that the rains cannot wash the furrows. In some of the older countries, as in Palestine, in Italy, and along the steep

slopes of the Rhine Valley, the land has been terraced, to make strips of flat or gently sloping ground for the cultivation of grapes and other fruit. The necessary soil is sometimes brought from a distance. The soil is the most precious gift of nature, and it takes much wisdom both to use it well now and also to preserve it for the use of future generations.

CLIMATE AND AGRICULTURE

107. Climate.—The Middle Atlantic States are in the track of the great westerly winds (Sec. 61). They border the ocean, and as the cyclonic storms cross them, the winds blowing toward the storm center from the south and east contain much moisture evaporated from the surface of the sea. For this reason there is enough rain over the entire region, but it is heavier near the sea. The rainfall is about 45 inches in the city of New York, on Long Island, and in the coastal parts of New Jersey; and about 40 inches in Philadelphia. The amount becomes less as we go inland, until we reach the borders of the Great Lakes, where we find about 35 inches; but in the higher regions of the Adirondack and Catskill mountains it again increases (Fig. 72).

The climate of the whole coastal region is made milder by the nearness of the ocean. The interior uplands, especially in the Adirondacks and in southwestern New York, have very cold winters and much snow. Frosts there may come as early as September and linger into May. Along the Great Lakes and the large lakes of west-central New York, however, the winters are less severe, and grapes, peaches, and quinces are raised in abundance. Long Island, southern New Jersey, and southeastern Pennsylvania have rather mild winters. The chilling of the damp ocean air when it reaches the land often causes heavy fogs at New York and Philadelphia, and ships must sometimes wait until the fog disappears before they can come to port or sail from it.



U. S. Dept. of Ag., Forest Service

Fig. 122. A hillside, showing gullies



Fig. 123. Truck farm on Long Island



Fig. 124. Apple orchard in western New York

108. The Wheat Crop.—The Middle Atlantic States raise all the grains that flourish in a temperate climate, such as wheat, corn, barley, oats, rye, and buckwheat. The population is large; more people live in towns and cities than on farms, and their work is chiefly in trade and manufacture. On account of this dense population much of the bread supply is brought from the western states, as is the case in New England. The Middle Atlantic States, however, raise much wheat, while the New England States produce very little.

Pennsylvania raises many million bushels of wheat, though less than a number of states in the western part of the country.

New York averages not far from one bushel of wheat for each one of its population. Since each person on the average consumes about six bushels of wheat in a year, we can see that most of the wheat used in New York must come from outside the state. Western New York was once the wheat center of the United States, and Rochester was then called the Flour City because of the large flour mills operated by the Falls of the Genesee River at that place. Now the farmers on the prairies and plains of the West can raise wheat more cheaply than can the farmers of New York state.

109. Vegetables and Fruits.—The farmers of the Middle Atlantic States, like those of New England, raise special crops for the city markets. All along the Atlantic Lowland, in Pennsylvania, New Jersey, and on Long Island, *truck farming*, or market gardening, is a great business (Fig. 123). Millions of people in the cities of the lowland must be supplied with common vegetables and small fruits. The Hudson Valley also is a good place for market gardening because there are many cities along the river and the city of New York is at its mouth.

Grapes and peaches are among the fruits that flourish in the coastal lowlands, in the Hudson Valley, and along the lakes of western and central New York. The lake waters store the heat of the summer sun, and slowly give it off during the autumn. Killing frosts do not come until late in October, and the fruit has plenty of time to ripen. Many apples are grown in western New York (Fig. 124) and in the Hudson Valley, and they are the chief orchard fruit in Pennsylvania.

The fruit crop of New York is greater in value than that of any other state except California. In the western part of the state, along the shore of Lake Ontario and bordering the Niagara River, is one of the greatest fruit-growing regions in the United States.



Fig. 125. A vineyard in the Chautauqua Grape Belt

Along the shore of Lake Erie in western New York and northwestern Pennsylvania is a region of vineyards known as the Grape Belt (Fig. 125). Grapes are grown in large quantities also near Keuka, Seneca, and other lakes in west-central New York. Some grapes are sold in baskets, as a table fruit, while many are used in the manufacture of grape juice.

Among the special crops are hops and onions in parts of New York, tobacco in southeastern Pennsylvania, and sweet potatoes in southern New Jersey. The common potato is raised almost everywhere.

110. Dairying.—People in cities must have daily supplies of milk, cream, and butter; hence dairying has become the most common industry on the farms of these states. Milk is carried to the city of New York by daily milk trains, many of which run from western and northern New York and from the shores of Lake Ontario. There are milk stations along the railroads. Some are near the regular passenger and freight stations, and others stand by themselves, at points convenient to the farms. The farmer drives to the milk station each day, sometimes taking the milk cans of his neighbors as well as his own. At the station the milk is weighed, and loaded in the milk car. The cars are cooled with ice, and the milk is kept sweet until it is delivered at the city homes. To

supply the milk and cream needed in one day in the city of New York requires 1,500,000 quarts of milk. Some of this comes from New Jersey, eastern Pennsylvania, Connecticut, and western Massachusetts, as well as from New York state.

In some of the dairy districts of Pennsylvania and New York, the milk is used in creameries and cheese factories for making butter and cheese. There are many such factories in the central and northern parts of New York, and the city of Utica has long been a well-known market for the cheese produced there.

The great forage crops are hay and corn. Hay is needed for the cattle and horses on the farms, and some hay is pressed into bales so that it can be conveniently shipped to market in town or city. Much of the corn is cut when fully grown but not fully ripened. The stalks, leaves, and ears are cut into short pieces and stored in the *silo* (Fig. 126), a tall building, usually round, which is a familiar sight in connection with the farmers' barns. The material stored in the silo keeps through the winter in a juicy state and is fed to cows to keep up the flow of milk.

The raising of poultry is also a very extensive and profitable industry in the Middle Atlantic States and in many other states. The eggs and the fowls find a ready market in the cities and larger towns.



Fig. 126. Cattle barns, with silo at right

Review. 1. What is soil? 2. What are some of the main kinds of soil? 3. What is the origin of soils? 4. How do soils in the region once covered by ice differ from other soils?

5. What is the advantage of keeping soils well cultivated? 6. What is the rotation of crops? 7. Why is it important?

8. What use should commonly be made of lands with steep slopes? 9. Why are slopes in some parts of old countries terraced?

10. What are the prevailing winds in these states? 11. How does the sea affect the climate of this region? 12. How does the rainfall vary from the seacoast to the Great Lakes? 13. How do the lakes affect the products of New York?

14. About how much wheat is brought each year from the West for each one of the population of New York? 15. Where was the former center of wheat production in this country? 16. At what city were the largest flour mills?

17. What are the chief localities for truck farming? 18. What important fruit crops are raised in New York? 19. How does New York compare in fruit raising with California? 20. Name some of the special crops in the Middle Atlantic States.

21. Give an account of the milk supply of the city of New York. 22. What is a silo?

covered them with layers of mud. Later the swamp deposits were changed into coal and the mud layers were turned into rock. In Pennsylvania we find coal beds 5, 10, or more feet thick, lying between beds of rock.

112. Coal Regions.—In eastern Pennsylvania, between the Delaware and Susquehanna rivers, is found nearly all the anthracite in this country. It is hard, shiny, and burns with little flame. In western Pennsylvania is much soft, or bituminous, coal. It is softer than anthracite, lights more easily, burns with more gas and flame, and gives less heat, lasting a shorter time.

The anthracite is all in the region of the Appalachian Mountains (Sec. 48). The pressure that folded the rocks also pushed up the beds of coal, and squeezed them so that they gave off some of their gases and became hard; that is, they were changed into anthracite. The soft coal is in the Appalachian Plateau (Sec. 49). These beds of coal are horizontal, like the rocks; not so much gas was driven off, and the coal did not become so hard.


A number of cities have grown up about the hard coal or anthracite mines. The largest of these is Scranton. Among the others are Wilkes-Barre, Hazleton, and Pottsville. Many of the mines are several hundred feet underground. The coal is dug out by the miners, hoisted to the surface, and run through a breaker, where the pieces of rock are picked out. The coal is then screened into the common sizes, such as pea, chestnut, and egg, and sent to market.

When anthracite was discovered, about a hundred and twenty-five years ago, the people thought it worthless, for they did not know how to make it burn. Only a little soft coal was used. To-day, coal produces the steam that turns the wheels of far more cars and mills than any other power.

There is an enormous demand for anthracite, especially for heating and cooking, and the railroads that run into the anthracite region make a vast business of hauling the coal.

VALUABLE MINERALS

III. Origin of Coal.—In ancient periods in the history of the earth, forests grew in great swamps and on their borders. The wood, leaves, and mosses gathered for a long time and were kept from decay by the water. This mass of plant substances was turned into coal, in much the same way as vegetation in swamps may now change into the brown substance called peat, which is used for fuel in Ireland and in a number of other countries. We know that coal is made from plants, because it consists mainly of a substance, called carbon, which is abundant in plants, and because in connection with coal beds we find leaves, tree trunks, roots, and fruits in a petrified, or fossil, condition. We also find peat, woody coal or lignite, bituminous coal, and hard coal or anthracite, a series that shows all degrees of change from wood to the hardest coal. Water came in over these great swamps and



The cities of New York, Philadelphia, and Baltimore are the most important markets, and are all reached by short hauls over the railroads. Great quantities of coal are taken in barges from the railroad terminals, to many Atlantic seaports (Sec. 87).

Several railroads distribute the coal through New York state and New England. Large amounts go to the ports of the Great Lakes and the cities of Canada. In Canada the anthracite is carried as far west as Winnipeg, and in the United States beyond the Mississippi River. Thus we may follow the coal from the mine, by ship and train, to the houses and factories of two countries.

The bituminous coal of western Pennsylvania is a part of great beds which reach as far south as Alabama (Fig. 127). Vast quantities of this coal are used in the iron industry of the Pittsburgh region.

113. Petroleum.—Until the middle of the last century, whale oil and tallow candles were still the usual means of lighting homes and places of

business. Then petroleum, or rock oil, was found in large quantities by drilling wells into the sandstone rocks of western Pennsylvania. Before that time a little of the oil was sometimes found floating on the surface of springs or streams after it had come out of the earth with spring water. It was collected for use as a medicine, first by Indians and later by white men.

The oil lies among the grains of sand which make up the porous rock. In some places


it was many hundred feet below the surface but was under such great pressure of gas that when the drill reached it, the oil spouted above the surface. Such wells were known as "gushers." All the Pennsylvania wells now have to be pumped (Fig. 128).

The crude petroleum is sent to the great refineries in Philadelphia, Pennsylvania, or Bayonne, New Jersey, or other distant cities, through pipe lines, equipped at intervals with pumping stations. At the refineries the crude oil is separated into kerosene, gasoline, vaseline, paraffin, and many other substances.

Kerosene and other oils are carried in tank cars and ships to all parts of this country and to foreign lands, and distributed from local

stations of the oil companies and by retail dealers. To get the raw material, carry it to a factory, where it is made into the desired products, and then take them to market,—these are the steps in almost every great industry.

The oil wells of Pennsylvania are not



so productive as they once were. Much oil is now found in West Virginia, Illinois, Kansas, Oklahoma, Louisiana, Texas, and California (Fig. 129). More petroleum is produced in the United States than in all the other countries of the world.

114. Natural Gas.—Natural gas is found in the rocks, in some places with petroleum, but in other places without it. The gas is obtained by drilling and is piped to houses and factories, to be used for light and heat, and to produce power.

In western Pennsylvania and western New York gas is abundant and is much used in Pittsburgh, Buffalo, and other cities. Gas is found also in Central New York.

115. Iron.—Iron is mined in the Adirondacks in New York, in the New Jersey highlands, and in various parts of Pennsylvania. But most of the ore used in the iron furnaces of Pittsburgh, Buffalo, Lackawanna, and other places in these states is brought from the Lake Superior region.

116. Salt.—Much salt is found in New York state. The Indians knew of springs of salt water where the city of Syracuse now stands. The early settlers also made salt there by boiling down the salt water in kettles. Later it was evaporated in open vats or pans, which covered many acres near Syracuse, and by boiling. In 1880, a boring in western New York, which was sunk for oil, went through beds of rock salt. This was the beginning of a great salt industry in the Genesee Valley and about the heads of Cayuga and Seneca lakes.




Fig. 129. Petroleum and natural gas fields of the United States

Wells are bored several hundred or even two thousand feet deep, and water is pumped in. This dissolves the salt, and the brine is then pumped out, and the water evaporated by boiling.

117. Clays, Cement, and Building Stone.—Brick clays and clays for making drain and building tile are found in many places. The largest beds are along the Hudson River. The bricks are molded, baked, loaded into scows, and towed down the river to be used in the great city at its mouth or to be sent to other markets.

Natural, or *hydraulic*, cement rock occurs in New York, but Portland cement is now more extensively used. It is made of clay and limestone, chalk, or marl, mixed properly, heated, and ground to powder. Large cement factories are found in all the states of this group (Fig. 130). The industry is most important in the southeastern lowland of Pennsylvania. The cement industry has had a rapid growth, because cement is used in the foundations and walls of



Fig. 130. Bagging cement in a Pennsylvania mill

buildings, and in sidewalks, bridges, dams, and many other structures.

Much building stone is quarried in the Middle Atlantic States. New York has marble and sandstone, and Pennsylvania has large slate quarries.

118. Water Resources.—The Middle Atlantic States have several important rivers (Sec. 103). In New York and those parts of the other states that were covered by the glacier, there are many lakes (Sec. 79). Because of the abundant rainfall, there is ordinarily plenty of water in the ground. Formerly most water for use in homes was pumped from wells or taken from streams. But in many places the waste from houses and factories pollutes the wells and rivers and makes their waters dangerous to health. Many cities now draw water from lakes, or build reservoirs to gather the waters of clean forests and mountain slopes. The city of New York gets its water from reservoirs in the basin of the Croton River (Fig. 131) and in the Catskill region. The borough of Brooklyn receives water from ponds and reservoirs on Long Island.

Much water power is available in these states. The greatest is that of Niagara River



Fig. 131. Part of the Croton Reservoir

at the Falls. By this power electricity is generated, which is transmitted to Buffalo and to other cities. The Upper Hudson, the Black River, and other streams of the Adirondacks afford a vast amount of water power, for many industries, especially

for pulp and paper mills (Fig. 132).

Review.—1. What is the origin of coal? 2. How do we know this? 3. What is anthracite? 4. Where is it found? 5. What cities have grown up on account of the mining of this coal? 6. What processes are necessary before the coal is ready for market? 7. What are the principal cities and regions to which it is sent? 8. In what ways is it carried? 9. What kind of coal is found in western Pennsylvania?

10. Where is petroleum found in this group of states? 11. How do the rocks hold the oil? 12. What is a gusher? 13. How is the crude oil taken to the refineries, and what is done with it? 14. What substances have you seen that are made from petroleum? 15. Describe, if you can, the appearance of a tank car for oil. 16. What states now produce much oil? 17. Where is natural gas found in the Middle Atlantic States?

18. Give an account of the salt industry in New York. 19. In what part of New York are many bricks made? 20. How are they transported, and where? 21. Where are the very large Portland cement plants located?



Fig. 132. One of the great paper mills on the Black River, New York

PRINCIPAL CITIES AND INDUSTRIES

119. Great Cities and Routes of Trade.
—We shall best understand this part of our country if we study two important trade routes and the cities which they connect.

The route from New York to Buffalo will be studied first. Both of these cities are in New York state. One is on the sea and is our main gateway to Europe. The other is on Lake Erie and is a gateway to the West. They are connected by the Hudson River and the Erie Barge Canal and by the New York Central and other railroads. New York is the eastern terminus, and Buffalo a stopping place, on several of the routes of travel and trade that lead across the continent.

The second route is from Philadelphia to Pittsburgh. Philadelphia is a great seaport. Pittsburgh is on the upper Ohio River, and is a gateway to the West, for the Ohio River leads to the plains of the Mississippi, as the Great Lakes lead westward from Buffalo. The route between Philadelphia and Pittsburgh is now the main line of the Pennsylvania Railroad, one of the largest railroad systems of the world.

120. The City of New York.
—At the eastern end of the first trade route mentioned above, is New York, the largest city in America. At the time of the American Revolution New York was smaller than Philadelphia, but it has grown more rapidly, for reasons that we shall see.

The first reason is, that New York has one of the best harbors in the New World. The Hudson River is wide and is deep enough for the largest ocean ships; great piers for their use have

been built on the New Jersey side as well as on the New York side. There is wharfage also on New York Bay and on both sides of the East River, in Manhattan and Brooklyn. The East River is not a river at all, but a strait joining New York Bay and Long Island Sound. On the map (Fig. 133), find Sandy Hook, the Lower Bay, the Narrows, New York Bay, Ellis Island, and the tidal inlets that extend into New Jersey. The port of New York has about 450 miles of water front, of which 125 miles are available for ocean steamships (Fig. 134).

A second reason for New York's greatness is that it is joined by several good routes to the interior of the country. The most important of these routes is along the Hudson to Albany, and west through the Mohawk Valley and along the Lake Plains to Buffalo and Chicago. The Hudson enters the ocean through a deep



Fig. 133. The city of New York and vicinity



Fig. 134. Great ocean liner entering its dock, New York

channel, and the Mohawk Valley is cut down nearly to sea level, across the Appalachians. Farther south the lowest passes for railroads or canals are from 1500 to 2500 feet above the sea. Along the shore line and coastal plain railroads find good grades from New York to Boston and from New York to Philadelphia and many other cities all the way to Florida.

121. Greater New York.—Until 1898 only the city on Manhattan Island and a mainland district northeast of the island were known as New York. In that year "Greater New York," or the city of New York as it is now, was formed, consisting of the five boroughs, Manhattan, the Bronx, Brooklyn, Queens, and Richmond (Fig. 133).

more than seven million people.

Manhattan, or the old New York, is the principal business section of the city. The great wholesale trade is in the lower part of the borough, the retail trade in the middle portion, and the better residence sections lie

to the north. Broadway is one of the longest and most magnificent business streets in the world (Fig. 135).

In addition to the surface cars and trains in all the boroughs, there are several lines of elevated railroad and subways which run the length of Manhattan and extend far into the Bronx and Brooklyn. Several bridges span the East River between Manhattan and Brooklyn, and tunnels run under the



Fig. 135. Lower New York at night

The population of New York in 1920 was over 5,600,000. There are cities containing in all more than a million people, across the Hudson, in New Jersey, which cannot be put under the same city government because they are in another state. If these, and the people of Yonkers, Mount Vernon, New Rochelle, and other adjoining places in southern New York are added to the population of the city of New York, we find that the real metropolis contains

Hudson and East rivers. By one of these tunnels the Pennsylvania Railroad line passes under the Hudson River, and enters, in the heart of the city, a large new railroad station. Of the tunnels passing under the East River, one connects the Long Island Railroad with the Pennsylvania system. A great station has been constructed for the New York Central lines also (Fig. 136). The various means of travel already mentioned, and numerous ferries, are used every business day by several hundred thousand people who work in Manhattan but live in one of the other boroughs or in some suburb of New York.

New York's coasting trade reaches all the ports of eastern Canada, eastern United States, the West Indies, and the Gulf of Mexico. Steamship lines of Great Britain, the United States, France, Holland, Norway, Sweden, Italy, Spain, and Greece ply regularly between New York and European ports. The fastest steamships of the world run between New York and the ports of Great Britain and France (Fig. 134). Nearly half of the exports and imports of the United States pass through the port of New York.

Of the immigrants coming to this country to live, nearly all come by way of New York. A large number of these people stay and find work or business in the city, and hence all races and languages are found there.



Fig. 136. The Grand Central Railroad Station, New York

New York is by far the greatest manufacturing city in America. The largest item is the making of clothing. The printing of books and papers is second. Sugar-refining is carried on in Brooklyn and is a very great industry. Petroleum is brought in pipe lines (Sec. 113) and refined in New Jersey, across the Hudson from New York. Many of the manufactures of Jersey City, Newark, and other New Jersey cities have reached their present development because they are so near the great industrial and trade center of New York. An example is found in the silk mills of Paterson, the largest silk center in this country (Fig. 137). Not only silks, but textiles of every kind, are made in and near New York. But the city is too great to be known by any one industry, as Fall River is known for cotton, Lynn for shoes, or Pittsburgh for iron.

As more business is done in New York than in any other American city, it has become the principal financial center of the country. Many of the largest banks and other corporations have their offices on or near Wall Street.

The oldest and largest and best known of the higher institutions of learning in the city of New York is Columbia University.



Fig. 137. Winding ribbons in a silk mill, Paterson, N. J.

New York University, Fordham University, and several colleges also are located there.

Life in New York is like that in most large cities. The poorer people live in the tenements, where a whole family may have only a few rooms or sometimes but one or two. There are tenement buildings in which hundreds of people live in this crowded way under one roof.

People of moderate means usually live in apartment houses, which are houses of a better class than the tenements, and in each of which a number of families have their separate apartments. Some apartments are very large and provide elegant and expensive homes for people of wealth. Thousands of people go many miles each day to reach a modest home in a suburb of the city. Most of the houses in the crowded parts of large cities are built close together in solid blocks. A few of the very rich live in houses which, in the older countries of Europe, would be called palaces.

To feed, clothe, and house the people of the city, to build and maintain stores, offices, factories, churches, schools, hotels, streets, and sewers, requires the labor of millions of men. Many of them live in or near the city, and many live far away.

122. From New York to Buffalo.—The easiest route from New York to Buffalo leads up the Hudson to Albany, from Albany to Schenectady, through the Mohawk Valley to Utica, and thence by way of Syracuse and Rochester. This route was followed by the canoes of the savages and by their forest trails. The white men built roads through the wilderness along the same route. In 1825 the Erie Canal was completed, and boats were drawn by horses or mules between Lake Erie and the Hudson River. On the Hudson the canal boats were lashed together and towed to New York by steamboats.

Soon afterwards a railroad was built from Albany to Schenectady. As the years went on other sections of railroad were built by different companies. These short roads were finally united to form the New York Central and Hudson River Railroad, and freight and passengers could then be carried without change of cars from New York to Buffalo, and by connecting roads to points farther west.

The Erie Canal and branch canals have recently been improved, and are known as the "barge canal" because they have been made large enough for barges holding each a thousand tons of freight (Fig. 138). The new routes are shown in Figure 115.




Fig. 138. A large lock on the barge canal, replacing the smaller locks on the right. Eastern end of the Erie Canal



Fig. 139. West Point Military Academy, seen from the Hudson River

Along this main route from New York to Buffalo are most of the larger cities of the state, and it is bordered by rich farms. Within a few miles of it live three fourths of all the people of the state.

Going up the Hudson River from New York, we pass the city of Yonkers, with its sugar refineries and extensive carpet and elevator factories; and then the cities of Newburgh, Poughkeepsie, and Kingston, each a manufacturing and trading center. The cliffs of the Palisades extend on the west side to the Highlands. In the Highlands is West Point Military Academy, a school maintained by the United States government for training officers for the army (Fig. 139). North of the Highlands, on the west side of the Hudson, the Catskills are seen.

Near the point where the Mohawk enters the Hudson there are several cities. Albany is the largest and is the state capital. Troy is second and is the chief center in the United States for the manufacture of collars and cuffs and laundry machinery. Cohoes is on the falls of the Mohawk and is one of the largest centers for cotton knit goods.

Northward from these cities is an open valley followed by a canal to Lake Champlain and by a railroad along the shore of Lake Champlain to the St. Lawrence

at Montreal. Eastward two trunk railroads lead to Boston. One of these goes by the Hoosac tunnel (Sec. 98) and the other by Springfield and Worcester (Sec. 99). Albany and Troy are near the head of navigation on the Hudson, and have grown up where great routes running north and south and east and west cross each other. We shall find other large cities that have grown up at such "crossroads" of trade.

In the Mohawk Valley, about fifteen miles northwest of Albany, is the flourishing city of Schenectady. Here are located large locomotive works and also one of the world's greatest plants for the manufacture of electrical machinery and supplies (Fig. 140). Farther west is Amsterdam, with knitting mills and other industries. A few miles to the northwest are the two small cities of Gloversville and Johnstown, which make almost half of the gloves made in the United States.



Fig. 140. Electric works at Schenectady




Fig. 141. Buffalo and vicinity

Utica is on the Mohawk, where railroads from the Adirondacks and the St. Lawrence on the north, and from towns of the plateau on the south, meet the New York Central Railroad. Utica is the center of a rich farming region and is an important cheese market. It has large cotton and woolen mills and manufactures of men's clothing.

Syracuse, like Utica, is an important railroad center. It had its beginning in the salt industry. When that industry moved farther west (Sec. 116), the city continued to grow because other industries were established there,—among them the making of automobiles, typewriters, and agricultural implements. The city is the seat of Syracuse University. Near Syracuse is a large establish-

ment that makes soda ash and other products from limestone and the brine obtained from the salt wells near the city. By a branch of the barge canal, Syracuse is connected with the port of Oswego on Lake Ontario.

Auburn is a center for the making of agricultural implements.

Rochester is at the falls of the Genesee River, a few miles from Lake Ontario. In Rochester, as in Syracuse, the first important industry is no longer the chief business (Sec. 108), though much flour is still made there. Rochester is a great manufacturing city, producing photographic and optical supplies and apparatus, clothing, shoes, and many other things in its hundreds of factories. It is also a center for the growing of garden seeds and nursery stock. Many steam and electric railroads enter the city.

123. Buffalo and Vicinity.—Buffalo was founded little more than one hundred years ago, but its advantageous location has helped to make it the second city of New York state (Fig. 141). It is at the east end of Lake Erie, and on the edge of the Lake Plains (Sec. 102), which extend eastward to the Mohawk Valley. Several railroads from New York to the West were built to this point. From Buffalo they continue westward to Chicago, either south of Lake Erie, or, by crossing the Niagara River, north of the lake through a part of Canada. Because the Ni-

agara Falls are a barrier for ships, much of the freight that comes down the lakes in steamships is transferred to cars or to boats on the Erie Barge Canal, in order to be sent farther east.

Much grain comes to Buffalo from the West. Here the first elevator was built in 1843. An elevator (Fig. 142) is a large, and usually a high, building, with bins, carriers, and chutes for unloading, storing, and re-



Fig. 142. Grain elevators, Buffalo Harbor

loading grain. Buffalo has many such elevators. Iron ore is brought here from the Lake Superior region, and Lackawanna, south of Buffalo, has one of the largest steel plants in the world. Lumber also comes down the lakes and is marketed at and near Buffalo. Live stock from the West, and fish from the lakes, are important commodities in the trade of the city.

More than twenty railroads enter Buffalo. Those from the south and southeast bring enormous quantities of coal, which meet the local needs and are shipped to cities on the lakes.

Buffalo has manufactures of airplanes, automobiles, and other iron and steel products.

Niagara Falls is an important manufacturing city, because of its immense water power. Electrical energy is developed at very low cost, and is used in the manufacture of the light metal aluminum and in other industries. Much electrical power also is transmitted to Buffalo and other places.

124. Other Cities and Industries of New York.—West and north of the Adirondacks, toward Lake Ontario and the St. Lawrence River, is a belt of agricultural lowlands, of which Watertown and Ogdensburg are the chief centers. At and near Watertown are pulp and paper mills, originally located there because of water power and of spruce forests close at hand (Fig. 132). Much of the pulp wood now used in these mills, however, is brought in from Canada. The same industry exists at Glens Falls and other places on the upper Hudson. Much of the output is sold to the newspaper, magazine, and book publishers of New York.

Several cities in southern New York are reached by the Erie, the Delaware Lackawanna and Western, the Lehigh Valley, or other railroads. Among these are Binghamton on the Susquehanna River, Elmira on the



Fig. 143. Philadelphia and vicinity

Chemung River, and Jamestown at the outlet of Chautauqua Lake. These are important manufacturing cities, and trading centers for the regions around them, and they are brought into touch with the large city markets by the railroads that pass through them. Ithaca, at the head of Cayuga Lake, is the seat of Cornell University, one of the great universities of the country.

125. Philadelphia.—In 1681 William Penn, a sturdy English Quaker, received from the king of England, in payment of a debt, a grant of the land which now forms the state of Pennsylvania. The name was then suitable, for it means Penn's Woods. Penn founded Philadelphia, which to this day is often called the Quaker City. It is on the tidal part of the Delaware River, as far up the stream as the large ocean ships of the present time can go (Fig. 143).



Fig. 144. Shipyards at Philadelphia. The traveling crane carries parts and materials to their places. A bent beam is being lowered to a ship

with all the large eastern cities. To the west the city connects by trunk lines of railroad with Pittsburgh, and through Pittsburgh with all the large cities of the West and Southwest.

The railroad systems of the United States have developed to such a degree that all the great cities of the country are connected with one another, in some cases by a number of dif-

Philadelphia, with more than 1,800,000 people, is larger than any other American city except New York and Chicago. In it are the Independence Hall and the Liberty Bell, and here the Declaration of Independence was written and the Continental Congress held its sessions. Here, after the war of the Revolution was over, the Constitution of the United States was adopted, and Philadelphia was for a short time the capital of our country.

Like all large cities, Philadelphia has many industries. Among the greater are manufactures of wool, cotton, leather, and iron, and the refining of sugar and petroleum. The crude oil is brought by pipe lines from the oil region (Sec. 113). The woolen manufactures are largely carpets and rugs, of which Philadelphia makes more than any other city; it also makes much clothing. Iron work includes bridges, locomotives and cars, and ships. In the shipyards of this city are built many vessels for commerce and for war (Fig. 144).

The location of Philadelphia gives it many commercial advantages. As a seaport it takes part in the coastwise trade with cities of the Atlantic and Gulf coasts. Several steamship lines also run vessels between Philadelphia and foreign ports. The city is connected by rail

ferent and competing lines.

Philadelphia is the seat of the University of Pennsylvania. Pennsylvania State College, another large educational institution, is located in the central part of the state.

126. From Philadelphia to Pittsburgh.—In the early days a *turnpike* road was built as far west as the Susquehanna River. About 1758, in the time of the French and Indian War, the road was extended to the site of Pittsburgh for the use of English soldiers. In the early days of railroad building, a line, now the main line of the Pennsylvania Railroad, was built between these two cities. A network of railroads now extends into all parts of the state, and the traffic in many products carried by them is very large. The coal traffic of Pennsylvania is enormous. Much coal is carried to Philadelphia for the coasting trade (Sec. 112), to Baltimore, to New York, to the Great Lake ports, and to western cities.

From Philadelphia to Lancaster and Harrisburg, the railroad runs through a rich farming region. Harrisburg is a few miles south of the water gap by which the Susquehanna River cuts through Blue Mountain. It is the capital of the state and has large iron furnaces.



Fig. 145. Railroad bridge across the Susquehanna River, above Harrisburg

Above Harrisburg the railroad crosses the Susquehanna River (Fig. 145) and runs in narrow valleys among the Appalachians to Altoona, which lies between the mountain belt and the great wall, or *escarpment*, which rises to the Appalachian Plateau. At Altoona there are enormous railroad shops, in which thousands of men are employed.

The railroad climbs to the plateau by a great loop, and soon passes through Johnstown, which is close to beds of coal and has very large steel works. The road then continues through a mining region to Pittsburgh, the second largest city of the state. In connection with neighboring cities and towns Pittsburgh is the most important center for iron working to be found in any part of the world.

127. Pittsburgh and the Iron Industry (Sec. 5; Fig. 146).—The point of land lying between the Monongahela and Allegheny rivers, where their waters mingle to form the Ohio River, was for a short time in the possession of France. When it was taken by the English, in 1758, the fortification was named Fort Pitt, and the city that grew here was called

Pittsburgh, in honor of the statesman who directed British affairs at the time of the French and Indian War.

Following the Revolution, many pioneers made their way over the new roads to Pittsburgh, fitted out rude boats for themselves and their goods, and floated down the river to some point where they wished to take up land and make a home.

Pittsburgh is not only on an important line of travel, but it is close to beds of bituminous coal. This is also a region of abundant natural gas (Sec. 114), and the city owes much of its importance to its cheap and abundant fuel and excellent facilities for transportation.

A part of the material used in its mills,

however, comes from other states. Vast deposits of iron ore are found in Michigan, Wisconsin, and Minnesota, not far from Lake Superior. This ore is mined, taken to Duluth, Two Harbors, Ashland, Marquette, or other of the lake ports, and brought down the lakes in ore boats to Cleveland or other ports on Lake Erie (Fig. 222). Much of the ore is carried thence by rail to Pittsburgh, near the coal




Fig. 146. Pittsburgh and vicinity

and limestone needed for separating the iron from the ore.

Iron ore is a mixture of iron with other matter. To separate the iron, the ore must be melted. The coal used for fuel is first turned into coke; that is, it is heated in large ovens until some of its gases are driven off. Then coke, iron ore, and broken limestone are put into the blast furnace. The furnace has a tall stack or cylinder supplied with a blast, or forced draft, to increase the heat. The limestone is put in as a flux; that is, to make the impurities separate from the iron and form slag.

At intervals the iron is drawn off and run into molds in sand, making pig iron. Or, the melted iron is run into a converter, where it is further purified and certain substances are added to it, so that it becomes steel.

Pig iron is brittle, and so are the many objects made from it, such as stoves. Steel is hard and elastic, and suitable for tools, girders, rails, watch springs, and boiler plates. From the time that the ore is melted, the iron may not be allowed to cool until it comes out as a steel rail ready to spike down as part of a railroad track. Wrought iron, made by a different process, is a kind of iron that can be bent or hammered into any desired form.

The making of glass has become an important industry of Pittsburgh, because of the supplies of cheap fuel and of glass sand near at hand. Much of the American plate glass is manufactured here (Fig. 147).

In the neighborhood are McKeesport, Braddock, Homestead, and other cities that share the industries of Pittsburgh. About fifty miles northwest of Pittsburgh is New Castle, also a center for the manufacture of iron and steel. To the southeast is Connellsville, where there are many coke ovens.

In Pittsburgh are the Carnegie Institute of Technology and the University of Pittsburgh.

128. Other Cities and Industries of Pennsylvania.—Erie, on Lake Erie, has a good harbor. It manufactures iron and steel goods and is an important trade and shipping center.

Williamsport, on the west branch of the Susquehanna River, stands, like Altoona, in a valley between the mountain belt and the plateau. Its chief industries are the manufacture of silk, and of rubber boots and shoes.

In the eastern part of the state are: Scranton, the third city of Pennsylvania in population, with silk mills and other manufactures, and an immense traffic in anthracite; Wilkes-Barre, another anthracite mining center; Reading, a railway center with large steel works, rolling mills, railroad repair shops, and knitting mills; Allentown, with manufactures of silk and iron; Bethlehem, with a large steel plant; and Easton, with silk mills and other manufactures.

In the southeastern part of the state, Norristown, near Philadelphia, has knitting mills. Chester, on the Delaware, has a large shipbuilding industry and manufactures of cotton and woolen goods. York, like Lancaster, is surrounded by rich farms and has factories of many kinds.



Fig. 147. Interior of a Pittsburgh glass factory

129. Cities and Industries of New Jersey.—In spite of the fact that New Jersey is a small state, it has a large population (Fig. 80) and many important industries. The greater part of its people live near the Hudson River opposite New York, and near the Delaware River opposite Philadelphia. Many lines of railroad cross the state from the west on their way to New York, or to join the two cities.




Fig. 148. Making thread, Newark. This machine winds the thread on small spools

In northern New Jersey the cities nearest New York are Hoboken, Jersey City, and Bayonne. They lie along the southern extension of the Palisades ridge on the west bank of the Hudson. Here are the terminals of the railroads from the interior, except the Pennsylvania and the New York Central (Sec. 121). Several of the chief lines of Atlantic steamships have their docks on the New Jersey side of the river, where it is convenient to transfer, from car to ship, goods that are being sent to Europe. Bayonne has refineries for petroleum; the oil is received by pipe lines from the wells of Pennsylvania, Ohio, and other states (Sec. 113). Jersey City has large slaughterhouses, soap factories, and many other manufactures.

The largest of New Jersey cities is Newark, with copper smelters and manufactures of leather, jewelry, paints, thread, and many other things (Fig. 148). Paterson is the great silk center (Fig. 137). Passaic makes textiles. Perth Amboy, at the mouth of the Raritan River, has an excellent harbor, with dry docks and shipyards. Through this port and Elizabeth is shipped much coal from the mines of Pennsylvania. Both these cities

smelt and refine copper, and Elizabeth manufactures sewing machines and wire.

All the New Jersey cities already named, with many other cities and towns, are places of residence for people who work in New York.

Camden is near Philadelphia. Here ships are built, and leather, pens, and talking machines are manufactured. The city is also a residential city for many who work in Philadelphia.

Trenton is at the head of navigation on the Delaware River. It has water power (Sec. 47), large pottery works and other industries, and is the state capital. New Jersey produces more pottery than any other state in the Union except Ohio. Trenton produces about half of the output of the state. China, white granite ware, and porcelain are made. Much of the raw material is obtained from other states.

Several towns in the southern part of the state manufacture glass. Atlantic City is a place of both summer and winter resort, being relatively cool in summer and mild in winter. The village of Princeton is the seat of Princeton University.

Review.—1. Give reasons for the growth of the city of New York. 2. Compare the Hudson and Mohawk Valley route with other routes across the Appalachian Mountains. 3. What boroughs form Greater New York? 4. Describe the various means of transportation in the city. 5. What share of the foreign trade of the United States passes through the city of New York? 6. Describe the kinds of homes in a great city.

7. Give an account of the Erie Canal. 8. What route leads from New York to Montreal?



Fig. 149. Lake Placid, in the Adirondack Mountains

These have been purchased by the state of New York and reserved for the use of the people. Most of these spring waters are believed to be helpful in curing certain diseases, and people come even from distant places to drink them.

Review by States. ~~A~~New York (N.Y.). 1. Describe

9. What reasons can you give for the growth of Buffalo? 10. What is a grain elevator? 11. What important products pass through Buffalo?

12. Give an account of the origin of Pennsylvania and Philadelphia. 13. What historical events have taken place in Philadelphia? 14. What ways of communication has it, by land and sea? 15. What are its principal industries?

16. What rivers unite at Pittsburgh? 17. Give facts about the history of Pittsburgh. 18. How is the iron ore of the Lake Superior district brought to Pittsburgh? 19. Where is the coal found which is necessary for melting the ore? 20. How is coke made? 21. Why is limestone used in the blast furnace? 22. What is pig iron? 23. How does steel differ from pig iron? 24. What is wrought iron? 25. What other mineral industry is important in Pittsburgh? ~~X~~

RESORTS

130. Places of Resort.—Since the Middle Atlantic States have over 22,000,000 people, there is much need of places for recreation. In addition to the places of resort along the New Jersey and Long Island shores, there are many resorts among the mountains, especially in the Adirondack region (Fig. 149), where the state of New York has large forest reservations. In like manner, the wooded heights of the Catskills, the lakes of central New York, the Great Lake shores, and the mountains and water gaps of Pennsylvania afford rest and change to the toilers of town and city. Saratoga Springs has the most remarkable group of mineral springs on the continent.

the surface of New York. 2. Give an account of the drainage. 3. Bound the state and locate its capital. 4. On what river is Watertown? 5. Why is this city a favorable point for manufacturing? 6. Where are the wood pulp and paper factories of the state located? 7. Where is a market found for much of the product? 8. Draw from memory a sketch map of the Hudson River system, and on it locate ten cities, including centers for the making of electrical supplies, collars and cuffs, carpets, gloves, and knit goods. 9. Give the location and industries of Utica, Syracuse, and Rochester. 10. What are the chief regions for grapes? 11. Give the location of Binghamton, Ithaca, and Elmira.

New Jersey (N.J.). 12. Where is Sandy Hook? 13. To what physical region of the country does southern New Jersey belong? ~~X~~ 14. In what great cities do many people of this state do their work? ~~X~~ 15. What is an important industry in Trenton? 16. What important cities are near New York? 17. What city has large manufactures of silk? 18. Where are great petroleum refineries found? 19. What are the leading industries of Newark? 20. What is the density of population of New Jersey (Fig. 80)? How does this compare with that of your own state?

Pennsylvania (Pa. or Penn.). 21. Bound the state and locate its first city, its second city, and its capital. 22. What is a large industry in Williamsport? 23. What is the principal railroad system of the state? 24. What is the principal business in Altoona? In Johnstown? 25. What cities near Pittsburgh share its industries? 26. Where is the bituminous coal found? The anthracite? The natural gas? 27. Where is a rich farming district in the state? 28. Make a sketch map of the state, locating the principal rivers and cities. ~~X~~

THE SOUTH ATLANTIC STATES

131. Early Settlements. — The discovery of the New World was followed at once by active exploration, but many years passed before permanent settlements were established in what is now the United States. Although the Spanish government claimed title to all this region, it was never able to enforce the whole claim. As a result the northern part of the land now occupied by the South Atlantic States was explored and settled by the people of England.

The southern part of our country was, however, actually explored by the Spanish. To a large region in the southeast they gave the name Florida, which means "land of flowers" (Fig. 150). It was not until long afterward, when this region was divided into several states, that the use of the name was limited to the present state of Florida.

All of the early Spanish expeditions were sent out to search for gold, and the Spaniards cared little about settling in any part of the country where gold or silver could not be found. For that reason they established few permanent settlements, even in the southern part of the country.

The English also laid claim to much of the New World, and as they were able to enforce their claim they gave at first the name Virginia to the territory from which the original thirteen colonies were formed. The different parts of the region later received other names, but the name Virginia was kept by one of the states of the South Atlantic group. At first

the English settlers in the northern states of the group also wasted their time in a vain search for gold. Finally, however, they became more sensible, established homes, and began to cultivate the soil. Agriculture soon became profitable and it has steadily increased in importance down to the present time. Other industries have been established and many crops not at first cultivated have

been introduced. One of the most interesting of the recent industrial developments of our country has been the rapid increase of manufacturing in the South.

In no part of the country are the people more truly American than they are in the southern states — South Atlantic and South Central. Many of them are the descendants of the proud and cultured pioneers who settled here two or three hundred years ago, and some of them still own and cultivate the

land which their ancestors first subdued and brought under cultivation.

Most of the immigrants who have in recent years come to our country have settled near the northern ports where they entered, or have moved farther west. Very few of them have gone into the southern states.

The negroes in the southern states form a large part of the population. Most of them are good workers who recognize the southern white man as their friend, and who find opportunity for profitable employment in the old as well as in some of the new industries of the South.



Fig. 150. Tropical vegetation in Florida



Fig. 151

Physical and Political

SOUTH ATLANTIC STATES

Scale of Statute Miles
0 60 100 150 200
12 1/2 MILES TO ONE INCH

Capital of Country thus: ● Capitals of States thus: ○

ELEVATIONS IN FEET

[Dark Orange Box]	OVER 5000
[Orange Box]	2000 TO 5000
[Light Orange Box]	1000 TO 2000
[Yellow Box]	500 TO 1000
[Green Box]	SEA LEVEL TO 500

THE SOUTH ATLANTIC STATES

	AREA, Sq. MI.	POPULATION, 1920	CAPITAL
Delaware . . .	2,370	223,003	Dover
Maryland . . .	12,327	1,449,661	Annapolis
Dist. of Columbia	70	437,571	—
Virginia . . .	42,627	2,309,187	Richmond
West Virginia . .	24,170	1,463,701	Charleston
North Carolina . .	52,426	2,559,123	Raleigh
South Carolina . .	30,989	1,683,724	Columbia
Georgia . . .	59,265	2,895,832	Atlanta
Florida . . .	58,666	968,470	Tallahassee

Map Study.—1. Which of the South Atlantic States are partly in the Appalachian Mountains?

2. What rivers discharge their waters into the Chesapeake Bay? 3. What river has its source in Virginia and its mouth in Albemarle Sound? 4. Trace the course of the Kanawha River. What name has its upper part? 5. Which is the longest river in North Carolina? 6. What states in this group are separated by a river?

7. Which state of this group has many lakes? 8. Locate the Dismal Swamp; the Everglades. 9. Where are the Florida Keys?

10. Which state of this group has no sea-coast? 11. Has this state any communication by water? 12. Which state has the longest coast line?

13. Name and locate the capital of Georgia; of Virginia. 14. Name and locate two seaports of the same name, one in Delaware and the other in North Carolina. 15. Name the chief seaport of Georgia; of South Carolina; of Virginia. 16. Name and locate the southernmost city of this group.

PHYSICAL FEATURES

132. Surface and Drainage.—The South Atlantic group includes the seven states of Delaware, Maryland, Virginia, North Carolina, South Carolina, Georgia, and Florida fronting on the Atlantic, and the inland state of West Virginia. As

a study of the map (Fig. 151) will show, almost the entire group of states is included in the Atlantic Lowland (Sec. 47) and the Appalachian Mountains (Sec. 48). West Virginia is the only state in the group that includes any part of the Appalachian Plateau (Sec. 49).

The Atlantic coastal plain (Figs. 61, 152) includes nearly all of Delaware, more than half of Maryland, the eastern parts of Virginia and the Carolinas, and large sections of Georgia and Florida. We have already learned why this long belt of lowland is called the Tidewater country (Sec. 47). Not only are the lower parts of the rivers tidal, but many of them flow into broad bays due to the sinking of the coast. Of such bays, the Chesapeake is the greatest. The Potomac, Rappahannock, and James rivers flow into it, and its harbors and approaches are deep enough for the largest ships.

Farther south, indenting the mainland of North Carolina, are two large sounds, Albemarle and Pamlico. Into Albemarle Sound flow the waters of the Roanoke and a number of smaller rivers; and Pamlico Sound receives the waters of the Pamlico and Neuse rivers. These sounds were formed in the same way



Fig. 152. Logs ready for the mill on the coastal plain of South Carolina




Fig. 153. Canal in the Dismal Swamp

as the Chesapeake Bay, but their waters are shallow and can be safely used only by smaller vessels. They are separated from the ocean by a long chain of narrow, sandy "barrier" beaches, built up by the waves and winds. From these beaches a number of capes extend into the ocean, and the shoals near them are very dangerous to navigation. Off Cape Hatteras is one of the most stormy and dangerous parts of the Atlantic.

Farther to the south, the bays are smaller, but they too are due to the sinking of the land; and the rivers, such as the Savannah, admit the tides to the inner edge of the coastal plain.

A flat country close to the sea level may have many swamps. The South Atlantic States have several that are very large. One of them is the famous Dismal Swamp, 30 miles long and 10 miles broad, in Virginia and North Carolina. A part of it has been drained by a canal cut through from Norfolk, Virginia, to Elizabeth City in North Carolina, and much of the drained area has been cleared and brought under cultivation. The Dismal Swamp Canal (Fig. 153) is one of the works that make it possible for the smaller ships engaged in the Atlantic coast trade to make

use of 2500 miles of protected inland waterways; other canals so used are Cape Cod Canal and the canal connecting Delaware and Chesapeake bays.

A much larger swamp is the Everglades of southern Florida (Fig. 154). The central part appears to be occupied by shallow water covering a layer of muck. In this muck, tough, sharp-edged saw grass takes root and grows to a considerable height. In the shallow waters are also many islands, some large and some small, covered with a dense growth of grass, underbrush, and trees. So luxuriant is the growth of saw grass, and so intricate is the maze of waterways, that parts of the Everglades are difficult to explore. As in the Dismal Swamp, however, large parts of the Everglades have been drained by canals and brought under profitable cultivation.

Many of the rivers, such as the Potomac and the James, are large streams where they cross the Fall Line (Sec. 47), and the rapids and falls there furnish water power. Among the larger cities that have grown up on or near the Fall Line are the following: Washington and Alexandria on the Potomac River; Richmond on the James; Raleigh near the Neuse; Columbia in South Carolina; Augusta on the Savannah, in Georgia; and Macon, also in Georgia.

Just west or northwest of the coastal plain is the Piedmont Plateau (Sec. 47). Most of this region is a rolling upland from 500 to 1000 feet above the sea; it is a belt of good farming land.



Fig. 154. A treeless part of the Everglades




Fig. 155. Mt. Mitchell, North Carolina




Fig. 156. Stalactites in the Luray Cavern

The Appalachian Mountains rise steeply from the Piedmont. The eastern part of these mountains is the Blue Ridge (Figs. 16, 64). The Potomac cuts through the Blue Ridge by a deep gorge at Harpers Ferry. Southward the Ridge rises, broadens, and includes Mt. Mitchell (Fig. 155) and other peaks in North Carolina (Sec. 14). The mountains continue into South Carolina and northern Georgia. In the heart of these mountains in North Carolina is Asheville, 2000 feet above the sea, and surrounded by forests and peaks. This region is one of the most popular of the southern summer resorts. It is often called the "Playground of the South."

133. The Great Appalachian Valley.—West of the Blue Ridge, in Maryland, Virginia, and West Virginia, are other ridges belonging to the Appalachians. But directly west of the Blue Ridge these other mountain ridges are so much worn down that a broad valley runs between mountains on either side, through Maryland and Virginia, into Tennessee and Alabama. This is the Great Appalachian Valley. In Virginia it contains the


Shenandoah River and part of the upper James; and in southwestern Virginia and Tennessee it is drained by the Tennessee River and some of its tributaries.

This is not a valley carved out by a single stream, but one that has been made by the wasting of softer rocks, between mountain ridges of harder rocks. Many of the rock beds (Sec. 45) in the Great Valley are of limestone. Water slowly dissolves them, and this is one reason why there is a valley. Where water works for a long time underground in limestone it makes *caverns*. In places some of the dissolved lime may be

deposited again by the evaporation of dripping waters, so that beautiful pendants, called *stalactites*, are formed. This explains the shaping of the Luray Cavern (Fig. 156) in the Great Valley in Virginia. In places a stream may flow some distance underground in a cavern, wearing away the bottom and sides. When most of the roof falls in, leaving a little still standing, we have a natural bridge. The best known of such formations is the Natural Bridge in the Great Valley of Virginia (Fig. 157).



Fig. 157. The Natural Bridge. Height, 263 feet. On the top is a road



134. Climate.—This group of states extends from about 25° to about 40° north latitude. The difference of nearly 15° in latitude makes much difference between the temperatures of northern Maryland and of southern Florida (Secs. 25 and 59). There is rarely a frost in southern Florida, while on the coastal plain in Maryland and Virginia freezing weather may occur from late October to early April. In central Florida the growing season averages 300 days, and on the plains of Virginia 200 days. Even this is 50 days longer than in central New York or Nebraska (Fig. 71).

The effects of altitude in these states are marked. On the low coastal plain flourish crops requiring a relatively high temperature, such as cotton and rice. The cooler Piedmont and mountain valleys grow such crops as corn, hay, tobacco, and wheat, common

crops of temperate regions. In the mountain forests are trees of the kinds found in the lowlands farther north. There are numerous summer resorts among the mountains, for the days there are pleasantly cool even when the lowlands are hot.

The nearness of the sea makes the lowlands much warmer in winter and slightly cooler in summer than they would otherwise be. The waters of the Gulf Stream are near the shore, and south winds bring the warm, moist air to the land. This explains the heavy rainfall of all this coast region and of the southern Appalachians (Sec. 60).

Occasionally a tropical cyclone, or *hurricane*, originating in the West Indies, moves northward over the eastern United States or along the Atlantic coast (Fig. 158).

St. Augustine, Jacksonville, Palm Beach, Miami, Tampa, and other cities in Florida are places of resort for many who, for the sake of health and for pleasures in the open air, seek to escape the severe winters of the northern states. St. Augustine, originally a Spanish settlement, is known as the oldest city on the mainland of the United States. It was founded in 1565.

Review. 1. What physical regions are included in the South Atlantic States? 2. What has resulted from the sinking of the coast? 3. Where is Cape Hatteras, and for what is it well known? 4. Name and locate two large swamps on the coastal plain. 5. For what is the Fall Line important? 6. Describe the Piedmont Plateau and state why it is so called. 7. Where is Harpers Ferry? 8. Where is Asheville and what is its altitude?

9. What rivers flow in the Great Appalachian Valley? 10. What cavern is found in this valley in Virginia? What are stalactites? 11. How may a natural bridge be formed?

12. About how many degrees of latitude are covered by this group of states? About how many miles, allowing 69 miles for each degree? 13. Give the length of the growing season in Virginia and in Florida. 14. How does the climate of the coastal plain differ from that of the lands farther west? 15. What storms affect the coast region?

MINERAL WEALTH AND FORESTS

135. Useful Minerals and Rocks.—The chief natural wealth of the South Atlantic States is in their thousands of square miles of good soil. In most of these states building stones, clay, and cement materials also abound. The soft coal belt surrounding Pittsburgh extends through western Maryland and is very important in West Virginia (Fig. 159). Coal is mined also in Virginia. West Virginia has much petroleum and is rich in natural gas. The mineral mica, which splits into thin, transparent sheets and is generally used in stoves, is more extensively mined in the mountains of North Carolina than anywhere else in the United States. Small quantities of gold are found in the mountain belt. Beds of phosphate rock occur in parts of Florida and South Carolina, and large quantities are mined for use as a fertilizer. Iron ore also is found, and West Virginia manufactures much iron.

136. Hardwood Forests.—The hardwood forests are most extensive in North Carolina, but are found in all the states that reach into




Fig. 160. Part of the Appalachian National Forest

the mountains. The common kinds of trees in these forests are oak, ash, maple, chestnut, hickory, black walnut, and birch. A large amount of lumber is produced, and in some regions the forests have been entirely cut away. On the slopes thus left bare the heavy rains have cut gullies and washed away much soil (Fig. 122). In such regions, after each rain storm the water flows into the streams very quickly, making disastrous floods down the river valleys; and when the dry season comes on there is often not enough water to furnish power for mills and factories. In order to preserve some of the forests, protect valleys from floods, and maintain water power, the government is acquiring land for an Appalachian forest reservation (Fig. 160).

137. Pine and Cypress.—In Georgia and other states a hard pine, with long leaves, abounds. This is known as Georgia pine. The wood is especially good for floors and other interior work. The cypress is another common tree of the southern coastal plain, and is now much used for building material.




Fig. 159. Coal mine and coke ovens, West Virginia

138. Turpentine and Tar.

—Pine trees abound in all the coastal states from North Carolina to Texas, and their sap is used for making turpentine, rosin, and tar. The great pine belt that stretches along the Atlantic coast from North Carolina to Florida furnishes about nine tenths of the world's supply of these products. The trees are tapped and the sap is caught in earthen jars or buckets fastened to the trees (Fig. 161). The sap is distilled to form turpentine, and what is left is rosin. Pine tree roots, as well as other parts of the trees, are used in the manufacture of tar. The tar may be made by burning the wood under a cover of earth to keep out most of the air, or by heating the wood in a closed retort or oven.

North and South Carolina formerly led in this industry, but Florida and Georgia now lead, and these *naval stores*, as turpentine, rosin, and tar are called, are made also in Alabama, Mississippi, and Louisiana. Much of the product goes to the port of Savannah to be shipped to the various markets.



U. S. Dept. of Ag., Forest Service

Fig. 161. Gathering pine sap, Ga.

AGRICULTURE AND OTHER INDUSTRIES

139. Tobacco.—The tobacco plant is a native of the New World and hence was not known in Europe or Asia until America was discovered. The raising of tobacco was first developed as an important industry in the colonies of Virginia and Maryland. During the early days tobacco was used in place of money, and for a long time it was one of the largest exports to Europe. The ships sailed up the

tidal rivers to the farmer's wharf and took his crop of tobacco to London. In time the culture of tobacco spread into the Carolinas and across the mountains to Kentucky and Tennessee. Although mainly cultivated in these southern states, it also grows farther north, especially in Ohio, Wisconsin, Pennsylvania, and Connecticut (Sec. 86).

Almost all the tobacco in this country is raised east of the Mississippi River (Fig. 162). Kentucky grows the largest crop, and North Carolina ranks second, followed by Virginia and Tennessee, in the amount of tobacco produced. The fine quality of much of the North Carolina tobacco gives it special value, so that this state stands first in the value of its tobacco crop.

Richmond is a very large tobacco market and manufacturing center, and much tobacco is manufactured also at Durham and Winston-Salem in North Carolina, and at Key West and Tampa in Florida. A part of the tobacco used in Key West and Tampa is raised in Cuba.




Fig. 162. Tobacco-producing regions of the United States

140. Rice and Other Food Grains.—Some rice is raised in the four most southern states of the group, especially in the lowlands of South Carolina, which used to be the leading state in growing this crop. But Louisiana, Texas, Arkansas, and California are now by far the greatest rice-growing states, and more is said about this crop in describing the agriculture of the South Central States. Other cereals, or food grains, are raised in the South Atlantic States in larger quantities than rice,—among them wheat and especially corn. But the study of these cereals is taken up in connection with the North Central States, where the largest wheat and corn crops are grown.

141. Cotton.—Cotton was cultivated in India in southern Asia long before the New World was discovered, and cloth made from this "tree wool," as it was called, was very highly valued. Columbus found a variety of the cotton plant growing in the West Indies in 1492, and later explorers found cotton cloth in common use for clothing in Mexico. It was also well known in Peru and Brazil in South America. At the present time much cotton is grown in North America, Asia, and Africa, and smaller quantities in South America, southern Europe, and Australia. In the South Atlantic States cotton is grown from Virginia southward, chiefly in Georgia, South Carolina, and North Carolina.

There are several varieties of cotton, classified according



Fig. 163. Cotton bolls

to the length of the fiber. Most of the crop in our country has short fibers,—that is, from $\frac{5}{8}$ inch to $1\frac{1}{8}$ inches in length. The fiber of Egyptian cotton and some other varieties is from $1\frac{1}{4}$ to $1\frac{3}{4}$ inches long.

Cotton is raised on plantations; that is, on large farms devoted mainly to this

crop. In our country it is grown each year from the seed and can be produced only in regions which are free from frost for seven months of the year. About three months after planting, the blooms appear, and the seed pods, or bolls, are soon formed. To the seeds in the boll are attached the fluffy masses of white fiber, or lint. The bolls open as they ripen, and the pickers go over the fields several times to gather such of the masses of lint as are ready to be picked (Fig. 163). The lint, with seeds attached, is then taken to the ginhouse, where the cotton is ginned; that is, the lint is separated from the seeds.

It was really the invention of the cotton gin that made possible the development of



Fig. 164. Cotton-producing regions of the United States

the modern cotton-growing industry of the South. For years the lint had been separated from the seed by hand, a much slower and more expensive process. The gin is a machine that does this work of separating the lint from the seed, and its use has greatly lessened the cost of production. In one form of gin the lint is pulled from the seed by rollers which do not allow the seeds to pass between them. In another kind of gin the lint is pulled from the seed by the teeth of revolving saws.

The cotton lint, after being separated from the seeds, is pressed into bales of about 500 pounds each and sent to market. It may go to cotton mills in or near the state in which it is raised, or it may go to New England or to a foreign country. Vast

quantities of cotton are sold for the mills in England, and much goes to all the other great countries of Europe, for the United States raises about two thirds of the cotton supply of the world.

Texas raises more cotton than any other state. It is interesting to notice, however, that the area of Texas is almost twice as great as the combined area of North Carolina, South Carolina, and Georgia, which together have a cotton crop larger than that of Texas. Savannah and Charleston are the chief cotton ports on the Atlantic coast. From these ports the cotton goes by coasting vessels to northern cities, or by other ships to Europe.

142. Cotton Seed. — The cotton seeds, except those needed for the next year's crop, were formerly thrown away. Now the seeds are hulled and ground and the oil pressed

out. This cottonseed oil is used as a substitute for olive oil, is burned in miners' lamps, and is used in making cottolene, a substitute for lard. Both the cottonseed hulls and the meal that is left after the oil has been pressed out of the ground seeds, are used as food for stock. They are fed to dairy cows not only in our own country and Canada but also in several European countries.




Fig. 165. Making the warp for cloth in a southern cotton mill

143. Cotton Manufacture.—For a long time the cotton states sent away all their cotton, but now there are many mills in the South. These southern mills have been built near the Fall Line and in the Piedmont, where water power is furnished by the streams that flow from the upland forests. There are many great cotton factories in North Carolina,

South Carolina, and Georgia. The southern states now use more bales of cotton than they send to New England factories. The modern cotton mills of the South are among the finest in our country (Fig. 165). They give employment to many workers, and some of the goods manufactured find a ready sale in such widely scattered markets as Central America, South America, China, and Africa.

144. Peanuts and Other Crops. — Another crop of the South Atlantic States, particularly in North Carolina and Virginia, is the peanut, a semi-tropical ground nut. In the autumn the vines are pulled (Figs. 166, 167), the nuts are cleaned, and many are sent to Norfolk, in Virginia, to be shipped to various parts of this country and to Europe. The peanut is really an excellent food and it is now being prepared in several forms, such as peanut butter.



Fig. 166. A peanut plant



Fig. 167. Stacking peanut plants after they have been pulled

Another product, the sweet potato, is raised as far north as New Jersey. It grows best, however, in a warm, sunny climate with a long growing season, and the South is its natural home. It is very extensively used in the South, but part of the crop is sent to northern markets.

Tropical fruits are raised in Florida in great abundance, and this is one of our chief fruit-growing states. Of these tropical fruits the best known is the orange. The grapefruit (Fig. 168), which is much like the orange, is increasing in popularity for table use. It is light yellow in color, much larger than an orange, and has a slightly bitter taste. The pineapple crop also is large.

Throughout the South much interest is taken in the study of the best methods of agriculture. This "scientific farming," as it is called, has led to a large increase in production and an improvement in the quality

of the more important crops, as well as the introduction of many new ones.

145. Truck Farming.—In all the northern cities there is a market for fresh vegetables and fruits out of season, that is, long before they will ripen in the North. To meet this demand and that of the southern cities, truck farming has come to be a great industry on the coastal plain of the South Atlantic States. The use of cold storage and fast ships and trains makes it possible to carry such perishable products as strawberries, lettuce, radishes, and watermelons for long distances. Strawberries (Fig. 169) are a good example, for the ripening season begins in the far south in late winter or early spring, is later as we go northward, and occurs in June and July in the northern states. These differences in climate, with good transportation, make the strawberry market last several months in some cities.




Fig. 168. Growing grapefruit in Florida



Fig. 169. Shipping strawberries to northern markets

146. Fisheries.—

Oysters are found in the warm, shallow waters of many of the bays along the Atlantic and Gulf coast from Cape Cod to Galveston. They reach their best development along the Atlantic coast from Cape Cod to Cape Hatteras. The principal place for this industry is Chesapeake Bay, with Long Island Sound second in importance. The oysters are gathered up from the sea floor by the use of long-handled "tongs" or by means of a dredge, and several thousand boats are used by the oystermen in gathering them (Fig. 170). The oysters are landed at Baltimore, Hampton in Virginia, and other ports. Some are canned, but most of them are shipped fresh to market, even long distances, either in their shells or after being "shucked."

Atlantic waters yield also crabs and various fish, such as shad, Spanish mackerel, and menhaden. The menhaden are small fish used to produce oil and fertilizer.

147. Power Development. — The increasing need of power for the growing industries of




Fig. 170. Oyster boats at Baltimore

enough power to make the South one of the great manufacturing regions of the world.

Review.—1. Which of the South Atlantic States have coal beds? 2. Which has petroleum and much natural gas? 3. What use is made of phosphate rock? In which states is it found? 4. What other minerals are found in this group of states?

5. What will be the advantages of an Appalachian forest reservation? 6. What are the important trees of these states? 7. What substances besides lumber are made from some of them? How are they made?

8. Give some facts about the history of tobacco in the colonies. 9. What are the important states for raising tobacco? 10. What cities in the South Atlantic group are important in the manufacture of tobacco?

11. Name the most northern state in which cotton is raised. 12. Where is sea island cotton raised? What are its qualities? 13. Describe the cotton boll. 14. What is a ginhouse? 15. About how much cotton is contained in one bale? 16. What is the leading state in the raising of cotton? 17. Name two important ports for shipping cotton.

18. What are some of the products of the cotton seed? 19. What change has taken place in the location of cotton mills?

20. Where are peanuts grown? 21. What fruits are raised in Florida?

22. Give an account of southern truck farming for northern cities.

23. Where are the principal oyster fields? Name a center for oyster canning.

24. What parts of the South Atlantic States have much water power? Why?



Fig. 171. Dam and power house, near Spartanburg, South Carolina

CITIES AND
ROUTES OF TRADE

148. Seaports.—

On Hampton Roads, formed by the broad mouth of the James River where it joins Chesapeake Bay, are the cities and harbors of Norfolk, Portsmouth, and Newport News. Early vegetables (Sec.




Fig. 172. The overseas railroad to Key West

that reaches it across many islands and over many bridges (Fig. 172). Key West is a naval station of the United States, and is the headquarters for the sponge fisheries of the Gulf of Mexico. Tampa and Pensacola are the chief Gulf ports of Florida.

Delaware has one large city, Wilmington, which contains nearly half the people of the state. This city is near the Delaware River, at the junction of two small streams. Explosives, cars, and ships are among the chief products (Fig. 173).

Most of the cities on the Fall Line are inland places, at or near the head of navigation on some river. The greatest of the Fall Line cities, however, is Baltimore, a seaport near the head of Chesapeake Bay.




Fig. 173. Shipbuilding in Wilmington, Delaware

145), peanuts, and cotton are shipped from Norfolk, which is visited by steamships of many lines. At Newport News is a large shipbuilding plant. Near the city is Old Point Comfort, a place of resort; and a few miles up the James River is the site of Jamestown, the first successful English settlement in America.

Wilmington is the principal seaport of North Carolina, Charleston of South Carolina, and Savannah of Georgia. Wilmington's importance as a seaport is increasing. Among the industries of this city are the manufacture of lumber, the canning of vegetables and fruits, the extraction of oil from cotton seed, and the handling of naval stores. Savannah and Charleston are among the chief ports of the South engaged in shipping lumber and cotton.

Jacksonville, on the St. Johns River near the ocean, is the chief port on the Atlantic side of Florida. It ships the natural products of the lowlands that lie back of it, including oranges, garden truck, and lumber. Key West, built on an island off the coast of Florida, is joined to the mainland by a railroad




Fig. 174. Chesapeake Bay region

Largely because of its position, it has grown to be one of the leading commercial and manufacturing cities of the country. It contains more than half of the population of Maryland, and is the largest city in the South Atlantic group of states. It was named for Lord Baltimore, the founder of Maryland.

Ships of several Atlantic lines run between Baltimore and European ports. The Baltimore and Ohio Railroad, begun as one of the earliest of American railways, extends westward from Baltimore to the Ohio River, Cincinnati, St. Louis, and Chicago. The city is on the main line of traffic which joins the northeastern cities to the national capital and the South. The chief manufactures of Baltimore are metal goods, clothing, and fertilizers. The canning of fruit, vegetables, and oysters is an important industry.

Baltimore is the seat of Johns Hopkins University.

Annapolis is the capital of Maryland and is the seat of the United States Naval Academy.

149. Other Important Cities.—Cumberland, in the mountains of Maryland, is a railroad center, and deals in coal, lumber, and iron. Of the larger cities of West Virginia, Wheeling and Huntington are on the Ohio River, and Charleston, the capital, is on the Kanawha. Wheeling is not far from Pittsburgh, and like its larger neighbor it is engaged in the smelting of iron and the manufacture of iron products. Huntington has manufactures of railroad cars and glass. Clarksburg is another important center of glass making.

Richmond, the capital and chief city of Virginia, is at the head of navigation on the

James River. Not only is it a great center for the manufacture and marketing of tobacco, but it has large locomotive works and other factories. At Roanoke are large railway repair shops. Lynchburg and Petersburg are other manufacturing centers. At Charlottesville, in the Piedmont country, is the University of Virginia, one of the oldest and best known of American universities.

Through lines of railroad run from Baltimore and Washington, along the coastal plain,

to Florida. The country is so flat that little grading was necessary in building the roads. Another line runs from Richmond through the Piedmont region, to Atlanta, the capital of Georgia. On this line are several manufacturing cities, including Danville, Virginia, the center of a rich tobacco region;



Fig. 175. A business street in Atlanta

Charlotte, North Carolina, and Spartanburg, South Carolina, both of which are centers of cotton manufacture. Raleigh, the capital of North Carolina, is on another division of the same road. Other railroad lines pass from Baltimore, Washington, and Richmond, through gaps in the Blue Ridge, into the Great Appalachian Valley (Sec. 133). They run through this valley southwestward, to Chattanooga in Tennessee, and Atlanta, the capital of Georgia.

Atlanta is at the southern end of the Appalachian Mountains, where the railroads of the Piedmont belt and the Great Valley meet. Railroads also join Atlanta to Savannah, and to the important Gulf ports and western cities. After Baltimore and Washington, Atlanta is the largest city in this group of states. Atlanta is called the "Gate City," and has large wholesale houses and mills and factories

of many kinds. Forests, cotton fields, coal, and iron are not far away. Some of the largest cotton mills of the South are located here. Having abundant raw materials for mills, and being a railroad center, Atlanta is a progressive and growing city (Fig. 175).

Augusta, Macon, and Columbus, on the Fall Line, have large cotton mills.

Jan 5 1925
Review.—1. What cities are on Hampton Roads? 2. Name the chief ports of North Carolina and Florida. 3. Give the location of Wilmington, Delaware, and name its chief industries. 4. To what physical region does all of Delaware belong? 5. What means of communication, by land and water, has Baltimore? 6. What are its leading industries?

7. Give the location and industries of Wilmington, North Carolina. 8. What are the Fall Line cities of Virginia? 9. Give an outline of the railroad connections of Atlanta. 10. What are the important industries of Wheeling?



Fig. 176. The Capitol at Washington

THE NATIONAL CAPITAL

150. Washington. ^PBetween Virginia and Maryland is the District of Columbia, containing the national capital. ¹²The limits of the city and those of the district are the same. The district is under the authority of Congress. This place was selected for the capital in 1790, and George Washington marked out its boundaries in 1791. The city is not far below the Falls of the Potomac, and is therefore near the Fall Line. Washington is called "the city of magnificent distances." This name was first given because the city was planned so large and the buildings were far apart.

Among the notable buildings are the Capitol (Fig. 176), the White House (Fig. 177), which is the home of the President, the Congressional



Fig. 177. The White House, Washington

Library, the National Museum, and the buildings of the various departments of the government. Washington is now beautiful, and when present plans are carried out it will be one of the finest of all cities. It is the headquarters of many organizations, and is the seat of several universities, including Georgetown University, George Washington University, and the Catholic University of America.

Washington has nearly half a million inhabitants. It has few manufactures, and its trade meets only the daily needs of its people. It is thus very different from Baltimore, Pittsburgh, or Boston. It has grown because it is the capital of a great country. Some officers of the government live here during a part of the year, and many thousand workers in the various government departments make their homes in Washington. In addition, the foreign embassies make it necessary for a considerable number of people of other nations to live in the city, and there is a throng of visitors who, for politics or pleasure, come to the national capital at all seasons.

Review by States. — Maryland (Md.).

1. What kind of surface has eastern Maryland? western Maryland? 2. What river discharges its waters into the head of Chesapeake Bay? 3. What important river is on the border of the state? 4. What is the largest city of Maryland? 5. From what states can coal readily be brought to Baltimore? For what is this coal used? 6. What is the chief product of the waters of Chesapeake Bay? 7. What is the density of population of Maryland (Fig. 80)? How does Maryland compare with your state in this respect?

Delaware (Del.). 8. Compare Delaware with Rhode Island, in size and in population. 9. What waters are on the east of the state? 10. What is the chief city? 11. What are its leading industries?

District of Columbia (D.C.). 12. Give some facts about the history of the national capital. 13. How does it differ from other large American cities? 14. What classes of people make up much of its population? 15. Why is the capital not more centrally located with reference to our country as a whole?

Virginia (Va.) 16. On what river was the earliest English settlement in America made? 17. Where is the Fall Line on this river? 18. To what regions does the surface of Virginia belong? 19. What are the seaports of Virginia? 20. What important product is marketed and manufactured in Richmond? 21. Make a sketch map of Virginia, showing the boundaries, the Blue Ridge, and the chief rivers and cities.

West Virginia (W.Va.). 22. To what region does this state mainly belong? 23. What city stands where the Potomac flows through the Blue Ridge? 24. To what great coal field do the West Virginia coal beds belong (Fig. 127)? 25. What navigable river is on the border of the state? 26. What are the chief cities of West Virginia? 27. What are their industries?

North Carolina (N.C.). 28. Describe the surface of North Carolina. 29. What two sounds are along the shore line? 30. Why have these waters no great seaports? 31. What is the chief seaport of this state? 32. Give the name and location of the capital. 33. Name a city of the Piedmont belt. 34. What is the principal city in the Appalachian belt? Why is it much visited? 35. Name the chief products of North Carolina.

South Carolina (S.C.). 36. What is the chief port of South Carolina? 37. What city is on the Fall Line? 38. Why has South Carolina become a cotton-manufacturing state? 39. What parts of South Carolina produce sea island cotton? 40. What are the exports of Charleston?

Georgia (Ga.). 41. What kind of surface has southern Georgia? 42. Where are the mountainous districts of the state? 43. To what kind of tree has the state given a name? 44. What is the chief seaport of Georgia? 45. Name three products that would naturally come here in large quantities, for shipment. 46. What is the largest city of the state? 47. Where is it located? 48. What great railroad routes give it communication? 49. What are its chief industries? 50. Compare its population with that of Richmond, Baltimore, and Albany (see table of Cities in the Appendix).

Florida (Fla.). 51. Has Florida any uplands? 52. Has Florida any beds of coal? 53. Would the state be likely to become a manufacturing center? 54. What are the chief products of the soil? 55. What fertilizer is found here? 56. What are the principal seaports? 57. What fact is of special interest in the situation of Key West? 58. What ancient Spanish settlement is in this state?

THE SOUTH CENTRAL STATES

151. Early Settlement.—Within the South Central region are some of the oldest and some of the newest settlements west of the Appalachians. Originally explored by the Spanish, much of the region was later claimed and partly settled by the French, who approached it from the north by way of the Mississippi Valley, as well as along the Gulf coast.

There were two reasons why Frenchmen were so active in exploration. The first of these was that they were anxious to convert the Indians to Christianity, and with most of the expeditions the Catholic missionary went as a leader. The other reason was that the French early learned to make a profit out of the fur trade, and each expedition sought to gain in that way.

Most of the territory east of the Mississippi River was taken from France by the English in war (1754-1763), and afterwards was made part of the original United States. By the Louisiana Purchase of 1803 (Sec. 66), our own government secured a vast territory west of the Mississippi River.

In the early days frontiersmen from Virginia and other states followed the Great Appalachian Valley into the region that is now eastern Tennessee and made homes there. On the western side of the valley is a deep gap in the Cumberland Mountain (Fig. 178). Through this gap Daniel Boone and others

made their way to the Blue-grass country. These daring pioneers hunted, built log cabins, fought the Indians, and laid the foundations of the first states west of the mountains, Kentucky and Tennessee.

For many years Texas was a part of Mexico, but in 1836 the Texas people declared themselves independent, and nine years later Texas became a part of the United States. This added to our country a vast territory of fertile fields and rich grasslands, for Texas is by far the largest of our states.


For a long time Oklahoma was known as the Indian Territory, because many Indians were placed there on reservations by the government. When the western half — the first to be called Oklahoma — was opened for settlement




Fig. 178. North wall of the Cumberland Gap, through which Boone made his way

by white people (beginning in 1889), there was a rush for homes and farms, and within a few years it had a population of several hundred thousand. The eastern half was Indian Territory until 1907. There are now more Indians in Oklahoma than in any other state.

Throughout this entire South Central region agriculture and grazing were for many years almost the only industries of importance. Later lumbering also became important. In recent years the discovery of useful minerals and of the mineral oil, petroleum, has led to much activity in mining and to a rapid development of manufacture in metals.





THE SOUTH CENTRAL STATES

	AREA, Sq. MI.	POPULATION, 1920	CAPITAL
Kentucky . .	40,598	2,416,630	Frankfort
Tennessee . .	42,022	2,337,885	Nashville
Alabama . .	51,998	2,348,174	Montgomery
Mississippi . .	46,865	1,790,618	Jackson
Arkansas . .	53,335	1,752,204	Little Rock
Louisiana . .	48,506	1,798,509	Baton Rouge
Oklahoma . .	70,057	2,028,283	Oklahoma City
Texas . .	265,896	4,663,228	Austin

Map Study.—1. What states belong to the South Central group? 2. Which of them border the Mississippi River on its east bank? On its west bank? 3. Which have no sea-coast? 4. Give the boundaries of Texas.

5. What is the most conspicuous feature of the shore line? 6. Find two cases in which a bay and a city on its shore bear the same name.

7. What rivers serve, for a part of their course, as state boundaries? 8. Trace the course of the Tennessee River; of the Cumberland River. 9. What rivers of this group of states enter the Gulf of Mexico east of the Mississippi River? West of the Mississippi River? 10. Trace the course of the Red River; of the Canadian River.

11. A degree of latitude covers about 69 miles. Refer to the map of the South Atlantic States and find how much farther south Florida extends than Texas.



Fig. 180. Memphis, on the bluffs along the Mississippi River

12. Name and locate the capital of Tennessee; of Texas; of Oklahoma. 13. Locate Houston and Dallas in Texas; Louisville in Kentucky. 14. What large city is in north-central Alabama? 15. What large city is on the Mississippi River, not very far from its mouth?

PHYSICAL FEATURES

The South Central group includes eight states, of which four border the Gulf of Mexico, namely, Alabama, Mississippi, Louisiana, and Texas. The interior states of the group are Tennessee and Kentucky on the east of the Mississippi River, and Arkansas and Oklahoma on the west.

152. Gulf Plains.—The southern parts of the Gulf states are flat lowlands. In all the states except Louisiana and parts of Mississippi, these lowlands are coastal plains, like that of the South Atlantic States. That is to say, they are old sea bottoms that by elevation have become dry land.

153. Mississippi Flood Plain and Delta.—The surface of Louisiana is a plain made mainly by the Mississippi River and its branches, in the form of delta and flood-plain deposits (Secs. 18, 20). To make the lowlands of the coastal plain, a sea bottom has risen above sea level. To make the river plains, a shallow sea has been filled by waste brought from the land.

Below the mouth of the Ohio River the Mississippi flows through flood plains many miles wide. They are bordered in a number of places by high bluffs on the east or west. Memphis in Tennessee, and Vicksburg and Natchez in Mississippi, are examples of cities perched on these bluffs, overlooking the river and its lowlands (Fig. 180). In Louisiana the flood plain merges into the delta which forms the southern part of that state. Here many channels, or distributaries, break off from the main river and enter the sea at several points, thus distributing the water of the river to various parts of the sea border.



Fig. 181. A Mississippi levee in time of high water. Notice that the houses are at a lower level

154. Levees.—When a river overflows, it drops some of its muddy load on its banks. This makes the ground next the stream higher than the ground farther back from the river. Along these banks man builds high embankments called *levees* (Fig. 181), to keep the river from flooding the lower lands back from the channel. Many levees have been built along the banks of the lower Mississippi. During the ordinary stages of high water they afford ample protection to thousands of square miles of the bordering lowlands. But when a break, or *crevasse*, is made in a levee, or when the water rises so high as to overflow it, widespread and disastrous floods occur, doing great damage to cities and to farms.

In the lowlands on each side of the main stream, in parts of the flood plain as well as in the delta, there is a network of small streams called *bayous*. The stream channels are poorly defined, and much of the land which separates them is swampy and is covered with a heavy growth of underbrush.

155. Floods.—We can understand why the Mississippi River is subject to floods. Its great eastern branch is the Ohio, and from that tributary the Mississippi receives the greatest part

of its flood water. Look at the map and see how the branches of the Ohio reach into the highlands, all the way from New York to Alabama. All these highlands have ample rainfall. Consequently there is much water to flow from them, and as the slopes are steep, the rivers rise rapidly after a storm, and the lower Ohio and lower Mississippi are flooded. Reservoirs to hold back these flood waters have been proposed, but their construction would be very expensive. The Weather Bureau keeps flood stations on the Ohio River, the Mississippi, and many other rivers, to warn people of the rising of the waters, so that they can guard against damage to shipping, wharves, buildings, and crops (Fig. 182).




Fig. 182. Cities where the government maintains flood stations




Fig. 183. Jetties at the mouth of the South Pass of the Mississippi

156. Meanders.—The lower Mississippi has many bends (Sec. 19). It often cuts across the necks of these bends and leaves them as crescent-shaped lakes. Where the river is the boundary, such a change may transfer a farm from one state to another. The lower course of the river changes so much by cutting its banks and filling its bed that navigation is always difficult and sometimes dangerous. It requires much skill to pilot a Mississippi steamer.

157. Jetties.—Where the Mississippi enters the Gulf of Mexico it deposits a part of the load of mud that it is carrying and makes the water shallow (Sec. 20). For many years after New Orleans was settled the shallow waters at the mouth of the river did not seriously interfere with the commerce of the city. Ships at that time were small and had little difficulty in reaching the city to unload their cargoes and load again.

As the country grew and commerce increased it became more profitable to use large ships. These larger ships sank deeper into the water and found greater difficulty in reaching New Orleans from the Gulf. It became necessary to use small vessels called lighters in loading and unloading the larger ships, which remained in the Gulf at the mouth of the river. This was so expensive that the United States government decided

to remedy the trouble by building jetties at the mouth of the South Pass.

The jetties are artificial river banks which narrow the river channel and thus make the water flow faster. As a result the river is not only able to carry along the material which it formerly dropped, but it is also able to pick up fine particles of mud and thus scour the channel deeper. The depth of the river channel is now about 30 feet. In building the jetties

piles were driven into the mud of the river bottom on each side, and mattresses, made by lashing together many slender willow trunks and branches, were sunk between the piles. The mattresses soon filled with mud and made a solid wall (Fig. 183).

158. Appalachian Valley.—Read what is said in Section 133 about the Great Appalachian Valley. On the map (Fig. 179), follow this valley from Virginia into Tennessee. Here on the Tennessee River are the cities of Knoxville and Chattanooga. The valley is 40 miles wide, has rich farms, and is bordered on the east by the "Great Smoky Mountains," as the southern end of the Blue Ridge is often called. On the west, the Cumberland Plateau rises by a steep slope above the valley. Looking again at the map, follow the valley from Tennessee through the north-west corner of Georgia into Alabama, until it runs out on the coastal plains. In this part of the valley is the city of Birmingham, with its iron furnaces and other industries.

159. Cumberland Plateau.—West of the Great Valley is the southern part of the Appalachian Plateau (Sec. 49). It is called the Cumberland Plateau, and forms a large part of Kentucky, central Tennessee, and northern Alabama. The Tennessee River leaves the Great Valley at Chattanooga (Fig. 25) and flows for much of its lower course through the plateau. The course of the Cumberland

River is also largely in the plateau. South of Louisville, in the southern part of Kentucky, is the famous Mammoth Cave. It is much larger than the Luray Cavern (Sec. 133), although formed in a similar way; indeed, it is the most extensive cave known. It has streams, waterfalls, many large rooms, and 150 miles of passages.

160. Blue-grass Region.

—In the north-central part of Kentucky is a region of about 10,000 square miles known as the "Blue-grass region" (Fig. 184). It is so named from a kind of grass that grows in the meadows and pastures. The soil is made by the wasting of the limestones which lie below (Sec. 105), and it is one of the finest farming soils in the world. The people throughout this region are very prosperous, as rich soils when properly farmed yield large crops, and these provide money for homes, food, and clothing, for education and travel.

161. The Region West of the Mississippi River.—This region varies much in surface and rainfall. West of the Mississippi are the lowlands of eastern Arkansas, which belong partly to the Arkansas River and partly to the flood plains of the Mississippi River. The western part of the state is an upland, with low, wooded mountains. These mountains extend westward into the eastern part of Oklahoma. In the interior of Texas, beyond the coastal plain, the surface rises sharply and becomes a part of the Great Plains (Sec. 51). In western Texas are mountains which rise at one point to an altitude of 9500 feet. Oklahoma has a large area of prairies like those of the North Central States. At the west it reaches



Fig. 184. In the Blue-grass region of Kentucky

into the belt of the higher and drier country called the Great Plains.

162. Climate.—The rainfall of the South Central States, east of the Mississippi River, varies from about 60 inches in southern Alabama, Mississippi, and Louisiana to about 45 inches in northern Kentucky (Fig. 72). It decreases in amount as the distance from the Gulf increases, because most of the rain that falls in these states sweeps over the land with the winds from the Gulf. The rainfall of western Texas and Oklahoma is less than that in the eastern part of the group. This is because the Gulf winds do not reach that western section, and moisture from the Pacific Ocean is shut out by the western mountains.

Along the coast the summer temperature is moderated by the Gulf winds and the heat is never extreme. Farther inland the summer temperature is somewhat higher. The winter temperature seldom falls to the freezing point along the Gulf. In the uplands and farther north, however, snow is not uncommon, and ice several inches in thickness forms on the surface of quiet waters during the coldest weather.

One of the climatic peculiarities of this group of states is the bitterly cold storms that sometimes sweep over the western part during the winter. During these storms, which blow from the north and are therefore called *northers*, the temperature occasionally drops 50° in a few hours.

The leading crops of the southern part of this group of states are those of warm countries. The crops of the northern part of the group are for the most part those of temperate latitudes.

Review.—1. What are the Gulf Plains, and where are they? 2. What state is mainly a plain made by the Mississippi River?

3. What are levees? 4. Along what part of the Mississippi has it been necessary to build levees? 5. What is a break in a levee called? 6. What are bayous? 7. What causes great floods in the lower Mississippi River? 8. How has it been proposed to check these floods? 9. How are the residents of flood districts warned of the approach of floods?

10. Describe the jetties at the mouth of the Mississippi River and state their use.

11. What cities of this group of states are in the Great Valley? 12. What name is given to the Appalachian Plateau in Kentucky, central Tennessee, and northern Alabama? 13. Where is the Mammoth Cave? 14. How are such caverns formed? 15. Give the name of the most fertile part of Kentucky and the reason for its fertility.

16. Which part of Arkansas is a lowland? By what rivers was it formed? 17. Which part of Arkansas is upland? 18. Describe the surface of Texas; of Oklahoma.

19. In what part of the South Central States is the rainfall heavy? Why? 20. Where is it very light? Why? 21. What are northers?



Fig. 185. A Texas cotton field

AGRICULTURE

163. Cotton (Secs. 141-143).—In spite of the fact that manufacturing is developing rapidly in the South, agriculture is still the most important industry of the South Central States. In all the states of this group except Kentucky, cotton is an important crop, and Texas is the leading state of the Union in its production (Figs. 164, 185). India is

second to the United States in the raising of cotton, and Egypt and China stand next; yet Texas raises more cotton than all India, and more than Egypt and China combined. Cotton is one of our largest exports to Great Britain, France, Germany, Italy, Belgium, and Japan.

When the cotton of the South Central States is ready to be shipped it is sent by rail or boat, principally to Galveston, Houston, New Orleans, and Mobile. Then, if it is to be sent abroad, it goes by ship to Liverpool, Havre, Bremen, Genoa, or some other port.



Fig. 186. Cotton compress, Oklahoma City

From these ports it is distributed to mills in many cities, and the finished cotton goods are sent to markets all over the world. Much of our cotton, however, is sold directly to the southern cotton mills or sent to mills in New England or the North Atlantic States.

There are many steps in the cotton industry, from the planting of the cotton seed to the cotton garment. Picking is almost the only one of the processes that is performed by hand (Fig. 185), and some cotton picking machines are in use.

164. Sugar.—Nearly all the sugar cane in the United States is raised in Louisiana, on the rich lands of the Mississippi delta. Some is raised in Georgia and in other states of the far South. Sugar cane is cultivated in nearly all the tropical and semitropical countries of the world. It was introduced into Louisiana by the French in 1751, but it was not until some varieties of cane from Java were introduced in 1820 that the industry became really important.

The plant grows from 10 to 16 feet high (Fig. 187). The stems are from one to two inches thick and contain a pith filled with a sweet juice, from which the sugar is made. Each cane is made up of sections connected by knots called nodes. Each node has a bud or eye, and if a piece of the



Fig. 187. Sugar cane in Louisiana

cane is planted, the eye will grow and produce a young cane. Therefore a part of each year's crop of cane is saved for planting, although seed could be used if necessary. The soil is usually prepared for the crop by throwing it up into ridges six or seven feet apart. A furrow is opened in the top of the ridge, and cuttings or whole canes are put in and covered with soil.

When the cane is ripe, it is cut close to the ground and taken to a mill where it is crushed between rollers to squeeze out the sweet juice (Fig. 188). By various processes, including boiling, this is changed into crude brown sugar and molasses. Much of the brown sugar is sent to refineries in northern cities, to be made into the various kinds of white sugar that we see on our tables.

Nearly all the sugar of the world was formerly made from cane. But it has been




Fig. 188. Mill where sugar cane is crushed




Fig. 189. Production of sugar cane and sugar beets in the United States

found that sugar can be made from some kinds of beets. As beets will grow in a cooler climate, many states and countries in the temperate latitudes can now make their own sugar. This way of getting sugar has made such progress that Germany and some other countries of Europe no longer import sugar, and some of them even export large quantities. Some beet sugar is made in the United States, but not so much as we use. Colorado, Michigan, Utah, and California are the leading beet sugar states, and beet sugar is made also in Idaho, Ohio, and other states (Fig. 189).

We import a great deal of cane sugar from Cuba and the Hawaiian Islands, and some from the Philippines, besides smaller quantities of beet sugar from Europe.

Sugar is made from the sap of maple trees in Vermont (Sec. 93) and in some other northern states, but the amount of maple sugar produced is very small compared with the cane and beet sugar production.

Sugar can be made also from the juice of sorghum, a tall plant that grows somewhat like corn, and is raised in many states for fodder and for making sirup.

165. Rice.—Rice belongs to the group of food plants known as cereals. Large crops are raised in southeastern Asia and the islands of the East Indies. It supplies the principal food of several hundred million people. It thrives only in a warm climate, and the best kinds of rice are grown on flat ground

where plenty of water can be used. During a part of the growing period such rice fields must be flooded, and this is done two or three times between planting and ripening. Upland rice does not require flooding, but little is grown.

When ripe, rice is harvested and threshed in much the same way as other grains. The kernel has a clinging hull, and the rice is put through a machine that removes this coat and polishes the grains, leaving them ready for market.

There is much level land in Louisiana, Arkansas, and Texas, so located that it can

be flooded by the use of water pumped from deep wells into a system of irrigation ditches. Such a region is well adapted to the rice crop, as it is easy to flood the fields for the planting season and yet drain off the water so that they will be dry during the harvesting of the crop (Fig. 190).

This makes it possible to harvest the



Fig. 190. Harvesting rice in Arkansas

crop by machinery instead of by hand. As the crop is afterward threshed by machinery the cost of production is still further lessened. Rice can thus be grown in our country for less than in China, where the work is all done by hand, even though the laborer in China is paid only a few cents a day for his work. Louisiana, Texas, Arkansas, and California are the great rice-growing states of our country; and South Carolina and a few other states produce smaller quantities.

More than two hundred years ago a Spanish sea captain, whose ship was in Charleston harbor for repairs, gave one of the citizens a handful of rice. The Charleston man planted it, and thus started the industry. The crop has increased very greatly in recent years, but not nearly enough is raised in this country to supply our people. Much of the rice that we import comes to us from Burma.

166. Other Crops.—Much corn is raised in every South Central state, but this grain is studied especially under the North Central States, where still larger crops are produced. Wheat is grown in Kentucky, Tennessee, and Texas, and large crops are raised in Oklahoma, which is just south of Kansas, one of the great wheat states of the North Central group.

Hemp is grown in Kentucky. It is a tall plant (Fig. 191) which yields coarse fibers used for making bags and the sails



Fig. 191. Cutting hemp, Kentucky

and cordage of ships. Much hemp is raised also in Russia. The Manila hemp that is brought to this country from the Philippine Islands comes from a different plant.

Kentucky leads all other states in the raising of tobacco; it produces about one third of the crop of the United States (Figs. 192, 162). As our country is a large exporter of tobacco, much of the Kentucky crop is sent to European countries. Louisville, on the Ohio River close to the tobacco district, is the greatest tobacco market in the country (Fig. 200), and has large tobacco factories.



Fig. 192. Cultivating tobacco in Kentucky

167. Cattle Raising.—In the drier part of Texas many cattle are raised, for grass will grow on the plains where there is hardly enough rain for cultivated crops. The cattle are pastured on ranches. Some of them are fattened for market on the home ranch, others are sent to farmers in the corn belt farther north to be fattened.

Review.—1. In what states of this group is cotton grown? 2. How does Texas rank as a cotton-growing state? 3. What are the chief cotton ports of the Gulf of Mexico? 4. Name some of the foreign countries to which our cotton is sent. 5. What work connected with cotton growing is still done by hand?

6. In what states is sugar cane grown? 7. Describe the plant and the method of cultivation. 8. What processes are necessary for making cane sugar? 9. From what other plants is sugar made?

10. To what group of useful plants does rice belong? 11. Where in this group of states is it raised? 12. Why can it be cultivated so cheaply in these regions? 13. How did the rice-growing industry get its start in this country? 14. Name two other cereals of which large crops are raised in this group of states.

15. What use is made of hemp fiber? 16. What state grows hemp? 17. From what other countries do we get hemp? 18. How does Kentucky rank as a tobacco-growing state? 19. What city is the greatest tobacco market in our country? 20. In what state are many cattle raised?

LUMBER AND MINERAL WEALTH

168. Lumbering.—There are great forests, especially of pine and cypress (Fig. 193), in the Gulf states, and hardwoods in the higher lands of the interior. These forests make this group of states one of the chief lumber regions of the country. Logs cannot be hauled on sleds as they can be over the snows of New England, and it is not a common practice to float them downstream to mills. In the Gulf Plains there is so little water power that the logs are hauled to mills which use steam for power. Many portable steam mills are set up in the woods. Such a mill is kept in one place until the logs of a small

district are worked up; then it is taken to some other part of the forest.

Memphis, the largest city in Tennessee, is on a bluff overlooking the Mississippi River. Across the river is Arkansas, and just to the south is Mississippi. These three states have extensive forests. As ships can reach Memphis from the Gulf, and as the city has

many railroads, it has become one of the chief lumber markets of the country, especially for hardwoods. Its factories make furniture and planing mill products, such as blinds, sashes, and doors.

The lumber industry is important also in many other cities and villages in the South. For example, Shreveport, the second largest city in Louisiana, is a lumber-manufacturing center, and the chief industries of Fort Smith in Arkansas are based on the lumber industry. They include the manufacture



Fig. 193. Cypress forest, Mississippi

of furniture, refrigerators, and wagons.

169. Iron and Coal.—Nearly all the states of this group have some coal, but the beds of coal in Kentucky, Tennessee, and Alabama are especially important. The soft coal beds about Pittsburgh in Pennsylvania extend westward into Ohio and southward into West Virginia, and continue southwest into the three states mentioned above (Fig. 127).

Texas and Arkansas have some iron, but the largest beds of the ore in this part of the United States are in Tennessee and Alabama, in the Great Appalachian Valley. There are also beds of limestone in the same region. As the iron ore and limestone are near the coal fields, it does not cost very much to bring together these three heavy materials for the manufacture of iron and steel.

Birmingham, in Alabama (Fig. 194), is in the center of a region rich in iron, coal, and limestone, and these natural advantages have made it second only to Pittsburgh as a center of the iron industry in this country. Birmingham was named after a great iron-working city of England. In the ten years beginning in 1900 it showed a larger percentage of increase of population than any other city in the United States of over 25,000 inhabitants. This rapid growth was due to the iron industry. Many people are needed to work the mines, railroads, and furnaces, and many others to supply food, clothing, and other necessary articles to the workers. The cities of Rome and Atlanta in Georgia, and Chattanooga and Knoxville in Tennessee, also share in the iron industry of the South (Fig. 195).

170. Sulphur.—An industry of great importance in Texas and Louisiana is the mining of sulphur. The deposits are found along the coast of the Gulf of Mexico. They are in beds several hundred feet underground, where they were first located through borings made in a search for petroleum. Wells are sunk to the sulphur beds, and very highly heated water—much hotter than steam—is forced down them under great pressure. The sulphur is melted by the heat of the water. It flows to the surface and is stored in large bins where it quickly cools, forming solid blocks of almost pure sulphur.

171. Other Mineral Products.—Knoxville, in the Great Valley, is close to beds of marble and deposits of copper and zinc. Tennessee has also large deposits of phosphate rock, one of the most valuable of mineral fertilizers. In Arkansas as well as Tennessee are found the deposits from which aluminum is made, and fine hard sandstones used for whetstones.

Petroleum and natural gas are found in Oklahoma, Texas, Louisiana, and Kentucky. The oil region of southern Texas and southern Louisiana is known as the Gulf oil field. Much oil has been found also in the northern parts of these states, and the railways of Texas make much use of crude petroleum for fuel. The Oklahoma oil field is a still larger producer, yielding about a third of the annual output of petroleum in the United States. Beaumont, Texas, has large oil refineries.

Beds of salt are found in both Louisiana and Texas.

Review. ^X1. Where are forests found in the South Central States? 2. What methods are used in cutting the trees into lumber? 3. Name three cities which are lumber markets. 4. What are some of the industries that depend for their prosperity upon the lumber industry?

5. In what states are iron and coal found? 6. What state has large sulphur deposits? 7. How is the sulphur secured? 8. What state has marble? Phosphate rock? 9. What states produce petroleum? 10. Where is salt found? ^X



Fig. 194. A business street in Birmingham



Fig. 195. Iron furnaces in Tennessee

[Handwritten signature]



Fig. 198. Ships loading cotton at Mobile



Fig. 199. River steamers at Nashville

steamers can reach the larger river ports. If this were done, iron or coal from Pittsburgh, flour from Minneapolis, meat from Kansas City, and cotton from Memphis, could be sent to all the ports of the world without the expense of unloading on the way.

By the Panama Canal a ship can go from New Orleans to ports on the Pacific Ocean as readily as it can to ports on the Atlantic. This has increased still further the importance of New Orleans as a shipping center.

Railroads enter New Orleans from the east, north, and west (Fig. 82).

174. Other Cities.—Galveston is one of the leading seaports of the United States. It stands on a low island at the mouth of Galveston Bay. In the year 1900 a storm wave from the Gulf swept over the city and did terrible damage. Since that time the city has built a sea wall seventeen feet high and more than three miles long for its protection. As Texas raises more cotton than any other state, its chief seaport, Galveston, exports much cotton (Fig. 9). Grain and live stock reach the city by railroads from the states west of the Mississippi River. Several steamship lines run between Galveston and Europe.

The deepening of the harbor of Houston, and the construction of a ship canal from this harbor to the Galveston jetties, have given Texas another important port. Houston ships cotton, cottonseed oil, rice, and lumber.

Austin is the capital of Texas, and the seat of the University of Texas. It is a live-stock,

cotton, and wool market, and the trade center for the western and central parts of the state. San Antonio is the center of a live-stock and farming region, with growing manufactures and a large trade. Dallas is the principal shipping and financial center of Texas. It has a large trade in wheat, fruit, cotton, meats, and live stock, and manufactures leather goods, cotton ginning machinery, cottonseed oil, and agricultural implements. At Fort Worth are stockyards and packing establishments. El Paso is a health resort and a center of trade with Mexico.

Mobile, on Mobile Bay, Alabama, is about one hundred miles nearer the Panama Canal than New Orleans is. It is the trade center for a large region, and ships cotton and lumber from the coastal plain (Fig. 198). Montgomery, the capital of Alabama, is in the center of the cotton-growing region of the state.

Meridian, Jackson, and Vicksburg, in Mississippi, are trading centers and shipping points for cotton, the growing of which is the leading industry of the state.

Nashville, on the Cumberland River (Fig. 199) is the capital of Tennessee. It has manufactures of flour, lumber, and many other things. It has also important institutions of learning, including Vanderbilt University and Peabody College for Teachers. Memphis is a cotton market and a lumbering center, and has cottonseed oil mills. Knoxville (Sec. 171) is the seat of the University of Tennessee, one of the large universities of the South.

Louisville is the chief city of Kentucky. It is a center of the tobacco industry (Fig. 200; Sec. 166), and manufactures farm implements, wagons, and leather. Covington is a trade center for a rich agricultural and stock-raising region, and Newport is a residential city next to Covington. Both of these cities are near Cincinnati, Ohio, and many people who work in Cincinnati have their homes in these Kentucky cities. Lexington is the chief city of the Blue-grass region. Paducah is in a rich agricultural district and has a large wholesale trade.

Little Rock is the capital and the principal city of Arkansas. Hot Springs is a health resort.

Oklahoma City is the capital and largest city of Oklahoma (Fig. 186). It is a center for meat packing and manufactures. Tulsa is the second city and Muskogee is in a thriving agricultural region.

Review by States.—Kentucky (Ky.). 1. What are the boundaries of Kentucky? 2. Where is the best region for agriculture? 3. What are the leading crops in the state? 4. Name and locate the chief city; the capital. 5. What Kentucky cities are near Cincinnati? 6. What is the density of population of Kentucky (Fig. 80)? How does it compare with that of Tennessee? Mississippi? Georgia? Pennsylvania?

Tennessee (Tenn.). 7. What is the largest city of Tennessee? 8. What is the capital? 9. What important rivers cross or border the state? 10. What uplands lie on either side of the Great Valley? 11. What cities are in the Great Valley? 12. What are some of their industries? 13. Name two educational centers in the state.

Alabama (Ala.). 14. What is the seaport of Alabama? 15. What is the capital? 16. What is the chief interior city? 17. Why has this city grown so rapidly in recent years? 18. How does

its growth compare with that of other large cities? 19. Describe the surface of Alabama.

Mississippi (Miss.). 20. What are the boundaries of Mississippi? 21. What is the capital? 22. How is Vicksburg situated? 23. What large cities in adjoining states are near Mississippi? 24. What is the leading business of the state?



Fig. 200. Tobacco ready for shipment at Louisville

Arkansas (Ark.). 25. What river is on the eastern border of Arkansas? 26. What other river has wide flood plains in the state? 27. What is the capital? 28. What is the chief city? 29. What useful rock is found in this state?

Louisiana (La.). 30. What is the character of the surface of Louisiana? 31. What rivers are on the eastern and western borders? 32. What is the largest city in the South Central States? 33. Describe the city. Why is it an important trade center? 34. What freight is carried on the Mississippi River? In which direction? 35. Why cannot large ships be used in this trade? 36. What crops does Louisiana produce? 37. Draw a map of Louisiana, showing rivers and cities.

Oklahoma (Okla.). 38. Name a large river that crosses Oklahoma. 39. What river is on its southern border? 40. What crop in Oklahoma is grown also in the states north of it? 41. What crops are the same as those in states south and east of it? 42. Describe the surface and climate of the western part. 43. Give some important facts concerning the history of the state.

Texas (Tex.). 44. How does Texas rank in size with other states? 45. To what country did it once belong? 46. What natural boundaries has Texas? 47. Describe the surface of the southeastern part; of the central and northern part; of the western part. 48. In which part of the state are large crops raised? 49. What are the leading products? 50. Name two important seaports of Texas. 51. What great works have been constructed for these ports? 52. What are their great exports? 53. What are the leading cities of eastern Texas? 54. What city is in western Texas? 55. What is the density of population in Texas? 56. How many people would Texas have, if it were as densely populated as Rhode Island?



Fig. 201. A Dakota prairie. Harvesting wheat

THE NORTH CENTRAL STATES


175. Early Settlement.—The French missionaries, explorers, and traders were the first white men to make their way into that part of our continent from which the North Central States were later formed. These early explorers followed the water route of the St. Lawrence River and the Great Lakes into the interior. From several points on the Great Lakes they made their way up the courses of small streams flowing into the lakes, and across low divides to eastern tributaries of the Mississippi River. Down these they went to the main stream, which La Salle finally explored to its mouth.

A number of trading posts were established by the French, as they wished not only to convert the Indians to Christianity, but also to develop the fur trade. The trading posts thus established, however, were small, few in number, and widely scattered. It was only when much of the best land of New York, Pennsylvania, and other Atlantic states was occupied that real settlement of the

North Central States began. Then the people of the East were attracted by the stories which they heard about the great fertile plains of the interior.

To Ohio, which was then in the "West," new settlers came by wagons from New England and New York. Their route was along the south shore of Lake Erie. Others from the East made their way across the highlands of Pennsylvania to Pittsburgh. From that place they floated down the Ohio River in boats to some point in Ohio, Indiana, or Illinois where they wished to take up land and make a home. Many, however, came to these states from Kentucky and other parts of the South. Michigan and Wisconsin were easily reached by the lakes, or across the plains that lay about them. Missouri was settled by men from both North and South. In the other North Central States west of the river most of the early settlers were from the North. Many of the later settlers are immigrants from Europe.

W



THE MATTHEWS-NORTHROP WORKS, BUFFALO, N. Y.

100°

95°

Longitude West



Fig. 203. Mississippi River at Davenport, Iowa, separating Illinois from Iowa

THE NORTH CENTRAL STATES

	AREA, SQ. MI.	POPULATION, 1920	CAPITAL
Ohio	41,040	5,759,394	Columbus
Indiana	36,354	2,930,390	Indianapolis
Illinois	56,665	6,485,280	Springfield
Michigan	57,980	3,668,412	Lansing
Wisconsin	56,066	2,632,067	Madison
Minnesota	84,682	2,387,125	St. Paul
Iowa	56,147	2,404,021	Des Moines
Missouri	69,420	3,404,055	Jefferson City
North Dakota	70,837	646,872	Bismarck
South Dakota	77,615	636,547	Pierre
Nebraska	77,520	1,296,372	Lincoln
Kansas	82,158	1,769,257	Topeka

Map Study.—1. What states lie along the Mississippi River on the east? On the west? 2. What states are bordered or crossed by the Missouri River? 3. What states lie on the north bank of the Ohio River? 4. What states have a direct outlet for their goods by way of the Great Lakes? 5. Which state has the longest shore line on the Great Lakes? 6. In what way does northern or southern Michigan resemble Florida?

7. Make a sketch map showing the outlines of all the states in the group, with the courses of the three chief rivers and the outlines of the Great Lakes. 8. On this map locate, on these rivers and lakes, Cleveland, Detroit, Duluth, Milwaukee, Chicago, St. Paul, Minneapolis, St. Louis, Kansas City, Omaha, and Cincinnati.

9. What branch of the Missouri River crosses Nebraska? 10. What large river crosses southern Kansas? 11. What large

river flows out of this region into Canada? 12. What states are bordered by this stream? 13. What three state capitals are on the Mississippi River?

14. What river rises near Chicago and flows into the Mississippi River? 15. What river leads from central Wisconsin into the Mississippi River? 16. What large bay opens into Lake Michigan? 17. Follow the stream that enters this bay to a point near Portage, on the Wisconsin River, and give a reason for the name of this city.

18. What bay belongs to Lake Huron? 19. What natural boundaries are found between Minnesota and Canada? 20. If a boat goes down the river from Fargo, what city of Canada will it reach (Fig. 46)?

21. What states of this group can be reached by sailing up some stream belonging to the Mississippi River system?

PHYSICAL FEATURES

176. Location and Drainage.—The North Central region includes twelve states. Five of them are east of the Mississippi River and north of the Ohio. They are Ohio, Indiana, Illinois, Michigan, and Wisconsin. They are sometimes called the "Old Northwest." West of Lake Superior and the Mississippi River are the other seven states of the group; namely, Minnesota, Iowa, Missouri, North Dakota, South Dakota, Nebraska, and Kansas. The three first named lie along the Mississippi, and all but Minnesota are either bordered or crossed by the Missouri River.

Most of the region, therefore, is included in the basin drained by the upper Mississippi River, together with its two great tributaries, the Ohio and the Missouri. Six of the states lie partly along the Great Lakes, in the drainage basin of the St. Lawrence River system. Five of these, however, send the greater part of their waters into the Mississippi system, but the state of Michigan drains almost entirely into the Great Lakes. North Dakota and Minnesota drain in part into Canada through the Red River of the North. Thus the waters of the North Central region reach the Atlantic Ocean through the Gulf of Mexico, the Gulf of St. Lawrence, and Hudson Bay.

177. Central Lowlands.—A large part of the plains in the North Central group are prairies. The first white men to visit the prairie region found few trees except along the streams, on the flood plains and bordering bluffs. The prairies are usually free from stones, and are covered with a black, rich soil which is in places ten feet in depth. In some parts of the East it was almost the work of a lifetime to clear away the trees and bowlders, and subdue a farm. But on the prairies a team could break up the matted roots of the prairie plants, and large crops soon rewarded the pioneer farmer.

At first the land could be purchased from the government for \$2 an acre, later for \$1.25 an acre, and still later the government gave land to settlers if they would make a home on it and cultivate it for five years. As a result most farms were larger than those in the East. They often consisted of a

quarter section; that is, of one fourth of a square mile, or 160 acres. A single farm might contain a half section, or even a whole section. As the land was nearly level, or only gently rolling, large fields could be laid out, and when modern plows, grain drills, and reapers were invented, they could be used to advantage on the smooth, broad fields. The larger part of the lowlands of Ohio

and Indiana were originally covered with forest. These woodlands have been cleared and converted into highly productive farms. The central lowlands, both prairie and forest areas, have become the chief farming region of the United States. Here are raised the greatest crops of wheat, corn, and oats, and the largest numbers of live stock.

178. Uplands.—In southern Ohio and southern Indiana are

uplands varying from about 1000 feet in altitude in parts of Ohio to a few hundred feet in Indiana. These upland surfaces descend on the west and north to the central lowlands. In the hilly counties of Indiana and Ohio there are still considerable areas of forest.

There are also upland areas in northern Michigan and in northern and southwestern Wisconsin. The highest elevation in Wisconsin is nearly 2000 feet above the sea, and northern Michigan has points that rise above 2000 feet. The uplands of both these states were originally covered with forest and are still important producers of lumber. The same hilly upland extends into central and northern Minnesota. This region is covered by glacial drift, is dotted with thousands of lakes (Fig. 204), and bears extensive forests.



Fig. 204. In the lake region of Wisconsin

Much of the southern half of Missouri, or the part that lies south of the Missouri River, belongs to the Ozark Plateau. Its surface is from 800 to 1800 feet above the sea, and it is largely a region of forests and mines, quite unlike the prairies that extend over and beyond the northern half of the state.

179. Great Plains.—The eastern parts of North and South Dakota, of Nebraska, and of Kansas have more than 20 inches of rainfall annually (Fig. 72), and therefore bear abundant grasses and other crops without irrigation or special methods of farming. The western parts of these states, in the Great Plains (Sec. 51), are higher and drier, having less than 20 inches of rainfall. The natural grasses there are not so thick and luxuriant as those of the prairie; but profitable crops are grown with the aid of irrigation or by means of dry farming. These ways of farming are described (Secs. 227–233) in connection with the Plateau States, where they are more extensively used than in this group of states. Many farmers on the plains protect their homes and fields from the strong winds by planting trees, thus forming windbreaks (Fig. 66).

The prairies and the Great Plains form a continuous, rather even surface, with a gradual increase of elevation from the Mississippi River to the foot of the Rocky Mountains. There is no abrupt passage from prairies to the high plains, but there is a gradual thinning of the vegetation.

In parts of western South Dakota and North Dakota, and of eastern Montana, the heavy

rains, which sometimes come even in dry regions, have washed away much of the soil, leaving hills and gorges with sides and walls partly of bare rock. These regions, called Bad Lands, bear no crops, although some of them afford pasture; they are so rough that it is difficult to travel through them.

In the western part of South Dakota rise the Black Hills. They are really a group of

rugged mountains. Part of the region is covered with a forest, which has been made a forest reserve by the government of the United States. Gold and other minerals are mined here (Fig. 205).

180. Glacial Deposits.—While the prairies are plains, it must not be thought that they are everywhere quite flat. They are uneven, partly by reason of the valleys which the rivers and smaller streams have cut below the general surface. They are uneven also because the




Fig. 205. The Homestake gold mine, Lead, South Dakota

glacial ice (Sec. 32) left its deposits of waste irregularly.

The ice sheet covered most of the prairie regions and left the surface in some places gently rolling. In other places it deposited waste in the form of hills or moraines. Some of these moraines are several miles wide and extend for long distances. Yet to one who lives in a hilly or mountainous country the surface of the prairie would seem almost level.

Many parts of the prairies were swept by streams of water that flowed from the melting ice in the glacial time. These streams deposited fine mud and sand over the regions which they flooded.

We can now see the reasons why prairie soils are so fertile. The prairies have a deep cover of wasted and pulverized rock, and upon it for several thousand years, following the ice invasion, plants grew and the decaying roots and tops mingled with the rock waste, until a deep, black soil was formed, full of plant food.

181. Climate.—The climate of the North Central region is continental (Sec. 27); that is, the land is far from the sea, and has hot summers and cold winters. The rainfall ranges from 50 inches in the southeast, to less than 20 inches in the west (Sec. 60). The region is swept by the prevailing westerly winds, and is in the track of the cyclonic storms (Sec. 62). It is the south and south-east winds of the cyclonic storms that bring moisture from the Gulf of Mexico and the Atlantic Ocean.

The average period between killing frosts, that is, the crop-growing period, is 200 days in the extreme south of Illinois and Missouri, on the lowland along the Ohio and Mississippi rivers. It is 110 days in the northern parts of Minnesota and North Dakota. In the heart of the prairie country it varies from 140 to 170 days, allowing ample time to mature the chief crops of temperate latitudes (Fig. 71). It must be remembered, also, that the summer days are longer in the north than in the south; so that the 110 crop-growing days in northern Minnesota have more daylight hours, in which crops can grow, than 120 days in southern Illinois.

The water of the Great Lakes is warmed during the summer and accumulates heat. As water does not cool so quickly as land, the autumn winds are warmed in passing across the lakes, and the temperature of the land along their

shores is moderated. As a result the growing season is longer near the lakes than in adjoining but less favorably located regions in the same latitude.

In general, therefore, the North Central States have warm summers for the growth of crops, and winters that are cold but clear, and hence are bracing and favorable to health and activity. The soils are rich, many of the rivers and lakes are navigable, and the plains are level so that railroads have been easily constructed (Fig. 206). These facts explain the rapid increase of population and the growth of many cities.

Review.—1. Which of the North Central States are bordered by the Ohio River? By the Mississippi River? By the Missouri River? 2. What states are crossed by the Missouri River? 3. Which states are bordered by the Red River of the North? 4. Which states have a frontage on Lake Superior? On Lake Michigan? On Lake Erie?

5. What conditions are favorable to farming on the prairies? 6. What parts of the North Central region are uplands? 7. What name is given to the upland of Missouri? 8. What are the Bad Lands? 9. What states consist almost entirely of prairie? 10. Explain the origin of the rich soil of the prairies.

11. Describe the summers and winters of this region. 12. What facts can you give concerning the length of the growing season in these states? 13. What effect have the Great Lakes upon the climate of adjacent lands?

14. Point out resemblances in surface and rainfall among the four states: Kansas, Nebraska, South Dakota, and North Dakota.




Fig. 206. Railroad yards at St. Paul



Fig. 207. Wheat-producing regions of the United States

wheat belt of North America is in northern United States and southern Canada.

Far more wheat is produced in Europe than in any other continent. It is raised also in north Africa, in Asia, in Australia, and in Argentina. Wheat-raising extends around the world, mainly in the two belts of temperate climate.

The wheat-growing regions of the United States are shown in Fig. 207. From this chart the student should make a list of twenty or more states where

WHEAT, CORN, AND OTHER CROPS

182. Use of Wheat.—In most parts of our country, bread is made chiefly of wheat flour. This is true also in Canada, Great Britain, and France, and much wheat is used in Germany, Italy, Spain, and many other lands in the temperate zones. But the United States uses more wheat than any other country — about 600,000,000 bushels a year.

183. Where Wheat is Raised.—Wheat is raised in North America, from the highlands of Central America and Mexico to the basin of the Mackenzie River, at about 60° north latitude. In the far south it can be grown because the highlands are cool (Sec. 26). In the far north spring wheat can be raised, as it grows and ripens in a short time because of the very long summer days. The great

the wheat crop is important. The greatest wheat region in the country is west of the Mississippi River, and includes Minnesota, the Dakotas, Kansas, Nebraska, and Missouri. In this region the soil and climate are especially well suited to the growth of wheat. Other states with large wheat crops are Ohio, Indiana, Illinois, and Washington.

184. Raising and Harvesting Wheat.—In Minnesota and the Dakotas the seed is sown in the spring. Farther south, as in Kansas, Missouri, or Ohio, winter wheat is raised. It is sown in early autumn, makes a small growth before winter, and matures the following summer.

In the early days wheat was sown by hand, reaped with a sickle, and threshed by hand. By these simple means wheat bread could be produced only for the few. Now gang plows



Fig. 208. Three gang plows, followed by a disk harrow, turning over the soil

(Fig. 208), drawn by teams or powerful engines, turn over the soil. When it is seeding time a dozen teams with wide grain drills may be at work in a single field. The ripe wheat is cut and bound by harvesting machines (Fig. 209), and afterward the grain is separated from the straw by threshing machines (Fig. 67). Through the invention of machinery, the cultivation of the great wheat lands, and the building of railroads and ships, it is possible for hundreds of millions of people to have bread at a moderate price."

185. Wheat Markets.—After the wheat is raised it must be taken to market. Many railroads have been built to bring the wheat from the prairie fields. The farmer hauls it to the railroad station. If it does not go at once into a freight car, it is hoisted into a grain elevator, where it is stored until needed. When it is to be shipped the grain is loaded into freight cars through chutes. The rail-



Fig. 209. Reaper and binder, Nebraska

road takes it to some milling center such as Minneapolis, or to a Great Lake port such as Chicago, Superior, or Duluth in the United States, or Fort William or Port Arthur in Canada. In such places are elevators (Fig. 210) that hold millions of bushels of wheat awaiting shipment down the lakes, and, it may be, across the ocean.

186. Flour Mills.—

Much wheat is taken to Minneapolis, the largest wheat-milling center in the United States. The city is on the Mississippi River by the Falls of St. Anthony, in a vast wheat region; and trains on many railroads bring in the crop. Large Minneapolis mills make many thousands of barrels of flour in a day. Barrels and sacks are needed, in which to pack the flour, and hence people are kept busy in the lumber and paper mills. The railroads that handle the crop and the manufactured flour must have steel for rails and engines, wood for ties, and both iron and wood for freight cars, stations, and elevators. Thus the people of the farm, the forest, the mine, the mill, and the railroad all help to supply the loaf of wheat bread,—and we do not really get the loaf until the wholesale and retail dealers in flour and the baker have done their parts.

187. Corn.—Corn is also known as maize and is often called Indian corn, because the Indians raised it. It is a native of the Western Hemisphere, but was introduced into Europe soon after the discovery of America. Although it is now raised in many parts of the



Fig. 210. Grain elevator at Duluth




Fig. 211. Corn-producing regions of the United States

world that have a suitable climate, the crop in the United States is far larger than the crops of all other countries together. Corn thrives best in a warm-temperate climate, with abundant sunlight. In comparison with wheat it grows better farther southward. Thus, more wheat than corn is raised in Canada; but much more corn than wheat is raised in the southern states. The *corn belt* extends from Ohio, through Indiana, Illinois, Iowa, and Missouri, to central Kansas and Nebraska (Fig. 211). Here nearly every farmer cultivates a field of corn. Some of it is cut for the silo (Sec. 110) before it is entirely ripe, but most of it is allowed to ripen, so that the matured grain may be fed to stock or taken to market.

About 800,000,000 bushels of wheat are raised each year in this country, and about 3,000,000,000 bushels of corn, or nearly four times the amount of wheat produced. The number of bushels of corn raised in the United States is about three fourths the number of bushels of wheat raised in all the countries of the world.

Some of the corn is hulled and broken for hominy. Corn is also ground for cornmeal and is used for

making cornstarch and breakfast foods. The making of breakfast and health foods, from corn, wheat, and oats, is one of the chief industries of Battle Creek, Michigan. Corn is consumed also in making sirup, oil, and other corn products. The greater part of the corn, however, is fed to hogs and cattle. This is the reason why the corn belt is also the chief live-stock region in the United States. As the price of meat is very high, it generally pays better to use

the corn to fatten hogs and cattle than it does to ship the grain to a distant market.

188. Cereals.—Wheat and corn are familiar sights in the fields and on the farms of the North Central States. In the Red River Valley of Minnesota and North Dakota the land is almost as flat as a floor, and the wheat, waving in the wind just before the harvest, is like a yellow sea as far as the eye can reach. The corn of Indiana, Illinois, or Iowa presents a different appearance, the thick green stalks tasseling out at a height of eight or ten feet (Fig. 212). Forty or eighty acres of corn look more like a young forest than like a field of grain. Where the



Kansas State Agricultural College

Fig. 212. Cutting corn in Kansas




Fig. 213. Harvesting flax in Michigan

U. S. Department of Agriculture



Fig. 214. Kafir corn

summers are somewhat cooler, as in Minnesota or Canada, the stalks are usually shorter and more slender, and the yield is not so great.

Wheat and corn are by no means the only cereal crops raised on the farms of this region. Three fourths of the oats raised in the United States are produced in this group of states. Illinois and Iowa, which have the largest proportion of prairie land, are the leaders in raising this grain. Most of the oats are fed to horses and poultry, but some are used for the food of man. At Cedar Rapids, Iowa, for example, there are large oatmeal factories. More than half of the barley crop of the country is raised in the northern states of this region, namely, Minnesota, North Dakota, South Dakota, Wisconsin, and Iowa. Barley will grow even farther north than wheat, but it also thrives in warm climates, as in California and southern Europe. Considerable rye is raised, especially in Wisconsin, Michigan, and Minnesota.

189. Other Crops.—Much flax (Fig. 213) is grown in North Dakota, South Dakota, and Minnesota, not for its fiber, but for the seed, which is used for making linseed oil. After the oil, which is mainly used in mixing paint, has been pressed out, the cake that remains is a valuable food for stock. Most of the flax fiber used for making linen is raised in Europe. Hay is a very important crop of the North Central States. Besides hay, the forage plants include alfalfa,

corn, sorghum, and Kafir corn (Fig. 214), a forage plant that does well in dry regions.

Other leading products are: potatoes, of which many are raised in all the North Central States; beans, and sugar beets. Kalamazoo, Michigan, is the shipping center of one of the districts where fine celery is grown. Michigan and Wisconsin raise more sugar beets than any other states east of the Mississippi River, and have a number of factories for making the sugar. Tobacco is raised in Ohio and in Wisconsin (Fig. 162).

The North Central States produce much fruit. Many grapes are grown in southern Michigan, near Lake Michigan; and in northern Ohio, near Lake Erie. Apples, peaches, and other orchard fruits are grown in abundance in these two states and also in Missouri, Illinois, Kansas, and other states.

Review. 1. How far to the north and south is wheat raised in North America? 2. What is now the greatest region for wheat in the United States? 3. What inventions make it possible to raise much wheat at the present time? 4. Why is Minneapolis a large center for making flour?

5. By what other name is corn known? 6. In what parts of the world is it grown? 7. What kind of climate is favorable to it? 8. What states are in the corn belt? 9. For what is corn used?

10. What is the importance of the oat crop in the North Central States? 11. Which of these states raise the most barley? 12. For what purpose is most American flax raised? 13. What states are the main producers of flax? 14. What states of this group lead in raising sugar beets?



Fig. 215. Hogs. In the background is a corn crib. The ground is littered with corn husks

A farmer owning 160 acres (a quarter section), or 320 acres (a half section), in one of the North Central States, may plant a quarter or a third of his farm in corn, and have also some fields of oats, of grass and clover, and perhaps of wheat, besides pastures. The corn will fatten the cattle and hogs, and if the farmer keeps a dairy, the hogs will be fed partly with the skim milk, buttermilk, and whey left after making the butter and cheese. Many farmers in the prairie states get their

STOCK RAISING AND MEAT PACKING

190. Live Stock on Farms.—In the North Central States many domestic animals are raised on farms and on ranches. The farms are numerous in all the states of the group. The ranches are in the drier districts of the western states. On a great many farms both crops and stock are raised, because the animals require the corn, oats, and hay that are produced by the fields. The farmer finds it profitable to feed his corn and hay to his stock and in this way turn them into beef, butter and cheese, pork, mutton, and wool; and in general the states that raise the most corn, raise the most cattle and hogs (Figs. 215-218). In Iowa, Illinois, and Missouri, large numbers of hogs and cattle are fattened for the market. Wisconsin, Iowa, and Minnesota, with New York, lead in the number of dairy cows. Texas, however, is first in beef cattle (Figs. 217, 218). This is not only because Texas raises much corn, but especially because it has thousands of square miles of wild grasses for pasture.

money mainly from the sale of the cattle and hogs, and from milk, butter, cheese, and poultry. Iowa, Missouri, Illinois, and Ohio are the leading states in the poultry industry of our country. Near the great cities, such as Chicago, St. Louis, Cleveland, Cincinnati, Minneapolis, and many others, truck farming and dairying take the place of general farming. Land has become very valuable in the prairie states, and the farmer who has a good quarter or half section paid for, equipped with proper buildings and tools, and well stocked with farm animals, is a prosperous, and in many cases a wealthy, man.




Fig. 216. Swine-producing regions of the United States

191. Sheep.—Many sheep are raised in the North Central States, especially in Ohio, Michigan, and Missouri. This industry, however, is studied under the Plateau States, which raise a far greater number.

192. Cattle.—Ranches and cattle ranges are found in parts of Kansas, Nebraska, and the Dakotas. Many cattle also are pastured on the plains of Oklahoma and Texas, and many on the open lands of Montana, Wyoming, Colorado, New Mexico, and of the states farther west (Fig. 217). In all these regions rains are light (Sec. 60), and the native bunch grass, though highly nutritious, is thin. One or two acres of corn or grass land will keep a beef animal in Iowa, but fifteen or twenty acres are necessary on the dry plains.

The grass, which grows green and fresh in the time of the spring rains, is dried up and cured like hay by the summer sun. In former times, therefore, the cattle were left on the open plains the year round, winter as well as summer. Better methods are now in use, and the cattle are sheltered and fed during the winter. Their increase in value




Fig. 217. Distribution of cattle in the United States

more than pays for the cost of the shelter and extra labor.

As the land in the western states is being taken up for dry farming, the cattle ranches are decreasing in number and size.

Some cattle need to be "finished off" with corn feeding before they will bring the best price in the market. Thousands of cattle are sent from the ranches to the farmers of the prairie states farther east, who feed them with corn, and finally send them to the packing houses of some neighboring city (Sec. 195). Many hogs and beef cattle are shipped alive, or "on the hoof," to eastern cities and slaughtered there. Trainloads of cattle and hogs moving eastward are common sights on several of the railroads of the North Central States.

Trainloads of cattle and hogs moving eastward are common sights on several of the railroads of the North Central States.

193. Ranchmen.—Most of the unfenced ranges are now found in the Plateau States farther west. The ranchman's house is usually placed by a stream or spring, and near it are a corral, a barn, a blacksmith shop, and often a fenced pasture for the horses. The helpers are called cowboys. It is their work to help the owner



Fig. 218. Distribution of dairy cows in the United States

or the foreman look after the cattle. Since the cattle may wander a hundred miles or more and mingle with those of many other ranchmen, this cattle herding is no light task. The cowboy must, so far as he can, protect the herds in time of storm, must see that they can get water, and must look out for cattle thieves.

194. The Round-up.—Twice each year on the unfenced ranges there is a round-up. The cowboys of various ranches gather and spread out in lines or parties and drive in or round up the cattle for a number of miles. Day after day they take a different section of the country. When the cattle have been rounded up they are found to belong to many different owners. Each grown animal bears its owner's brand, and as the young calves will usually follow their mothers, it is easy to pick them out also. The calves that do not follow their mothers are divided among the owners according to the number of cattle each one owns. Each calf is branded by a hot iron with its owner's mark. In the autumn round-up the animals that are ready to be marketed, or to be shipped to the prairies for "finishing off," are separated from the herd by the cowboys, and the rest of the herd are allowed to wander back on the range.

195. Meat Packing.—In former times the people of a city were supplied with meat by farmers near at hand, who drove in their cat-

tle, sheep, or hogs and sold them to the local butcher. To-day, beef and pork enough to supply Paris, London, New York, or Philadelphia cannot be raised near these cities. They must often be brought from a great distance. Modern trains and ships make this possible. Some animals are shipped alive, but the greater number are slaughtered in cities that are not far from the stock farms and ranges.

Such cities are known as packing centers. Chicago is the greatest of these. It is not only in the midst of the prairie stock farms, but is easily reached by railroads from the stock ranges west and southwest. Still nearer the ranges are the packing houses of Omaha in Nebraska, Kansas City and Wichita in Kansas, Sioux City in Iowa, St. Joseph and St. Louis in Missouri, and East St. Louis in Illinois. The five leading cities in the meat-packing industry are Chicago, Kansas City, New York, Omaha, and Indianapolis, the capital of Indiana.

The stockyards in Chicago (Fig. 225) receive the animals as they come from the trains. Thousands of cattle and hogs and sheep are killed every day, and the families of those who work in the packing houses would people a good-sized city. Much of the meat is sent in quarters or whole carcasses, by refrigerator cars (Fig. 219), to cities and towns in all parts of the country. The local depots of the

great meat packers are seen in every city. Some of the meat goes abroad in cold storage. Some is salted, smoked, or sealed in air-tight cans, and is thus prepared for keeping and for sending to all parts of the world.

196. By-products.—The meat furnishes only part of the profit from the slaughtered animals.




Fig. 219. Loading meat on a refrigerator car at Chicago

The hair and bristles are used in upholstery, in making brushes, and for other purposes. The hides are tanned for leather, and the blood and other refuse make valuable fertilizers. The horns and bones are turned into buttons, hairpins, combs, brush-backs, and handles of many kinds. Other parts serve for making glue, soap, glycerin, poultry food, gelatin, and for various medical preparations. Nothing is wasted.

- Review.**—1. Where are the livestock ranches mainly found? 2. Which are the leading states in this group in dairy interests? 3. Where are many sheep raised? 4. To what kinds of animals is corn chiefly fed? 5. From what products of this region do many farmers get most of their money? 6. How much land in the ranch country may be necessary for a single head of cattle? 7. What is the chief city for meat packing? 8. What other cities are important in this industry? 9. What conditions favor the industry at these places? 10. By what means are meats preserved? 11. What are some of the by-products of meat packing?

MINING AND LUMBERING

197. Useful Minerals.—The North Central States are well provided with useful minerals. Most of these states have coal beds. Minnesota, Wisconsin, Michigan, Ohio, and Missouri have deposits of iron, and the three states bordering on Lake Superior produce enormous quantities of the ore. Copper is found in northern Michigan, and lead and zinc in Missouri, Kansas, and




Fig. 220. Iron mining in an open pit, Minnesota. The steam shovel is dumping a shovelful of ore into a car

Wisconsin. Petroleum and natural gas, building stones, and useful clays are found in many states of the group.

198. Iron.—Minnesota produces more iron ore than any other state. Most of the iron ore used in the Pittsburgh district (Sec 127) comes from the three states of the Lake Superior region. Much of it is an earthy ore that is easily dug in open pits. Trains of ore cars are run into these broad pits, and the cars are filled by steam shovels (Fig. 220). When filled, the ore cars go to Duluth, Superior, Two Harbors, Ashland, or Marquette on the shores of Lake Superior, or to Escanaba on the shore of Lake Michigan. They are run out on long piers, and the ore is dumped into great pockets and from these into the holds of ore vessels, to be taken down the lakes (Fig. 221). The ore is unloaded at Cleveland, Ashtabula, Conneaut, Buffalo, Erie, Lorain, Toledo, or some other port of Lake Erie, or at Chicago or Gary on



Fig. 221. Ore vessel on the Great Lakes




Fig. 222. Distribution of iron ore from the Lake Superior district

Lake Michigan (Fig. 222). Some of it is smelted in these cities, and much goes to Pittsburgh. Thus in most cases the iron ore is brought near the coal beds, or near large markets. But the big freight steamers that bring iron ore from Lake Superior to the lower lake ports do not have enough freight to carry on the return trip. Therefore, they can afford to carry coal very cheaply. A steel plant recently built at Superior, Wisconsin, uses as fuel coal brought from the lower lakes in this way.

In the North Central group the manufacture of iron and steel, and of iron and steel castings and machinery, is not only important in the cities already mentioned, but also in many others. It is, for example, the chief industry of Youngstown, Canton, and Steubenville in Ohio; and of Joliet in Illinois.

199. Coal.—While most of the states in this group have coal (Fig. 127), the most important beds are found in Ohio, Indiana, Illinois, Iowa, and Kansas. About two thirds of the surface of the state of Illinois is underlain by coal beds. Manufactures are

already important in many of these states, and with so much coal to supply power, they may become as well known for manufacturing as for farming.

200. Copper.—Michigan stands with Arizona, Montana, and Utah as one of the four leading states of our country in the production of copper. The Michigan copper is found on the Keweenaw Peninsula (Fig. 202), and has been longest known, for pieces of the metal were broken from exposed ledges of rocks and carried southward by the glacier. The Indians sometimes picked them up and hammered them into implements. Now the

copper ore, consisting of small particles of metal scattered through the rock, is found far below the surface. The Calumet and Hecla mine, with the depth of about a mile, is one of the greatest as well as deepest of mines.

The United States produces more than half of the world's supply of copper. This metal is much used for making wire, because copper wire is a good conductor of electricity, and is needed for trolley and telephone wires and electric lighting. Copper is also the chief metal in the alloys known as brass and bronze. Much copper is exported to other countries.

201. Petroleum and Natural Gas.—Petroleum and natural gas (Secs. 113, 114) are found in Illinois, Ohio, Kansas, and Indiana. Illinois is the largest producer of petroleum in this group of states, and outranks all other states east of the Mississippi River.

202. Cement.—The lime and clay needed in the manufacture of cement (Sec. 117) are found in many places in the North Central States. There are large cement factories

in Michigan, Ohio, Indiana, Illinois, Iowa, Missouri, and Kansas. The limestone quarries along the Mississippi River in Missouri and Illinois make the district around Hannibal, Missouri, and Quincy, Illinois, one of the largest cement-producing fields of the country.

203. Other Products.—Joplin, in the southwestern part of Missouri, is an important center for the mining of lead and zinc; Missouri ranks first among the states in the production of these two metals. Gold is mined in the Black Hills in South Dakota (Fig. 205), and Michigan produces more salt than any other state in the country. East Liverpool, Ohio, is one of the chief places in the United States for the making of pottery and porcelain (Fig. 223), and Zanesville, Ohio, is noted for its manufacture of decorative tile.

204. Lumbering.—There is still much lumbering in the forests of Michigan, Wisconsin, and Minnesota, though most of the white pine and much of the other timber have been cut. So much of the timber of these North Central States has now been cut that the industry is no longer so important as it once was, or as it is now in some states of the South and on the Pacific coast.

205. Lumber Markets and Manufactures.—Duluth and Superior, at the head of Lake Superior, are centers for lumber; and Minneapolis, Minnesota, and Oshkosh, Wisconsin, are other large lumber markets. At Sheboygan, Wisconsin, are large chair factories. Grand Rapids, Michigan, and Rockford, Illinois, are especially known as furniture-manufacturing cities. The output of their factories, includ-

ing all grades of office, house, and school furniture, is sold in all parts of the country.

The making of farming implements has become a very important industry in this group of states, for here are found: (1) supplies of lumber, (2) supplies of iron, and (3) farms that offer a market for the product. Illinois makes nearly half of the agricultural implements of the country, and Chicago makes far more than any other city. Chicago is near the lumber and iron of the Lake Superior region, and has supplies of coal for her factories, and a ready market in all the prairie states. Among the many other centers of this manufacture are Moline, Peoria, and Rock Island, Illinois; Racine, Wisconsin; Springfield, Ohio; and South Bend, Indiana.



Fig. 223. Pottery molds ready for baking

Review. 1. What three states furnish the iron ore of the Lake Superior region?

2. From what ports is it

shipped? 3. At what ports is most of it unloaded?

4. Why are Lake Erie ports favorable to iron manufactures?

5. What part of Illinois is underlain by coal beds? 6. What other states have coal fields?

7. Give an account of the copper production in northern Michigan. 8. What are the principal uses of copper?

9. What states of this group produce the most petroleum? 10. What states have large plants for making cement? 11. What metals are mined near Joplin? 12. What industry is important at East Liverpool?

13. Where are the chief timber lands of the region? 14. Name and locate some of the chief cities having lumber industries. 15. What conditions make a place suitable for the manufacture of farm implements? 16. Name and locate two cities with large manufactures of furniture; two with large manufactures of agricultural implements.

CITIES

206. Cities of the Great Lakes.—Of the twelve or thirteen largest cities in the United States, five are on the Great Lakes. They are Chicago and Milwaukee on Lake Michigan, Cleveland and Buffalo on Lake Erie, and Detroit. The last-named city is on the Detroit River, but it is on the line of lake traffic, and is therefore properly thought of as one of the lake cities.

207. Chicago.—Of these cities Chicago is much the largest, with a population of about 2,700,000. It is the fourth city of the world, being surpassed in population only by London, New York, and Paris. Where Chicago now stands a town was first laid out in 1830. It is near the head of Lake Michigan, the only one of the Great Lakes that lies wholly within the United States (Figs. 202, 224). Not far from Chicago are

the rich fields, mines, and forests of Michigan, Wisconsin, Indiana, and Illinois, and the city has naturally become the center of great business activity. The country on the east, south, and west is so nearly level over large areas that many railroads have been easily built from the city, extending far beyond the states that lie on the shores of Lake Michigan. These railroads, the shipping on the lakes, the vast and rich prairies, and the coal, iron, copper, and lumber that are not far away, have all helped to make Chicago the chief city of the central lowland of North America.

A small stream called the Chicago River has been deepened and forms part of the harbor of the city. The outer harbor is protected by long breakwaters. The water supply of Chicago comes from Lake Michigan. It is taken from the bottom of the lake at a point some miles out from the shore. To avoid the pollution of the water with sewage the city dug the Drainage Canal. This canal is cut through earth and rock, and is nearly 30 miles long, with a minimum depth of about 22 feet, and a width that varies from 200 to 290 feet at the surface. It conducts the waste of the city, mingled with water from Lake Michigan, to the Illinois River. It is hoped at some future time to make use of this canal as the connecting link between the Great Lakes and the Mississippi River system and to make it an important route for commerce whenever the channel of the Mississippi is deepened enough to permit the use of larger vessels.

Chicago has many lofty business buildings (Fig. 10), splendid boulevards and parks, and the means of transportation common to great cities, such as surface and elevated railroads. There are also subways for carrying freight from one part of the city to another. Iron, coal, and grain are the staple commodities carried by its ships. Its stockyards (Fig. 225) and meat-packing business are the largest in the world. In the making of agricultural im-




Fig. 224. Chicago and vicinity



Fig. 225. Part of the Chicago stockyards, which cover 500 acres

plements it is the first city in the world (Sec. 205), and in the manufacture of clothing it is second only to New York. It has the leading grain exchange of the country, and its elevators have a capacity of many million bushels. It manufactures much iron and steel. The parlor, sleeping, and dining cars on many of the American railroads are made in Pullman, a part of Chicago, and many street and freight cars also are built there.

208. Other Lake Cities.—Milwaukee is on the shore of Lake Michigan, about 85 miles north of Chicago, and is the chief city of Wisconsin. Like Chicago, it has the advantage of sending and receiving goods both by lake and by railroad. Its manufactures include leather, in which Milwaukee ranks first among cities; machinery, iron and steel, flour, knit goods, and shoes. Milwaukee is an important grain-shipping port and has enormous grain elevators. It is also a distributing point for the coal brought in by lake steamers from Michigan, Ohio, and Pennsylvania, and shipped throughout the Northwest.

Among other cities on Lake Michigan are Racine in Wisconsin, a manufacturing center for agricultural implements, automobiles, and carriages; and Gary

in Indiana, a steel-making city of recent origin.

At the head of Lake Superior are Duluth in Minnesota and Superior in Wisconsin, which have iron furnaces and great steel mills, and ship iron ore, lumber, and grain. These cities are coal-distributing centers for the Northwest, and have large grain elevators and ore docks.

Bay City and Saginaw, near Lake Huron, are manufacturing cities and trading centers for large agricultural regions.

All traffic from the upper to the lower lakes passes the city of Detroit (Fig. 226). This city is an important railroad center and there is a railroad tunnel under the Detroit River. Detroit is fourth in size among the cities of the United States and has manufactures of drugs and medicines, stoves, and, most important of all, automobiles, motor trucks, and airplanes and their parts and accessories. Highland Park and Hamtramck, although politically independent, are closely identified with Detroit; their chief industry is the making of automobiles. Other Michigan cities in which this is an important industry are Flint, Jackson, Pontiac, and Lansing, the capital of the state.



Fig. 226. Hotels on Grand Circus Park, Detroit

Several important cities in Ohio are on Lake Erie. Cleveland is the greatest of these. Like Chicago, it has a river harbor. It receives iron ore (Fig. 227) that is on the way from Lake Superior to Pittsburgh, and ships coal to all points on the upper lakes. Much of the coal and the iron ore received in Cleveland are not shipped out of the city, for Cleveland has vast iron industries, including many foundries. It also refines petroleum and builds ships for lake traffic. Among its many other manufactures are automobiles and clothing.

Toledo, at the west end of Lake Erie, on a fine river harbor, has a large trade by lake and rail. Among its manufactures are iron and steel goods, automobiles, electrical machinery, glass, clothing, and ships.

209. Cities of the Mississippi River.—St. Louis, the chief city of Missouri and of the country west of the Mississippi River, is the largest city on the Mississippi River system. It is a little below the mouth of the Missouri River (Fig. 228) and has a position midway between the traffic of the upper and that of the lower Mississippi. Railroads from Chicago, Pittsburgh, New York, Philadelphia, and Baltimore center here. From St. Louis other railroads lead to the trade centers of




Fig. 227. Unloading iron ore at Cleveland

West, wheat from the North, coal from Illinois, and the lead, zinc, coal, glass, and iron of Missouri. It is a great lumber and fur market, and its manufactures include boots and shoes, clothing, tobacco, chemicals, and railroad and street cars. It is also a meat-packing center.

Several bridges cross the Mississippi River at St. Louis. On the opposite side of the river is East St. Louis, with flour mills and other factories, besides some large meat-packing establishments just outside the city limits. East St. Louis is in Illinois.

At Keokuk, Iowa, 140 miles northwest of St. Louis, is a concrete dam across the Mississippi River, 31 feet high and nearly a mile long, the greatest power dam in the world (Fig. 229). In the power house the water turns immense turbines and generates electricity. Most of this power is used in driving machinery and street cars in St. Louis and other cities. Steamboats going up or down the river pass the dam by means of a lock.




Fig. 228. St. Louis and surrounding country



Fig. 229. Keokuk Dam. The power house is seen at the farther end of the dam

On the Mississippi, between St. Louis and Keokuk, is Quincy, Illinois, with stove works and other factories. Still farther up the river is an important industrial center formed by Davenport in Iowa, and Rock Island and Moline in Illinois. Davenport manufactures flour, locomotives, and steel cars; Rock Island manufactures agricultural implements; and Moline is known for its steel plows. Other important cities on the river are Dubuque in Iowa, a manufacturing city and distributing center for lumber, and La Crosse in Wisconsin, an important center for northwestern trade, especially in lumber.

At the head of navigation on the Mississippi River are St. Paul and Minneapolis in Minnesota. St. Paul is the capital of the state, and Minneapolis is the largest city. The two cities are so close to each other as to be one center of population, having together more than 600,000 people. They are often called the Twin Cities. Minneapolis owes its development as a manufacturing city to the water power of the Falls of St. Anthony in the Mississippi River. The great wheat fields of the northwest are near, and Minneapolis has become the largest center in the world for making flour. It also has large linseed oil mills (Sec. 189). St. Paul has a large wholesale and retail trade and is a printing and publishing center. Many railroads center in the two cities (Fig. 206), with lines running eastward to Milwaukee and Chicago, northward to Winnipeg, westward to Seattle and Portland, and southward to St. Louis.

210. Cities of the Missouri Basin.—On the Missouri River in Missouri is Kansas City, with a large trade in live stock, grain, and agricultural implements. Across the state line is Kansas City, Kansas, which, although much smaller than the sister city in Missouri, is the largest city in Kansas. Meat packing is the leading industry, and Kansas City is one of the largest live-stock markets in the world.

Up the river is St. Joseph, Missouri, which is also a trade and meat-packing center. On the Missouri in Nebraska is Omaha, a great railroad center with lead and silver smelting and refining works, and great packing houses. On the Iowa side of the river, opposite Omaha, is the smaller city of Council Bluffs, a trading center for the surrounding region, particularly in agricultural implements, and the eastern terminus of the Union Pacific Railroad.

Some distance west of the Missouri River are Topeka in Kansas and Lincoln in Nebraska, each the state capital and the trade center of a fertile and productive farming region. The cities of North Dakota and South Dakota are still small because the natural resources of these states have not been fully developed. Sioux Falls is the leading railroad center and the largest city of South Dakota; and Fargo, on the Red River, is the largest city of North Dakota.

Springfield, the largest city of southwestern Missouri, lies in the Ozark Plateau, just outside the Missouri basin. It is the trading center of a mining, lumbering, and farming section.

211. Cities of the Ohio River.

—Cincinnati is the largest port on the Ohio River except Pittsburgh, and is an important railway center. It is a gateway to the South, the city having built its own railroad to Chattanooga. It is a manufacturing center for boots and shoes, clothing, machinery, tools, and ornamental iron. Its Rookwood pottery has a world-wide reputation (Fig. 230). It is a large market for distributing fruits and vegetables, and handles large amounts of hardwood lumber. Many residents of adjoining cities in Ohio and Kentucky carry on business in Cincinnati.

On the Ohio River in Indiana is Evansville, a hardwood lumber market. It has flour and grist mills and furniture factories.

212. Other Cities.—Des Moines, the capital, largest city, and chief trade center of Iowa, is in the central part of that state. In Ohio, Indiana, and Illinois there are many important cities not on lakes or on rivers of navigable size. Among these the largest is Indianapolis. It is an important center of steam and electric railroads (Fig. 235), and is the center of trade for the state. It has large pork-packing establishments, machine shops, and automobile and other factories. In Indiana, also, Fort Wayne has large machine shops and car shops; South Bend manufactures carriages, wagons, and plows; and Terre Haute has flour mills and machine shops.

In Illinois, there are large watch factories at Elgin, at Peoria, and at Springfield, the capital. Rockford manufactures furniture, machine tools, and agricultural implements. Decatur has flour mills. Aurora, Danville, and Bloomington have railroad repair shops.

Columbus, the capital of Ohio, is a large city near the coal and iron fields of the state, and has many manufactures, especially of machinery, stoves, and shoes. At Dayton, another large city of Ohio, are manu-



Fig. 230. A glimpse of Cincinnati. At the left is the Rookwood Pottery

factured railroad cars, airplanes, and most of the world's supply of cash registers. Akron has extensive rubber and cereal manufactures. Hamilton has paper and other factories. Lima is the center of a petroleum region.

213. Educational Centers.—Most of the universities and colleges of the Atlantic states are supported by the gifts of private persons. In the North Central region, as generally in the South and West, every state supports a university. Among the largest are the University of Michigan at Ann Arbor; of Wisconsin at Madison, the state capital; of Minnesota at Minneapolis; and of Illinois at Urbana. Some others also, including the Ohio State University, the University of Missouri, and the University of Nebraska, enroll several thousand students each. In some states, as Iowa, Kansas, and Indiana, the state college of agriculture and mechanic arts is not part of the state university, but is maintained as a separate institution.

There are also many large universities and colleges supported by private gifts. Among these the largest are the University of Chicago (Fig. 231), and Northwestern University at Evanston, Illinois. Industrial and technical schools abound in this region, and there are also many normal schools.

Review. 1. Compare Chicago as to size with other great cities of the world. 2. What are its advantages of location? 3. What are its chief industries? 4. Give an account of the Drainage Canal.

5. What are the industries of Milwaukee?
6. What are the chief ports of Lake Superior?
7. Where is Detroit, and what is its chief industry?
8. What are the principal industries of Cleveland?
9. In what respect is St. Louis well situated for transportation? For manufactures?
10. Where is the largest power dam in the United States, and how is it used?
11. Name and locate the Twin Cities.
12. Name and describe three other important cities on the Mississippi River.
13. What two cities of the same name are on the Missouri River?
14. What are their industries?
15. What are the other large cities on the Missouri River in this group of states?
16. Name the principal cities that stand on the banks of the Ohio River.
17. In this group of states, where are rubber goods manufactured? Plows? Watches? Cash registers?
18. Make from memory an outline map of the North Central States, showing the rivers and the capital and chief cities of each state.

TRANSPORTATION

214. Early Ways of Travel.—By transportation we mean the moving of men and products from one place to another. If a family, or the people of a small village, should raise all their own food, grow cotton, wool, or flax and make their own clothing, and cut down trees and build their own houses, and if they did not wish to travel, they would not need facilities for transportation. But the moment they send for things that are produced elsewhere, or whenever they would

travel for any purpose, roads and vehicles become necessary. If we imagine all the roads removed from our neighborhood and ourselves compelled to beat a path across the fields or through the woods in order to go anywhere, we shall understand what the first white settlers in America had to do.

The earliest routes of travel were trails, such as were used by the Indians and even by the buffalo and other animals that walked long distances to reach watering places and salt springs. Goods were carried on the backs of men and of beasts of burden, sometimes through vast forests and across wide deserts. Besides traveling by land, both the savage and the pioneer built canoes and transported their loads on lakes and streams, where, as on the Great Lakes or the Mississippi River, they could easily paddle, or drift with the current, for hundreds of miles.

215. Roads and Railroads.—As soon as possible the pioneers and early settlers cut roadways through the forests of the East; but at first the roads were not good, for there were stumps, stones, and mud that made the way almost impassable. On the prairies of the West no trees had to be cut, and the task was easier.

More than a hundred years ago there was a movement to build good roads along the Atlantic Lowland and across the Appalachian Mountains. These roads were often called turnpikes, and to meet the cost of building and keeping them in repair travelers paid a small sum as toll at many toll gates. Soon, however, railroads were built from New York, Philadelphia, and Baltimore westward to Buffalo and Pittsburgh. They were later extended westward along the shores of the Great Lakes and through the Ohio Valley and beyond until they now cover the North Central States like a network (Fig. 82).



Fig. 231. Part of the University of Chicago

© Detroit Publishing Co.

As soon as a good road was built along the Hudson Valley, farmers found it easier to send their grain, fruit, and vegetables to New York, and the village storekeepers could more easily get their stock for the

He finds that over good roads he can haul a much greater load of apples, wheat, or potatoes, in less time, and with less strain on horses, harness, and wagon.

216. Transportation in the North Central

States.—No other part of the United States is so well adapted to the development of transportation routes to all parts of the country as the North Central region. The country is nearly level, or at least is not so hilly as to interfere with the making of good roads. Though many prairie roads are muddy, generally there are quarries near at hand that can supply suitable stone for making excellent roads.

It costs less to build railroads in a level country than



Fig. 232. A fast train from Chicago to New York

season. When a turnpike road reached out from Philadelphia to the Susquehanna River, the rich lowland of Pennsylvania could easily exchange its farm products for goods made in the city, or brought to the city from Europe. After the Erie Canal was dug (Sec. 122) the price paid to the western farmers for wheat was higher because it could be cheaply carried to markets where there was a great demand for it. When railroads reached Chicago from New York, the city on Lake Michigan could transact all necessary business with New York swiftly (Fig. 232), while it could still send heavy freight by way of the Great Lakes, the Erie Canal, and the Hudson River.

Now we are realizing that we need better roads both for carriages and wagons and for motor cars (Fig. 233). The government wishes good roads for the rural free delivery of the mails. The townspeople wish them in order that it may be easier for people to come into town to trade. The farmer wishes them for easy access to school, church, and market.



Fig. 233. A good road in North Dakota

in a mountainous region, because there are no expensive cuts and embankments. It has been easy to join Cleveland, Detroit, and Cincinnati by many railroads with Chicago, Milwaukee, and Indianapolis, and other railroads have been built westward to St. Paul, Minneapolis, St. Louis, Kansas City, Denver, and other western cities. In the older days there was much traffic down the Ohio and Mississippi rivers from Pittsburgh, Cincinnati, Louisville, and St. Louis, to Memphis and New Orleans. In later years railroads

have been built from north to south along the Mississippi Valley, and there is not so much traffic on the rivers, except that vast amounts of coal are carried down the Ohio River from Pennsylvania and West Virginia.

The Great Lakes, although closed to navigation by ice during the coldest months of the year, make one of the chief routes for freight in the world. Ships large enough to cross the ocean sail on these lakes and carry freight and people to and from Chicago, Milwaukee, Duluth, Detroit, Toledo, Cleveland, and Buffalo. Boats drawing fourteen feet of water can pass through the Welland Canal to Lake Ontario, the St. Lawrence River, and the Atlantic Ocean.

Past the rapids in the St. Marys River the American government has built two canals (with four separate locks), and the Canadian government one canal. Through these "Soo Canals" an enormous amount of freight passes. Iron ore passes down to ports on Lake Erie and Lake Michigan. Wheat and lumber also are shipped in large amounts. Coal is the largest item of the freight shipped up the lakes.

Thus in the North Central region transportation is easy. The region is mainly a lowland, there is a network of roads, it is crossed by great rivers, and has on its northern boundary the greatest



Fig. 234. Lock in a Soo Canal

system of fresh-water navigation in the world.

In this region also there are large systems of electric interurban railroads (Fig. 235). Some states, such as Ohio, Indiana, and Illinois, are developing networks of these lines.

A business man of Chicago may go to and from his suburban home by steam or electric car. By

means of the telephone he can transact business with men in Milwaukee, Minneapolis, St. Louis, or more distant cities. He can go to New Orleans or New York in a day, and in less than three days to San Francisco, without losing meals or sleep. In three weeks he can visit London, Paris, or Berlin, transact business, and return to his home. He lives in a region so rich in resources that many others can live near him in city and country. All can readily transact business, not only with one another, but with those who are far away.

Review.—1. What favors land transportation in this region? 2. What are the two great systems of water transportation? 3. Which is now the more important? 4. Where are the Soo Canals? What conditions made them necessary? 5. What are the chief commodities carried on the Great Lakes?

6. What advantages do lines of railroad offer to a great city? 7. What are the advantages, to the farmer, of good roads? 8. In what states have interurban railroads developed?




Fig. 235. An interurban railroad car, Indianapolis

Review by States.—Ohio. 9. What advantages has Ohio for transportation? 10. What is the density of population (Fig. 80)? How does it compare with that of Illinois? North Dakota? Pennsylvania? Georgia? 11. Name and locate the capital of Ohio. Where is Cleveland? Cincinnati? Name five other important cities of this state. 12. In which of these eight cities are iron and steel manufactures important? 13. What are the mineral products of Ohio? 14. What are the chief crops?

Indiana (Ind.). 15. By what states is Indiana bounded? By what rivers? 16. How does the surface of northern Indiana differ from that of the southern part of the state? 17. What is the chief Indiana city on the Ohio River? 18. Name and locate the state capital. 19. What very great city lies just beyond the border of Indiana? 20. What young Indiana city is noted for steel manufacture?

Illinois (Ill.). 21. Has Illinois or Indiana the longer coast line on Lake Michigan? 22. Describe the course of the Illinois River. 23. What part of Illinois is prairie? 24. What are the chief products of the farms? What are the chief mineral products? 25. What are the chief industries of Chicago? 26. What are some of the industries of Peoria, Joliet, Elgin, and East St. Louis?

Michigan (Mich.). 27. What is the chief city of Michigan and why is its position favorable for growth? 28. What cities are on or near the shores of Saginaw Bay? 29. Where is Grand Rapids, and what is its principal industry? 30. Name three cities where automobiles are made; one that ships celery; one that manufactures breakfast foods. 31. What two metals are mined in northern Michigan? 32. What makes the climate of southern Michigan favorable for raising fruit?

Wisconsin (Wis.). 33. What rivers and lakes form parts of the state boundary? 34. What is the principal river within the state? Describe its course. 35. Name and locate the state capital. 36. What is the chief city of the state? What are its leading industries? 37. Locate Oshkosh, Racine, and La Crosse. 38. What metal is mined in northern Wisconsin? 39. Name two Wisconsin ports on Lake Superior. What kinds of freight are shipped from them?

Minnesota (Minn.). 40. Name five rivers and two lakes that form parts of the boundary. 41. What river crosses the state? 42. Why has Minnesota thousands of small lakes within its

boundaries? 43. Where are the forests of this state? The prairies? 44. Describe the climate. 45. What kind of wheat is raised in Minnesota? 46. From what ports is iron ore shipped? 47. What are the two principal cities of the state? 48. What are the industries of Minneapolis? Duluth?

Iowa. 49. What states border Iowa? What rivers? 50. What is the most important crop? 51. In what respects do the surface and farm products resemble those of Illinois? 52. Name the capital; two cities on the Missouri River; two on the Mississippi. 53. Describe the course of the Des Moines River. 54. For what is Sioux City important? Keokuk?

Missouri (Mo.). 55. Contrast the surface of northern and of southern Missouri. 56. What river crosses the state? 57. Name and locate the state capital. 58. What are the important industries of St. Louis? 59. Name three cities in the western part of the state. For what is each important? 60. Name four important products of Missouri.

North Dakota (N. Dak.). 61. What river crosses North Dakota? 62. Describe the surface and climate. What differences are there between the eastern and western parts? 63. What are the chief products of the state? 64. Name and locate the state capital. 65. What important city is on the Red River?

South Dakota (S. Dak.). 66. In what respects does South Dakota resemble North Dakota? 67. Where are the Black Hills? 68. What are the important products of the state? 69. Name and locate the state capital; the chief city of the state. 70. In what part of South Dakota are its chief forests?

Nebraska (Nebr.). 71. What long river flows through the central parts of Nebraska? 72. What city is near its junction with the Missouri River? 73. What are its leading industries? 74. In what general direction does the surface of Nebraska slope? How do you know this? 75. What are the important grain crops of Nebraska? 76. Name and locate the state capital.

Kansas (Kans.). 77. Where has Kansas a natural boundary? 78. What states adjoin Kansas? 79. What is the largest city of Kansas? Near what larger city is it? 80. What river enters the Missouri at Kansas City? 81. What great river crosses Kansas? 82. Name and locate the state capital. 83. What are the important products of Kansas?



Fig. 236. Pikes Peak, in the central part of Colorado

THE PLATEAU STATES

217. Explorers and Pioneers.—The first white men who visited the Plateau region were Spanish explorers who entered it from the south. Until 1848 the southern part of the region belonged to Mexico.

After the Louisiana Purchase in 1803 (Sec. 66) an expedition was sent out under Captains Lewis and Clark to explore the northwestern wilderness. They started at St. Louis, went up the Missouri River, crossed the Rocky Mountains, and went down the Columbia River to the Pacific coast.

When Lewis and Clark were on the way home in 1806, a young officer of the army, Captain Zebulon Pike, started westward on a more southern trail. He explored part of the Rocky Mountains, and his name was given to the great peak that overlooks the plains of Colorado (Fig. 236).


About thirty years later Captain Bonneville carried on explorations in Idaho, Washington, Utah, and Nevada.

These are a few of the many daring men who "broke the wilderness," and made known the wonders of its sandy deserts, deep can-

yons, mighty waterfalls, snowclad mountains, and fertile valleys.

The trails of the pioneers were bordered by the graves of those who died on the way. Thus in hope and daring the life of the West began. Railroads now follow the trails, and homes and palatial hotels have taken the place of tents. The Indians have been subdued after many fierce wars and much wrongdoing on both sides. They no longer roam the wilds, but are settled on government reservations, or have homes like those of white men. They seldom live by the chase, but have fixed occupations. Many of them till the soil, keep sheep, or pursue some of their native industries, such as the weaving of blankets, rugs, and baskets.

Great as the industrial progress of the Plateau States has been, much remains to be done in opening the stores of iron, coal, and precious metals, and in bringing the suitable regions under cultivation. Even now, however, the people of both city and country have advantages similar to those enjoyed by the people of the older East.



THE PLATEAU STATES

	AREA, Sq. Mi.	POPULATION, 1920	CAPITAL
Montana . .	146,572	548,889	Helena
Idaho . . .	84,313	431,866	Boise
Wyoming . .	97,914	194,402	Cheyenne
Colorado . .	103,948	939,629	Denver
New Mexico .	122,634	360,350	Santa Fe
Arizona . . .	113,956	334,162	Phoenix
Utah	84,990	449,396	Salt Lake City
Nevada . . .	110,690	77,407	Carson City

Map Study.—1. What states are included in this group? 2. Trace the Rocky Mountains through the several states in which they are found. 3. What region is east of the Rocky Mountains (Fig. 58)? 4. What is the principal mountain range of Utah, and in what direction does it extend?

5. In what state are the most northern waters of the Colorado River system? 6. What other states contribute waters to this great river? 7. In what state is the Grand Canyon of the Colorado?

8. What large river has many sources in the northeastern part of this region? 9. What tributary of the Missouri River flows from Colorado? 10. What tributary of the Mississippi flows from the same state? 11. Where is the Yellowstone National Park? 12. Trace the course of the Yellowstone River.

13. What river crosses southern Idaho? 14. To what river system does it belong?

15. What lands belong to the Great Basin?

16. Are there any large rivers in this region?

17. Where do the rivers find their outlet?

18. What states of this group border on Mexico? 19. What states border on Canada?

20. What parallel of latitude forms the boundary between these states and Canada?

21. How far is it in this region from Mexico to Canada, allowing 69 miles for each degree of latitude? 22. What states adjoin the region on the west?

23. Where is the largest lake within this group of states?

DESCRIPTION OF THE REGION

218. Surface and Drainage.—The states of the Plateau group occupy the central part of the vast upland of the western United States. The Great Plains are so far above

sea level that they are really a plateau. In eastern Montana, Wyoming, Colorado, and New Mexico, the plateau is from 4000 to 6000 feet in altitude. Some smaller plateaus among the mountain ranges, in western Colorado, Utah, and other states, are higher, in places reaching altitudes of 7000 or 8000 feet. Above the plateaus rise the Rocky Mountains and other ranges to altitudes of from 10,000 to 14,000 feet (Fig. 15). Many of the highest peaks are nearly three miles above the level of the sea.

The group includes eight states and covers more than 800,000 square miles of surface, or more than one fourth of the country. Even the smallest state of the group is much larger than the total area of the New England States.

The Plateau States include a part or all of the following streams and drainage basins: (1) The western sources of the Mississippi, including the Arkansas and many long branches of the Missouri; (2) all the upper waters of the Rio Grande; (3) almost all the basin of the Colorado River; (4) most of the Great Basin, whose waters find no outlet to the sea; (5) most of the basin of the Snake River, and parts of smaller branches of the Columbia River.

The greatest mountain mass is that of the Rocky Mountains. In the north they lie on the boundary of Idaho and Montana, and reach far into each state. In Wyoming they are high in the northwest, but lower in the south-central parts, where the Union Pacific Railroad crosses the state. In Colorado there are several high ridges, and between the ridges are valleys, some of which are called *parks*. These parks are mainly grasslands, although parts of them are fine farming regions. The Rocky Mountain system continues south through New Mexico and into western Texas. The continental divide, or watershed between the Atlantic and Pacific oceans, follows the Rocky Mountains from the Canadian to the Mexican boundary (Fig. 237). In the moun-

tains of Colorado are the sources of streams that feed the Missouri, the Arkansas, the Rio Grande, and the Colorado.

The Wasatch Mountains (Fig. 238) are a short range, mainly in Utah. The range runs north and south and separates the Colorado Plateaus on the east from the Great Basin on the west. In the Great Basin a number of parallel ridges have a north and south direction. West of the basin is the Sierra Nevada. All of this range, except some of the eastern foothills, is in California.

219. Climate and Vegetation.—The climate of this region shows wide variation between north and south. In Montana the temperature averages less than 70° in July and 20° in January; in southwestern Arizona it averages 90° in July and 50° in January. Severe winters may interfere with pasturing flocks and herds on the plains of Montana and Wyoming, but in the pasture lands of New Mexico and Arizona cattle and sheep can live out of doors at all seasons. Southwestern Arizona is low, lies in a southern latitude, and is one of the warmest parts of the United States. In Montana, Utah, and Colorado there is perpetual snow on some of the higher mountains. Most of the plateau surface is so high that the air is always cool at night, and comfortable in the shade, even at midday.

For the rainfall, read again section 60. Where there is enough moisture the mountains have much forest, except on the summits and highest slopes. The Great Basin is one of the driest parts of the region. The rainfall there is small and the evaporation rapid; the rivers flow into lakes or sinks which have no outlet to the sea. As evaporation goes on, the salt and other minerals dissolved from the rocks by rain water remain in the lakes, and their waters become salt. The largest of these lakes is Great Salt Lake in Utah, with an area of about 2500 square miles. In some shallow basins there are lakes in the rainy season and salt flats in the dry season.

220. The West Compared with the East.—There are sharp contrasts between the eastern and the western parts of the United States. In the East the fields are generally green and most of the mountains are low enough to be covered with forest. In the more arid parts of the West, grasses and shrubs are scattered and the landscape is gray, like the hue of the desert, except where lines of trees border the streams, and where irrigation has covered the fields with green. In other parts the land is high and rugged, partly covered with forests on the middle slopes, and rocky and snow-clad on the upper slopes and summits.




Fig. 238. Wasatch Mountains, from Salt Lake City



Fig. 239. Royal Gorge of the Arkansas River



Fig. 240. Snake River Canyon, Idaho

In the East the rains come gently, or in storms which are seldom of great violence. In the drier parts of the West, rains come infrequently, and the dry season may last for months. In such regions there are occasional violent storms, called *cloudbursts*, when torrents of water rush down the dry beds of the rivers. In the East the air is often humid; that is, full of moisture, which makes it sultry in hot weather, and chilly in cold weather. In the West there is little moisture in the air, which is clear and bracing at almost all times. In the Plateau States the general elevation of the land is nearly or quite a mile above sea level, the air is thin or rare, and people breathe more rapidly and deeply. Because of the rarity and dryness of the air the region has become a noted health resort. Persons who have just come from the dense air of the lowlands are sometimes made uncomfortable by the rarefied air, and are unable to run or labor as usual. The clearness of the air makes the sun and the stars seem to rise and set suddenly, and at night the heavens are far more brilliant and more stars can be seen than in the East.

There is a difference in the natural scenery also as compared with the East. The mountains are higher and more majestic. In many gorges and on many peaks there are snows that do not disappear even in midsummer. On the desert plains, the winds sweep with violence, for there are no barriers to hinder their movement. There is no good cover of grasses and roots to hold down the earth and sand, and enormous quantities of dust are sometimes blown into the air. Such a dust storm may be somewhat like the blinding snows of a winter blizzard. In some places the winds pile up the sand into hills, forming sand dunes.

The rivers have cut deep valleys and narrow gorges in the plateaus and through the mountains. These may be half a mile or even more in depth. Examples are found in the Royal Gorge of the Arkansas River in Colorado (Fig. 239), in the canyons of the Gunnison in the same state, in the canyons of the Snake River in Idaho (Fig. 240), and especially in the Grand Canyon of the Colorado River.



Fig. 241. Grand Canyon of the Colorado River

221. The Grand Canyon of the Colorado River.—The Colorado River rises in the lofty Rocky Mountains of northern Colorado. It flows southwest across Utah, passing through many deep gorges that it has cut into the rocks of the high plateau. In this state also it is joined by the Green River, a large tributary which rises in Wyoming. When the river enters Arizona, it bends to the westward and flows in a canyon which is, in some parts, a mile deep. This is the *Grand Canyon*, the most wonderful gorge in the world (Fig. 241). At the bottom the river flows as a swift torrent, with many dangerous rapids. From the water, the walls rise in places almost vertically half a mile or more. Then the canyon widens, so that at the top it is from eight to twelve miles across.

Many side canyons join the main one, and some layers of rock, being harder than others, have been sculptured into walls, buttresses, and towers, like the buildings and cathedrals of a city built on a scale far above that of man's work. The rocks are of many colors,—reds, grays, yellows, and browns of various shades,—and under the changes of sunlight and shadow they make a world of wonders. A railroad now leads to the rim of the Grand Canyon, and every year thousands of travelers visit it.

222. The Yellowstone National Park.—In the high mountain region where the three states, Wyoming, Montana, and Idaho, come together, is the Yellowstone National Park (Fig. 242). Most of it is in the state of Wyoming. The continental divide crosses the park, which lies in the basins of the Missouri and Snake rivers.

The canyon and falls of the Yellowstone River, and hot springs and geysers to the number of a thousand or more, furnished the chief reasons for laying out a national park here. Hot springs are found in many parts of the United States, as at Hot Springs, Arkansas, and Glenwood Springs, in western Colorado. The waters of such springs have



Fig. 242. Yellowstone National Park


been heated by contact with hot rocks not far below the surface.

The park is one of the few places in the world that have *geysers*, or springs that spout hot water. "Old Faithful" is so called because once in a little over an hour, with great regularity, a column of steaming water rises from it 120 or 150 feet into the air. Other geysers spout every few hours, or days, or irregularly, but the cause is the same in all. At some distance below the surface of the earth the water in the geyser becomes so hot that it is suddenly changed into steam. The expansion of the steam forces the water above to rush out of the opening and rise high into the air. When the steam has escaped, water again collects in the geyser and is heated until the spouting is repeated.

Hot waters dissolve many substances out of the rocks. When they reach the surface, the waters become cooler and cannot hold so much dissolved matter. They deposit it at the mouth of the spring, and in this way terraces of wonderful colors and forms have



Fig. 243. Hot springs and terraces, Yellowstone Park



U. S. Dept. of Ag., Forest Service
Fig. 245. A forest ranger

been slowly built up about some of the hot springs in the park (Fig. 243).

Hunting in the park is forbidden, and animals such as elk and bear lose their fear of man and become less wild. A herd of buffalo is kept in the park. This, and a few other small herds kept in Canada and the United States, are all that remain of millions of these animals that once roamed our western plains.

There are excellent roadways and hotels in the park, and the mountain air, the wild animals, the geysers and springs, the lakes, rivers, and canyons will always attract thou-

sands who are seeking health, pleasure, and knowledge.

223. Glacier National Park.—In 1910 the government set aside an area of about 1500 square miles in northwestern Montana as a national park. It is a region of great natural beauty, with towering peaks (Fig. 70), lovely valleys, and gem-like mountain lakes. As there are many glaciers within its borders it has been named the Glacier National Park.

224. National Forests.—In the Plateau States, and also in some other states, the government has established a number of

forest reserves (Fig. 244). They are mainly in mountain districts where there is sufficient moisture for trees to grow. It is expected that these forest lands will always be kept under government control, as the preservation of the forests will prevent the washing away of the soil and the destruction of property in the valleys. Men trained in forestry, which is the science of caring for trees, have charge of these reserves. Under their direction are many forest rangers (Fig. 245), who lead



Fig. 244. National forests and national parks

a lonely but a very busy life, constantly moving about on horseback or on foot. Among many duties they prevent forest fires, put them out when started, and prevent the stealing of timber.

The reservation of these lands by the government does not mean that they cannot be used. Cattle, horses, and sheep may be pastured here, under government regulation and on payment of a small fee for each animal. The herders must put out their camp fires, and must not allow the grass to be eaten too closely. Tourists and hunters are free to use wood, and permits are given also to cut timber, but only the fullgrown or "ripe" trees. Some of the giant trees of California are included in a government reservation. There are so few of one or two species, that if this were not done they might soon become extinct.

Review.—1. How large are the Plateau States as compared with New England? 2. What are the "parks" of the Rocky Mountain region? 3. Where is Pikes Peak? Why does it bear this name? 4. Describe the consequences of the small rainfall of the Great Basin.

5. Compare the East and the West in at least three respects.

6. Define *canyon*, and name the greater canyons of this region. 7. Describe the Grand Canyon of the Colorado River.

8. What region has geysers? Describe the action of a geyser. 9. In what park are there glaciers? Where is this park? 10. What are the duties of forest rangers? 11. What restrictions are put upon pasturing in the government forest reserves?

GRAZING

225. Cattle.—Cattle, sheep, and horses are raised in large numbers in the Plateau States; for much of the land is valuable only for pasture. Cattle raising is carried on in both the




Fig. 246. Distribution of sheep in the United States

South Central and the North Central States (Secs. 167 and 192-194), but the industry extends westward, and is important throughout the Plateau States.

226. Sheep.—The Plateau States raise more sheep than cattle. Every state in this group has a large number of sheep, and all together the Plateau States have nearly half of the sheep in the United States. Outside this group, the largest producers of sheep are Texas in the South, California and Oregon on the Pacific coast, and Ohio, Michigan, and Missouri in the North (Fig. 246).

In the Plateau States the sheep live mainly on the open range, and many thousand may be found in the flocks of a single owner. A sheep herder and camp tender are usually in charge of each herd of two or three thousand sheep. During the summer the sheep graze on the mountains. As winter approaches they are driven to the lower ranges and thence out upon the plateau. For some months each year the herder and his camp tender live alone with only a covered wagon as a home.

As the pasturage of the plains is thin, the flocks must often be moved to fresh grounds. Sheep eat so closely that if kept long on the same pasture, they destroy even the roots of many of the plants on which they feed.

Besides the grasses of the desert, sheep feed on other plants, including low shrubs. One of these is a thorny shrub called "shad scale," and still another is "winter fat," which produces nutritious seeds that cling to the stems all winter.

Sheep may be sheared on the ranch, or driven to shearing stations. The shearers go about from ranch to ranch or from station to station, beginning in the south and going north as the season advances. In the north early summer is the shearing season. Billings, Montana, on the Yellowstone River, is one of the many centers of the sheep trade.

As in the case of cattle, every part of the sheep is valuable. The wool goes to the woolen mills. Many animals are fattened for mutton. The hides are made into leather, and the bones and other parts add to the farmer's supply of fertilizers for his fields.

The United States ranks third among the great sheep-raising countries. Australia leads all others, followed by Argentina and then by the United States. Many sheep are raised in European Russia, South Africa, and western Asia. The countries east of the Mediterranean, and Turkestan, east of the Caspian Sea, abound in sheep and shepherds, as they have for thousands of years in the past. In

almost every case the sheep-raising countries of the world have wide areas of dry plains on which the sheep are pastured. Much care has been taken to improve the breeds, so that they furnish better mutton and heavy fleeces of long and fine wool.

IRRIGATION AND CROPS

227. Irrigation.—In the eastern part of the United States, and on the prairies, the farmer depends on the rains to water his crops and to replenish the wells and springs that supply his home and his stock. In a time of drought he may wish he could water his potatoes or his corn, but there is usually enough moisture to bring his crops to a good harvest.

In the greater part of the Plateau States, however, the annual rainfall is small, and frequently the water that falls comes down in fierce storms and runs quickly away in torrents, or soaks into the porous soils of the plains, beyond the reach of roots. The abundant rains are in the mountains, where the climate is too cold and the land too rough for crops. On the plains, where the soil is easy to plow, there is not enough moisture.

Therefore the water in the streams is in many places made to flow upon the fields of the valleys, where it will water crops of grain, fruit, and vegetables. This is irrigation, a process that farmers have practiced since ancient times in Egypt, in India, and in many other dry regions. Even the cliff dwellers of our Southwest used irrigation in a small way, long before the Spanish explorers came to that region.

228. Irrigation in Utah.—In the year 1847, the Mormon settlers found their way to the region of Great Salt Lake, in the center of the present state of Utah. They could not have supported themselves in that dry country without



Fig. 247. A sheep ranch in Montana



Fig. 248. Distributing ditch—one of the main canals of an irrigation system—in Arizona

watering their fields. The region first settled is at the western foot of the Wasatch Mountains. Never-failing streams flow out of these mountains, and the Mormon people dug ditches, watered their crops, and made the region productive and prosperous.

229. Irrigation in Colorado.—The greater rivers of the western mountains furnish much water to the plains, for they are fed by the rains and snows at their sources. The waters of the Platte and Arkansas rivers in Colorado have long been used for irrigation. Large ditches near Denver take water out of the South Platte River. Each ditch is tapped at many points and the water carried in smaller ditches to the fields below it. The fields are leveled, if necessary, and still smaller channels and furrows are made, to convey the water to the seeds and roots. In villages or parks the small ditches are so arranged as to water the rows or clumps of shade trees.


In the early days a man might make a ditch of his own to bring the river water to his farm, but soon so many farmers needed water that there was need of coöperation. Companies were formed to build the dams, cut the main ditches (Fig. 248), and sell to each farmer the right to use a certain

amount of water. This is still done in many places, both in Colorado and in other states. In many places, also, water for irrigation is pumped from deep wells.

230. The Reclamation Service.—In 1902 the government of the United States organized the Reclamation Service,* in order to reclaim, or make useful, more of the arid lands. Under this plan the government selects a suitable site on a large river and builds a great dam (Figs. 1, 249). A site is suitable if the valley is narrow, with a good bottom, if a large lake or reservoir can be formed by the dam, and if the lands down the stream



Fig. 249. A government reclamation dam, New Mexico



are good, and lie in such gentle slopes or plains as to be readily reached by the water.

We must not think that citizens of all the states are taxed in order to furnish water to western farmers. The money was raised from the sale of public lands in the states where it is now expended for irrigation; and the farmers who buy the land, and use the water, must pay back to the government, in several installments, the cost of the improvements. When these payments are completed the farmer receives full title to the land. The money paid for it is used to make similar improvements in other dry regions.

There is not space in this book to describe all of these *irrigation projects*. The map (Fig. 250) shows their locations and many of the rivers that supply the water.

Some of the reservoirs made by the government really form large lakes (Fig. 249) that add much to the beauty as well as to

the usefulness of the region. Great feats of engineering are required, as in the Gunnison tunnel in Colorado. Here daring surveyors and engineers found a route and dug a tunnel through a mountain from the canyon of the Gunnison to the flat lands bordering the Uncompahgre River. In the one valley there was water but little land; in the other were broad fields but very little water. Government experts have brought the two together. In some cases the reservoirs can be used to furnish water power, thereby promoting manufacture as well as agriculture.

231. Crops raised by Irrigation.—A great va-

riety of crops is raised on the irrigated lands of the West. In the more northern states, such as Montana, Idaho, and Wyoming, wheat and other grains, vegetables, and hardy fruits are raised. Most important among these is the apple. Many large and profitable orchards are found in these states and also in Oregon and Washington, the northern states of the Pacific coast.

In Colorado millions of acres of land are "under the ditch," and there are many thousand miles of irrigation canals. Without the artificial use of water, this land would be useless save for pasturing a few animals. As a result of irrigation it is worth from \$60 to \$300 per acre, makes homes for many thousand people, and feeds the cities and mining camps of the state. Potatoes and other vegetables, peaches and other fruits, and the sugar beet are raised in abundance. Alfalfa produces several crops a year, and

the farms, under most careful tillage, are really large and productive gardens.

Some parts of New Mexico and Arizona have almost a tropical climate. Especially is this true along the Salt and Gila rivers in Arizona, where cotton is raised and where orchards of date palms are producing fruit. The palms were brought from Africa by the United States Department of Agriculture. On irrigated lands in California nearly every kind of grain and fruit is produced.

232. Life in Irrigated Regions. Farmers who make use of irrigation cannot cultivate large farms. They must spend their time on a few acres, in careful or *intensive* culture. Thus, while the mountain streams have water enough for only a small part of the dry plains, food for millions can be raised. As farms are small, people live close together, almost as in a village. Neighbors are near, schools, churches, and all the conveniences of life are close at hand. Such life develops skill and has many comforts and advantages that do not come so easily to people scattered on the large farms and ranches of the prairies and Great Plains.

233. Dry Farming. In the drier parts of the West many early attempts at agriculture failed except where irrigation was employed. In recent years agricultural methods have been so improved that large areas have been brought under cultivation in regions where the annual rainfall is less than 20 inches. This is called *dry farming*, although of course no crop can be grown absolutely without water. The term really means farming where there is less moisture than is usually thought to be necessary.

Water in the soil is lost either by being evaporated directly from the surface or by being taken up by plants and evaporated from them. In dry farming there are four important things to do: (1) The ground must be plowed before the rainy season so that as much rain as possible will soak into the soil. (2) The surface layer of soil should be cultivated frequently so as to prevent

the evaporation of the moisture; for evaporation takes place very slowly when the deep-lying moist soil is protected by a covering of finely pulverized dry soil. (3) Care should be taken to raise such crops as require the least moisture for their successful growth. (4) Sometimes it is best to grow a crop only once in two years, keeping the soil cultivated and fallow in the meantime so as to secure for the use of the plants as much as



Fig. 251. Wheat raised by dry farming, Wyo.

possible of the two years' rainfall.

Review.—1. What two states lead in sheep raising? 2. What other states raise many sheep? 3. Describe the keeping of sheep in the Plateau region. 4. Name and locate a sheep market in Montana. 5. Name the three chief sheep-raising countries of the world in order of their importance in this industry.

6. Name three countries in which irrigation is practiced. 7. When and by whom was irrigation introduced into Utah?

8. Describe the method of bringing the water to the fields.

9. What is the Reclamation Service? When was it organized? 10. Explain the financial plan of government reclamation work. 11. What use is made of the waters of the Gunnison River?

12. What crops are raised by means of irrigation in Montana and Idaho? In Colorado? In Arizona?

13. What effects has irrigation upon the manner of living of the people?

14. What is dry farming? How is it done?

MINING

234. Ores. — The Plateau States form one of the great mining regions of the world. The most important metals found in them are gold, silver, copper, lead, and zinc. These metals are usually mixed or combined with other minerals, and the whole mass in which a metal occurs is called an *ore*.

235. Precious Metals.—Gold and silver are called the precious metals because small amounts of them have a high value. They are used in making coins, ornaments, and many artistic as well as useful things. These metals are most commonly found in mountain regions. The reason for this is that the rocks in such regions have been folded, cracked, or crushed, and sometimes heated. In some places the metals have been dissolved by water in the rocks and deposited in pockets and cracks along with other substances, thus making *mineral veins*, composed of ore.

The sides and tops of mountains have been worn away by frosts, glaciers, and streams. Where the rocks contain veins of gold ore, these also have been worn away, and particles of gold are mingled with the sand and gravel which are carried down the mountain and deposited by streams. Such gold-bearing earth is called a *placer*.



Fig. 252. Sluice mining

236. Mining Methods.—When gold was first found in the placers, the miners put the gravel and sand into a pan with water and shook the pan. In this process of *placer mining* the particles of gold sink to the bottom, because they are many times heavier than the rest of the material. The miner can therefore gather them from the bottom of the pan. Pieces of considerable size, called nuggets, are sometimes found.

In order to secure the gold more rapidly, a powerful stream of water is turned upon a bank of gold-bearing gravel, through a large hose. The gravel is washed through a trough or sluice having crossbars in the bottom (Fig. 252). The gold, being heavy, sinks behind the crossbars and is gathered. When water is thus used on a large scale, the process is called *hydraulic mining*.




Fig. 253. Metal production and mining regions of the United States

When metal-bearing rock is found in veins, it is dug out, usually from mines beneath the surface, even at a depth of hundreds or thousands of feet. Shafts are sunk to reach the vein, or tunnels, called *drifts*, are dug into a mountain side. The vein may be several inches or several feet thick, and this is followed and blasted out. In many of the great mines there is a network of shafts and tunnels, with every convenience for drilling, blasting, and hoisting the ore. Pumping is often necessary to keep the mines from being flooded with ground water, and in some mines, as at Virginia City in Nevada, hot water and steam make it difficult to work the mine at all. The roofs of large chambers must be supported by heavy timbers, making large demands on the forests of the neighborhood. The drills may be driven and the mines lighted by electricity.

There are various methods of extracting the metals. In some cases the ore is crushed into powder by powerful stamping machinery, and then treated by the aid of various chemical processes to separate the metal. Other ores are put through a blast furnace, and the metals, as in the case of iron, are separated by means of heat. A plant for separating metals in this manner is known as a *smelter*. There are smelters at Leadville, Pueblo, Colorado City, and Denver, in Colorado, at Butte, Great Falls, and Anaconda in Montana, near Salt Lake City in Utah, and at various other places. Some ore is shipped as far east as Omaha to be smelted.

Many of the richest mineral regions are on lands owned by the government. A man who searches for ores is called a prospector. When he is successful in finding a productive spot, he files a claim to it, and thus secures the right to work the claim and enjoy the profits of it.



Fig. 254. The Anaconda mine at Butte

Rich finds of the precious metals often cause great excitement. Men rush in, it may be by thousands, hoping to gain sudden wealth. Tents are set up, rude cabins are built, mining machinery is brought in, and stores are quickly fitted out with all kinds of supplies. Such a mining camp may in a few months contain as many as ten thousand people. If the locality remains productive for a number of years, substantial buildings are erected, streets are laid out and improved, and the conveniences of modern life are provided for the people. If the supply of ores is very large, or if the place becomes a center of trade for surrounding regions, a permanent city is established. If the ores are exhausted, and the place has no other advantages, it may in a few years be almost abandoned.

237. The Great Metal-mining States.—All the states of the Plateau group produce gold and silver. Montana yields much silver and mines more copper than any other state except Arizona. Butte (Fig. 254), in the western part of the state, is the center of a mining region that has produced more copper than any equal area in the world.

Great quantities of silver and lead are produced in the Cœur d'Alene district in northern Idaho. Much of the trade of this region goes to the important city of Spokane in Washington.




Fig. 255. Mine and smelter at Tonopah

Colorado has large mining sections in various parts of the Rocky Mountains. It produces large amounts of gold, silver, zinc, and lead; it also yields ores from which tungsten, radium, and other metals are obtained. Leadville grew to be a city because of deposits of silver and lead. It is situated in the Arkansas Valley about two miles above sea level. Cripple Creek sprang up as a gold-mining camp, and is now a city of several thousand people. Ouray, Silverton, and Telluride are mining towns in the San Juan Mountains in southwestern Colorado.

Utah has many mines and yields large amounts of copper, silver, lead, and gold. It ranks with Montana, Nevada, and Idaho as one of the great silver-producing states.

Nevada, which is one of the driest of these states and has but little agriculture, is a large producer of precious metals at Goldfield, Tonopah (Fig. 255), and other places. Nevada stands with Colorado, California, South Dakota, and Arizona among the leaders in gold production. It is also one of the great silver-mining states, and produces much copper.

Arizona is the greatest copper-mining state in the Union. Bisbee and Jerome are the principal centers of copper production in this state. There are some copper mines also in New Mexico.

238. Coal and Iron.—Besides the metals already named, the Plateau States have enormous beds of coal. Colorado is the greatest producer of coal, and Wyoming is second. Montana, Utah, and New Mexico also are coal-mining states. Trinidad, Colorado, and Sheridan, Wyoming, are coal-mining centers. Coal is needed in the Plateau States for running the mines and smelters, as well as for railways, factories, and domestic

use. Iron ore is found in many places, and is smelted at Pueblo, in Colorado. Much petroleum is produced in Wyoming, and Casper is a great center of this industry.

239. Summary.—At first people were attracted to this region by the discovery of gold and silver; the other mining industries, and the cattle and sheep ranches, were of later development. As the number of people increased, irrigation was encouraged, and agriculture became an important industry. Churches, libraries, schools, and colleges were soon established; as in the North Central group, every state supports a university, and in some cases also a separate college of agriculture and the mechanic arts. A region which seemed barren, and which was once called "the Great American Desert," has been made into a land of wealth, culture, and prosperity.

Review.—1. What is an ore? A mineral vein? 2. Describe placer mining; hydraulic mining. 3. What are some of the processes of extracting metals from the ores?

4. Which three states of this group produce much copper? Name a copper-producing city.

5. Where is the Cœur d'Alene district, and what metals does it produce? 6. Give an account of mining in Colorado. 7. What are the chief mineral products of Utah? Of Nevada?

8. What states in this region mine the most coal?

ROUTES AND CITIES

240. The Earliest Rail Route.—In the ten years from 1850 to 1860 the United States government sent out many surveying parties to find suitable railroad routes from the Mississippi River to the Pacific coast. In 1869 the first railroad was opened to the western coast. This was, in part, the Union Pacific Railroad, which crosses Nebraska and Wyoming to Ogden, Utah, in the center of an agricultural and fruit-growing region. From that place a connecting railroad passes through the Great Basin, and over the Sierra Nevada to San Francisco. On this trans-continental line, in Wyoming, is Cheyenne, the state capital, located in a fine grazing region; and in Nevada is Reno, the largest city and chief trade center of that state. At the foot of the Wasatch Mountains is Salt Lake City, the capital of Utah, the chief city between Denver and the Pacific coast, and one of the great business centers of the West (Fig. 256). From this city connecting lines of the Union Pacific system cross southern Idaho to Portland, Oregon. On this route are Pocatello, with railroad repair shops, and Boise, the capital of Idaho and an important manufacturing and trading center.

241. Northern Routes.

—In the states to the north, the Northern Pacific, the Great Northern, and the Chicago Milwaukee and St. Paul railroads pass through the chief cities of North Dakota, South Dakota, Montana, Idaho, and Washington to Seattle and other ports on Puget Sound. These roads get supplies of freight from the grain fields of the plains, the stock ranges of Montana, the mines of



Fig. 256. Salt Lake City




Fig. 257. Denver and surrounding region

Montana and Idaho, and the wheat fields, lumber mills, and orchards of Idaho and Washington.

Helena is the capital of Montana. It is on the border of a rich farming district, and near many mines. It has large quartz crushers and railroad shops. Much smelting is done at Anaconda and Great Falls. Missoula is the center of a prosperous lumbering, mining, and farming region.

242. Colorado Routes.

—Several roads cross the Rocky Mountains in Colorado. The first to be built was the Denver and Rio Grande, which passes from Denver and Pueblo (Fig. 257) through the Royal Gorge and over the continental divide to Salt

Lake City and Ogden. Denver is the capital of Colorado and one of the great cities of the West. It is on the South Platte River, a few miles east of the Rocky Mountains. Many railroads center here from all directions. It has a large wholesale trade with the rich agricultural and mining regions around it, and is the chief live-stock market of this part of the country. In addition it has large smelters, machine shops, flour mills, and meat-packing establishments.

Colorado Springs, near the foot of Pikes Peak, is a health resort and the financial center for Cripple Creek and other mining places. Pueblo, on the Arkansas River, has smelters for iron, silver, and lead, and is the second city of the state. The University of Colorado is at Boulder.

243. Southern Routes.—The Atchison Topeka and Santa Fe Railway and the Southern Pacific cross New Mexico and Arizona, and reach Los Angeles and San Francisco in California. In the northern part of New Mexico is Santa Fe, the capital of the state. This is one of the ancient Spanish settlements, as its name indicates. It was founded by a Spanish pioneer in 1605. Many of the homes are of *adobe*, or sun-dried brick, and some of the people still speak the Spanish language. One of the historic routes from Missouri to the West is known as the old Santa Fe trail. The largest city of New Mexico is Albuquerque, a health resort and railway center, with stockyards, large railroad shops, and lumber mills.

In Arizona, Tucson and Phoenix, the capital, are centers of beautiful farming and grazing regions. The region around Phoenix is irrigated with the water stored in reservoirs on Salt River.

Review by States.—Montana (Mont.). 1. Describe the drainage of this state. 2. What is the latitude of its northern boundary? 3. What livestock industry is important in Montana? 4. What mountains extend through the western part of this state? 5. Name and locate the

capital. Locate Butte, Billings, and Great Falls. 6. What transcontinental railroads cross Montana? 7. What is the density of population of this state (Fig. 80)? How does this compare with Colorado? Nevada? Missouri?

Idaho. 8. Name the states on the boundary of Idaho. 9. Locate the Spokane River; the Salmon River; the Snake River. 10. Which of these rivers has cut deep canyons? 11. What important mining region is in this state? 12. What is the trading center for this mining region? 13. Name and locate the capital.

Wyoming (Wyo.). 14. Describe the boundaries of Wyoming. 15. Where is the Yellowstone National Park? 16. Which parts of Wyoming are in the Missouri basin? 17. Name and locate the capital; locate Sheridan. 18. What useful mineral is extensively mined in Wyoming? 19. What railroad crosses Wyoming?

Colorado (Colo.). 20. Name and locate the capital of Colorado; in what ways is it important? 21. Make a drainage map of the state, and on it locate seven cities. 22. What are the chief products of Colorado? 23. Locate Pueblo, and name an important industry of that place. 24. Name and locate an important health resort in this state. 25. Locate Boulder, Cripple Creek, and Trinidad.

Utah. 26. Who first settled Utah? 27. What mountains furnish water for irrigation? 28. What is the principal lake and why is it salt? 29. What transcontinental railroad was first completed? When? What city of Utah is on this line? 30. Name and describe the capital. 31. What great river crosses the state? What river from Wyoming joins it? 32. What states border Utah?

Nevada (Nev.). 33. Describe the rainfall of Nevada. 34. What mountain range is west of the state? 35. What is the chief river of Nevada? 36. Why does it not reach the sea? 37. What river borders Nevada on the southeast? 38. What metals are mined in large quantities in Nevada? 39. Name and locate the capital; the chief city.

New Mexico (N. Mex.). 40. Bound New Mexico. 41. What river crosses it? 42. Name and locate the capital. Give an account of its history. 43. Name and locate the largest city. 44. What great railroads cross the state?

Arizona (Ariz.). 45. What great river crosses the northern part of Arizona? 46. What river crosses southern Arizona? 47. Name and locate the capital. 48. Describe the climate of Arizona. 49. What are the chief products of the state? 50. Locate Bisbee and Tucson.



Fig. 258. The water front at Seattle, one of the large cities of the Pacific coast

THE PACIFIC STATES

244. Discovery and Settlement.—Before there were colonies in Massachusetts or Virginia the western coast had been visited by several Spanish explorers, and by Sir Francis Drake, the great English navigator of Queen Elizabeth's time. These early voyages were in the sixteenth century. Not much, however, was known concerning this region until about the time of the American Revolution. Then Spanish priests from Mexico established missions at San Diego and elsewhere along the coast of California, and converted the Indians to Christianity. Many of the old Spanish churches are still standing or have been restored.

In 1792 Vancouver sailed along the coast; the island at the opening of Puget Sound bears his name. In the same year Captain Robert Gray of Boston, commanding the *Columbia*, after much difficulty, sailed against the current into a great river, and gave to it the name of his ship. It was not long after this that Lewis and Clark came across the mountains to the same place

(Sec. 217). The development of Oregon and Washington as an agricultural region began with settlements made in 1832.

In 1844 Captain John C. Frémont, a famous American explorer of those days, came overland into California. During the war with Mexico he took part in the American conquest of that region. In 1848 gold was discovered in the river gravels, and in 1849 began a rush of tens of thousands of people from the East.

For a time more than half the people of the Pacific coast were engaged in mining; and later the industries of lumbering and fishing became very important. But most important of all at present is agriculture, for which there is abundance of rain in the great valleys and near the coast, except in the south. In other regions irrigation and dry farming are very successful. Commerce and manufacturing have developed, large cities have grown up, and the Pacific States have become one of the most prosperous parts of our country.

THE PACIFIC STATES

	AREA, SQ. MI.	POPULATION, 1920
Washington	69,127	1,356,621
Oregon	96,699	783,389
California	158,297	3,426,861

Map Study.—1. How far apart are the northern and southern boundaries of California, allowing 69 miles for each degree of latitude? **2.** Compare the longitude of San Francisco with that of the city of New York (see map of the United States). **3.** Give the position and main direction of the Sierra Nevada. **4.** Where is the Yosemite National Park? **5.** Locate Mt. Shasta, Mt. Hood, Mt. Rainier, and Mt. Baker.

6. Where is Point Conception? **7.** What important bay indents the Pacific coast of the United States? **8.** Trace the course of the Columbia River. **9.** What mountain ranges border the Pacific coast? **10.** What large island is at the opening of Puget Sound? **11.** Compare the Atlantic and Pacific coast lines of the United States. **12.** What group of islands lies off the coast of California?

13. Name and locate the chief city of southern California; the chief seaport of central California. **14.** Describe the location of Portland in Oregon; Seattle and Spokane in Washington. **15.** What important cities in western Canada may be reached by a short voyage from the city of Seattle?





Fig. 260. Lassen Peak in eruption

DESCRIPTION OF THE REGION

245. The Sierra Nevada.—Of the three states in the Pacific group California is the largest, and has the highest mountains. The Sierra Nevada, named by the early Spanish settlers from a range in southern Spain, extends nearly north and south through eastern California. This name means *snowy range*. Much of the Sierra has an altitude of 13,000 feet, or almost two and one half miles. Mt. Whitney rises to 14,502 feet, — the highest elevation in the United States (exclusive of Alaska), — and other peaks are nearly as high. Lassen Peak is the only active volcano in the main part of our country (Fig. 260). Farther north is Mt. Shasta (Fig. 69), a volcanic cone almost as high as Mt. Whitney. On Mt. Shasta and on other high

slopes of these mountains are several glaciers and many fields of perpetual snow. The range has a gentle slope toward the west, but is steep on the east, where it overlooks the Great Basin in Nevada. The lower western slopes of these mountains are covered by forests or have been cleared to form fertile fields; but the upper slopes are above the timber line, and consist of bare rocks and rock waste.

246. Cascade Range.—The same mountain range continues northward through Oregon and Washington, but in those states it is called the Cascade Range. It is not so high as the Sierra Nevada, but is broader and is covered with great forests. Above it rise several volcanic cones, to the region of glaciers and perpetual snow. Seen in the sunlight they are like bright jewels rising above the setting of the dark green forest. Among these peaks are Mt. Hood in Oregon, and Mt. Rainier and Mt. Baker in Washington. Mt. Rainier is 14,363 feet in altitude, and is one of the noblest mountain peaks in the United States (Fig. 261).

247. The Great Valleys.—West of the Sierra Nevada and Cascade Range is a series of wide, open valleys, with a fertile soil and a large population. One of these is the Great Valley of central California, shut in by the Sierra Nevada on the east and the



Fig. 261. Mt. Rainier. Observe the reflection in the water



Fig. 262. Coast Range, southern California. The men in the foreground are piling beans

Coast Ranges on the west (Fig. 262). It is four hundred miles long and fifty miles wide. The southern part is drained by the San Joaquin River, which flows northwest. The northern part is drained by the Sacramento River, which flows southward. Both rivers receive many tributaries, and they unite before entering San Francisco Bay. The bay connects with the ocean through the Golden Gate, a break in the Coast Ranges (Fig. 263). The eastern tributaries of both rivers are fed by the rains and melting snows of the Sierra Nevada. Many of them are small during the dry season. The western tributaries, coming from the eastern slope of the Coast Ranges, are much less important. This slope gets but little rain. For this reason it is scantily covered with forest, and none of its streams reach the trunk rivers in the valley during all of the dry season.

West of the Cascade Range in Oregon is the fertile Willamette Valley, a region about the size of Massachusetts. Through this valley the Willamette River flows northward and joins the Columbia River. On the Willamette, a short distance from its mouth, is the city of Portland. West of the Cascade Range in Washington is

a broad, fertile valley whose northern part is deeply indented by Puget Sound.

248. Coast Ranges.—Like the Sierra Nevada and Cascade Range, the Coast Ranges extend north and south through the three states. The northern Coast Range in Washington, between Puget Sound and the ocean, is known as the Olympic Mountains. The Coast Ranges are rugged in many places, but are much lower than the Sierra Nevada.

249. Columbia Plateaus.—East of the Cascade Range in Oregon and Washington is a plateau country, often called the Columbia Plateaus. The region lies along the Columbia River in Washington, and extends through Oregon southward. Spokane is the principal city of the Columbia Plateaus. Over much of this region the surface rocks are of lava. The lava was poured out, in a

fluid state, from many ancient volcanoes or from long fissures or breaks in the earth's crust. It was so abundant that it covered thousands of square miles to a depth of hundreds of feet. Weathering has changed the surface lavas into soil. The canyons of the Columbia and Snake rivers are cut across these lava fields.



Fig. 263. The Golden Gate

250. Yosemite Valley and Crater Lake.

—The Yosemite Valley is a deep canyon in the Sierra Nevada (Fig. 264). The Merced River and some of its branches enter the canyon by falls from 300 to 1600 feet high. The Yosemite is as well known, though not so large, as the Grand Canyon of the Colorado.



Fig. 264. Yosemite Valley, California

In the heart of a low, broad, volcanic mountain in the Cascade Range is a pit six miles across and 4000 feet deep, half filled with water, called Crater Lake (Fig. 265). The basin was formed by the sinking of the central part of the mountain. This place, like the Yosemite Valley, has been reserved by the government as a national park.

251. Climate.—The climate of this region shows sharp contrasts (Secs. 25–27), the climate of western Washington being temperate, while that of Death Valley and some other parts of California is marked by great heat. In each state the temperature of the great valleys is moderate, while the high mountains show Arctic conditions of frost, snow, and ice. All the lowlands that lie near the Pacific Ocean have a mild climate, being cooled in summer and warmed in

winter by the prevailing westerly winds blowing from the sea.

There are also great contrasts in rainfall in this region. Here are the wettest, and some of the driest, lands in the United States. Except in high mountains, the winter season is wet rather than snowy, and the summers are dry,—so dry, on some

of the lowlands, that bags of wheat and trays of fruit can be left out of doors for many weeks without injury from moisture.

The average annual rainfall in western Washington is about 65 inches. In some parts of the mountains it is even more than this, and is the heaviest in the United States. Eastern Washington, on the other hand, is east of the mountains and has but about 20 inches of rainfall. Oregon shows a like difference between its western and its eastern parts. Northern California, and the high mountains toward the south, have plentiful rains, while the southern parts of the Great Valley are so dry as to need irrigation, and parts of southeastern California are among the driest of deserts. The range of rainfall in the state is from 3 inches in some southern parts to 80 inches in the mountains of the northwest (Fig. 72).




Fig. 265. Crater Lake, Oregon

Review.—1. Which is the largest state in the Pacific group? 2. How does it compare in size with your own state? 3. Where is the principal mountain range in the Pacific States? What names has it? 4. Where are the great valleys of the three Pacific States? 5. What rivers drain the Great Valley of California? 6. What river drains the great valley in Oregon? 7. Locate and describe the Columbia Plateaus. 8. Describe the Yosemite Valley. 9. What is Crater Lake? 10. Compare the rainfall of eastern and of western Washington; of northwestern and of southeastern California (Fig. 72). 11. Explain the differences observed. 12. Where are the wettest and the driest parts of Oregon? Why?

INDUSTRIES

252. Agriculture.—The leading industry of the Pacific States is agriculture. In the Puget Sound and Willamette valleys and in the northern part of the Great Valley of California, rainfall is sufficient for crops. Even where the rainfall is scanty, as is the case in much of eastern Washington, eastern Oregon, and the southern and south-central parts of California, dry farming (Sec. 233) may be practiced or irrigation works may be constructed to bring the water of the mountain streams to the fertile lands of the valleys.

In the early days of the agricultural development of these states wheat was a leading crop, and it is still an important crop in eastern Washington and Oregon. As the great wheat districts of these two states are east of the Cascade Range they are



Fig. 266. A header—combined harvester and thresher

largely in a region of small rainfall (Fig. 72) where dry farming or irrigation is necessary. The soils are fertile, however, and large crops of this cereal are grown. The grain cures while standing, so that combined harvesters and threshing machines are used (Fig. 266). Washington has become, in recent years, one of the great wheat-growing states of our country. In California the large wheat farms of a few years ago have disappeared. They have been divided into smaller farms which are more carefully cultivated and on which products in great variety are now raised.

In the plateau section of central Washington and Oregon there are several valleys in which irrigation has made possible the raising of all temperate-latitude fruits and vegetables. One of the most productive is the Yakima Valley in Washington, known for its wonderful orchards (Fig. 267) and hop yards. Still farther west is the great valley between the Cascade Mountains and the Coast Ranges.

This includes the Willamette Valley of Oregon, a most prosperous agricultural region. In many parts of the great valley the land has high value, the farms are small, and fruits and garden crops are raised. Some agriculture also is carried on in the valleys of the west slope of the Coast Ranges.

The recent agricultural development of California has been in the raising of fruits, vegetables, and



Fig. 267. Packing apples, Washington

nuts. It is now the greatest fruit state in the Union. It is best known for fruits of warm climates, such as oranges and lemons, but three fourths of all its fruit crop is in fruits of temperate latitudes, such as apples, peaches, apricots, and pears. California surpasses all other states in raising grapes, from which grape juice and raisins are made. In recent years California has become even more important than Spain as a raisin-producing region. Many of the vineyards are in the valley of the San Joaquin River, in the southern part of the Sacramento River valley, and in the district north of San Francisco Bay. The region around Fresno is the great raisin district. The orange groves are chiefly in the southern half of California (Fig. 268). Many of the mountain streams, when they reach the plains, are turned into irrigation canals and distributed over the fields. Here in a region once given over to herds of cattle and great wheat farms, there are now flourishing cities and villages, and a large and prosperous population. In addition to the products already named, sugar beets, sweet potatoes, almonds, walnuts, melons, rice, cotton, olives, and figs are raised in abundance.

In the semi-arid regions of eastern Washington and Oregon and in the dry plains and mountain pasture lands of California there are many stock ranches, and cattle and sheep raising are important industries. On many of the farms of the great valleys dairy cattle are kept, and the milk, butter, and cheese pro-

duced find a ready market. Poultry raising is increasing in importance, especially on the farms in the great valleys and in the neighborhood of the larger cities.

253. Forests and Lumbering.—One of the largest and most important of the lumbering regions of the United States is in the three states of the Pacific coast. The great forests there are in part due to the heavy rainfall (Sec. 251). Both Oregon and Washington have an enormous amount of timber still standing, and Washington cuts more lumber than

any other state of the Union. The manufacture of lumber products is carried on at Seattle, Tacoma (Fig. 269), Everett, Bellingham, and other Puget Sound ports, and at Portland. From these places some of the lumber is sent to such distant points as Alaska, Hawaii, Japan, China, Australia, and South America. As the lumbermen do not depend upon snow on which to sled the logs, the work can be carried on at all seasons.

Several kinds of trees, unknown in other parts of our country, grow to heights of 200




Fig. 268. Orange grove in southern California



Fig. 269. Lumber mill at Tacoma

U. S. Dept. of Ag., Forest Service

or 300 feet, and many have diameters of ten, twenty, or even thirty feet. Among the greatest are the "big trees" (Fig. 270), a species of sequoia that grows on the slopes of the Sierra Nevada and Coast Ranges in California. Both the nation and the state have set apart reserves containing the big trees in order to save them from the lumberman and from destruction by fire. Some of these trees are believed to be at least four thousand years old. In the Coast Ranges of northwestern California, there are extensive forests of the very large trees called redwoods (Fig. 271).

In the Cascade Range and the Olympic Mountains of Oregon and Washington are found spruce, pine, hemlock, and cedar trees. The Douglas fir, however, is the most common, and the greatest producer of lumber. This tree is found also in abundance in the mountains of British Columbia, and to a less degree in the Rocky Mountains. Besides the foreign markets, the growing cities and many mines of the Pacific States furnish a large market.

To prevent careless lumbering and destructive fires, the national government

has within a few years set apart vast tracts, as national forests, in the Sierra Nevada, the Cascade Range, and the Coast Ranges of the three states (Sec. 224).

254. Fisheries.—Hundreds of miles from the ocean, along the headwaters of the Columbia River, and of the Fraser River, in British Columbia, one may see the salmon as they head up the stream. They live in salt water, and every year, at the spawning season, the full-grown salmon swim up the rivers into fresh waters. In the mountain streams the young salmon are hatched, and swim down to the ocean to make their growth. After about four years they are mature; then they

move up the rivers to spawn, and vast numbers are caught on the way. When Lewis and Clark and other explorers came to the region, they found the Indians living mainly on these fish. Now for many years the white man has made a business of catching and canning them (Fig. 272), and salmon from the Columbia River or from Puget Sound are seen in every provision store. In air-tight cans, the fish can be kept a long time. Fresh salmon also are shipped long distances in refrigerator cars.



U. S. Dept. of Ag., Forest Service

Fig. 270. Grizzly Giant: 91 feet in girth, and about 400 feet high



Fig. 271. Redwood logs on the way to the mill

U. S. Dept. of Ag., Forest Service

One of the canning centers is Astoria, a small city in Oregon at the mouth of the Columbia River. This city was named for John Jacob Astor, the ancestor of a well-known family, because he made the place a depot for the fur trade of the Northwest, in which he was for a long time engaged. The fur trade has now become comparatively unimportant, and the fishing industry has taken its place. Canning is also done at Bellingham and elsewhere on Puget Sound. This industry is important also along the shores of British Columbia and southern Alaska.

The state governments restrict fishing so that many fish can escape the nets and other fishing apparatus, and make their way up to the spawning grounds. Otherwise a valuable industry would in a few years be destroyed. Artificial hatcheries are established, to stock the rivers with young salmon, which will go down to the salt water to grow.

Tuna, halibut, crabs, and oysters are taken along the Pacific coast.

255. Mining.—Much that is said about mining in regard to the Plateau States (Sec. 236) is true for this region also. The first great incentive to mining in the West was the discovery of gold in California in 1848. Ever since then California has been a great producer of this metal, and it now ranks first among the states. There is not so much placer mining as formerly, but the parent veins in the mountains are worked, and the gold is separated by crushing and other processes. California produces also much of the liquid metal called quicksilver or mercury. All the Pacific States are producers of gold, silver, lead, and copper.

One of the largest smelters is at Tacoma,

Washington, where silver, gold, lead, and copper ores are treated. A part of the ore smelted in this and other Puget Sound smelters comes from Alaska, Asia, and South America. There are smelters also in eastern Washington and in California.




Fig. 272. Salmon canning factory, Astoria

Washington is the chief Pacific state in the production of coal (Fig. 127). California is one of the leading states of the country in petroleum. The largest oil wells are in southern California in the region about Bakersfield.

California has little coal, and petroleum is used as fuel in the railway engines and steamships, and in heating plants in the cities. The desert areas of southeastern California yield salt, soda, and borax.

Review. — 1. Which of the Pacific States raises much wheat? 2. Where are the wheat regions of Washington and Oregon? 3. What farming methods are employed in these regions? 4. Why does California raise less wheat than it once did? 5. What crops are now taking its place? 6. Where is the Yakima Valley? For what is it noted? 7. What are the industries of the great valleys in Washington and Oregon? 8. How does California rank as a fruit-growing state? 9. What fruits are grown in large quantities? 10. Where are the cattle and sheep ranches? Where are the dairying districts?

11. How does Washington rank as a lumbering state? 12. Where is lumber manufactured, and to what foreign countries is it exported? 13. Where are the "big trees" found?

14. Describe the habits of the salmon. 15. Where are they caught, and in what stage of their life history? 16. How are they prepared for market? 17. How is the fishing industry controlled, and how are the rivers stocked?

18. Of what metals is California the principal producer in this country? 19. Where are the chief California oil wells? 20. Where is coal found in the Pacific region?

MANUFACTURING AND COMMERCE

256. Manufacturing and Commercial Advantages.—Manufacturing is developing rapidly in the Pacific States. Already it stands next to agriculture in importance. To a remarkable extent the other industries already studied furnish the raw materials for the leading manufactures, which include: (1) the cutting of timber and its manufacture into boards, shingles, boxes, and furniture; (2) the manufacture of flour; (3) slaughtering and meat packing; (4) the canning of fish, fruit, and vegetables; (5) the refining of petroleum; (6) the manufacture of butter, cheese, and condensed milk; and (7) the smelting of ores. The manufacture of lumber and lumber products is highest in value in all three states. The manufacture of flour is carried on in Portland, Seattle, and Tacoma, from which points it can easily be shipped to Pacific coast, South American, or Asiatic markets. Some flour is made at Spokane,




Fig. 273. San Francisco and vicinity



Fig. 274. Union Square, San Francisco

a trading center in the wheat-growing region of eastern Washington. The falls in the Spokane River at this point are capable of furnishing an enormous amount of power.

The manufactures of the Pacific States have been stimulated by their commercial advantages. Railroads have been built through the great farming and mining regions, and they bring the products of the fields and mines to the cities. The trans-continental railroads carry many trainloads of fresh fruit across the mountains to eastern markets every year. The fine harbors of the greater seaports are easily reached from the ocean, and to them come ships from China, Japan, and many other distant lands. Commerce with our Pacific possessions — Alaska, Hawaii, and the Philippines — is increasing, as it is also with Australia, New Zealand, and the South American and Asiatic countries. The Panama Canal has increased the water traffic with New York and other Atlantic ports, and also with European countries.

257. Cities.—San Francisco stands upon a peninsula between the Pacific Ocean and San Francisco Bay. Its harbor is reached through the Golden Gate. The wharves and business streets of the city are on the east side, toward the bay, while the residence part is on the ocean side. San Francisco Bay and the Golden Gate furnish the natural outlet for the Great Valley of California,



Fig. 275. Stage for the production of moving pictures, in course of erection near Los Angeles

moving picture industry (Fig. 275) and has much trade with Pasadena, Long Beach, Santa Barbara, and other places of resort. Water for city supplies and for irrigation is brought from a distance of 240 miles. The city extends to the coast (Figs. 47, 57), where a great harbor has been constructed to handle the growing commerce. Its construction was an expensive work, but it was necessary because there was no large and safe natural harbor on this part of the coast.

California has few harbors, for the coast line is little broken. In the far south is San Diego, with a splendid harbor, important fisheries, and canning establishments. Its uniform and attractive climate makes it a great health resort.

If you should sail up the Columbia River and turn southward up the Willamette River, at about 100 miles from the ocean you would come to Portland, the chief city of Oregon (Fig. 276), which ranks with San Francisco, Los Angeles, and Seattle as one of the great cities of the Pacific coast. The water is deep enough for ocean ships, and hence Portland is both a seaport and a river port, like New Orleans. It is the outlet of the rich farm and fruit country of the Willamette Valley and is the chief market and manufacturing center of the state of Oregon.




Fig. 276. Portland, with Mt. Hood in the distance

and this has helped to make the city the leading industrial and commercial center of the state. Several transcontinental railroads connect San Francisco with the Plateau States and with the central and eastern parts of the United States. The harbor is one of the best in North America (Fig. 273), and the foreign trade is large, especially with countries bordering the Pacific Ocean.

Oakland is east of San Francisco, across the bay, and is the terminus of the railroads from the East. Alameda and Berkeley are also on the east shore of San Francisco Bay, near Oakland. At Berkeley is the University of California, one of the largest in the country; and at Palo Alto, south of the bay, is Leland Stanford Junior University. San Jose also is in this part of the state.

Sacramento, on the Sacramento River, is the capital of California. It is one of the oldest cities of the state, is at the head of navigation for large boats, and is a market for fruit. Stockton is at the head of navigation on the San Joaquin River, and is also a market for fruit as well as for grain and flour.

Los Angeles is the largest city in the state, though it has fewer people than the metropolitan region of San Francisco, including with that city Oakland and other suburbs. It is the center of a great fruit region and the seat of the University of Southern California. Los Angeles is a center for the

Live stock, poultry, fruit, potatoes, flour, lumber, and wool are among the principal commodities. Ships connect Portland with Alaska, with the countries of Asia, and with other lands bordering the Pacific Ocean.

To the south, farther up the Willamette, is the state capital, Salem; and still farther on are the Oregon State Agricultural College at Corvallis and the University of Oregon at Eugene.

Seattle is the largest city of Washington and is the seat of the University of Washington. It is the terminus of transcontinental railroad lines, a port for the shipping of the Orient (Fig. 258), and the chief port for the trade with Alaska. It has a large ship-building industry. The growth of Seattle

has been very rapid. Lumber, coal, grain, and smelting afford most of the industry and trade of the Puget Sound ports—Seattle, Tacoma, Bellingham, and Everett. Spokane (Sec. 256) is the principal city in the eastern part of the state. Walla Walla is in the southeastern wheat district, and Yakima is the largest city in the central part of the state.

Review by States.—California (Cal.). 1. Describe the Great Valley, its surface, boundaries, and drainage. 2. Compare the rainfall of the northwestern and of the southeastern parts of the state. 3. What kinds of large trees are found in California? What measures have been taken to preserve them? 4. Name and locate the capital. 5. What waters does the Golden Gate join? 6. What conditions favor the growth of San Francisco? 7. Where is Oakland? 8. Give all the facts you can about Los Angeles; about San Diego. 9. What are the mineral products of California? 10. What fruits of temperate latitudes are raised here? What fruits that are characteristic of warm regions? 11. Where is Death Valley? 12. Give the boundaries of California. 13. Draw from memory a map of California, showing the chief mountains and rivers, San Francisco, Oakland, Sacramento, Los Angeles, and San Diego.

Oregon. 14. What river is on the northern boundary of Oregon? 15. What river is on the eastern border? 16. What states are on the southern boundary? 17. What important valley is west of the Cascade Range? 18. What is the capital? Give location. 19. What is the principal city? What products give it commercial importance? 20. Where is Mt. Hood? 21. Describe the rainfall of Oregon.

Washington (Wash.). 22. Where is Cape Flattery? The Strait of Juan de Fuca? 23. What is the capital? Give location. 24. What is the chief city? 25. What conditions have given it rapid growth? 26. What other important ports are on Puget Sound? 27. Where is Spokane? Walla Walla? 28. Give location and altitude of Mt. Rainier. 29. What mineral fuel is found in the state? 30. What grain is raised in eastern Washington? 31. What fruit is raised in the Yakima Valley? 32. What is the most important tree for lumber in this state? 33. How does the density of population (Fig. 80) compare with that of your own state?




Fig. 277. Puget Sound and vicinity



Fig. 278. A government railroad in Alaska

OUTLYING POSSESSIONS OF THE UNITED STATES

	AREA, SQ. MI.	POPULATION, 1920	CAPITAL
Alaska	590,884	55,036	Juneau
Canal Zone	527	22,858	
Porto Rico	3,435	1,299,809	San Juan
Virgin Islands of U. S.	132	26,051	St. Thomas
Hawaiian Islands	6,449	255,912	Honolulu
Philippine Islands	115,026	10,350,640	Manila
Guam	210	13,275	Agaña
Tutuila, etc.	77	8,056	

ALASKA

258. History.—Alaska was at first a Russian possession, but in 1867 William H. Seward, then Secretary of State, arranged a treaty by which this country bought it for \$7,200,000. Although regarded at the time as a waste of money, the purchase has proved

to be a good investment. Products many hundreds of millions of dollars in value have been taken from Alaska, and its exports to the United States have amounted to as much as \$70,000,000 in a single year.

A complete code of laws for Alaska was enacted by Congress in 1899. It is now an organized territory; that is, it elects a legislature of its own, and has a delegate in Congress. In 1909 the importance of the territory was recognized by an exhibition of its resources held at Seattle, and called the Alaska-Yukon-Pacific Exposition.

259. Physical Features.—Alaska has nearly 600,000 square miles and is more than twelve times as large as the state of New York. Its southern end is in about the same lati-






Fig. 280. A miner's cabin on the Yukon River in Alaska

tude as northern Germany, and its most northern cape, Point Barrow, is at about latitude 71° , or 300 miles north of the Arctic Circle. At Bering Strait, Cape Prince of Wales is within 40 miles of Siberia. In the southwest the narrow Alaska Peninsula and the Aleutian Islands extend westward more than a thousand miles in a long, bow-shaped curve. The islands are of volcanic origin, and contain a number of active volcanoes. Some small islands have risen above the sea within recent years.

Southern Alaska, bordering the Pacific Ocean, is a region of high and rugged mountains. Middle Alaska, along the Yukon and its branches, is a rolling plain. Northern Alaska, along the Arctic Ocean, is a low and treeless plain.

Many long and deep inlets, or *fjords*, extend from the Pacific Ocean into the mountains of southern Alaska. Of these bays, the largest are Prince William Sound and Cook Inlet. Great glaciers move slowly down the valleys into the sea at the heads and along the sides of the fjords (Fig. 34). Many other glaciers are found farther back in the mountain valleys. There are more than a hundred large glaciers and several thousand of small size in the territory. The mountains

are steep and high, and the scenery is, in its grandeur, like that of Norway and Switzerland combined, for it has the fjords of the one and the high mountains of the other. Mt. St. Elias is the loftiest of the mountains near the ocean, and Mt. McKinley, in the interior, is the loftiest peak on the continent, with an altitude of almost four miles.

Central Alaska is crossed by the Yukon River from east to west. This river flows for 1200 miles in Alaska, after leaving the Canadian border (Figs. 14, 280). Dawson, in Canada, is not far from the boundary. The delta of the Yukon is a flat area of 9000 square miles.

Much of northern Alaska is a region in which the ground is always frozen to great depths. The surface part thaws out during the brief summer, and produces a growth of plants. Such regions are called *tundras* and are common on the northern plains of North America, Europe, and Asia. At Nome, on the Seward Peninsula, north of the Yukon delta, the miners found frozen earth 120 feet below the surface.

260. Climate.—Alaska has great variety of climate. Southern Alaska is not very cold, but it has much cloudy weather, and much rain and snow. The warm winds from

the Pacific Ocean are cooled by the mountains and part with their moisture, as on the Pacific coast farther south. In some places 100 feet of snow or even more may fall in a year. This fact accounts for the large number of glaciers. The thermometer has been known to show 87° at Sitka in August, and the lowest temperature recorded there in the winter is 3° below zero. Our northern states all show lower temperatures than this.

At Point Barrow the sun is not visible for about forty days during the winter, and the temperature averages below zero from November to April. On this Arctic shore the rainfall is less than 7 inches. The climate of the interior of Alaska is continental; that is, quite warm in summer, and very cold in winter (Sec. 27).

261. Mining.—The chief mineral products of Alaska are copper and gold, and the output of each of these amounts to several million dollars in value each year. The most productive copper mines are located in southern and southeastern Alaska. Gold to the value of \$350,000,000 has already been taken from Alaskan mines. Much of it was obtained by placer mining along the streams and in the sands and gravels of the Nome coast lands. Gold is still produced at Nome in spite of the short summers, the great distance of this settlement from manufacturing centers, and its poor landing facilities. Fairbanks, on the Tanana River, and Juneau, the capital, in the southeast, are other important mining centers. The mining near Juneau is in the bed rock, and a great stamp mill is in operation there. Some of the miners spend the long winter in Alaska, but many others leave the territory as winter approaches.



Fig. 281. Seals on the Pribilof Islands

There are extensive deposits of coal in Alaska, but little of it is mined. Silver, tin, lead, and petroleum are also found.

262. Fisheries and Forests.—The waters of Alaska abound in salmon (Sec. 254), of which there are various kinds. Some of these fish run 1800 miles up the Yu-

kon. There are many canneries, and the export amounts to several million dollars in value each year. There are almost as many plants for salting these fish as for canning. A number of hatcheries have been established to keep the waters well stocked. Cod, halibut, herring, and trout also are caught in these waters.

Alaskan waters are the great field for taking the fur seal (Fig. 281). Stringent laws are now in force to regulate the number of seals to be taken each year, and to prevent slaughtering the mother seals. In spite of restrictions, however, the seals are fewer than formerly, and the skins now have a high value. The Pribilof Islands in Bering Sea are the breeding ground of the seals. Walrus and whales also are taken in the seas about Alaska.

There are extensive forests in many valleys of southern Alaska and along the Yukon and its branches. The trees are, as a rule, not large, and much of the forest will be more useful for wood pulp than for timber. Much lumber is brought in from Puget Sound ports.

263. Agriculture.—The country is too far north for extensive agriculture, for the summers are usually too short to ripen grain. Grass is raised and grain is cut green for forage. Potatoes and some other vegetables are successfully grown (Fig. 282). The government has an agricultural experiment station at Sitka. Stock might be kept in considerable numbers. Years ago reindeer

were imported from Siberia, and on account of the similarity of the climates these useful animals have thrived and increased until there are now many large herds in the territory (Fig. 283). The missions of the various churches care for many of these animals, which are used for the benefit of the native people—



Fig. 282. A field of potatoes, Tanana Valley

Indians and Eskimos. While most of the few thousand natives are ignorant, their children are gathered in schools and have begun to learn the ways of civilized life.

264. Transportation.—A good wagon road runs from the seaport Valdez to Fairbanks on a branch of the Yukon River. The United States government has built and operates the principal railroad of Alaska, extending from Seward, on the south coast, 467 miles to Fairbanks. Passengers and freight are thus readily transported to the heart of the territory, and various mining regions are opened to traffic. Another railroad leads from the seaport Skagway to White Horse on the upper Yukon; from

there one may travel by steamboat down the Yukon to the sea. Coast steamers run all along the south shore of Alaska, and northward to Seward Peninsula and Nome. Along winter trails, small flags are placed every few hundred feet to guide and save the traveler amid the dreadful storms. Travel is dangerous because the streams are without bridges.

There are several thousand miles of telegraph and telephone lines. A submarine cable connects Alaska with Seattle, and a powerful wireless station is maintained.


Review.—1. Give an account of the purchase of Alaska. 2. What is the area of the territory? 3. Using the map, describe the position of the Aleutian Islands. 4. What large cities in Europe have latitudes similar to those of Juneau or Sitka (Fig. 279 and map of Europe)? 5. What is the most northern point of Alaska? 6. How long is the sun not visible at this place each winter?

7. Describe the shore line of southern Alaska. 8. What is a tundra? 9. What part of Alaska has much tundra? 10. In what part of Alaska are rains and snows heavy? Why? 11. Give an account of the Yukon River, and its delta. 12. Why does Vermont or Minnesota often have much lower winter temperatures than Sitka?

13. What is the chief mineral product of Alaska? 14. Give location and other facts about Nome. 15. Give the facts about the fur seals.



Fig. 283. A herd of Alaskan reindeer



THE PANAMA CANAL ZONE

265. The Panama Canal.—In 1513 Balboa, a Spanish explorer, left his ships, climbed the hills and went through the forests of the Isthmus of Panama, until he came to the Pacific Ocean. He was the first European to

stand on the Pacific shore in the Western Hemisphere. Very soon there was talk among the Spanish of a canal, but it was not to be dug until almost four centuries later.

In 1881 the canal was begun, with French capital, under a French engineer, at a point where the isthmus is about 40 miles wide. This enterprise failed after much work was done. In 1903 the United States acquired, by treaty with the Republic of Panama, the *Canal Zone*, a strip of land 10 miles wide from ocean to ocean. The canal runs through the middle of this strip; it was completed in about ten years. The Panama Railroad, also owned by the United States, passes through the Zone from Colon to Panama (Fig. 285). For the canal and Canal Zone a governor is appointed by the President of the United States.

The Gatun Dam, a vast structure, has turned the valley of the Chagres River into a large lake. By locks, the largest ocean ships are raised to the level of this lake (Fig. 286). They sail on the lake partly across the isthmus, and descend by other locks in the Pacific end of the canal. The Atlantic end of the canal is farther west than the






Fig. 286. Locks on the Panama Canal. Ships passing the locks are moved through and held in place by electric locomotives




Fig. 287. San Juan harbor, Porto Rico

on the northeast side than on the southwest. There are parts of this island where irrigation is needed at some period of the growing season.

267. People and Industries.—

The area of Porto Rico is about three fourths that of Connecticut. The population is nearly equal to that of Connecticut, about three fifths being white and two fifths

Pacific end, so that a ship sails southeast in passing from the Atlantic Ocean to the Pacific. The canal is fortified by the United States and is open to the ships of all nations.

Before the Suez Canal and the Panama Canal were dug a ship could not go from New York or London to the Pacific Ocean without going around either Cape Horn or the Cape of Good Hope. Now, by way of these canals, a ship can go around the world in the Northern Hemisphere. The Panama Canal makes it much easier for vessels from Atlantic and Gulf ports to reach our Pacific ports, as well as those of Asia and western South America. It saves 8000 miles in the voyage from New York to San Francisco.

Review.—1. What are the length, width, and position of the Canal Zone? 2. How was it acquired by the United States? 3. What European first crossed the isthmus? At what date? 4. What are the chief features of the canal? 5. Make from memory an outline map of the isthmus and the canal.

PORTO RICO

266. Climate.—Porto Rico is the most eastern of the four large islands of the West Indies. It lies at about 18° north latitude, and has an even, tropical climate. It is not excessively hot, because it is surrounded by ocean waters, and is in the course of the northeast trade winds (Sec. 29). As the island has mountains of moderate height the trade winds are forced to higher altitudes in crossing them, and as a consequence more rain falls

negro. The island was long under the rule of Spain, but was ceded to the United States in 1898, following the war of that year. The governor and some other officers are appointed by the President of the United States, but the people elect the legislature, so that Porto Rico is largely self-governing.

A modern educational system is being developed, and roadways, including railroads, are being constructed, with telegraph and telephone lines. Sugar is the chief product, and the amount has vastly increased under American rule. Coffee, tobacco, and a variety of tropical fruits also are raised. Vegetables are now sent in large quantities to the winter markets of New York and other northern cities and may be purchased in these cities within a week after being gathered from the truck farms of Porto Rico. San Juan, the capital (Fig. 287), and Ponce are the largest cities.

268. St. Thomas, etc.—East of Porto Rico are the Virgin Islands. Three of them were bought from Denmark by the United States for \$25,000,000 in 1916. They are St. Thomas, St. John, and St. Croix. They are chiefly valuable to our country because of the excellent harbor in St. Thomas. Most of the people are negroes.

Review.—1. Give latitude and area of Porto Rico. 2. Which side of the island receives the greater rainfall? Why? 3. What changes have taken place since 1898? 4. What are the leading products? 5. Give the name and location of the capital. 6. What are the products of Porto Rico?

7. Locate St. Thomas. For what is it noted?

THE HAWAIIAN ISLANDS

269. Size and Location.—The Hawaiian group consists of a chain of nine islands extending southeast and northwest in the north Pacific Ocean. They are between 18° and 23° north latitude, or just south of the Tropic of Cancer, and are about 2000 miles from San Francisco, and about 5000 miles from Hongkong. The total area of the islands is considerably less than the area of Massachusetts, and the population is more than 250,000. Hawaii is the southeastern member of the group and contains more than half of the land surface; it is over 70 miles across in any direction.


270. Volcanoes.—All the islands are volcanic and have been built up from the deep sea bottom by volcanic eruption. The highest peaks are on Hawaii and reach nearly 14,000 feet above the sea. At the top of Mauna Loa, and at another point on the east side of the mountain, are the largest craters of active volcanoes in the world. They are basins several hundred feet deep and two or three miles wide. When the volcanoes are quiet, the floors of these craters are cooled in places, and hard enough to walk on, but they contain lakelets of spluttering lava. At intervals of some years, the lava rises in the higher crater until it runs out of some break in the side of the mountain and flows

slowly down the slope (Fig. 288). The stream of melted rock may flow fifty miles and fall into the sea.

271. Climate.—The islands are in the belt of the northeast trade winds, which blow over the Pacific the same as over the Atlantic Ocean. Hence the northeastern slopes of the islands receive more rain than the southwestern parts. The climate is mild and even, because the islands are in the tropical region and are surrounded by warm ocean waters. The winters are wet and the summers dry, but the temperature varies only about 10° throughout the year. The vegetation is luxuriant (Fig. 289).


272. Government and People.—The islands were under native rulers until 1893, when a republic was established. Five years later they were annexed by the United States. They now form the organized territory of Hawaii, with a legislature, and a delegate in Congress at Washington. The original population was Malayan, like that of many other islands in the Pacific Ocean. The people are now of many nationalities,—natives, Japanese, Chinese, Portuguese, Filipino, American, and others. Chinese immigrants are now excluded. The English language is commonly spoken and is used in the schools.

273. Industries.—Pineapples and other tropical fruits, tobacco, and rice are raised for home use and export, but by far the greatest



U. S. Dept. of Ag., Forest Service

Fig. 288. Lava flow from a Hawaiian volcano



U. S. Dept. of Ag., Forest Service

Fig. 289. Hawaiian jungle




Fig. 291. The harbor of Honolulu

product is cane sugar. Much American capital is invested in this industry, and much of the raw sugar goes to San Francisco to be refined. The islands are one of the chief sources of sugar for use in the United States. The annual export of sugar to this country is more than 1,000,000,000 pounds. Most of the commerce is with the United States.

Hilo is the chief city of the island of Hawaii. Honolulu is a larger city on the island of Oahu, and is the capital of the territory (Fig. 291). Many lines of steamships touch at Honolulu, especially those plying between the ports of our Pacific coast and those of Asia. There is a United States naval station for the coaling and repair of ships. As a calling point and coaling place the city is important. The voyage across the Pacific Ocean takes about three weeks for the fast steamers, and it would be difficult for a ship to carry all the coal needed for so long a voyage.

Review.—1. Give the number, latitude, and area of the Hawaiian Islands. 2. Which is the largest of the group, and what is the distance across it? 3. Which island has active volcanoes? 4. Describe the craters and the manner of eruption. 5. In what respect

does the rainfall resemble that of Porto Rico? 6. Give the important facts in the history of the islands. 7. What is the chief product? 8. What special value have these islands to the United States?

THE PHILIPPINE ISLANDS, GUAM, AND SAMOA

274. Physical Features.—The Philippine Islands are southeast of China, and lie between 4° and 22° north latitude. They are separated from the mainland of Asia by the South China Sea. There are

many hundreds of the islands, with a total area of about 115,000 square miles. Luzon in the north is the largest, with 41,000 square miles of surface, and Mindanao in the south has 36,000 square miles. Much of the land is hilly or mountainous, and there are many volcanic peaks. Earthquakes are not uncommon. The higher peaks are from 8000 to 10,000 feet in altitude.

275. Climate.—The climate is warm, and the rainfall is heavy. The lowest temperature ever experienced in Manila is about 60° . The cool season, or winter, is dry, and the summers are wet. The soil and rock waste are deep, and the ground is shaded with a dense growth of plants.

Because of the dampness, houses are raised above the ground (Fig. 292), and the roads and trails are often impossible. The most needed improvement in the islands is the construction of good roads.

276. History.—These islands were discovered by Magellan in 1521, in the first exploring expedition that went around the world. Magellan himself was killed here, but the islands soon came under Spanish rule.

The battle of Manila Bay



Fig. 292. Filipino native house

in 1898 ended in the destruction of the Spanish fleet and led to the transfer of the islands in that year to American control. The islands contain about 10,000,000 people. Of these, a small number are Americans and Europeans, 50,000 are Chinese, and a smaller number are blacks, known as Negritos; but most of the people are Malaysians. Chinese immigration is now forbidden, as it is in Hawaii and in the main part of the United States.

Before 1898 little was known of a large part of the islands. Much exploration and surveying have now been done by the American army and by men of science, and the United States Coast Survey has done a great work in making soundings and charts of the dangerous seas in and about the islands.

277. Government and Education.—The governor general and a few other officers are appointed by the President of the United States. A Philippine legislature of two houses is elected by the people; but its



Fig. 293. Baling hemp

acts may be vetoed by the governor general, or annulled by Congress. An excellent system of education has been organized under a director of education and division superintendents, and the schools are taught by several hundred American teachers and several thousand Filipinos. A few districts, because their people are only partly civilized, are still under military rather than civil government.

278. Agriculture.—The resources of the islands are very

large, but are not yet well known and are little developed. The soils are very deep and rich; in many places they are derived from volcanic rocks and fertilized by ages of plant growth in a moist, warm region.

Manila hemp (Fig. 293) and Manila rope are well known in the United States, and form much the largest export of the islands. The value of this export in one recent year was more than \$22,000,000. Coconuts are raised, and copra, the dried meat of these nuts, used for making soap, is a profitable

export. Other products are rice, corn, sugar, tobacco, bananas, coffee, and various spices. The methods of farming are rude, the tools are primitive, and the water buffalo is used for tilling the soil and as a beast of burden. This animal is slow and unruly, and requires a frequent plunge in mud and water. This habit of the creature fits it, however, for use in the rice fields, which must often be flooded (Fig. 294).



Fig. 294. Filipinos cultivating a rice field with water buffaloes

279. Forests.—As in most warm and wet countries, the forests of these islands are luxuriant. Many kinds of trees are found, including more than fifty species of hardwoods. Some of these are heavy and take a fine polish, and are therefore suitable for cabinet work. Some are so hard that an ordinary saw will not cut them. The top of a large dining table is sometimes made from a single slab of native wood. There are fourteen forest districts and

fifty-five stations, all in charge of expert foresters. In this new care of the forests, as well as in the agricultural experiment stations, in the educational system, and in the charting of the coasts, the good work of the American government is seen.

The bamboo and rattan are put to a variety of uses by the natives, especially in making tools, domestic utensils, and the houses of the poor. While the cultivated Filipinos have homes of comfort and elegance, the poorer people and the savage tribes often live in huts of poles, roofed with a thatch of boughs or of grass.

Soft coal is found, and nearly all the important metals are known to exist in the Philippines, but as yet little mining has been done.

280. Commerce and Cities.—Much of the surface is covered with a jungle, and the muddy trails will only permit a man to pass on foot. The soils, forests, and minerals cannot be much used until good roads are made. Several railroads have been built during the recent years of American occupation, and there are now in the islands about 5,000 miles of telegraph lines. There is ocean cable service both to Asia and to the United States.

The chief city is Manila, the capital, which has a population of about 250,000 (Fig. 295).



Fig. 295. Street in Manila, Philippine Islands

The second city in population and importance is Iloilo, on the island of Panay.

281. Guam.—A few hundred miles east of the Philippines is the small island of Guam, which the United States took from Spain in the war of 1898. It is useful as a coaling station for vessels visiting the United States, Hawaii, and the Philippine Islands.

282. Samoan Islands.—The island of Tutuila and a few smaller islands of the Samoan group belong to the United States; the others are controlled by New Zealand. Tutuila is a mountainous island, with the excellent harbor of Pago Pago, where a United States naval station is maintained.

The American flag has also been raised over a few other very small islands in the Pacific Ocean (Fig. 290).

Review.—1. What is the range of latitude in the Philippine Islands? 2. Which is the largest island of the group? 3. What is the condition of the roads in the islands? Give reasons.

4. What white man discovered the Philippines? Give the date. 5. What event took place in 1898? 6. How large is the population? What kinds of people compose it? 7. How are the islands governed? 8. What is the system of education?

9. What is the most important product for export? 10. What are important facts about the forests and woods?



**DOMINION OF CANADA
NEWFOUNDLAND AND GREENLAND**

Capitals of Countries thus: Capitals of Provinces thus:
COPYRIGHT, BY AMERICAN BOOK COMPANY






Fig. 297. First session of the Canadian Parliament held in the new Parliament Building, Ottawa, February 26, 1920

NORTHERN COUNTRIES OF NORTH AMERICA

	AREA, Sq. Mi.	POPULATION, 1910	CAPITAL
Canada	3,759,365	8,788,000	Ottawa
Newfoundland, etc.	49,680	268,000	St. Johns
Greenland	838,000	14,000	

Map Study.—1. What provinces of Canada border the United States? 2. What two provinces are east of New Brunswick? 3. What lakes form a large part of the southern boundary of Ontario? 4. What water touches northern Ontario? 5. Bound the territory of Yukon.

6. What is the principal river system of northern Canada? 7. What lakes belong to it? 8. Trace a water passage from Edmonton, in Alberta, to the Atlantic Ocean; from Winnipeg, in Manitoba. 9. What river flows south in British Columbia? What rivers form part of the boundaries of Ontario?

10. What provinces lie on the shores of the Gulf of St. Lawrence? 11. What is the capital of each of these? 12. Locate Montreal; Ottawa; Toronto. 13. Name two cities on the western side of Lake Superior. 14. Locate Winnipeg; Vancouver; Victoria.

THE DOMINION OF CANADA

283. Surface and Provinces.—The most southern point in Canada is in about 42° north latitude, on the shores of Lake Erie, not far from Detroit. The northern parts are on the Arctic Ocean, but a few hundred miles from the Pole. Like the United States, Canada has low mountains in the east, high mountains in the west, and broad plains lying between the two highlands.


Southern Canada may be divided into four regions. On the east are Nova Scotia, New Brunswick, and Prince Edward Island, which are often called the Maritime Provinces. This is a good name because Nova Scotia is a peninsula, Prince Edward Island lies in the Gulf of St. Lawrence, and New Brunswick has long shore lines on the Bay of Fundy and the Gulf of St. Lawrence. An old name for this region is Acadia. Here are the only ports of eastern Canada that are free from ice throughout the year. The most important

are Halifax, St. John, Sydney, and Charlottetown. The surface is low and nearly flat in Prince Edward Island, but higher and quite hilly in the other two provinces. The relief in general is much like that of New England, except that the latter region has real mountain ranges and peaks.

The second region consists of the provinces of Quebec and Ontario. These lie along the St. Lawrence River and the Great Lakes, and extend northward into a wilderness of rocks, mountains, and forest. Northern Ontario and Quebec border Hudson Bay, and Quebec has a long shore line on the Gulf of St. Lawrence. The lowlands along the St. Lawrence and the Great Lakes have rich farms and the largest cities and densest population of the country. Some of this region is hilly, but in southern Ontario there are lake plains like those of western New York.

The third region embraces the provinces of Manitoba, Saskatchewan, and Alberta. It consists of prairie and dry plains, and, at the south, is like the plains of North Dakota, Nebraska, and Montana. This region has in it Lake Winnipeg, and much of it drains by the Red River, the Saskatchewan, and other streams, through the Nelson River into Hudson Bay. It is the most important part of Canada for the raising of grain. A part of the province of Manitoba lies west of Hudson Bay and is similar to northern Quebec and Ontario.

The fourth region is the province of British Columbia. Through it, the Cordilleras extend from the United States on the south. They also reach over into western Alberta. On the east are the "Canadian Rockies" (Figs. 32, 38, 300), on the west is the northern continuation of the Cascade Range of Washington, and between them is the Selkirk Range. The glaciers in these mountains of Canada are larger and more numerous than in the



Geological Survey of Canada

Fig. 300. Snow and ice fields in the Canadian Rockies

western United States, but not so numerous or so large as those of Alaska. The southern parts of British Columbia are drained by the Columbia and Fraser rivers, and the northern parts by branches of the Mackenzie, which flows into the Arctic Ocean, and by smaller streams flowing to the Pacific Ocean.

The northern plains of Canada extend to the Arctic Ocean and include the provisional districts of Mackenzie and Keewatin. In the southern part of this region are forests, and in the north are treeless tundras (Sec. 259). In this region are Great Slave Lake and Great Bear Lake, tributary to the Mackenzie River, and many other large lakes whose outlets lead to Hudson Bay or the Arctic Ocean. The Yukon territory is mountainous and continues the highlands of British Columbia northward.

North of the main body of the continent are many large and many small islands. Much of the region is bound in perpetual ice and snow, is visited only by explorers or prospectors, and is inhabited only by a few tribes of Eskimos. A part of northern Canada is often called the Barren Lands. Some of these lands are free from snow in summer and are brilliant with flowers; they are visited by myriads of wild fowl.



Fig. 301. Vancouver harbor, and part of the British Columbia coast

284. Shore Line.—Nearly all the shore lines of Canada are rugged and broken, with deep inlets or fiords, bold headlands, and many mountainous islands. For this reason there are good harbors in British Columbia and in the Maritime Provinces. The St. Lawrence River is at tide level as far as Montreal. Along the western shore, vessels go from Seattle or Vancouver northward to Alaska in quiet waters behind the fringe of islands that border the coast. Many bays reach far into the land between high mountain spurs, or promontories (Fig. 301). Hudson Bay is an inland sea, 900 miles long, lying in the interior of Canada. It was named for Henry Hudson, whose sailors here set him adrift to perish about three years after he had sailed up the Hudson River. Both the eastern and the western coasts of Canada are important for their commerce; those of Hudson Bay may become important; but the Arctic shores must always be barren and uninhabited by white men, except possibly by a few miners.

285. Climate.—The climate of the Maritime Provinces, and of the region along the St. Lawrence and the Great Lakes, resembles that of New England, New York, and Michi-

gan. The storms of the westerly winds pass over this part of Canada, and moisture from the Atlantic that comes with the east and south-east winds gives abundant rains in summer and heavy snows in winter. Southern Ontario, in the latitude of southern Michigan, is almost surrounded by lakes, and has a mild climate. Here grapes and peaches flourish, as in western New York and southern Michigan.

The Labrador coast is washed by waters drifting south from the Arctic seas, and is rainy and cold.

The summers of Manitoba, Saskatchewan, and Alberta are much like those of our own western plains, but as these provinces are farther north, the winters are longer and colder. Still, Saskatchewan and Alberta are warmer than the lands eastward about Hudson Bay. One reason is that westerly winds, called *chinooks*, in those provinces as well as southward in the United States, blow across the mountains, and the air warms as it descends upon the plains. The climate of western British Columbia is moist and mild like that of western Washington (Sec. 58).

286. Indians.—Canada, with its abundant forests, rivers, and lakes, was a natural home for many Indian tribes. They could hunt in the forest, fish in the waters, and gather abundance of wild fruits. Their canoes enabled them to make long journeys by water. These were made of strips of birch bark sewn together with split roots of spruce, lined with thin strips of cedar, and made strong by cedar ribs. The gum of some evergreen tree was used to make the seams watertight, and the canoe was so light that it could move in

shallow water and easily be carried across the portages. There are so many lakes and streams that the Indians could go almost everywhere without long portages.

287. Explorations.—The first explorations up the St. Lawrence and along the Great Lakes were made by Frenchmen, and the land was long under the French flag (Sec. 35). The missionaries and the fur hunters went through all parts of the great wilderness, and they found nothing so useful to them for travel and for carrying their packs of skins to market, as the Indian's birch-bark canoe. The search for fur-bearing animals really was more important than any other fact in the early history of Canada. After the English took possession of Canada, the hunting went on, and the Hudson's Bay Company, which had been formed long before, spread its operations over most of the country, holding many fortified posts, called factories, to which the pelts were brought in from the woods (Fig. 302). The Hudson's Bay Company is still in business as a private corporation, and has large stores and fur depots in Winnipeg, Montreal, Edmonton, and other centers.

Large parts of the vast Canadian wilderness are little known even yet, but for many years the members of the Geological Survey of Canada and other explorers have sought knowledge of the rocks, minerals, forests, rivers, and soils, making long and toilsome

journeys with canoes no larger than those used by the red men centuries ago. In this way maps are prepared, information about the country is provided, and immigrants and settlers learn where there is good land for farms, where rich masses of minerals have been found, and where to build their roads.

288. Government and People.—After 1763 the several colonies of Canada were under the rule of Great Britain. It was not until 1867, however, that they were united under the name of the Dominion of Canada. The central government is located at Ottawa, in the province of Ontario. The governor-general is named by the British government, and the parliament consists of a senate, the senators being appointed for life, and a house of commons whose members are elected by the people.

The total population of Canada is about 9,000,000. A large number of the people still commonly use the French language. Many of the French-speaking people live in the province of Quebec, where the customs of the early settlers have remained the same until the present time. Most of the English-speaking people are of English or Scotch descent, and several hundred thousand of them were born in the United Kingdom. Many immigrants come from the United States, and smaller numbers from continental Europe and from China and Japan.

289. Forests.—The forests cover more than 800,000 square miles, or nearly one fourth of the country. The eastern provinces bear many hardwoods, and pines, as well as spruces, aspens, and larches. More than a third of the area of Nova Scotia is covered with forest. The great lumbering region of the Maritime Provinces is New Brunswick, which has large mills at Fredericton and St. John.

The eastern forests run through Quebec and Ontario. The Ottawa Valley is important for its white pine, which, with other timber, is floated down the river to Ottawa, where



Fig. 302. A Hudson's Bay Company trading post

large mills work it up into lumber. Much lumber is also manufactured and marketed at Montreal and Toronto.

The forests of central Canada extend between Lake Superior and Hudson Bay to the northwest, across the upper parts of the Mackenzie basin, and merge with the forests of British Columbia. The valleys and lower slopes of this province are covered with wonderful forests of cedar, spruce, and Douglas fir, similar to the trees of Washington and Oregon. Here is the third great center for lumbering in Canada (Fig. 303), and much of the product goes to Vancouver and is shipped to foreign lands.

Many of the soft woods, like spruce, especially the smaller and imperfect trees, are used for making wood pulp. The forests of northern Quebec have not many large trees, but the timber is suitable for pulp, railroad ties, telegraph poles, fences, mining timber, and firewood. Tree growth in the cold north is very slow, and a small tree may have required hundreds of years for its development.

Forest fires are very destructive, and they are started not only through carelessness of hunters and by sparks from locomotives, but also by lightning. In a dry time the mossy floor of the forest, the thick undergrowth, the dry, fallen timber, and the pitchy character of many of the trees, cause a fire to spread with fearful rapidity, outrunning and destroying the swiftest animals of the forest. Half of the timber wealth of Ontario is said to have been destroyed by fires. While the forests are one of the main resources of Canada, there is danger of their exhaustion, and measures are being taken for their care and preservation.

Two regions have few trees or none. These are the plains west of Winnipeg and the Barren Lands of the north. On the western plains many farmers are planting trees, for windbreaks, for fuel, and for other uses.

290. Fisheries and Furs.—Canada has a broken shore line, and in its numerous bays there are found great numbers of fish. On the east, off the shores of Nova Scotia, is the

shallow water of the Banks of Newfoundland. Here and in the Gulf of St. Lawrence a great many fish are caught. In all the Maritime Provinces fishing is an important industry. The cod, herring, and halibut are especially valuable. Many lobsters also are taken. Nova Scotia has the largest fishing industry in the eastern part of Canada, carried on from Halifax, Yarmouth, and other ports (Fig. 304).



Fig. 303. Logging in British Columbia

The country has thousands of lakes and rivers in which trout, whitefish, pickerel, pike, and other fresh-water fish flourish. Tourist fishermen from the United States frequent these waters in summer. Fishing is a large business on the lakes of Manitoba, and many men are thus employed. The fisheries of British Columbia are like those of Washington (Sec. 254) and Alaska (Sec. 262). The annual product amounts to several million dollars. The most valuable fish is the salmon; but halibut and herring also are numerous, and shellfish are gathered near the shores.

On both the Atlantic and the Pacific sides of Canada, seals, walruses, and whales are still captured in considerable numbers, but this branch of the fishing industry is smaller than it formerly was.

St. Pierre and Miquelon, near Newfoundland, are still owned by France (Sec. 38), and are used as headquarters for fishing in the adjacent waters.

Codfish from the Labrador coast are marketed in Spain, in Greece, and especially in Italy. Codfish has been called the "bread of the sea," because it is abundant, nutritious, and is easily preserved by salting, smoking, or drying. Parts of these fish are used for making glue, oil, and fertilizer, and in Arctic lands they are used even for fuel. The ordinary codfish weighs only a few pounds, but large specimens weigh more than 100 pounds each.

The Dominion is the leading fur producer among all the countries of the world. Hunting in the wild lands is now supplemented to an important degree by fur farming; foxes, raccoons, minks, muskrats, and other animals are bred for this purpose.

291. Mining.—One of the most important minerals of Canada is coal. There are three principal regions for coal mining in the Domin-



Fig. 304. Drying codfish at Digby, Nova Scotia

© Paul Yates

ion. The first is Nova Scotia, where mining has been carried on for many years; Cape Breton Island abounds in coal and has large iron furnaces at Sydney. Nova Scotia furnishes most of the coal used for domestic purposes and for manufacturing in eastern Canada. The second locality is in the plains east of the Canadian Rocky Mountains. In this region the greater part of the coal is soft, and has not yet been extensively mined. The large region between Winnipeg and the St. Lawrence River has no coal, and either imports it from the United States, or brings it from Nova Scotia. The third region is British Columbia, which, like Washington on the south, has much coal. It is found both on the mainland and on Vancouver Island.

Petroleum has been found in the provinces of Alberta and British Columbia, and in the Mackenzie district. Large deposits of oil-bearing shales exist in New Brunswick and Nova Scotia.

Some iron is found in various parts of Canada, but in many cases the mines are far from coal, and the iron-smelting industry of the Dominion is not yet large.

In the province of Ontario, north of Lake Huron, are several mining centers. One of them is Sudbury, where much nickel is found; another is Cobalt, in the midst of great silver mines; and another is Porcupine, where much gold is produced. Ontario is now by far

the largest producer of gold in Canada.

The Klondike region in Yukon territory, on the borders of Alaska (Fig. 305), also yields much gold; it produced about \$180,000,000 worth in one period of eighteen years. The mining center is Dawson.

Another important mineral region of Canada is in the province of British Columbia. Mountain ranges occupy much of this region, and as in the Plateau States, they abound in deposits of gold, silver, lead, and copper. Gold is found both in the gravels and in the bed rocks, and the province ranks high as a gold producer.

Much of the Canadian wilderness has been but little explored. Hence it is almost certain that many valuable mineral deposits are still unknown, and will in coming years be found in the mountains of British Columbia and in the wild and rocky parts of Ontario and Quebec. Much mineral wealth may also be discovered in the Barren Lands.

292. Agriculture and Manufacturing.—In the Maritime Provinces, mixed farming is carried on. Grain, fruits, and vegetables are raised and live stock is kept. Fine apples are produced in Nova Scotia. The most valuable live stock in Canada are the silver foxes that are bred in captivity in fox "ranches" on Prince Edward Island.

Southern Ontario is the chief farming region of eastern Canada, having along the Great Lakes excellent soils and a mild climate. Here wheat, apples, grapes, peaches, and various small fruits are raised. Canada ships much butter and cheese

to Great Britain, and a large part of the dairy products comes from Ontario.

In recent years Manitoba, Saskatchewan, and Alberta have become wheat-raising regions. The surface, soil, and methods of raising and harvesting (Fig. 12) are like those in the great wheat region of North Central United

States. Winnipeg, the chief wheat market for the district, has a grain exchange similar to that at Chicago. Many cities and villages, on all the railroad lines, have elevators to which the farmers draw their wheat for transfer to the railroads. Oats are raised (Fig. 306), but the summers are short and cool, and corn does not do so well as in the North Central States. Wheat has been raised, though not in large quantities, in the valley of the Peace River, belonging to the Mackenzie River system. Cattle and horses are raised on the dry plains, especially in Alberta (Fig. 307).

British Columbia has rich agricultural regions, though only partly developed. They are suitable for grain and general farming, and the mild climate of the coasts and valleys especially fits these areas for fruit culture.




Fig. 305. Hydraulic mining, Klondike



Fig. 306. Harvesting oats in western Canada



Fig. 307. Round-up of horses on an Alberta ranch

The manufactures of Canada include agricultural machinery and other iron and steel goods. The weaving of textiles and the preparation of food products and of lumber and wood pulp are also important.

293. Transportation by Water.—The principal eastern seaports are Halifax, St. John, Quebec, and Montreal. Ships of several lines sail from Montreal to European ports, except during the winter months, when the St. Lawrence River is blocked with ice. From Montreal ships of considerable size can go to the head of the Great Lakes at Duluth or Chicago. By canals they pass the rapids of the St. Lawrence River and enter Lake Ontario. By the Welland Canal they go up to Lake Erie. Near the head of Lake Huron, the Soo Canal conveys them to Lake Superior.

The Red River and the Saskatchewan are navigable for boats of small draft for hundreds of miles, to Lake Winnipeg. From the lake to Hudson Bay the Nelson River is broken by difficult rapids. The Mackenzie River and its branches afford extensive navigation in northern Canada. The Hudson Bay is not much used by ships,

but many Canadians believe that it will become an important outlet to Europe for the grain of the western plains. The Canadian government has begun to build a railroad from Winnipeg to Hudson Bay.

Both transportation and manufactures will be favored by the water power which can be made available in Canada, amounting to more than 18,000,000 horse power at ordinary minimum flow of the streams.

294. Railroads.—Canada is building many railroads. The Canadian Pacific Railway joins St. John, Quebec, and Montreal in the east with Winnipeg and Vancouver in the west. It has branches to Toronto and many other cities in the eastern provinces, and in the prairies and plains has a network of lines that carry away much of the product of the farms and ranches of Manitoba, Saskatche-



Fig. 308. Bridge across the St. Lawrence near Quebec, completed in 1917. The largest ships can pass under it

wan, and Alberta. It goes through wonderful valleys and passes in the western mountains, and at Vancouver connects with steamships of the same company bound for Japan, China, and Australia. From Montreal the company's ships run to Liverpool, Glasgow, London, and Antwerp.

The Grand Trunk Pacific Railway now extends from Moncton, New Brunswick, to Winnipeg, to Edmonton, the capital of Alberta, and to Prince Rupert, a new seaport on the Pacific just south of Alaska. Other parts of this system connect Chicago and Portland, Maine, with Montreal. The entire system is now controlled by the Canadian government.

Another transcontinental system is the Canadian National, including lines formerly known as the Intercolonial and the Canadian Northern Railways. It joins Halifax to Vancouver and is in process of extension to Hudson Bay (Sec. 293), so that there are three great railroads reaching across Canada from ocean to ocean. Port Arthur and Fort William on Lake Superior receive wheat by the railroads, store it in elevators capable of holding millions of bushels, and thence ship it down the lakes for eastern markets, or for export to Liverpool.

295. Cities.—Ottawa is the capital of the Dominion of Canada, and is an important industrial center, especially for the timber product of Ontario (Fig. 297).

Quebec is an old city standing on a bold promontory north of the St. Lawrence River. It was here that Wolfe won his victory over Montcalm on the Heights of Abraham. It was as a result of this battle, fought in 1759, that this part of America passed from the French to British rule. The dredging of the

St. Lawrence has made it possible for ocean vessels to go up to Montreal, and consequently Quebec, though prosperous, is not relatively so important a port as in an earlier period.

Montreal, with more than six hundred thousand people, is the metropolis of Canada (Fig. 309). It is served by the transcontinental railroads, and is connected by rail with Ottawa on the north, and with New York, by way of Champlain and Hudson valleys, on the south. It is the seat of McGill University.

Toronto is the largest city of Ontario, and the second city of Canada. It has much manufacturing, is in the midst of a fertile region, has many fine buildings, and is the seat of Toronto University. Kingston is at the foot of Lake Ontario. Hamilton is at the head of the lake, and is in the midst of the fruit region. There is an extensive development of electrical power on the Canadian as well as on the American side of Niagara Falls.

Winnipeg is the metropolis of western Canada. It has grown rapidly on the site of one of the forts of the Hudson's Bay Company, where the Assiniboine joins the Red River. All the great railroads that cross Canada center at this market city of the prairies. Southward, railroads run to Minneapolis and Chicago. Regina and Moosejaw in Saskatchewan, and Calgary and Edmonton in Alberta, are railroad centers and are important and growing cities.



Fig. 309. Montreal, seen from the water front. Mount Royal in the distance

Vancouver is the great Canadian seaport on the Pacific coast. Its site was a forest until 1885, and it is now a large and splendid city, the terminus of the Canadian Pacific Railway, and the point of departure for ships running to all countries on the Pacific Ocean (Fig. 301). Victoria, at the south end of Vancouver Island, has a beautiful situation, and is chiefly important as the capital of British Columbia.




Fig. 310. On the barren and rocky coast of Labrador

NEWFOUNDLAND

296. Newfoundland is a colony of Great Britain, but did not, like other colonies of this region, join the Dominion of Canada. It is nearly as large as the state of New York, but has only about a quarter of a million people. A strip of the Labrador coast is under the government of Newfoundland (Fig. 310). The island has many lakes and rivers, but much of it is rocky or marshy, and unproductive. There is some timber, and English firms have built large paper and pulp mills. Iron, copper, coal, gold, silver, and lead are found. The principal industry is fishing. A narrow-gauge railroad crosses the island from east to west, ending on the east at St. Johns, the capital and the only city of considerable size. Its interests are fishing and shipping.

GREENLAND

297. Greenland is the largest island in the world. It has over 800,000 square miles of surface, most of which is covered by an ice sheet. There are several towns and villages on the coast, inhabited by Danes and the native Eskimos. The island was discovered more than nine hundred years ago by the daring sailors of northern Europe, and it now belongs to Denmark. Furs, ivory, eider down, and seal oil are the chief products.

Review.—1. Name and describe the four regions of southern Canada. 2. Describe the northern part of Canada. 3. What name is often given to much of northern Canada? 4. How far is the St. Lawrence River affected by the tides? 5. Describe the shores of British Columbia. 6. What are the chinook winds? 7. Why has southern Ontario a milder climate than the rest of eastern Canada?

8. Describe the canoes of the Indians. 9. Give an account of the Hudson's Bay Company. 10. When was the Dominion of Canada formed?

11. What parts of Canada have little or no forest? 12. What are the three leading lumber regions of Canada? 13. What causes the forest fires to spread rapidly?

14. What are the chief fishing centers of Nova Scotia? 15. Give an account of the uses of the codfish.

16. In what parts of Canada is coal found? 17. What is the chief region for gold mining?

18. Make a map of Ontario, and name the provinces, states, and waters that are on its boundary.

19. What are the leading seaports of eastern Canada? 20. Which are free from ice throughout the year? 21. What railroad has its Pacific terminal at Prince Rupert? 22. What large cities are connected by the Canadian Pacific Railway?

23. What Canadian cities are on the shores of Lake Ontario? 24. Locate the capital of Canada and name one of its important industries. 25. What advantages of location has Winnipeg? 26. What important product has a large market at this place? 27. Locate St. John.

28. Of what country is Newfoundland a colony? 29. What is the leading industry of Newfoundland? 30. What and where is its chief city?

31. Give an account of Greenland.



SOUTHERN COUNTRIES OF NORTH AMERICA

	AREA, SQ. MI.	POPULATION	CAPITAL
Mexico . . .	767,300	15,503,000	Mexico
Brit. Honduras .	8,600	45,000	Belize
Guatemala . .	43,640	2,100,000	Guatemala
Salvador . . .	8,170	1,501,000	San Salvador
Honduras . . .	44,276	637,000	Tegucigalpa
Nicaragua . . .	49,550	638,000	Managua
Costa Rica . .	18,690	468,000	San Jose
Panama . . .	33,300	401,000	Panama
Cuba . . .	44,000	2,889,000	Havana
Haiti . . .	11,070	2,500,000	Port au Prince
Dominican Rep.	18,750	897,000	Santo Domingo
Jamaica . . .	4,840	858,000	Kingston
Lesser Antilles .	4,905	1,450,000	
Bahama Islands	4,400	53,000	

two countries included in one of these. 19. How long is Cuba? (Use scale of miles, Fig. 311.) 20. Locate Havana; Santiago de Cuba; Kingston. 21. Where are the Lesser Antilles? 22. What great river flows into the ocean near the island of Trinidad? 23. Where is Yucatan Channel? Florida Strait? Windward Passage? 24. Where are the Bahama Islands?

MEXICO

298. Physical Features.—The area of Mexico is about one fourth that of the United States. The most northern and the most southern points are about equally distant from the Tropic of Cancer. A narrow lowland runs along the Gulf of Mexico and also along the Pacific Ocean. Above these lowlands, on each side of the country, rise steep and rugged mountain ranges. The country narrows southward, and these mountain ranges come together south of the city of Mexico. Where

Map Study.—1. What is the latitude of northern Mexico? Of southern Mexico? 2. What is the latitude of the city of Mexico? 3. Compare with it the latitude of Bombay (see map of Asia); of Manila. 4. What peninsulas form part of Mexico? 5. What countries border Mexico on the southeast? 6. What river is on the northern boundary? 7. What large river of the United States enters the sea through Mexico? 8. What important isthmus is in southern Mexico? 9. What port is southward from Mexico city? 10. What port is eastward from Mexico city? 11. Locate Guadalajara; Puebla; Tampico. 12. Where is Mt. Popocatepetl?

13. Name the seven countries of Central America. 14. Which of these belongs to a European country? 15. Which countries of Central America extend from the Caribbean Sea to the Pacific Ocean? 16. What large cities of the United States are in nearly the same longitude as the city of Panama (Fig. 11)?

17. What are the four principal islands of the West Indies? 18. Give the names of




Fig. 312. Popocatepetl

the two mountain systems join, volcanic peaks rise to great heights. Their upper parts are covered with snow and ice, even though they are in the Torrid Zone. The highest of these is Orizaba, which rises 18,314 feet above sea level, and is nearly as high as Mt. McKinley. Mt. Popocatepetl is 17,888 feet high (Fig. 312), and several others have altitudes of from 12,000 to 16,000 feet. Orizaba and Popocatepetl still send up hot vapors. Jorullo, a small volcanic mountain, was built up by a violent eruption in 1759.

Between the mountains of eastern and of western Mexico is a vast plateau, an inland

(Secs. 25-27). In most of Mexico there is a dry season from November until June, and a rainy season during the rest of the year. The northeast trade winds (Sec. 29) blow across Mexico, and hence the slopes facing the Gulf of Mexico are wet. The coastal lowland up to 2000 or 3000 feet is known to Mexicans as the *tierra caliente*, or hot country. The slopes that lead up to the plateau are temperate, but rather warm. The *tierra fria*, or cool zone, is on the plateau; it has a temperate climate, and is so dry that irrigation is, in many places, necessary for raising crops. The west coast, including the peninsula of Lower California, is hot and dry, like southern California and Arizona. The southern lowlands and hills are very hot, and since the distance from ocean to ocean is short, moisture is almost everywhere abundant. The result of the variety in climate is that the soils produce the fruits, grains, and forest trees of both temperate and hot countries.

300. History and People.—

People who used many of the arts of civilization had lived in Mexico for hundreds and perhaps for thousands of years before the Europeans

came. They were Indians, divided into many tribes, of which the strongest was the great nation of the Aztecs. The Aztecs built fine buildings (Fig. 313), made roads, watered their fields, and carried on commerce. They made articles of clay, silver, gold, cotton, and silk, and lived an orderly life. The country was conquered by the Spanish general Cortes and was subject to Spain for three hundred years. About a hundred years ago Mexico threw off the rule of Spain, and for most of the time since then has been a republic with a government somewhat like that of the United States. There are twenty-eight states, two territories, and a Federal District (Fig. 314).

Most of the rivers flow down the mountain slopes on the east and west. They are short, and offer little chance for navigation. The coast line of Mexico is about 6000 miles long, but has few bays and few good harbors.

299. Climate.—Since the country extends over eighteen degrees of latitude, is washed by the sea on both sides, and has such differences of altitude, it has many kinds of climate



Fig. 313. Aztec ruins in Mexico

came. They were Indians, divided into many tribes, of which the strongest was the great nation of the Aztecs. The Aztecs built fine buildings (Fig. 313), made roads, watered their fields, and carried on commerce. They made articles of clay, silver, gold, cotton, and silk, and lived an orderly life. The country was conquered by the Spanish general Cortes and was subject to Spain for three hundred years. About a hundred years ago Mexico threw off the rule of Spain, and for most of the time since then has been a republic with a government somewhat like that of the United States. There are twenty-eight states, two territories, and a Federal District (Fig. 314).

There are about 15,000,000 people in Mexico, including natives or Indians, the descendants of the Spanish settlers, and half-breeds, or mestizos. The Indians are descended from the Aztecs and other early peoples, and most of them belong to the working or serving class. These are often called peons. They buy a cotton suit for a dollar, a pair of sandals for a dime, and a blanket for a dollar and a half. They are poor, polite, often lazy, and live in filth and ignorance. The mestizos are descended from Spanish people who married natives, and they consider themselves the real Mexicans (Fig. 315). There are now many Americans and Europeans carrying on mining and other kinds of business in the country.

Rude and simple ways of living are found side by side with those of modern life. Some of the farmers still use wooden plows (Fig. 316), and peons called cargadores carry heavy loads on mountain trails. The burro, or donkey, is much used as a beast of burden. There are, however, a number of well-equipped railroads, and the wealthier people travel much in automobiles. The houses of the poor are only a story in height and are built of sun-dried brick or adobe, which stands well because there are no hard frosts. Straw is mixed with the clay in these mud bricks, as in ancient Egypt.

Beans and corn are much used for food. The poor soak the corn, grind it with a pestle, and

make it into round cakes. These are baked in an open iron pan and are called tortillas. A kind of century plant, or agave, which, like many desert plants, has much juice, supplies a common drink. The heart of the plant is scooped out and the juice collects in the cavity. This is collected and fermented and makes an intoxicating beverage called pulque. It is the curse of the poorer Mexicans.




Fig. 314. The political divisions of Mexico



Fig. 315. Mexican women in native costume



Fig. 316. A Mexican plow

301. Mining.—The Spanish took from the conquered natives great treasures of gold and silver, and for centuries took vast quantities of the precious metals from Mexican mines. A single nugget of silver, found in Mexico in the state of Sonora, weighed 2750 pounds. There are mines in almost every state, and the value of the silver produced has in some years amounted to \$70,000,000. There are many gold mines and many copper mines, and near Durango is a great deposit of iron known as Iron Mountain. Quicksilver, lead, zinc, and sulphur also are found. In the production of petroleum Mexico ranks second among the countries of the world. Among the precious stones found in Mexico are onyx, opals, turquoises, topazes, emeralds, agates, and garnets. Hundreds of millions of dollars are invested by Americans and other foreigners in Mexican mines and oil wells.

302. Agriculture.—Corn, wheat, beans, and tobacco are raised in the cooler parts of the country. Corn is the chief crop and is the staff of life to many Mexicans. Almost all trop-




Fig. 317. Mahogany trees

ical fruits are grown, as well as sugar, coffee, cotton, indigo, rice, and the vanilla bean. From the last is taken the flavoring extract we know as vanilla. Henequen is a kind of hemp that is extensively raised in Yucatan. It is used in the United States for making rope, twine, bagging, rugs, and carpets. Some kinds of cactus contain fibers suitable for making paper. Many hammocks are woven in Yucatan, and some are very beautiful and costly. Mahogany (Fig. 317), rosewood, logwood, and other tropical trees abound in the hot parts of Mexico, and their lumber forms one of the valuable exports. Some rubber is produced.

303. Grazing.—The dry plateaus of northern Mexico, like those of the western United States, furnish pasturage for thousands of cattle. The life on the ranches, with their cowboys and round-ups, is similar to that on the plains of the western United States. Some estates are very large and contain many villages and even private railroads. There is also much progress in irrigation in the states of northern Mexico.



Fig. 318. The Cathedral and Plaza, Mexico city




Fig. 319. In the harbor at Vera Cruz, Mexico

304. Cities and Routes of Trade.—Mexico is the capital and the largest city, with about a half million people (Fig. 318). Much of it is well built, and its cathedral is one of the large churches of the New World. The oldest railroad of Mexico is the one between the capital and Vera Cruz (Fig. 319). The ascent from the coast to the plateau is accomplished by skillful engineering. Main lines of railroad extend northward and connect with trunk lines in the United States. Other lines reach Pacific ports and Central America. It is proposed to extend a line through Central America and South America. This is the Inter-Continental Railway, which will give the countries of the two Americas land communication with each other.

Tampico and Vera Cruz are the two important Gulf ports, and among the larger interior cities are Guadalajara, Puebla, and San Luis Potosi.

Review.—1. Describe the great plateau of Mexico. 2. Give the location and height of the principal volcanic peaks. 3. What conditions cause Mexico to have a variety of climate? 4. Where are the wet and the dry regions?

5. To what extent were the Aztecs civilized? 6. What classes of people make up the present population? 7. What is the meaning of each of the following: tierra caliente; peon; mestizo; adobe; tortilla?

8. How much silver is annually produced? 9. What precious stones

are found? 10. What is pulque, and how is it produced? 11. Where are the main lines of railroad? 12. What is the "Inter-Continental Railway"?

CENTRAL AMERICA

305. The Republics of Central America.—Until recent years there were in Central America one colony,—British Honduras,—and five small re-

publics,—Guatemala, Honduras, Salvador, Nicaragua, and Costa Rica. To these must now be added the republic of Panama and the Canal Zone. The distance between the Caribbean Sea and the Pacific Ocean is everywhere short, the countries are all less than twenty degrees from the Equator, and the climate is hot. As the land is narrow and in the region of the trade winds, there is a heavy rainfall nearly everywhere. The lowlands of the coast are swampy and unhealthy, while the mountains and hills on the west and southwest are more favorable for human occupation. There are several active volcanoes, and earthquakes are frequent.

Few of the people are educated, and the conditions of life are unsettled. As in other tropical lands, many of the houses are primitive. Coffee, sugar, rubber, and tropical fruits, especially bananas, are extensively raised and are the chief exports (Fig. 320).



Fig. 320. Hauling bananas to the railway, Costa Rica

All these countries are rich in cabinet woods and dyewoods. Like Mexico, these countries were long ruled by Spain, but became independent early in the last century. With education, with sanitary ways of living, and with the development of commerce on the isthmus, they will no doubt become prosperous. Some of the cities are well built. The largest city of Central America is Guatemala.

THE WEST INDIES

306. The West Indies in General.—The Caribbean Sea is partly separated from the Atlantic Ocean by a long chain of islands. The largest four of these are often called the Greater Antilles. They are Cuba, Haiti, Porto Rico, and Jamaica. The smaller islands are the Lesser Antilles, and most of them lie between Porto Rico and South America. They contain many volcanic formations, and some volcanoes are still active. Coral rocks are abundant: some have been raised high above sea level, and some are now in formation as reefs covered by living corals. Most of the islands are mountainous.

The West Indies are in the belt of the northeast trade winds, and hence their northeast parts often have a heavy rainfall, while the southern and western parts have much less rain and at times need irrigation. Fierce



Fig. 322. Tobacco growing under canvas

whirling storms, known as *tropical hurricanes*, often sweep the region and do damage on sea and land, and there are frequent earthquakes. As all the islands are south of the Tropic of Cancer, the climate is hot, except as tempered by the sea, and tropical trees and fruits abound, as well as coffee, rice, and tobacco. Lines of fruit steamers ply regularly to many ports of these islands, and of Mexico and Central America, to carry the bananas, oranges, pineapples, and other fruits to the market cities of the United States.

Many of the islands were long under Spanish rule, though none are so governed to-day. Spaniards, half-breeds, and negroes constitute most of the population.

307. The Greater Antilles.—Cuba is the largest of all the islands. It has plains, hills, and even high mountains, and has rich forests and productive fields. It gained its independence with the aid of the United States in 1898, after three centuries of Spanish control. The United States still holds the right to intervene in order to suppress disorders and protect foreign capital invested in railroads, mining, manufacture, and the sugar and tobacco plantations. Sugar (Fig. 321) and tobacco (Fig. 322) are the leading products of the soil, and the trade in these and other



Fig. 321. Cutting sugar cane in Cuba

things is mainly with the United States. Sugar is the largest item, but Havana cigars are even better known.

Iron and copper are found in eastern Cuba, near the chief eastern port, Santiago de Cuba. Havana is the capital and the largest city. It was cleaned and freed from yellow fever by sanitary engineers employed by the United States. A good road was built through the island from west to east.

Haiti is a rugged island east of Cuba. It is divided into two negro republics, Haiti in the west and the Dominican Republic in the east. The governments have been unstable, marked by many disorders and revolutions. Santo Domingo, the capital, and Puerto Plata are the chief cities of the Dominican Republic, and Port au Prince is the capital and main city of Haiti.

Porto Rico has already been described (Secs. 266-267).

Jamaica is a crown colony of Great Britain, but its people are nearly all negroes. Sugar production is important, and raw sugar is the leading export. Among the other products and exports are logwood and logwood extract, coconuts, and tropical fruits, especially bananas (Fig. 323). The main trade is with the United States. Ginger, the underground stem of a plant, is produced here. Kingston is the capital and principal seaport.

308. The Lesser Antilles and the Bahamas.—The Lesser Antilles belong to several different nations. Under British rule are many islands, including Dominica, St. Lucia, St. Vincent, Grenada, Barbados, and Trinidad. On Trinidad is Pitch Lake, about one half mile across, filled with pitch or bitumen,—the

residue of evaporated petroleum,—which supplies the material for most of the asphalt pavements laid in the cities of the United States.

Guadeloupe and Martinique are French colonies. On Martinique is the volcanic Mont Pelee, which became active in 1902. At that time an outburst of suffocating gases swept down upon the city of St. Pierre, and destroyed its entire population of more than 25,000 people.

Curaçao and several smaller islands form a Dutch colony.

St. Thomas, etc., belong to the United States (Sec. 268).

The Bahamas are a group of many small islands north of Cuba. They belong to Great Britain. They are low islands, largely of coral origin. It was on one of them that Columbus made his first landing in 1492. Sponge fishing is one of the industries of these islands, and Nassau is the principal city. Most of the people are negroes.



Fig. 323. Banana plantation, Jamaica

Review.—1. Give name and location of the only foreign colony of Central America. 2. What region is under the control of the United States? 3. Why has Central America a heavy rainfall? 4. What are the chief products? 5. How do the trade winds affect the rainfall of the West Indies? 6. What special class of steamships visit many West Indian and Central American ports? 7. How is the population of the islands chiefly made up? 8. What right is held by the United States in reference to Cuba? 9. What are Cuba's leading products? 10. In what direction is Havana from Florida? 11. What country holds the largest share of Cuban trade? 12. Give an account of Jamaica. 13. What sad calamity happened in Martinique? Give date. 14. What great historical event took place on one of the Bahama Islands? 15. Where is Trinidad? What is its chief product?



SOUTH AMERICA

	AREA, Sq. Mi.	POPULATION	CAPITAL
Brazil	3,300,000	30,645,000	Rio de Janeiro
Paraguay . . .	100,000	1,050,000	Asuncion
Uruguay	69,000	1,495,000	Montevideo
Argentina . . .	1,084,000	8,699,000	Buenos Aires
Chile	293,000	3,755,000	Santiago
Bolivia	440,000	2,890,000	La Paz
Peru	440,000	4,586,000	Lima
Ecuador	118,000	2,000,000	Quito
Colombia	466,000	5,855,000	Bogota
Venezuela . . .	364,000	2,412,000	Caracas
British Guiana .	95,000	298,000	Georgetown
Dutch Guiana . .	50,000	113,000	Paramaribo
French Guiana . .	30,500	49,000	Cayenne
Falkland Is., etc.	6,570	3,000	

Map Study.—1. What is the latitude of the most northern point of South America? 2. To what country does it belong? 3. Give the name and latitude of the most southern point of South America. 4. To what country does it belong? 5. Give the longitude of the eastern and the western points of the continent, and the countries to which they belong.

6. Beginning in the north, name in order all the countries that border Brazil. 7. What countries border the Caribbean Sea? The Atlantic Ocean? The Pacific Ocean? 8. What countries have no sea-coast?

9. Comparing South and North America, which continent has the more regular coast line? 10. The chief indentations of the South American coast are the mouths of the Amazon and the Plata rivers, and Lake Maracaibo. Locate each of these. 11. Locate the following islands near the South American coast: Falkland, Tierra del Fuego, Juan Fernandez.

12. Counting 69 miles to a degree of lati-

tude, how far do the Andes Mountains extend north and south? 13. Locate the following volcanic peaks: Chimborazo, Coto-paxi, Aconcagua.

14. What countries are partly drained by the Amazon and its tributaries? 15. Using the scale of miles, find the shortest distance from the headwaters of the Amazon to the Pacific coast. 16. Locate Manaos and Para (Brazil). 17. Trace the course of the Orinoco and locate its delta. 18. What is the latitude of the mouth of the Amazon? 19. Trace the course of the following tributaries of the Plata river system: the Uruguay, the Parana, the Paraguay, and the Pilcomayo.

20. Locate the capitals of countries bordering on the Atlantic Ocean. 21. Locate Punta Arenas, and the capitals of all the countries that border the Pacific coast.

PHYSICAL FEATURES

309. Position.

—Only a small part of South America is in the Northern Hemisphere, although seven countries lie entirely or partly north of the



Fig. 325. Punta Arenas, the southernmost city of the world

equator. Cape Horn, at the southern end of South America, is no farther from the Equator than the southern parts of Hudson Bay, hence South America has no cold polar region like that of North America. Its cold climates are found only in the higher parts of the Andes. Punta Arenas (Fig. 325) is the most southern city of the continent. It is about the same distance south of the Equator that London, the largest city of the world, is north of the Equator.

South America is farther east than most of North America. The western parts of Ecuador and Peru are in about the same longitude



as southern Florida and Lake Erie. If we look at a globe or at a map of the world (Fig. 350), we see that the Atlantic Ocean between South America and Africa is comparatively narrow.

310. Size.—South America is smaller than North America, but it is nearly twice as large as Europe. It has, however, only about 65,000,000 people, while North America has about 150,000,000. Europe, although so much smaller, has about seven times as many people as South America. South America has much rich soil, and when its lands are improved, can support several times its present population. Except in Argentina, most of the people live near the borders of the continent.

Brazil is larger than the main part of the United States, and Argentina is one third as large. We sometimes think of Peru and Bolivia as small countries, but each of them is about one seventh as large as the United States.

311. Surface.—The Andes Mountains are narrower and higher than the Cordilleras of our own continent. In their central part, however, the Andes are broad and consist of parallel ranges, with high mountain valleys and plateaus. The largest of these plateaus is that of Bolivia (Fig. 326). Several countries extend from the Pacific coast across the Andes to the lowlands and forests on the east of the mountains. Eastern Colombia is in the basins of the Orinoco and Amazon, and eastern Ecuador is in the Amazon basin. In central Peru branches of the Amazon flow 500 miles in a northerly direction, and then turn eastward into Brazil. Central and northern Bolivia is in the basin of the Madeira, a branch of the Amazon. The crest of the Andes forms a national boundary between Chile and Argentina only.

The higher peaks of the Andes rise to altitudes of more than 20,000 feet. Even at the Equator and for hundreds of miles through the Torrid Zone, the tops of the range are in a region of perpetual snow, with

numerous glaciers. The lowlands near the coast are hot, the middle heights are temperate, and the upper slopes are frigid, in climate. Several of the highest peaks are volcanoes. Among these are Chimborazo and Cotopaxi in Ecuador, each rising about 20,000 feet above the sea. Aconcagua, in Argentina, rises about 23,000 feet and is the highest mountain in the Western Hemisphere.

Along the Atlantic Ocean in eastern Brazil are mountains which are much lower than the Andes. Many of them have rolling summits covered with a dense forest growth similar to that of the Appalachians in the United States. North of the Amazon is an elevated region called the Guiana Highlands.

Between the Andes on the west and the Brazilian mountains and Guiana Highlands on the east are broad plains, which extend from the mouth of the Orinoco to the southern part of the continent. South America, therefore, like North America, has mountains in the east and in the west, and central lowlands reaching from the northern part of the continent to the southern.

312. Drainage.—The greater part of the central plain lies in the basins of the three great rivers of South America. The northernmost of these is the Orinoco, which has its sources in the Andes and drains much of Colombia and most of Venezuela. It is in a region of heavy rainfall. In consequence its volume is very great, and out of the land waste carried by its waters it has built a large delta opposite the island of Trinidad.

The Amazon is the largest river in the world. The Missouri-Mississippi is longer, but drains less territory and has far less water. The greatest length of the Amazon is about 3500 miles. Ocean ships can ascend the river more than 2000 miles, and smaller steamers can go hundreds of miles farther. At Tabatinga, 2000 miles from its mouth, the Amazon is $1\frac{1}{2}$ miles wide. At the entrance of the Madeira, several hundred miles from

the sea, it is 3 miles wide, and for more than 200 miles it is 50 miles wide. In times of high water vast areas of the Amazon forest are flooded, and many trees stand in deep water. The natives then move to higher ground, or live for a time in boats. The river pours so much water into the Atlantic that the ocean waters are made muddy far out of sight of land.

The third great river system is that of the Plata River. Its northern streams, the Parana and Paraguay, reach into the heart of the continent and are vast rivers in themselves. They drain much of Brazil and Bolivia, all of Paraguay, and northern Argentina. South of the Plata the plains east of the Andes are drained by several shorter rivers.

313. Coast Line.—The mouths of the Amazon and Plata are like wide, deep bays, and Lake Maracaibo in Venezuela is really an arm of the sea. As a whole, however, the coast of South America is much less broken than that of North America, and therefore has several thousand miles less of coast line. This condition is not favorable to the growth of coast cities. Several important cities of the west coast have harbors that need to be greatly improved to afford protection for ships in time of storm. Only the coasts of southern Chile and of Tierra del Fuego have headlands and fiords similar to those of Alaska and Labrador. Such coasts furnish excellent harbors, but in South America that part of the continent has so

few inhabitants that the harbors are of no practical value.

314. Climate.—The broad part of South America is in the Torrid Zone, where the sun at noon is always nearly overhead; so most of this part of the continent is hot throughout the year. The southern parts of South America are in the Temperate Zone, but they are narrow and are warmed in the winter by winds from the ocean. The continent as a whole is much warmer than North America.




Fig. 327. Annual rainfall and winds in South America

broad northern part of South America blow from the Atlantic Ocean—from the northeast in the north and from the southeast farther south (Fig. 327). As these *trade winds* reach the land, and as they cross the Guiana and Brazilian highlands, they are cooled by rising to higher altitudes, and heavy rainfall results. West of these highlands the winds descend, are warmed, and the rainfall diminishes. Here are the comparatively dry grassy plains called the *llanos* in Venezuela and the *campos* in Brazil. Still farther west the trade winds are cooled as they rise on the eastern slopes of the Andes, and the rainfall again is heavy, as it is also near the Equator where the trade winds meet.

On the west there is ample rain along the coasts of Colombia and Ecuador, but the lower slopes and coast plains of western Peru and northern Chile are a desert. The air of the trade winds has lost its moisture, and

as it descends the west slope of the Andes, it becomes warmer and is able to receive moisture instead of giving it off. This strip of lowland is one of the driest parts of the world, and in some places several years elapse between rains.

In the southern part of the continent, however, the Pacific coast has much rain, and the dry lands are east of the Andes, stretching several hundred miles, from central to southern Argentina. In these latitudes the prevailing winds are from the northwest. In southern Chile the cooling of the air due to the increase of elevation, and the rainfall, are therefore in the west. The eastern mountain slope and the plains to the east of the mountains are much drier. It is on account of the difference in the direction of the prevailing winds that northeastern Argentina is wet, while western and southern Argentina are dry.

Between the belt of northeast trade winds in northern South America, and the belt of southeast trade winds in central South America, is a belt of calms, heat, and abundant rain. In our summer time this rain belt is some distance north of the Equator. In our winter it has moved to the south of the Equator. Consequently in the llanos and campos of the interior, and on the west coast of Colombia and Ecuador, the year is divided into a rainy season and a dry season. The northward and southward movement of this rain belt also explains why some parts of South America near the Equator have two rainy seasons and two dry seasons each year.

Review.—1. What parts of the United States are in the same longitude as Ecuador? 2. Compare South America with North America and Europe in size and population.

3. What countries are partly drained by the Amazon and its branches? 4. Give the names and location of three volcanic peaks. 5. Give location and other facts about Tabatinga.

6. Compare the temperature of North America with that of South America and give reasons for the difference. 7. What part of South America is swept by the northeast trade winds? By the southeast trade winds? 8. What parts of South America are very dry? Why? 9. Where are the regions that have two wet and two dry seasons?

PLANTS AND ANIMALS

315. Forests and Grasslands.—Where the temperature is high and the rainfall large, dense tropical forests grow. This is especially true in the central parts of the Amazon basin. Since the eastern highlands of the Guianas and Brazil are in the trade wind belt, they also are moist and covered with forests. The same is true of the eastern slopes of the northern Andes. Because of the prevailing westerly winds, the western parts of central and southern Chile also have a heavy growth of trees. In the Amazon basin the rainfall is heavy and the slope of the land so gentle that the water drains into the streams very slowly. Here is one of the most luxuriant of all tropical forests (Fig. 328), and the large trees, the undergrowth, and the vines make a network of plant life so dense that the explorer must cut a path before he can make his way through the forest.

The llanos of Venezuela, the pampas of Argentina, and a part of the campos of Brazil,



Fig. 328. Forest along the Amazon River

are grasslands in regions of moderate or small rainfall, as are the prairies and western plains of the United States.

316. Animals.—Many of the native animals of South America are very different from those found in other parts of the world. This is partly due to the fact that the position of South America is such that the animals of other continents could not easily reach it. The continent is joined to North America by the narrow Isthmus of Panama. Oceans



Fig. 329. Jaguar

separate it from all the other continents, and there are few islands in the neighboring waters.

In western South America is found the llama, an animal somewhat like a small camel, but without a hump. It has a head like a camel's, a body like that of a sheep, and feet and legs like those of a deer. It was tamed and used by the Indians of the Andes as a domestic animal, and is still used as a beast of burden. The flesh, hides, and wool are useful, so that these animals to a degree take the place of horses, cattle, and sheep. The alpaca is a similar animal, with especially fine wool.

The llama and alpaca no longer exist in a wild state, but the vicuña, which is like them, is found wild in some parts of South America.

The tapir is a large animal that is related to the rhinoceros, but does not, like the latter, have a horn on its nose, nor does it grow to be so large. The two animals are alike in habit; they are shy, and wander at night, feeding on plants and bathing in the streams. The jaguar (Fig. 329) is a catlike animal, large and powerful, resembling the tiger of Asia and the leopard of Africa. It ranges from Mexico to the southern part of South America, and feeds on other animals. A strange quadruped is the armadillo, which is covered with a strong bony case or shell. It can run rapidly, however, and has strong claws by which it buries itself in the earth when in danger.

Like other tropical lands, the warm parts of the continent have many poisonous insects and serpents, and many brilliant and strange birds. The condor (Fig. 330) is the largest of birds. When its wings are spread, they measure nine or ten feet from tip to tip. It



Fig. 330. Condor

can kill and eat a sheep, goat, deer, or dog. The condor nests in the high Andes, and its young are nearly two years old before they can fly. The rhea is a large running bird resembling an ostrich. Birds of beautiful plumage and a great variety of brilliantly colored insects are found in the tropical forests, and numerous monkeys climb and chatter in the thick tree tops.

Horses, cattle, and sheep have been brought in modern times from other lands to South America. This continent, however, has not furnished other parts of the world with any useful animals.



Fig. 331. Ruins of an ancient Peruvian city

PEOPLE AND INDUSTRIES

317. History.—In the years following the first voyage of Columbus, the shores of South America were discovered by him and by other explorers from Spain and Portugal, and thus these two kingdoms gained control of almost the entire continent. They found everywhere, as in North America, native Indian tribes. Some of the Indians were savages, but others had developed many of the arts of civilized people.

The most advanced natives belonged to the empire of the Incas, whose capital was Cuzco, an ancient city among the mountains of Peru. Their dominions covered most of Ecuador and Peru, and parts of Bolivia and Chile. In the course of hundreds of years these people had developed skill in building substantial houses and cities (Fig. 331). They made strong forts and splendid temples, quarrying large blocks of stone and dressing them so that they fitted each other perfectly when laid into a wall. They mined much gold and silver, which they used in adorning their buildings and in making ornaments of many kinds.

The Incas, and the many tribes under their rule, were expert in tilling the soil, and, as much of their land was along the dry western

coast, they dug canals and irrigated their fields. They also made terraces on the steep slopes by building walls to hold the soil, and they raised potatoes, corn, and cotton. They found the potatoes and corn as wild plants, developed them by cultivation, and thus gave to the world two of its most important foods. They used the llama as a beast of burden. They built roads and sent messages by swift runners, but they did not have a written language.

The Spanish explorer Pizarro, with a small party of followers, invaded the country in 1532. With the aid of firearms, and by means of treachery, they captured and then killed the king of the Incas, stole their gold, and conquered the land for Spain, under whose rule most of South America remained for nearly three hundred years. Brazil, however, belonged to Portugal, and its conquerors and colonists were from that country.

About one hundred years ago, after several wars, the peoples of South America freed themselves from foreign rule. The Spanish colonies became republics, somewhat like the United States. For many years Brazil was ruled by an emperor, but this country also at last adopted a republican form of government. Only the three Guianas now remain under foreign rule.

318. People.—The people of South America are of many kinds, chiefly Indians (Fig. 332), Spaniards, Portuguese, and mestizos, or mixed races, with some negroes, whose ancestors were brought from Africa as slaves. The negroes are most numerous in Brazil. In later years Englishmen, Germans, Italians, and North Americans have gone to South America, but their numbers are small compared with the Europeans who have found new homes in North America.



Fig. 332. Indians of South America

The Panama Canal facilitates travel and commerce between North and South America. The Inter-Continental Railway also, when constructed, will promote trade among all the countries of both continents.

The republics of North and South America have organized the Pan-American Union, whose object is to promote friendly commercial relations. Its central office is a fine building in Washington (Fig. 333).

319. Products.—In North America the temperate regions are much larger than the tropical. In South America the opposite is true. The southern, or temperate, parts

raise wheat and corn, and furnish wool, hides, beef and dairy products. The northern and central countries produce rubber, cabinet woods, dyewoods, quinine, many tropical fruits, coffee, and cacao, from which chocolate is made. Among the most valuable commercial products of tropical South America are coffee and rubber (Secs. 321, 322).

All the countries of the Andes produce silver, gold, and copper. Nitrate, used extensively as a fertilizer, is found in northern Chile;

and tin in Bolivia. There is little mining of coal and iron, and for this reason railroad iron, rolling stock, bridge materials, and machinery of all kinds are mainly imported from the United States and other countries.

320. Commerce.—The commerce of South America, which is mainly with the United States and Europe, is rapidly growing. A very large part of the coffee and rubber is taken by the United States, while most of the corn, wheat, flour, meat, and dairy products of Argentina go to Europe, where countries like Great Britain have large populations and not enough farm lands

on which to raise their food. A large part of the trade with Europe is with Great Britain, Germany, France, and Italy.

South America is so far east (Sec. 309) that most of the ports of eastern South America are almost as near to the leading ports of Europe as they are to those of the United States. Better ships run between South America and Europe than between South America and North America.



Fig. 333. The home of the Pan-American Union in Washington

Since the completion of the Panama Canal much of the trade of the west coast makes use of that route. European trading nations have sought to gain control of the South American trade; and familiarity with the Spanish, Portuguese, and French languages has given them an advantage. We are now, however, more interested than formerly in South American trade. Our commercial travelers are beginning to learn the languages of the people, and American capital is being invested in South American railroads and mines.

The Panama Canal reduces the sailing distance between New York or New Orleans and the ports of Peru, Chile, and Ecuador by thousands of miles. From Callao to New York by the Cape Horn route is 10,700 miles. By the Panama route the distance is only 3600 miles. Better and swifter ships are being put into service, and trade between the United States and South American nations is steadily increasing.

For a great continent, South America has few railroads, but railroad building has progressed rapidly during recent years. The development of railroads will make it possible to export more of the produce of the plantations, the forests, and the mines.

Review. — 1. Describe the Amazon forest. 2. What are the llanos and pampas, and where are they found? 3. Why has South America some animals peculiar to itself? 4. Describe the llama, the tapir, the armadillo, the condor, and the rhea.

5. Give an account of the Incas. 6. To what nationalities do the South American people belong? 7. What is the Pan-American Union?

8. What are the most important tropical products of South America? 9. What part of South America is best supplied with minerals?

10. What countries have a large trade with South America? 11. How much does the Panama Canal shorten the sailing distance between New York and Callao?

COFFEE AND RUBBER

321. Coffee.—Coffee, like cotton, is raised in warm countries. The plant is said to have




Fig. 334. Coffee-producing regions of the world

derived its name from Kaffa, in Abyssinia, but it was first extensively cultivated in Arabia, where Mocha (the present Mokha) gave its name to a superior kind of coffee. In 1690 a Dutchman from Holland took some of the plants to the island of Java. Later, coffee plants were carried to the West Indies, to Brazil, and to the Philippine Islands.

Brazil now grows two thirds of the world's supply of coffee, but the crop is important also in Venezuela, Colombia, Central America, Mexico, and the islands of Haiti and Porto Rico. In the Old World coffee is grown in the East Indies, British India, Arabia, and east Africa (Fig. 334). In Brazil most of the coffee is raised in four southern states near the ocean. The principal port is Santos,



Fig. 335. Drying coffee, Brazil. The small railroads serve for carrying the coffee

from which many ships carry the coffee to the countries of the Northern Hemisphere. The United States uses much more coffee than any other country.

The plant grows to a height of from 14 to 18 feet, but when cultivated it is pruned to 6 or 8 feet. Its red berries grow in clusters, and each berry contains two seeds, or coffee "beans," surrounded by pulp and by inner and outer skins. The beans are separated

from the pulp by drying (Fig. 335) or by a process in which water is used.

The coffee plant needs high ground, with rich but porous and well-drained soil, some shade when it is young, and plenty of water. Within two hundred years the raising and drinking of coffee have spread to many lands in both hemispheres, like the production and use of potatoes and corn.

322. Rubber.—The discoverers of South America found some of the Indians playing with balls made of crude rubber. The Indians also made shoes and bottles of this material. The name *rubber* was finally given to it when an English chemist suggested that it was good for erasing pencil marks; and it was called *India rubber* because the first rubber used in England came from India.

There are many varieties of rubber trees, which flourish best in low, wet ground, and under shade.



Fig. 336. Carrying coffee on board a ship at Santos

The rubber collectors in Brazil cut their way through the dense forest and tap the trees (Fig. 337), which yield a milky juice. This is taken to the camp, and thickened in the smoke and heat of a fire of palm nuts. It is then "crude rubber" (Fig. 338), and is brought down to Manaus in the interior, or to Para, near the mouth of the Amazon. Para is a large city which exports little but rubber.

The United States, Great Britain, France, Canada, and Italy are the countries that lead in the consumption of rubber.

All the tropical countries of South America produce rubber, and much of the crop from Bolivia, Peru, and Ecuador, as well as from Brazil, goes down the Amazon to Para, for export. Central America and southern Mexico are rubber regions, and in the Old World, rubber is produced in the Kongo region in Africa, in Ceylon, the East Indies, and Indo-China. Most of the world's supply of rubber is produced from cultivated trees in the oriental countries, especially in the Malay Peninsula and Ceylon, but some rubber plantations have been started in other lands.

The crude rubber is changed by various processes, especially by mixing with sulphur, so that it will stretch when cold and not stick when hot. It is also made into hard rubber, such as is used in combs. Rubber is used for erasers, in garments and footwear, for insulation of electric wires, for hose, dental and surgical

goods, mats, cushions, toys, paint, for balls of many kinds, and for carriage and automobile tires. By taking care in tapping the trees and by increasing the number of rubber plantations, the world can always have enough of this important substance.

Review.—1. What country raises the greater part of the world's coffee? 2. What other countries are important in coffee culture? 3. Describe the plant and the coffee berry. 4. What country offers the largest market for coffee?

5. How did the natives of South America make use of rubber? 6. How is the crude rubber obtained? 7. What cities are important in the rubber trade? 8. What South American countries yield rubber? What North American countries? What countries in the Eastern Hemisphere? 9. Name some of the uses of rubber. 10. What countries use most of it? 11. How can the supply of rubber be maintained?





Fig. 337. Tapping a rubber tree



Fig. 338. Making crude rubber by smoking rubber sap

(For Southern Brazil, see Fig. 341)



BRAZIL

323. Description of Brazil.—Brazil is more than five sixths as large as Europe, but Europe has nearly fifteen times as many people as Brazil. In Brazil there are on an average only nine or ten persons for each square mile. Portuguese is the chief language of the country. Most of the people live near the coast or in a few of the southern states, and much of the interior is almost uninhabited.

Nearly all of Brazil is within the tropics, where the coldest and warmest months of the year differ in temperature only 5° or 10° . The country extends to about 33° south latitude, however, and in the southern states frosts are common in winter, and there are occasional snowstorms.

Northern and western Brazil are drained by the Amazon and its tributaries, and much of southern Brazil by the Plata system, while southern and eastern Brazil have many streams that do not unite in a single system but reach the sea independently. Of these the São Francisco is the largest.

South of the Amazon plain, the campos occupy the greater part of the country. They are rolling plains, in some places bearing grasses only, in others scrubby trees, and in a few places dense forests.

324. Products.—The forests along the Amazon and on the higher lands have a great variety of woods. As many as two hundred kinds were shown in an exposition at Rio de Janeiro. It is from the Brazil wood, which affords a red dye, that the country gets its name. Of other forest products rubber is the most important, and in addition there are cacao, vanilla, sarsaparilla, various dyes, and Brazil nuts.

Cacao seeds, exported in large quantities to the United States, Great Britain, and other countries, are the material from which chocolate and cocoa are made. Many cacao trees grow in the Amazon Valley and along the



Fig. 340. Rio de Janeiro

coast (Fig. 597). They require shade, and much warmth and moisture. The largest crop is grown in regions protected from strong winds, because the seed pods are large and are easily broken off the trunk and main branches to which they are attached. In the production of cacao Brazil outranks all other countries except the Gold Coast of Africa.

In southern Brazil and in Paraguay are ilex trees, whose leaves make maté, or Paraguay tea. The drink is prepared like ordinary tea, but tastes like a weak solution of turpentine. Maté leaves are exported to Argentina, Chile, and Peru.

In the grasslands of central and southern Brazil the cattle industries are important, and hides and meat are exported. German and Italian settlers have introduced modern methods of agriculture, and have established cotton and other manufactures.

Among the agricultural products of Brazil are coffee, corn, manioc, cotton, and sugar. Manioc is grown for its roots, from which farina and tapioca are made. From these roots the natives prepare a flour from which they make a sweetish kind of bread. The juice of some manioc plants is poisonous, and must be carefully pressed out when the roots are ground to make the flour. Coffee is the largest export, and rubber ranks second.

325. Cities.—There are few large cities, and most of them are on the Atlantic coast. The greatest of them is Rio de Janeiro, the capital (Fig. 340). It is the second in size of



South American cities, and has a splendid harbor. Other busy cities are São Paulo, in the coffee district, and its seaport, Santos (Sec. 321). On the coast between Para and Rio de Janeiro are Pernambuco and Bahia, which export cotton, tobacco, and sugar.

Review.—1. What is the range of temperature over most of Brazil? 2. Why is the southern part of Brazil its coldest region? 3. Describe the campos. 4. What are the chief products of Brazil? 5. What is maté? What countries produce it? 6. Locate the chief seaports of Brazil.

COUNTRIES OF THE PLATA BASIN

326. Argentina.—Argentina is more than 2000 miles long from the border of Bolivia to Tierra del Fuego. On the west it rises to the crest of the Andes, and on the east it is bounded by Paraguay, Brazil, Uruguay, and the Atlantic Ocean. It occupies more than half of the Temperate Zone in South America, and its products are somewhat like those of the United States. The people are very progressive, and Argentina has the largest immigration of all the countries of South America. About one seventh of the population are Italians. Outside of Italy, only our own land has more Italian people than Argentina.

The country is a great plain sloping from the Andes toward the rivers of the Plata system and toward the Atlantic. The central parts of the country around Buenos Aires are known as the *pampas*. They are like the prairies and plains of the Mississippi

basin. In the east they are well watered, and raise much grain. In the west they are drier and are used for grazing millions of cattle and sheep.

To the southward are the dry and cool plains of Patagonia (Sec. 314). Northward the country extends within the Torrid Zone, and in the eastern part receives abundant rain from the southeast trade winds. Here are tropical forests, and here also other growths of hot lands abound.

Agriculture and grazing are the great industries of the country. Argentina, like the United States and Canada, raises and exports much wheat. It is sent from Buenos Aires and Rosario, and most of it goes to Great Britain and other European countries to help feed the dense populations of the great manufacturing centers. As the wheat lands of Argentina are more fully occupied and better methods of cultivation adopted, the annual yield may be largely increased. This increased supply will be needed in European markets to take the place of wheat and flour from the United States, more and more of which is being used at home. Argentina also raises corn, and exports more of this grain than any other country. In recent years much corn is being used, as in the United States, for fattening cattle. Argentina has taken first place in raising flaxseed. Grapes and wine are produced on a large scale in the western parts, and sugar cane is grown in the tropical region about Tucuman.



Fig. 342. Hauling grain to market, Argentina

The grassy plains support herds of cattle and flocks of sheep. Beef and mutton are exported in large quantities, "on the hoof," or frozen, chilled, salted, or dried. Other cattle products are hides, tallow, and butter. All of these products find a ready sale in European markets, and some of them are now being sent to the United States in large quantities. The beef is needed because our own supply is no longer sufficient for our population, and the hides are needed for use in the manufacture of shoes. Only Australia has more sheep than Argentina, which produces a large part of the world's supply of wool and mutton.

Although there are some textile and paper mills, the chief manufacturing industries are of a very simple kind. They include meat freezing, butter making, flour milling, and brewing. Argentina will probably always be an agricultural rather than a manufacturing country, because there is very little iron or coal to support manufacturing industries. Quebracho wood and its extract, used for tanning, are important exports.

Near Jujuy, in the northern part of the country, there are mines that yield silver, gold, copper, and quicksilver.

Buenos Aires is the capital and has about 1,700,000 people. It is the largest city in the Southern Hemisphere, and the largest city in the world in which Spanish is the prevailing language. It is the chief center of Argentine railroads, and communicates by several lines of steamships with European countries. One of the principal railroads is a trunk line running northward from Buenos Aires to Rosario, Tucuman, and Jujuy. This line extends also beyond the boundary of Bolivia. Another line, the Trans-Andine Railway, runs westward, and by a tunnel crosses the Andes and connects Argentina and Chile. Another railroad extends from the capital



Fig. 343. Loading beef in Argentina

about 800 miles to the southwest. One line has 175 miles without a curve.

Many of the ships make "triangular voyages"; that is, they go from the United States to the Plata River, then to Europe with meat, grain, and wool, and back to the United States. Other vessels sometimes go from Europe to Brazil, take on rubber or coffee, carry these cargoes to the United States, and there load again for European ports. By following these routes the ships are usually sure to get cargoes for the round trip.

327. Uruguay and Paraguay.—Uruguay and Paraguay are small countries east of northern Argentina. They are crossed by the southeast trade winds and have abundant rainfall.

The raising of cattle and sheep is the largest industry of Uruguay. The capital is Montevideo, on the broad mouth of the Plata River.

Paraguay is one of the two South American countries without a seacoast. But it is on the Parana, a great and navigable river; and it is expected that ocean-going steamships will soon be able to call at Asuncion, the capital. Asuncion is now reached by rail from Buenos Aires. Paraguay has large forests of quebracho and other trees, but much of the land is like the campos of Brazil.

Paraguay tea is one of the chief exports, and another is oranges, which are both wild and cultivated. So abundant is the supply of oranges, however, that the greater number are eaten by birds or monkeys or lie on the ground and decay. Tobacco and cotton also are raised. Paraguay women are skillful in the making of lace.

Review.—1. Describe the surface of Argentina. 2. Describe the distribution of rainfall and give reasons.

3. What are the chief products of the farms in Argentina? Why are these exported to European countries? 4. What exports are provided by the grazing industries? To what countries are they sent? Why? 5. What kinds of manufactures are found in Argentina? 6. Give location and other facts about Buenos Aires.

7. Describe three great lines of railroad in Argentina. 8. What is meant by "triangular" voyages of ships that visit the ports of Brazil and Argentina?

9. What is the chief industry of Uruguay? 10. What means of communication with foreign lands has Paraguay?

COUNTRIES OF THE ANDES

328. Chile.—Chile lies on the west slope of the Andes, and the nearness of the mountains to the coast makes the country very narrow. It is, however, more than 2500 miles long (Fig. 341). For several hundred miles along the coast there is a lower range of mountains that shuts off the interior as a valley between itself and the Andes. This Central Valley includes the best soil and the largest centers of population, among which is Santiago, the capital.

The northern part of Chile is within the tropics; the central and southern parts are in the Temperate Zone

For this reason, and because the land varies in altitude from sea level to the summits of the Andes, there is a great variety of climate. The reasons why northern Chile is dry and southern Chile is wet have already been given (Sec. 314).

Chile, like Argentina, is known as a progressive nation. It had the first railroad on the continent, and is now active in three great branches of industry: mining, farming, and manufacture. Of these, mining is the most important, and the most valuable deposits are the beds of nitrate, a substance used in fertilizers and in the manufacture of explosives. A large part of northern Chile, from which the annual output of nitrate is about 3,000,000 tons, formerly belonged to Bolivia and Peru. Chile is also an important producer of copper, and has coal, gold, silver, and other mines.

Agriculture is the second interest in Chile. In the northern dry region irrigation is necessary. In the moist and cooler parts all the grains and fruits commonly produced in temperate latitudes are raised, and some wheat is exported. The cattle and sheep industries also are of considerable importance. Trade with the United States is increasing, and is favored by the opening of the Panama Canal.

Valparaiso is the principal port and is the gateway to the capital, Santiago, a city of about 500,000 people. Iquique, the second port of Chile, is the principal shipping point for the nitrate. Punta Arenas, the most southern city of the world, is on the Strait of Magellan (Fig. 325). It is a *free port*, no duties being collected on exports or imports.



Fig. 344. Packing nitrate in bags, Chile



329. Peru.—Peru has a long shore line, but the country is not so long or narrow as Chile (Fig. 324). It may be divided into three sections: first, a seacoast section west of the Andes; second, a mountain belt, with plateaus and valleys of high altitude, and temperate climate; and third, a section on the eastern slope of the Andes, and along the headwaters of the Amazon.

Peru is marvelously rich in minerals, especially gold, silver, copper, and petroleum. With good roads and modern methods of mining, Peru will yield more mineral wealth than was ever taken from the mines by the Incas.

An important vegetable product from the forests of Peru is quinine, the bitter medicine much used in cases of fever. It is made from the bark of the cinchona, a tree that grows in Peru, Bolivia, Ecuador, and Colombia. It is also called Peruvian bark. So many trees were killed by stripping the bark that fear arose that the supplies would fail. Hence about sixty years ago trees were transplanted to British India, Java, and other parts of the East. The result is that the world's market is now mainly supplied from India.

Rubber is produced in the forests on the east side of the Andes. Some of it may be sent to the Pacific coast and reach its market by way of the Panama Canal, but most of it is sent down the Amazon to Para.

Sugar and cotton, grown in the coastal regions, are, with coffee, wool, hides and skins, the chief agricultural productions. Peruvian cotton has a long woolly fiber, and is therefore

in demand among cotton manufacturers for making special kinds of cloth.

Callao is the principal seaport of Peru, and a few miles inland is Lima, the capital. A railroad extends from Callao and Lima to Oroya in the high Andes. Paita is the port for northern Peru, and Mollendo for the southern part. From Mollendo, a railroad

has been built across the mountains to Lake Titicaca, on the border of Bolivia. This lake, which has an area of about 4000 square miles, is the largest fresh-water lake in South America. It is nearly two and a half miles above sea level and is the highest navigable lake in the Western Hemisphere.

Upon the western slope of the Andes, at Arequipa (Fig. 346), Harvard University has an astronomical observatory. The air




Fig. 346. Observatory of Harvard University at Arequipa, Peru

is very clear, and many stars can be seen there that cannot be observed from the Northern Hemisphere. Arequipa is a market for alpaca and vicuña wools, most of which are sent to New York and Boston in our own country, and to France.

330. Bolivia.—Bolivia was named after General Bolivar, the liberator of the north-western parts of the continent. Like Paraguay, it has no seacoast. In the west it is a land of high plateaus among the Andes ranges, and in the north and east less elevated regions drain to the Amazon and Plata. In the highlands silver and gold have been mined since the times of the Incas. Tin ore is now the chief product and with the silver and gold is largely exported. Rubber and coca are products of the eastern forests.



Fig. 347. Part of La Paz, Bolivia

Although at a distance from the sea (Fig. 345), Bolivia has several ways of reaching it. Three railroads now reach the coast, one of these leading to Mollendo in Peru, another to the port of Antofagasta in Chile, and the third from La Paz to Arica. Another railroad extends through Argentina to Buenos Aires. Steamboats go down the waters of the Amazon system from Bolivia to Para on the Atlantic. Ships also go from Bolivia by way of the Parana system to Buenos Aires. The total length of navigable rivers in Bolivia is 12,000 miles. The capital and chief city is La Paz (Fig. 347). Potosi is the center of the silver-mining district.

331. Ecuador.—Ecuador is so named because it is on the Equator. It is much like Peru in its surface and products, but differs from Peru in having a well-watered coastal lowland (Sec. 314). Both the eastern and the western mountain slopes are forest covered to a height of 5000 feet.

The principal port is Guayaquil. The capital, Quito (Fig. 348), is far up among the mountains. A railway from Guayaquil to Quito was finished in 1908. Ecuador has deposits of copper, iron, lead, and coal. Cacao, from which chocolate is made, ivory nuts, and

coffee are the chief agricultural products. Many Panama hats are woven in Ecuador and in northern Peru. About Quito are Cotopaxi and other lofty volcanic peaks. Earthquakes are common, and many houses are built low, of timbers and bamboo laths, so that they may not be shaken down.

Review.—1. Describe the climate of northern Chile; of southern Chile. 2. What is the Central Valley? 3. What is the greatest mineral product of Chile? 4. Name and locate the capital; the chief seaport.

5. What three regions has Peru? 6. What are the chief ports of Peru? 7. Give an account of quinine. 8. Give two important facts about Arequipa.

9. What is the most important mineral product of Bolivia? 10. Describe the surface of Bolivia. 11. By what routes does Bolivia communicate with the outside world?

12. How does the coastal part of Ecuador differ from that of Peru? 13. Name and locate the capital and the chief port of Ecuador. 14. What is the leading product of Ecuador?

COUNTRIES OF THE NORTH COAST

332. Colombia.—Colombia borders the Pacific Ocean and the Caribbean Sea, and its chief port is Barranquilla, on the north shore, at the mouth of the Magdalena River. There are three ranges of the Andes in western



Fig. 348. Market place, Quito, Ecuador

Colombia, and the Magdalena and Cauca rivers flow northward in the intervening valleys. The eastern part of Colombia drains into the Orinoco and Amazon rivers, and belongs largely to the llanos, which continue eastward over much of Venezuela.

In the valleys and coastal lowlands many tropical products are raised, and on the higher grounds the fruits and grains of temperate regions flourish. The country has abundant mineral deposits, including gold and platinum.

Bogota is the largest city and the capital of Colombia. It is far in the interior and is more than 8000 feet above the level of the sea. It has street railroads and electric lights similar to those of a modern American city.

333. Venezuela.—Most of Venezuela is in the basin of the Orinoco River. There are low mountains in the south, and a range of the Andes in the northwest. Half the country is covered with forest. The products are similar to those of Colombia. The chief exports are coffee, cacao, and hides.

Caracas is the capital of Venezuela (Fig. 349), and although but a few miles from the Caribbean Sea, it is several thousand feet above the sea level. A narrow-gauge railroad leads down to La Guaira, the principal seaport. Maracaibo, on the lake or lagoon of the same name, also has large foreign commerce.

334. Guiana.—The Guianas belong to Great Britain, Holland, and France. They are undeveloped countries with a hot, moist climate and much forest. Sugar and molasses, made from sugar cane, are the chief exports. Gold is mined, especially in French Guiana. Georgetown, Paramaribo, and Cayenne are the three capitals.

ISLANDS

335. South American Islands.—The Falkland Islands are a wind-swept group 300 miles east of the Strait of Magellan. They are a crown colony of Great Britain. Some sheep are raised, but the chief use of the colony is as a coaling station for British ships.



Fig. 349. Capitol and National University, Caracas, Venezuela

Tierra del Fuego is an archipelago, whose whole area is about equal to that of the states of New Hampshire and Vermont. There are forests and grasslands, but the land has only a few thousand people. Part of it belongs to Argentina, and part to Chile.

Fringing the coast of southern Chile are many islands, and a few hundred miles to the west is Juan Fernandez, where an English sailor was cast away in the early days and had adventures which suggested the story of "Robinson Crusoe." The Colon Archipelago (Galapagos Islands) is on the Equator seven hundred miles west of Ecuador, to which country it belongs.

Review.—1. Describe the drainage of Colombia. 2. Name and locate the chief seaport. 3. What is the capital and how is it situated?

4. Name and locate the capital and two seaports of Venezuela. 5. What is the chief export?

6. Give the location and other facts concerning the Falkland Islands; Tierra del Fuego; the Colon Archipelago; Juan Fernandez. 7. Compare North and South America as regards islands.

8. Make from memory a map of South America, showing the countries, the chief mountains, the three chief river systems, and twelve or more important cities.

POSSESSIONS



hemispheres

Cape of Good Hope, Cape Horn, and the island of Tasmania. 10. Compare the latitudes of Bering Sea, the British Isles, and southern Greenland.

11. Compare the longitudes of Cape Race and Cape St. Roque; of Panama and Hudson Bay; of Panama and Cape Mendocino.

12. What seas in the Eastern Hemisphere are crossed by the Tropic of Cancer? What gulf in the Western Hemisphere is crossed by the same line? 13. What island groups of the Pacific Ocean lie near the Tropic of Capricorn? What group is near the Tropic of Cancer?




Fig. 351. Nearly half of this hemisphere is land

Fig. 352. Most of this hemisphere is water

OCEANS, POLAR REGIONS, AND WORLD WINDS

THE OCEAN

336. Oceans and Seas.—Nearly three fourths of the surface of the globe is covered with salt water (Figs. 351, 352). This great body of water, which surrounds the lands, is called *the ocean*, or *the sea*, but five of its larger parts are called *oceans*, and many smaller bodies of salt water, which are connected with the ocean but are more or less landlocked, are called *seas*, *gulfs*, or *bays*. The Mediterranean Sea, Red Sea, and Caribbean Sea, the Persian Gulf, Gulf of Mexico, and Gulf of California, and Hudson Bay and Bay of Bengal are examples.

337. Ocean Basins.—Because the bottom of the ocean is lower than the lands, we often speak of the *ocean basins*. We must, however, remember that the deepest waters extend downward only a few miles, and that oceans are thousands of miles wide. If we could see the earth without any water on its

surface, we should discover that the ocean basins are relatively slight depressions.

Around the continents, in most places, the water is shallow, that is, not more than a few hundred feet deep, for many miles from the coast. The shallow sea bottom bordering a continent is called a *continental shelf*. It is shown in the lightest blue tint, almost white, bounded by the 100-fathom (= 600-foot) line in Figures 326, 373, and other physical maps. If the continent and the shelf were to rise six hundred feet, this shelf would become land and be known as a coastal plain. At the outer edge of the shelf the sea bottom slopes down rather steeply until the water is several thousand feet deep, and a few places show depths of five or six miles. The deepest places of the sea measure about the same as the highest mountains, so that the total difference in elevation between the lowest ocean depth and the highest mountain top is nearly twelve miles.

338. Sea Bottoms.—The land surface and the sea bottom are very different in appearance. The land is made rough by the uplifting of mountains, and by the work of rivers, glaciers, and weathering. The ocean bottom, especially within a few hundred miles of the coast, is always receiving a cover of mud and sand that are brought from the land. The smallest of the mud particles are usually carried long distances from the continental border before they finally settle to the sea floor. Myriads of very small shelled animals, as well as fishes and larger sea creatures, live in the ocean; when they die, their remains dissolve and cover the deep sea bottom with fine oozy mud. As a result, the sea floor is mainly a plain, much wider and smoother than any prairie. There are places, however, where ashes and lava have accumulated around volcanic openings in the sea bottom, and some of these accumulations reach the surface, or even extend far above it as mountainous islands.

Many ships have been sent out for the study of the ocean waters, the living things in these waters, and the deposits on the bottom. Soundings of the deepest seas are made, and dredges or scoops bring up the mud and the animals of the sea floor. Many ships have also been sent to survey and map coasts and islands, and record the soundings for the benefit of navigators. The United States government publishes hundreds of maps of various parts of the ocean, especially along its own shores.

339. Coast Islands.—In the ocean are hun-

dreds of thousands of islands. Some are mere islets of rock, some have a few square miles of soil, and some are large; for example, Madagascar, Cuba, and Newfoundland. Some of the islands along the coast of the continents are high and rocky and have been cut away from the mainland or formed by the sinking of a coast land of hills and valleys until the sea water filled the valleys and left the hills as islands. Other coast islands are low and sandy and have been formed in shallow water by waves and winds throwing up mud and sand.

340. Volcanic Islands.—In the open ocean many of the high islands, such as, the Fiji and Hawaiian Islands (Fig. 353), have been made by volcanic eruptions. These began at the bottom of the ocean and have piled the materials higher and higher until in some cases they rise thousands of feet above sea level.

341. Coral Islands.—Other islands in the open sea, and in some instances not far from shore, are low and flat, and have been formed by the growth of animals called corals. The living animals have the appearance of flowers and stand fixed in their place. They live in shallow water, and have hard skeletons. The corals that are living, and the skeletons of those that are dead, make up a *coral reef* (Fig. 578). The living corals make

the surface of the reef, and below is coral rock, formed mainly from the hard parts of the dead corals.

342. Island Peoples.—Many of the islands are inhabited, the people having come to them from neighboring continents or other islands. The natives of



Fig. 353. A volcanic island, in the Hawaiian group

some of the islands of the Pacific Ocean are descended from people who came from Asia or the East Indies. Their ancestors, at an unknown period of the past, made their way first from the mainland to the neighboring islands and then from island to island in such boats as they were able to make (Fig. 354).



Fig. 354. Boat made by natives of New Guinea

343. The Water of the Ocean.—The rocks in many regions contain salt. The water in the ground is constantly dissolving some of the salt, which is carried by the rivers to the ocean. When water is evaporated from the surface of the ocean, the salt and other dissolved substances are left behind, and ocean water is salt. On some seashores where the climate is dry and hot and the water shallow, salt is formed by the evaporation of the ocean water. Near the mouths of rivers ocean water is partly fresh, and is called *brackish*.

There is much limy material in sea water, due to the dissolving of limestone by ground water. Many other minerals are found in sea water, including even a little gold.

In the tropical regions the surface waters are warm, and they grow cooler toward the Poles. The sea about the North Pole is covered with floe ice formed by the freezing of ocean water. This is from six to twenty feet thick, and masses of it sometimes break away from the southern edge of the ice fields and float hundreds of miles southward in the Atlantic Ocean before melting. Such ice forms also about the Antarctic Continent. In addition, many icebergs, broken from glaciers, are found in the polar seas.

At great depths the water is cold, even near the Equator. This is because cold

water is heavier than warm water, and so the cold water of the polar regions pushes slowly along the ocean floor underneath the warmer waters of the temperate and tropical seas. Self-registering thermometers have been let down to great depths, and have shown that the temperatures near the bottom are often but

a few degrees above the freezing point.

344. Life in the Ocean.—The ocean is so great, covering three fourths of the earth's surface, that it holds a vast amount of life.

Many food fishes and the common shelled animals, such as oysters and clams, live in shallow water or in the mud near the shore. Some animals, like the corals, thrive only in a beating surf. Barnacles and seaweeds cling to rocks, where they are in the water at high tide and in the air at low tide.

Other forms are found far out from land, swimming at or near the surface of the sea. Still other creatures live in the depths of the ocean, where it is dark and cold, where there is no wave action, no change from day to night, and no change of seasons.

WAVES, CURRENTS, AND TIDES

345. Waves.—Most waves are caused by winds, which stir the surface of the water. Even violent winds do not move the water more than a few hundred feet below the surface. A wave is a moving ridge of water. The top of the wave is called the crest. The depression between two waves is the trough. In a small pond waves may be a few inches high. On a lake a mile or two wide they may be high enough to engulf a small boat. On the ocean, in violent storms,

waves may be thirty or forty feet high, and may make it necessary for large ships to keep their course across the waves in order to pass through the storm safely. Persons on deck, and even parts of the rigging of ships, are often carried away by storm waves.

It is not the water itself, but the wave shape of the water that moves so fast along the surface. Drop a chip on the surface of a pond that is rippled by a strong breeze. The chip will move back and forth and go slowly over the pond, while the wave moves swiftly.

346. Surf.—We often see waves close to shore when farther out the water is still or has a gentle swell. A thousand miles out to sea there may be a heavy storm and big waves. Some of the wave motion passes through the more quiet waters outside the storm. Near the shore the water is shallow, and the quiet movement, or swell, makes a wave roll up, turn over, and break at the crest. Therefore we speak of *breakers* or *rollers*. This narrow belt of waves near the shore we call the *surf* (Fig. 355). Where the beach is low and slanting, the water of the breaking waves runs up the beach and back again continually. The water that runs back along the bottom in a strong current under the waves is called the *undertow*.

347. Work of Waves.—The surf waves cast up sand and pebbles and make a gently sloping *beach*. On the borders and around the head of a bay, beaches are usually smooth and beautifully curved. The surf acts like a mill upon the pebbles and sand grains of the

bottom. It stirs them, rubs them against one another, and thus grinds them to powder. Storm waves cast these materials up and build ridges at some distance inland from the usual shore line.

Where the waves beat against a steep coast, they wear away the rocks and form a cliff, which may be hundreds of feet high, because

in time they may cut far back into the side of the hill or mountain (Fig. 372). Where the waves beat harder at some places than at others, or where the rocks at one point are soft or full of joints, the waves may dig caverns for some distance into the face of the cliff.

Where the sea is shallow for a long way from the shore, a reef or beach may be built at some distance from the land. The waves gather up mud and pebbles which they drop when they break. The new land thus formed is




Fig. 355. Surf

called a *barrier beach*, and the narrow body of shallow water that separates it from the mainland is called a *lagoon*. On some shores, such as that of New Jersey, the barrier beaches extend many miles.

Sailors do not fear great waves on the open sea, where they have sea room, but they are in danger when the ship is so near the shore that it may be driven aground or dashed against the rocks by heavy surf. Great storm waves may rush in upon a city that stands on a low shore and cause much damage,—as at Galveston in 1900, before the city built its sea wall. Earthquakes sometimes start waves which destroy coast towns and even carry ships several miles inland.




Fig. 356. Ocean currents

348. North Atlantic Ocean Currents. — Along the Equator in the Atlantic Ocean the waters move slowly westward, from west Africa to South America. Along the coast of Brazil they divide, and the northern parts flow among the West Indies and through the Caribbean Sea and the Gulf of Mexico. From the Gulf of Mexico a strong current flows at the rate of four or five miles an hour through the Florida Strait, and bears northeast past the east coast of the United States. This part of the moving water is known as the *Gulf Stream*. It is about 75 miles wide and it is warmer than the water on either side because it comes from the tropics. As the Gulf Stream moves out toward the middle Atlantic it loses its velocity, broadens out, and becomes a slow *drift*. These drifting waters reach western Europe, and some of them go toward Norway, while some go southward past the Iberian Peninsula and join the west-moving equatorial current. Thus we have a complete circuit known as the north Atlan-

tic eddy (Fig. 356), whose waters move from left to right, like the hands of a watch.

There is also an Arctic current whose cold waters come past Greenland, Labrador, and Newfoundland, as far south as New England. Icebergs from the Greenland coast float to the region of Newfoundland or farther south before they melt, and fogs are common in that part of the Atlantic where the warm, moist air of the Gulf Stream belt mingles with the colder air over the Arctic current.

These ocean currents help to make the difference in temperature between the eastern coast of America and the western coast of Europe in the same latitudes (Fig. 590).

349. South Atlantic Currents. — The waters that turn southward along the Brazilian coast swing back to the east and flow northward along the coast of Africa, making a south Atlantic eddy (Fig. 356). In this eddy the waters move from right to left, or counter to the hands of a watch. We thus have two great eddies in the Atlantic Ocean


350. Pacific Currents.—The Pacific Ocean has two eddies like those of the Atlantic. The western part of the north Pacific eddy is the Japan current. It moves eastward past Alaska, and southward along the western coast of North America. On the west coast of South America the waters move from the Antarctic

regions northward and are known as the Peruvian or Humboldt current.

351. The Study of Ocean Currents.—We cannot see the motion of an ocean current, and we learn most about such currents by studying the movements of floating objects. Sealed bottles are thrown out, containing a record of the latitude and longitude at which they are cast into the sea. Some bottles dropped in the western Atlantic have been found on the shores of Norway and Ireland, and others have gone around to the West Indies. Abandoned ships, or derelicts, have been sighted at different times, and it

is found that they also drift with the ocean currents.

352. Tides.—On the shores of the ocean, even when no winds are blowing, the water slowly rises and falls. Such movements are called *tides*, and they are due to the low, wide waves known as tidal waves. The two extremes are called high tide and low tide.



When the water is falling, we speak of the *ebbing* of the tide. The interval between two successive high tides is 12 hours and 26 minutes.

On a flat shore the ebbing of the tide leaves a broad beach uncovered, and people who wish to bathe may have to go out several rods to reach the water. If the shores are steep, the bottoms of the cliffs may be laid bare. These are frequently covered with barnacles and dark, dripping seaweed, while small pools among the rocks are full of shelled creatures.

Boats are often left high and dry and cannot go out until the tide comes in again. (Figs. 358, 359). Many harbors and the



Fig. 358. Low tide, Digby, Nova Scotia



Fig. 359. High tide at the same point, six hours later



channels that lead to them can float large ships only at high tide. For example, large ships must often wait in the Lower Bay at New York for high tide before they can come up to the docks, and must time their sailing by the state of the tides. Tide tables are published so that sailors can always know at what hours they will find deep water in any of the world's great harbors.

Where the shores of a bay or river mouth narrow, the waters of the rising tide are pushed together and roll in rapidly, making a noticeable *tidal current*. A current is also formed when the water of the bay or river mouth falls rapidly at the time of the ebb tide. In thus sweeping in and out, the tides are useful in cleansing the harbors, carrying away sewage and other filth, which if allowed to remain would pollute the waters, causing bad odors and disease.

In some bays, as the Bay of Fundy on the Atlantic coast of Canada, and the Bristol Channel on the west coast of Great Britain, the shores converge for a long distance and the tides rise and fall fifty feet or more. Where the tidal range is so great, wide flats of mud may be exposed at ebb tide. Landing stages or floating piers are sometimes built in harbors. These rise and fall with the tide and are joined to the shore by inclined bridges.

Some rivers are entered by a swift-running tidal wave. It is like a heavy surf, or moving wall of water, and is called a *bore*. Examples are found in the lower Amazon and in the Seine in France.

Tides are very small in seas with narrow entrances, like the Mediterranean, and in the Great Lakes.

353. Cause of Tides.—The times of rising and falling tide correspond to positions of the moon, the nearest of the heavenly bodies (Sec. 574). The rising of the water, or the tidal wave, is due to the pull or attraction of the moon. As the earth turns on its axis the wave goes around the world. If the

surface were all water, a low, unseen wave, a few feet high and thousands of miles wide, would go around the globe. But because the lands interrupt, the tidal wave pushes up on the shores. Sometimes the moon and the sun are in line with the earth and pull together, and then the tides are a little higher than usual. It is not correct to use the words tidal wave for a large wave due to an earthquake or a storm.


USES OF THE OCEAN

354. Influence on Temperature and Rain-fall.—It is not a waste for the earth to have so much water instead of forests and fertile fields. We should remember that the oceans receive and hold the heat of the sun, and the currents move far north and south of the Equator. The winters in the temperate and polar regions are much warmer than they would be if the oceans did not stretch so far north and south. It is the ocean also that furnishes the water for rains and snows. Without the ocean, the earth would be a desert, a part of it hot and the rest of it cold, and animals and plants could not live.

355. Food Supply.—The ocean also furnishes food. For thousands of years the peoples dwelling by the sea have depended much on fish, and by the help of railroads and canning factories every one, however far inland, can now have sea food.

356. Highway.—The ocean is the greatest of highways. A nation that lives by the sea is neighbor to all other nations that live on the ocean border. There are no expenses for keeping the ocean highways in order. When docks and ships are built, men and goods can be carried around the world. Figure 360 shows the most important steamship routes.

357. History of Navigation.—In ancient times men learned to row or sail their small boats near the shores. At first they went



from point to point along the shores, or made their way from island to island. Gradually they built larger boats and ventured across large bays and out into the open ocean. It was thus that all the lands about the Mediterranean Sea were explored, and the gulfs and headlands of western and northern Europe became known. In modern times Columbus and others crossed the Atlantic, and the expedition of which Magellan was the leader went around the world.

Until about a hundred years ago ships were moved by sails, and it often took several weeks to cross the Atlantic. Now steamships are in use which travel at the rate of 20 to 25 miles an hour, and go from New York to Liverpool or Rotterdam in from five to seven days. Such are the large and fine ships built for passenger service. The larger of these are 700 to 900 feet in length and can carry several thousand passengers.

Slower ships carry freight and passengers across the Atlantic in about ten days, and the passage from San Francisco, Seattle, or Vancouver, to Japan, China, or the Philippine Islands, takes about three weeks. Besides the steamship *lines*, whose vessels make regular trips joining the great seaports and countries of the world, there are a vast number of merchant ships known as *tramps*, which go wherever they can find a cargo.

By means of the compass, by observations on the sun, and in other ways the captain of a modern vessel can tell just where his ship is (Fig. 362). If the ship is not far from shore, lighthouses may serve as guides. By wireless telegraph mariners not only communicate with each other but may call radio stations on the shore, which observe directions and quickly compute a ship's exact position. This method is specially important during fogs.




Fig. 362. Taking observations at sea

THE POLAR REGIONS

358. Arctic Ocean.—The Arctic Ocean covers the region of the North Pole and stretches southward to the shores of North America, Europe, and Asia. It is joined to the Pacific Ocean by Bering Strait, 36 miles wide, and to the Atlantic Ocean by the wide sea in which Iceland lies. East of


Iceland the warmer waters drift to the north of Europe and keep that part of the sea freer of ice than the regions north of our own continent. West of Iceland and west of Greenland, the Arctic waters flow southward and form the cold Labrador current.

359. Arctic Travel.—Many daring voyages and sledge journeys across frozen lands and ice floes have been made during the past hundred years in order to learn about these northern regions. Many men and ships have been lost, but others have dared to keep up the search. Explorers have been compelled at times to travel and camp in temperatures ranging from 50° to 70° below zero. They travel on land or ice, carrying their camping outfit and food on sledges drawn by dogs, and they sleep in bags made of skins. They usually have the help of the native Eskimos, from whom they also obtain the dogs.

The floe ice or ice pack crumples into rough ridges, or breaks into fields with lanes or "leads" of open water between, so that sledging over it is very dangerous.

The map (Fig. 361) shows that much of the Arctic region is still unexplored.

360. Recent Arctic Explorers.—In 1895 Nansen, a Norwegian explorer, took his ship, the *Fram*, far into the ice pack north of Asia, and then went by sledge to latitude $86^{\circ} 14'$. In 1900 part of the expedition under the Duke of Abruzzi, an Italian explorer, went to $86^{\circ} 33'$. On April 6, 1909, Peary, an






Photo Drygalski

Fig. 364. Antarctic sea border, showing vast tabular icebergs and the edge of the ice-covered continent

officer of the United States navy, reached the North Pole and raised the American flag there. He had explored northern Greenland and the polar ice for many years, and at last gained the goal for which so many explorers had long striven.

361. Antarctic Regions.—The Antarctic region is very different from the far north. There are no land masses to separate the Antarctic Ocean from the Atlantic, Pacific, and Indian oceans, but the name is given to the waters that stretch around the world near the Antarctic Circle. In these waters there are many icebergs from the great glaciers on Antarctic lands, for the south polar region is a continent instead of a sea. It is not known how far it is a true continent, nor to what extent the lands consist of large islands, but it is thought that the continent may be as large as Europe or larger. Explorers have sailed hundreds of miles along the edge of a single ice sheet where it pushes into the sea. In some places there are high mountains and active volcanoes. Mt. Erebus is an active volcano, and is more than 13,000 feet in altitude.

362. Recent Antarctic Explorations.—In 1909 a British exploring party under Sir Ernest Shackleton reached a point 111 miles from the South Pole. The Pole itself was finally reached by a Norwegian explorer named Roald Amundsen, on December 16, 1911. A few weeks later it was also reached

by another party under the leadership of Captain Scott of the British navy. On the return trip Scott and several of his men died of starvation. Records of their last days have been recovered, and the story which they tell is one of fearful hardship and wonderful bravery.

The elevation at the South Pole is about 10,000 feet above sea level. At the North Pole there is an ice-covered sea, and at the South Pole an ice-covered land.

Review.—1. How does the ocean bottom differ from the surface of the lands? 2. What is a continental shelf? 3. What is the origin of many of the high islands of the ocean? 4. What is a coral reef? 5. Why is ocean water salty? 6. How do the surface and bottom waters near the Equator differ in temperature?


7. Why are breakers often seen near the shore when the waters farther out are smooth? 8. What are the results of wave action on high coast lands? 9. What is a barrier beach?

10. Describe the currents in the north Atlantic Ocean; in the south Atlantic Ocean. 11. How is the direction of ocean currents determined? 12. Where is the Peruvian current?

13. What is the ebbing of the tide? 14. Name localities where the tides are high. 15. What causes tides?

16. Give some of the uses of the ocean. 17. What length of time do modern ships require for crossing the Atlantic Ocean?

18. Give the name of the explorer who reached the North Pole, and the year in which he discovered it. 19. Name the discoverer of the South Pole. 20. How does the north polar region differ from the south polar region?



WORLD WINDS

363. Westerly Winds of the North Temperate Region.—In studying sections 363–367 consult Figures 33, 365, 366, and 367. We have already learned some facts about the westerly winds in our study of North America and the United States. From the North Pacific Ocean they reach southern Alaska, Canada, and the United States. With them comes moisture which falls as rain and snow along the coast and on the windward side of the western mountains. But after crossing the mountains the winds descend to the lower lands farther east as drying winds, with the result that the plains and plateaus just east of the high mountain ranges are arid.

Along with these winds, on their way east, whirling storms, or cyclones, are produced, and we have a succession of warm weather with rain or snow, followed by cool and clear weather. The winds move on across the north Atlantic and bring to western Europe warm air and much rain, as in the case of the Pacific Ocean and western North America.

The westerly winds pass on across Germany and Russia, but they carry less heat and moisture to these countries, and still less to Asia. Eastern Europe and western and central Asia, therefore, have a continental climate, like that of the upper Mississippi basin, marked by extremes of heat and cold.

The prevailing westerly winds of the north temperate region do not blow exactly from the west, but usually from a direction south of west. An American making a voyage to Europe is much less likely to meet “head winds” than when returning. The pupils should make and study a record showing the direction of the wind twice a day for several weeks.

364. Westerly Winds of the South Temperate Region.—As the westerlies of the Northern Hemisphere do not blow directly

from the west but usually from directions south of west, so those of the Southern Hemisphere commonly blow from directions north of west. These winds of the south temperate region are much more steady than those in the northern latitudes, because they are much less disturbed by the influence of lands and high mountains. South America is the only continent that reaches far enough south to be across their path, and the southern part of this continent is narrow. The greater part of the zone of the westerlies is south of Africa and Australia, and hence they blow freely around the world. They are also much less interrupted by whirling storms or cyclones than the westerlies of the north temperate belt.

The strength and steadiness of these westerly winds is of importance to the masters of sailing vessels, who call the region the “roaring forties” and the winds the “brave west winds.” They dread to beat their way around Cape Horn to the west, because the winds are against them, the air is raw, and the sea is rough. A sailing vessel from the north Atlantic countries, bound for Australia or the south Pacific islands, will go eastward past the Cape of Good Hope and follow the westerlies to its destination. Then it will continue east with the favorable wind, pass Cape Horn, and return through the Atlantic Ocean to the place from which it started.

The effect of the prevailing westerly winds in giving rain to southern Chile and in making southern Argentina dry is described in section 314.

365. Northeast Trade Winds.—The northeast trade winds blow from the northeast across the West Indies, Mexico, Central America, and the northern part of South America (Sec. 314). Blowing from the ocean, they bring a heavy rainfall to the eastern highlands and slopes of these regions.

They continue across the Pacific Ocean and bring ample rains to the northeastern




Fig. 367. Mean annual rainfall of the world

slopes of the Hawaiian Islands. Likewise they bring rains to the Philippine Islands and to parts of southeastern Asia. India is in the trade-wind belt, but has special winds called *monsoons* which will be explained in section 373.

The northeast trades also cross southwestern Asia and north Africa. Here they blow for such long distances over the land that they do not receive much moisture. Since they blow from northeast to southwest, they are always passing from a cooler into a warmer region. As air grows warmer, more moisture can be evaporated into it; hence winds that are warmed are ready to receive moisture instead of giving it up as rain. The northeast trades passing over Arabia, Egypt, and the Sahara region are warmed, and are drying winds, and therefore these lands are deserts.

Sailors take advantage of the trades as they

do of the westerlies. It was easy for Columbus, in spite of his fear of unknown seas, to sail from a Spanish port to the West Indies because he was in the course of the northeast trade winds. It was also easy for other Spanish or Portuguese navigators to sail to the northern and eastern shores of South America.

366. Southeast Trade Winds.—South of the Equator the trade winds of the Southern Hemisphere blow from the southeast (Fig. 33). Crossing the south Atlantic, they blow across the widest part of South America. As the moist air is pushed to greater altitudes in crossing the higher lands, these winds bring a heavy rainfall to the eastern slopes of the Brazilian Highlands, and to the east slopes of the Andes. West of the Andes, however, in the "rain shadow" of the mountains, are the desert parts of Chile and Peru (Secs. 314, 328, 329).

Crossing the Pacific Ocean, the southeast trades reach eastern Australia. The principal mountains of this continent are in the east (Fig. 566), and as the air rises in crossing them it is cooled, and there is abundant rain on the eastern slopes. West of the mountains the rainfall is much less, so that the central and western parts of Australia are mainly desert.

In like manner these winds affect a large part of southern Africa. The well-watered regions are in the east, while the dry regions are on the western or Atlantic side of the continent.

367. The Belt of Equatorial Calms.—

Between the two trade-wind belts is a region of *equatorial calms*, or *doldrums*, in which there are no prevailing winds. This belt is dreaded by the masters and crews of sailing vessels because they often have to wait many days before there is wind enough to take them across it. It is also a region of frequent and heavy rains. The mornings are usually clear, but as the hot part of the day comes on the air is heated, expands, and in the upper atmosphere spreads out toward the polar regions. At the surface the cooler, heavier air of the trade winds pushes in from both sides and crowds under the heated air. As the heated and lighter air, containing much water vapor, is pushed upward, it is cooled, and the moisture condenses and falls as rain. This is similar to what happens in a thunderstorm in midsummer in the temperate latitudes.

A ship going from St. Johns, in Newfoundland, to Punta Arenas, in southern South America, would cross first the belt of the westerly winds of the Northern Hemisphere; second, the region of northeast trades; third, the belt of equatorial calms; fourth, the region of the southeast trades; and fifth, the belt of westerlies of the Southern Hemisphere (Fig. 33).

368. Shifting of the Wind and Calm Belts.

—In our summer in the Northern Hemisphere

the sun at midday is high, and as far north as the Tropic of Cancer is directly overhead at some time during the summer. In our winter the sun at midday is low; the vertical rays are south of the Equator, and near midwinter reach as far south as the Tropic of Capricorn. Thus the direct rays of the sun shift back and forth across the Equator, and the belt of greatest heat, which is the belt of equatorial calms or doldrums, moves northward and southward. The great wind belts to the north and south of it shift in the same way, through several degrees of latitude, with each year's change of seasons (Figs. 365, 366).

369. Wet and Dry Seasons.—Since rain is plentiful in the doldrum belt, we can understand why many warm countries have a dry and a wet season each year. When the belt of calms, in shifting its position to the north or south, is over one of these warm countries, that country has rains. When the belt of calms has passed to the north or south, the country is crossed by the trade winds and becomes comparatively dry. Near the Equator are some regions that are completely crossed by the shifting wet belt twice a year, and twice entirely left behind by it. Such regions have two wet and two dry periods each year.

370. World Winds and the Ocean Currents.—The waters of the equatorial currents (Secs. 348–350) move westward and thus have a direction much like that of the trade winds. The waters in the temperate belt of the north Atlantic move eastward, as do the prevailing westerly winds. In like manner the waters of the south Atlantic eddy move eastward in the track of the westerlies of the Southern Hemisphere. In the Pacific Ocean the east and west winds and currents correspond in the same way.

If there were no continents to block the way, these currents of water would flow around the earth. But they strike the lands and are turned from their course. For ex-




Fig. 368. Winds and rainfall of southern Asia in July




Fig. 369. Winds and rainfall of southern Asia in January

ample, the equatorial current of the Atlantic divides, in the western part of the ocean, and some water goes north and some south until it is caught in the east-moving current. The east-moving currents in their turn strike the coasts of Europe and Africa, and thus complete the two great eddies of the Atlantic Ocean. In this way the world winds and the continents combine to direct these slow but great movements of the ocean waters.

CAUSES OF WINDS

371. Movements in Small Bodies of Air.—When a door is opened between a warm room and a cold room, the heavier air of the cold room pushes in beneath the lighter air of the warm room, and there is what we call a draft. This is really a small wind. When a bonfire is built, the air above it, with the particles of smoke and the gases of the flame, is heated, expands, and is pushed upward. The air rises not because it has no weight, but because the cooler air is heavier and pushes in below the heated air. This movement is a light wind. The same thing occurs when a fire is built in a stove, or when a lamp is lighted in a room.

372. Shore Winds.—On the shores of a lake or ocean, breezes are formed in a similar way. In the daytime, under a hot sun, the land absorbs heat rapidly and becomes warmer

than the water, and the air over the land is heated and becomes lighter. This light, warm air is lifted up by cooler and heavier air that moves in from the water as a lake or sea breeze. At night the land cools more than the water, and the heavier air from the land spreads out under the warmer and lighter air that is over the water; this movement is a land breeze.

373. Monsoons.—In the summer the land of India and other parts of southern Asia is very much heated. The air expands and flows outward in the upper atmosphere so that the air that remains presses less heavily on the surface, and the cooler, heavier air from the Indian Ocean pushes in and creates strong winds blowing from the ocean over the land. A great amount of moisture moves inland with them and falls as rain, making a part of India the wettest region in the world. Along the lower Ganges, several hundred inches of water fall each year, and in the region of heaviest rainfall it amounts to 50 or 60 feet a year.

In the winter the land is cooler than the ocean, and the winds are then reversed, blowing southward and giving the country its dry season.

These seasonal winds, blowing from one direction in summer and from the opposite direction in winter, are called *monsoon winds*, or simply *monsoons*.

374. World Winds.—Since the earth's surface is warmer in the equatorial regions than it is in the temperate and polar regions, the air is expanded and its upper parts flow off to the north and south towards the poles. At the same time the cooler air at the surface of the earth on the north and south of the equatorial calm belt moves in and forces the warm air to higher levels. This is the cause of the trade winds.

These winds, however, do not blow directly toward the Equator from north and south, as we should expect, but they blow obliquely toward the Equator from the northeast and southeast. This turning of the trade winds to the westward is due to the rotation of the earth on its axis.

If the air should continue to move toward the Equator without any return currents, all the air would soon be piled up in one belt around the globe. But the air that moves upward in the belt of calms turns to the north and south and flows back over the trade winds. These upper currents are the *anti-trade winds* (Fig. 370). They are known to be real winds because they are felt on some high mountains that reach above the level of the trade winds. Sometimes also high clouds

drifting along with these winds may be seen moving in a direction opposite to that of the trades.

When the air of the anti-trades reaches the north and south limits of the trades, it descends to the earth in calm belts, known as the *horse latitudes* (Figs. 33 and 370). These lie between 30° and 35° north latitude and between 30° and 35° south latitude. Some of the descending air supplies the trade winds and goes back toward the Equator; some of it moves to the northeast in the Northern Hemisphere and to the southeast in the Southern Hemisphere, and forms, in both Temperate Zones, the prevailing westerly winds. While the trade winds turn toward the west, the winds of the Temperate Zones turn aside toward the east on account of the rotation of the earth.

Thus the great winds keep up a circulation of the atmosphere between low and high latitudes and between the lands and the oceans. In this way both heat and moisture are widely distributed over the surface of the earth, and countries are made useful to man that otherwise could provide little to meet his needs.

Review.—1. What regions of much rain are in the track of the westerly winds of the Northern Hemisphere? 2. Indicate the track of the westerly winds and their cyclonic storms in this hemisphere (Sec. 363 and Fig. 33). 3. What name is given by sailors to the westerlies of the Southern Hemisphere? 4. Why are these winds more steady than those of the Northern Hemisphere? 5. How do these winds affect the course of sailing vessels?

6. What great desert is in the track of the northeast trade winds? 7. What other dry regions occur in this belt? 8. Name the wet and dry regions in the track of the southeast trades.

9. Where is the belt of calms? Why is its rainfall large? 10. Why does the belt of calms shift in its position? 11. What is the effect upon the seasons in certain regions?

12. What are the causes of the great eddies in the oceans?

13. Give examples to explain the origin of winds. 14. Give an account of the anti-trade winds. 15. What are some of the advantages that come to man by means of the world winds?




Fig. 370. Winds on the earth's surface; also vertical section of the atmosphere, on a larger scale, showing circulation

EUROPE IN 1914, BEFORE THE WORLD WAR. For comparison with Fig. 371



TERRITORIAL CHANGES IN EUROPE, RESULTING FROM THE WORLD WAR

NEW COUNTRIES

Poland, about 150,000 square miles, population about 27,500,000.

Danzig, about 600 square miles, population 365,000.

Lithuania, about 25,000 square miles, population about 2,300,000.

Latvia, 24,000 square miles, population about 1,500,000.

Estonia, about 18,500 square miles, population 1,110,000.

Sarre Basin, about 750 square miles, population about 650,000.

Czechoslovakia, 54,700 square miles, population about 13,500,000.

Fiume, 10 square miles, population about 50,000.

Finland, 130,000 square miles, population about 3,400,000.

GAINS OF EXISTING COUNTRIES

France gained Alsace-Lorraine, about 5600 square miles with population about 1,800,000.

Belgium gained about 385 square miles with population about 150,000.

Denmark gained about 1530 square miles with population about 230,000.

Italy gained about 12,500 square miles with population about 1,900,000.

Serbia expanded into *Yugoslavia* by union with Montenegro and the southern provinces of Austria-Hungary, and slight gains from Bulgaria and perhaps Albania. Before the war Serbia and Montenegro together had an area of about 39,500 square miles and a population of about 5,000,000. Yugoslavia or Greater Serbia has about 95,000

square miles and about 12,000,000 population.

Roumania gained more than 60,000 square miles with population over 8,000,000. Both area and population were more than doubled.

Greece gained about 13,000 square miles with population about 1,400,000, in Europe, besides territory in Asia Minor; but as a result of war with Turkey in 1922 lost nearly all her gains except small areas south of Bulgaria.

LOSSES OF EXISTING COUNTRIES

Germany lost about 30,000 square miles with population about 6,000,000. It still has a much larger population than any other European country except Russia.

Austria lost about 84,000 square miles with population about 22,000,000. Austria now has about 30,700 square miles, population about 6,000,000.

Hungary lost about 89,000 square miles with population over 12,000,000. Hungary now has about 36,000 square miles, population about 7,800,000.

Bulgaria lost about 3000 square miles with population about 300,000.

Turkey lost most of the territory remaining to her in Europe, but in 1922 regained nearly all of it, so that her territory in Europe is now almost what it was in 1914.

Russia suffered severe losses. Before the war her area in Europe was about 2,000,000 square miles, population about 140,000,000. The losses aggregate about 300,000 square miles and (from cessions, war, and famine) 45,000,000 population, leaving about 1,700,000 square miles and 95,000,000 population for the present Russia in Europe.




Fig. 372. North Cape, as seen from the east

EUROPE

Map Study.—1. What is the latitude of North Cape? Of Gibraltar, at the southwest of Europe? 2. Find three important European cities that are near the parallel of 40° north latitude. 3. What states of our own country are crossed by this parallel?

4. What countries of Europe border the Black Sea? The Mediterranean Sea? 5. Locate the Baltic Sea; the North Sea; the Bay of Biscay; the White Sea. 6. Name the great peninsulas of Europe (Fig. 373). 7. Make a sketch map of the coast line of Europe, naming the principal seas and bays, and the important islands.

8. Describe the course of the Rhine, the Danube, the Rhone, and the Po. 9. Describe the course of three of the chief rivers of Russia.

10. What countries border upon Germany?

11. What countries have no seacoast?

12. On what waters would a ship travel in going from Odessa to Petrograd?

PHYSICAL FEATURES

375. Position.—Europe has many bays, seas, peninsulas, and islands along its coast. In proportion to its size it has a much longer coast line than any other continent. On the east, it has for the most part a land boundary, and we may think of Europe as

a great peninsula of the larger continent, for Asia is more than four times as large as Europe. Asia and Europe are sometimes considered to be parts of one continent, called Eurasia; but they have had such different histories that they are generally called two continents.

Europe joins Asia and is near Africa, and the journey between Europe and North America can now be made in about five days. No other continent is so near to all these other continents as Europe. Its central position among the continents has given its people great advantages in trading with other nations.

A very large part of its total area is in the temperate belt. The most northern point is North Cape (Fig. 372), a little more than 71° north of the Equator. Small parts of four countries, Norway, Sweden, Finland, and Russia, are north of the Arctic Circle. The most southern point is in Spain at about 36° north latitude. This corresponds in latitude with North Carolina, Tennessee, and northern Arizona. Although Europe has no land in the Torrid Zone, it is warmer, as a whole, than North America or Asia.



376. Mountains.—Europe has two mountain regions, with a lowland between them. This is also the general arrangement of highland and lowland in North America and in South America (Sec. 311). A chain of mountains runs the whole length of the Scandinavian Peninsula, where the highest peak is 8400 feet above the sea. There are also mountains in Scotland, in the north and west of England, in Wales, in Ireland, and in western France. All these uplands are old and much worn, and together make up the mountain lands of northwestern Europe.

The greatest mountains of Europe, however, are in the south. The chief ranges are the following: the Pyrenees, on the borders of France and Spain; the Alps, in France, Switzerland, Italy, Germany, and Austria (Fig. 374); and the Carpathians, in Czechoslovakia, Poland, and Roumania. South of these are other ranges, such as the Sierra Nevada in Spain, the Apennines in Italy, and many rugged uplands in the Balkan Peninsula.

Most of the mountains of southern Europe are much younger and higher than those of northwestern Europe. Since they were uplifted there has not been enough time for weathering, streams, glaciers, and the falling and sliding of rocks and earth to wear them down, as the mountains of Great Britain or Scandinavia have been worn.

The low ranges of the Ural Mountains form a part of the boundary between Europe and Asia.

377. Central Plain.—The central plain of Europe is narrow in the west and broad in the east. It includes parts of southern England, the northern part of France and Belgium, the Netherlands, Denmark, northern Germany, and nearly all of Russia. Around the British Islands the water is shallow, and the bottom is a part of the continental shelf (Sec. 337). If the continent and the shelf were to rise a few hundred feet, all this shelf, including the bottom of the North Sea and of the Baltic Sea, would become a part of the central plain.

South of the Ural Mountains and north of the Caspian Sea the plain of Europe joins with the Asiatic plain that extends through Siberia. There is therefore a continuous lowland reaching from the Atlantic Ocean across Europe and Asia to Bering Strait. In eastern Europe it stretches from the Black Sea to

the Arctic Ocean, and all of northern Asia belongs to it.

378. Drainage Slopes.—Europe has four drainage slopes (Fig. 377): (1) The Mediterranean slope includes all the lands that incline toward the Mediterranean and Black seas. (2) The Atlantic slope includes all lands whose rivers flow into the Atlantic Ocean, or into the adjoining North and Baltic seas. (3) The Arctic slope drains into the ocean of that name. (4) In the southeast is a part of the inland drainage basin of the Caspian Sea. This slope and most of the Arctic slope are in Russia.




Fig. 374. A glacier in the Alps

379. Glacial Invasion.—Like North America, Europe had a glacial period. The ice sheet covered all of Scandinavia and most of Great Britain. As the land then stood at a higher level than now, the ice covered the region of the North and Baltic seas, and swept over much of Germany and Russia (Fig. 375). Most of the Alpine country in Switzerland, France, Italy, Austria, and Germany was also covered with glaciers formed by heavy snows falling in the mountains. The soils were moved, the rocks worn, boulders scattered, and lakes formed, just as in those parts of North America over which the ice passed.

380. Existing Glaciers.—Small glaciers are still found in the Alps, in the Pyrenees, and in the Scandinavian Peninsula. Nearly all of them are in mountain valleys or on high mountain slopes, as in western America. Some, especially in Switzerland, have long been studied by men of science, and are visited by thousands of tourists every year.

381. Mediterranean Coast Line.—The entire coast line of Europe is very irregular. Seas penetrate far into the land, with the

result that the climate of western and southern Europe is oceanic rather than continental in character (Sec. 363). The seas also furnish highways for ocean ships, reaching the largest cities and the regions of densest population. The greatest of these seas is the Mediterranean, which borders Europe on the south, Africa on the north, and extends eastward to Palestine and Asia Minor. For much of the year it is swept by winds that blow across the lands of southern Asia and Europe into northern Africa. These are drying winds, and therefore there is much evaporation from the surface of the Mediterranean. As a result the Mediterranean waters are even more salt than those of the ocean.

Three arms of the Mediterranean extend northward. These are: (1) The Aegean Sea, between Asia Minor and the Balkan Peninsula; into the Aegean the Black Sea discharges through the Bosphorus, the Sea of Marmora, and the Dardanelles. (2) The Adriatic Sea, between the Balkan and Italian peninsulas; on its northern shores are the ports of Venice, Trieste, and Fiume. (3) The wide body of water between Italy and Spain; at its northern end is the Gulf of Genoa, and farther west is the great sea-port Marseille, near the mouth of the Rhone River.

Southern Europe has three great peninsulas: the Balkan, the Italian, and the Iberian. The Iberian Peninsula includes Spain and Portugal; it lies between the Mediterranean on the east and the Atlantic on the west. It is separated from Africa by the Strait of Gibraltar, which is only eight miles wide in its narrowest part.

There are also many islands in the Mediterranean and its tributary seas.



Fig. 375. Europe in the glacial period



Fig. 376. Iron Gate. In the background are forest-covered mountains

British Isles. They have a very uneven coast line, with deep bays, bold headlands, and many great seaports. Most of the rivers of the British Isles, and of the North and Baltic Sea regions, have deep tidal mouths, or *estuaries*. Hence seaports like Hamburg, Antwerp, and London may be a long distance inland, and sea trade is made easy. In the north, Scotland and Norway are mountainous, and the mountains are cut by steep-sided valleys, in which deep fiords extend from a few miles to as

382. Atlantic Coast Line.—The coast line in the west and north is as irregular as in the south. The Bay of Biscay is open to the Atlantic and has important seaports in northern Spain and western France. The English Channel connects the Atlantic Ocean and the North Sea and has a number of English and French ports on its shores. The North Sea has on its borders seven of the countries of Europe. It receives the Thames, the Rhine, and the Elbe, all rivers of great commercial importance. Through it sail the ships bound to or from the ports of London, Antwerp, Rotterdam, Bremen, Hamburg, and many other cities. The Baltic Sea is almost inclosed by lands. It receives many rivers, and since it is in a cool region, evaporation from its surface is small. Its brackish waters are only about one fourth as salt as those of the ocean. The least important of the great indentations is the White Sea, opening from the Arctic Ocean, but it has considerable commerce from northern Russia, through the port of Archangel.

The peninsulas of western Europe are Brittany, Denmark, and Scandinavia. The most important islands of the world are the

much as a hundred miles within the highlands. Thus there are many quiet and safe waters for fishing and for the ships of commerce.

383. Rivers.—Four large rivers have their principal sources in the Alps. The largest of these is the Danube, which rises north of the Alps, but is joined by many rivers which flow northward from these mountains. It crosses or borders seven countries on its way to the Black Sea. The river passes between the Transylvanian Alps and the Balkan Mountains by a wonderful gorge called the Iron Gate (Fig. 376).

The Rhine, which rises in the Alps, flows northward across western Germany and the Netherlands, and has built a large delta on the edge of the North Sea. The river has been deepened and improved and now furnishes the highway for an enormous river trade. There are many large cities on its banks.

The Rhone rises under the Rhone Glacier in Switzerland, flows a long distance between ranges of the Alps, passes through the Lake of Geneva, and enters France. It then flows southward to the Mediterranean.

Many large streams flow southward from the glaciers and snow fields of the Alps, into Italy. Most of them join the Po, which pours its waters into the Adriatic Sea.

The central parts of the Russian lowland are somewhat higher than the surrounding lands (Fig. 373), and from this region long rivers flow out in several directions. The Volga, the largest of these, is more than 2000 miles long and flows to the Caspian Sea. The Black Sea receives the Don and the Dnieper. The Pechora and Dvina flow northward into the Arctic Ocean, and the Duna flows westward into the Gulf of Riga, which is a part of the Baltic Sea (Fig. 377). Nearly all the rivers of this group are important highways of trade.

Many important rivers enter the Atlantic Ocean between the Gulf of Riga and Gibraltar. The Vistula flows for most of its course through Poland on its way to the Baltic. The Oder, the Elbe, and the Rhine all have the larger part of their courses in Germany. Find on the map (Fig. 371) the great seaports which have grown up near the mouths of these streams. Three of the

Atlantic rivers—the Seine, the Loire, and the Garonne—have their whole courses in France; and four smaller rivers are in Spain and Portugal.

The Thames, the Mersey, the Tyne, and the Humber are rivers of England, the mouths and lower courses of which have been improved to furnish harbors for ocean-going ships.

384. Fresh-water Navigation.—None of the European rivers, equal in size the principal rivers of the Western Hemisphere. Even the Volga and Danube are small in comparison with the Amazon or the Mississippi. Many of the small European rivers, however, bear thousands of ships and barges laden with freight, for they flow through countries of dense population, and where it has been necessary they have been fitted for navigation by dredging the mud or blasting out rocks to make the channels deeper. Their navigation has also been made easier by the building of dams and locks to form a series of deep-water levels along their courses.

Many of the European rivers have been connected by canals. Canal boats can go by river and canal from Bordeaux on the Bay of Biscay to the Mediterranean Sea; or from Havre, Antwerp, or Rotterdam to the mouth of the Rhone. A boat can go from the North Sea up the Rhine, cross a small section of southern Germany by canal, and go down the Danube to the Black Sea. In eastern Europe boats can be sent from Archangel or Petrograd to Astrakhan on the Caspian Sea; or from Riga on the Baltic to Odessa on the Black Sea (Fig. 371).

385. Climate of Central and Northern Europe.—For a continent that is so far north



Fig. 377. Drainage basins of Europe




Fig. 378. Isothermal map of Europe

(Sec. 375), Europe has a warm climate. Its western coasts are washed by the mild Atlantic waters, which drift northward and keep the northern shores of Europe comparatively free from ice (Sec. 348). The westerly winds bring the temperatures of the ocean far inland into central Europe (Fig. 378). They can do this, because there are no high mountains in western Europe, as there are in western North America, to break their course.

Although ample rains fall on the west coast of Europe, sufficient moisture is left in the air to furnish rain for crops in central Europe (Fig. 379). If Europe had a continuous range of high mountains in the west, corresponding to those in the continent of North America, there would be a desert on their leeward (eastern) side. As we go east in Europe the winters are colder and the summers are warmer. In Russia the climate is continental, with moderate rainfall and extremes of temperature as the seasons change. Some of the far northern plains of Russia are treeless, moss-covered tundras.

386. Climate of the Mediterranean Slope.—The Mediterranean Sea tempers the extremes of both winter and summer; with its tributary seas it reaches in among the lands and makes them warmer in winter and cooler in summer than they would otherwise be.

The high mountain barriers everywhere on the north shut out the cold north winds. As a result the Mediterranean shore of France called the Riviera is sought by thousands who wish to escape the severe northern winters. The same is true of the Italian Riviera east and west of Genoa, where palms and oranges grow in the latitude of southern Maine, Toronto, and the Yellowstone National Park. Compare the climate and the agricultural products of this Mediterranean region with those of the northern part of the United States, which is in the same latitude.

Owing to the shifting of the wind belts, the Mediterranean region in winter is in the track of the westerly winds, and plentiful rains fall. In summer, however, when the belt of calms and the wind belts move northward, the Mediterranean region is in the




Fig. 379. Average annual rainfall in Europe

track of the north-east trades. As we have already learned (Sec. 365), these winds in Europe and Africa are drying winds, because they blow mainly over the lands and because they pass from cooler to warmer lands. Therefore the summers are dry, and in many parts of Greece, Italy, and Spain irrigation is needed in raising crops, even though many of the lands are near the Mediterranean waters.




Fig. 380. Lands occupied by the different peoples of Europe

Review.—1. Why is the position of Europe favorable to commerce? 2. To what parts of the United States do the most southern parts of Europe correspond in latitude?

3. Give a brief description of the surface of Europe. 4. To what other continents is there a resemblance? 5. What ranges belong to the mountain belt of southern Europe?

6. Where on the coast are there large regions of shallow water? 7. What is the bottom of these regions of shallow water called?

8. What countries are partly or wholly included in the Atlantic slope of Europe?

9. What was the extent of the principal ice sheet of Europe? 10. Where are glaciers still found?

11. Describe the coast line of southern Europe, naming the main seas and peninsulas. 12. Describe the seas, gulfs, and peninsulas that lie between Great Britain and Russia. 13. What is a fiord? What countries of Europe have many fiords?

14. Name and describe the rivers which have their main sources in the Alps. 15. Describe the courses of the Volga, the Dnieper, the Dvina. 16. What important rivers have their courses mainly in Germany? 17. Name three rivers

in France. 18. Describe three courses along which it is possible to cross Europe by water.

19. Why has a region so far north as Europe so mild a climate? 20. Why is the rainfall of western Europe greater than that of central Europe? 21. Why have some parts of southern Europe dry summers?

HISTORY AND PEOPLE

387. Ancient History.—In very ancient times there were civilized nations in western Asia and Egypt. The Phœnician people lived at the eastern end of the Mediterranean Sea, and they sailed their trading ships everywhere in the Mediterranean region. The Grecian peninsula and islands are not far from Asia, and upon them grew up the first civilized city-states of Europe. The Greeks planted colonies in southern Italy, Sicily, and southern France.

Later the Roman people established a great empire. At first controlling only a small territory about the city of Rome, they grad-

ually extended their sway over all Italy, and then over all the countries that border the Mediterranean, in Europe, Asia, and Africa. They sent armies across the Alps and conquered much of Germany, and all of France, a region which was then known as Gaul. They conquered the Iberian Peninsula, and went across the English Channel and built roads, forts, and cities in Great Britain. They not only conquered the native tribes, but also taught them the ways of civilized people. In Gaul and the British Isles many of the natives were *Celts*, whose descendants make up a large part of the population of France, Scotland, Wales, and Ireland.

For several hundred years the Roman Empire ruled nearly all the lands that were then civilized. At length, however, the German and other tribes of the north grew strong and invaded and conquered Italy and other parts of the empire. The great Roman dominion was broken, and the countries of modern Europe slowly developed.

388. Latin Nations.—There are now more than twenty-five nations in Europe. With few exceptions each has a language of its own. The Italians, the French, the Spanish, and the Portuguese are called the *Latin* nations because they are descended partly from the Roman people, who spoke the Latin tongue. Their languages have all grown out of the Latin, and resemble one another as do members of the same family. The Roumanians likewise claim descent from the Romans, and are proud to bear their name.

389. Teutonic Nations.—The nations of central and northwestern Europe are related to one another in a similar way, and are sometimes called *Teutonic*. The Dutch and the German people still hold the lands where their early ancestors lived. Tribes known as Angles and Saxons went from the mainland to Great Britain, and from one tribe we have the name England, or Angleland, and from both names combined we have

the term Anglo-Saxon. The Danes, Swedes, and Norwegians also are Teutonic people. Some of their ancestors were known as Northmen and Vikings. They were daring sailors, pirates, and warriors. Many of them settled in Great Britain and northern France, in Iceland, and Greenland.

390. Slavic and Other Peoples.—Many of the people of eastern Europe, including Russia, Poland, Czechoslovakia, Yugoslavia, and Bulgaria, are called Slavs, or Slavonic people, from a leading tribe that once lived in that region. All of the peoples thus far named, including the Greeks, the Celts, the Latins, the Teutons, and the Slavs, belong to the white race. The Hungarians, the Finns, and a few other Europeans are of Mongolian origin; that is, they belong to the yellow race, and their ancestors came from Asia not many centuries ago.

391. Population.—Although a small continent, Europe has about 450,000,000 people,—more than any other continent except Asia (Fig. 381). They are descended from strong and active races, and have been successful in all lines of industry. As the climate is favorable and there is much fertile and well watered soil, a large part of the food needed by the enormous population is raised in their own fields. Many food fish, also,




Fig. 381. Distribution of population in Europe

are caught in the adjacent waters. In recent years, however, the growth of population has been favored by the development of manufacturing. This has led to the importation not only of food but also of a variety of raw materials. The bays and land-locked seas have favored the growth of commerce, and a large part of the world's commercial fleet is manned by European sailors.



Fig. 382. St. Peter's and the Vatican, Rome

392. Religions. —

In the Latin nations the prevailing religion is the Roman Catholic form of the Christian faith. There are also many Roman Catholics in Germany, Austria, Hungary, Czechoslovakia, Poland, Great Britain, and other countries of Europe. The home of the Pope and the seat of the papal government is the Vatican Palace in Rome. The majority of the Teutonic people are Protestants, while the Greeks, Russians, and some other peoples of eastern Europe hold to the ancient Orthodox form of Christian belief and worship. In southeastern Europe there are some Mohammedans.



Fig. 383. Lincoln Cathedral, England

393. The World War.—The war which began in August, 1914, involved all but six of the nations of Europe. Less than one seventh of the area of Europe and less than one eleventh of the population of the continent remained neutral. The war not only caused vast loss of life and property, but led to important territorial changes. Germany and Russia lost various parts of their domains; Austria-Hungary was dismembered, and several new nations were established (Fig. 371). To prevent future wars if possible, a League of Nations was formed, including most of the countries of the world.

394. Government.—Before the World War there were but three important republics in Europe. Switzerland has long had this form of government. France became a republic in 1871, and Portugal in 1910. All the other leading countries were *monarchies*. In some of these the rights of the people were fully protected by constitutions and lawmaking

bodies like our Congress. As a result of the war, Germany, Austria-Hungary, and Russia ceased to be monarchies. Most of the newly established nations of Europe adopted a republican form of government. About half the countries of the continent, however, still remain constitutional monarchies as they were before the war.

395. Postal Union.—

The countries of Europe, the United States, and all other progressive countries have joined in an International Postal Union. This union has an office in Bern, the capital of Switzerland, and a convention is held every three years to arrange for the quickest and most efficient mail service for all parts of the world.

396. Money.—Most of the countries have their own special forms of money. The unit in British money is the pound, which is equal, usually, to \$4.86 of our money. Gold coins of this value are called sovereigns and are accepted in almost all countries in payment of debts. In France and Switzerland the unit is the franc, usually worth nearly twenty cents, and in Italy it is the lira, which has the same value. The Germans use the mark, which was worth about twenty-four cents before the war. The banks in all the principal cities will exchange foreign for home money, and travelers carry letters of credit, or negotiable checks, on which they can draw funds. Conveniences of this sort are very necessary in countries that wish to develop and encourage trade with foreign people.

397. Roads.—The common roads of Europe are better built than those of any other continent, and most of them are kept in constant repair. The building of good roads began in the time of the Romans, and some of the Roman roads are still in use. In the hundreds of years that have passed since the time of Roman rule, good roads have been built in all parts of the continent except in Russia and southeastern Europe. Good roads make travel much easier, and a team of horses can draw a much larger load over them than they can over the unimproved roads in many parts of our country. The roads are used also by an enormous number of automobiles and motor trucks.

398. Railroads and Steamship Lines.—Europeans are advanced in railroad building. They build the roadbeds so firm and run the trains with such care that there are fewer accidents than in America. In the United States, however, there is a greater mileage of railroads than in Europe, and some of




Fig. 384. Road cut into a mountain side, Switzerland


the passenger trains are provided with more conveniences and luxuries than can be found on any European trains. The freight cars in America are much larger, and because of the great size of our country freight is usually hauled longer distances.

The greater part of the world's ocean shipping is controlled by European steamship companies, the largest of which belong to Great Britain.

OCCUPATIONS AND INDUSTRIES

399. Agriculture.—Several of the countries of Europe are densely populated. Some countries, as England and Belgium, have five or six hundred people on the average for each square mile. Much food is needed, and most of the good land, and much that is poor, is carefully cultivated.

More wheat is raised in Europe than in any other continent. All the Latin nations raise large crops, but it is all needed at home. Russia, however, and some of the other southeastern countries, raise more than they use, and have some for export. Rye and barley flourish in cool climates and are grown extensively in Germany, Russia, and some other northern countries. Much corn is



raised in Hungary, Roumania, and Italy, where the people use it chiefly for their own food rather than for fattening stock as in our country.

Germany raises more potatoes than any other country. Russia is second in producing this vegetable, and even France raises more than the United States. Potatoes form one of the chief food crops in Ireland. Sugar beets are grown throughout central Europe (Fig. 385). Germany leads in this industry and in normal times exports large quantities of beet sugar. Russia, Ireland, France, and Belgium all raise flax. The fiber of this plant is used to make linen, and the seed is used for the manufacture of linseed oil. The United States, Argentina, India, and Canada are the other leading countries in the production of flax.

400. Fruit Raising.—In western Germany there are many vineyards. In France there are vineyards in most parts of the country; and the grape-growing industry is important almost everywhere in Italy, Spain, and Portugal, and in many parts of southeastern Europe. Some of the grapes are eaten as fresh fruit, but most of them are used in the manufacture of wine, or are cured as raisins.

Subtropical fruits grow in the countries along the Mediterranean Sea. The most

important of these are oranges, lemons, olives, figs, and a kind of currant that is really a small raisin. These currants form the leading export of Greece.

Mulberry trees are grown in Italy and France, because the leaves furnish the necessary food for silkworms. Small fruits and garden vegetables are raised in all parts of Europe to supply the people of hundreds of cities and thousands of smaller towns.

401. Fishing.—Among other means of supplying food, fishing is important. The waters of the continental shelf and of the numerous shallow seas are full of fish. The North Sea especially is a field for fishermen, and most of the countries around it have for centuries sent out fishing fleets. Thousands of their men are engaged in gathering food from the waters (Fig. 386). They have fished both in European waters and along the Atlantic coast of North America. Some European rivers also are regularly stocked with fish.

402. Grazing.—Another source of food is in the herds of cattle and sheep. In nearly all of Europe except the northern forests and tundras sheep are raised in great numbers, both for wool and for mutton; but the supply does not meet the demand, and much wool and mutton have to be imported from Australia and Argentina. All the European



Fig. 386. Norwegian fisherman arranging a net for salmon where the tides are high

countries raise cattle, and yet both beef and leather must be brought from North and South America, Australia, and New Zealand. Milch cows are kept, and butter and cheese are made, in nearly all the countries of Europe. Butter is an important product of Denmark, while Switzerland makes and exports many kinds of cheese. Much cheese is made also in Holland, France, and Italy.

403. Forests.—Spain, Italy, Greece, and other countries once had larger forests than now. The trees were carelessly cut away, and now the people need much more wood than they have, while the steep hillsides have lost their soil from heavy washing by rains and torrents. To repair the damage Germany and France have planted many trees, and these countries, with some others, now watch over the forests carefully. Cutting of timber is regulated by law, and precautions are taken to prevent fires. There is considerable timber in Norway, Sweden, and northern Russia. There are many wood-pulp factories in Norway and Sweden.

In most European countries wooden houses and barns are few, as timber is too valuable to use for building purposes, except for doors, window frames, sash, and interior finish. Brick and stone are used for the walls, and the roofs are covered with tiles. Many European cities, seen from a church tower or a mountain side, look red because this is the color of the roof tiles.

404. Mining.—Iron and coal are most necessary minerals, as they are extensively used in all lines of modern industry. They are mined in Great Britain, France, Belgium, and Germany, and iron is mined also in Sweden and Spain. Gold and silver are not found in large quantities, but the mines of tin, lead, zinc, copper, quicksilver, and salt are important. Clay pits and stone quarries have been worked for centuries, especially in regions where the people build chiefly with earth materials instead of wood.

405. Manufactures.—Europe is the manufacturing center of the world. Many things are made as skillfully elsewhere, but no other continent has so many workers engaged in manufacture, or sells so many manufactured goods. Many of the raw materials they produce, and others they import. They cannot raise enough wool or silk for their factories, and they raise only a little cotton, but the money they receive for manufactured articles pays for their labor and buys more raw materials. Europe manufactures for the world, and Argentina, Australia, and Canada cultivate the soil and raise crops for the world. The United States is great both in manufacturing and in agriculture, but still it buys from Europe fine fabrics, artistic objects in gold, silver, and other metals, carved woodwork, toys, pictures, drugs, chemicals, and countless other things.

The great manufacturing nations are in western Europe. Russia devotes most of its labor to farming and buys the greater part of its finer manufactured goods. The people of the Balkan countries are backward and unskillful in most manufacturing.

Review.—1. What was the extent of the Roman Empire? 2. What are the Latin nations of to-day? 3. What are the Teutonic nations? 4. What races are found in eastern Europe?

5. How can a small continent support so large a population? 6. What are the principal republics of Europe? 7. Which of these recently became republics? 8. What other form of government is found in Europe?


9. What forms of Christian faith prevail in the several parts of Europe?

10. What is the unit of money in Great Britain? In France? In Germany? In Italy? 11. What are some of the differences between European and American railroads?

12. What are the principal grains raised in southern Europe? In northern Europe? 13. Where is wine culture important? 14. What vegetable products are much raised in Germany? 15. What countries produce the most from dairies? 16. Give an account of building materials in Europe. 17. Why is western Europe a great manufacturing region?


Fig. 387
Physical and Political
BRITISH ISLES

Scale of Statute Miles



Capitals (C)

ELEVATIONS IN FEET



COPYRIGHT, BY AMERICAN BOOK COMPANY





Fig. 388. Newcastle on Tyne, from the river; a great center of coal mining, manufacture, and commerce

THE BRITISH ISLES

	AREA, SQ. MI.	POPULATION	CAPITAL
Great Britain, etc.	89,030	42,918,000	London
Northern Ireland	5,320	1,250,000	Belfast
Irish Free State	27,040	3,140,000	Dublin

Map Study.—1. What is the latitude of Lands End? Of the Shetland Islands? What part of North America is included between these latitudes?

2. What waters separate Ireland from England and Scotland? 3. On what river is Liverpool in northwestern England? 4. On what waters are Dublin and Belfast in eastern Ireland? 5. What indentations of the Scottish coast lead to the cities of Glasgow and Edinburgh?

6. Locate the following seaports: Newcastle and Hull, in eastern England; Southampton and Bristol, in southern England; and Cardiff, in Wales. 7. Locate Birmingham, Sheffield, Leeds, and Manchester, in central England.

8. Give the position and direction of the Pennine Chain. 9. Locate the Strait of Dover, and use the scale of miles to ascertain its width.

406. Names and Position.—The British Isles include two large islands and many smaller ones, with a total area greater than that of New England and New York together. For a long time these islands were united under one government as the United Kingdom of Great Britain and Ireland.

Early in 1922, however, most of Ireland was organized as the Irish Free State with its own government. Great Britain consists of England, Wales, and Scotland, and, with Northern Ireland, constitutes the United Kingdom.

Because of its island position, Great Britain has never kept as large a standing army as several of its continental neighbors. It has always maintained a powerful navy, however, as well as a great merchant marine, for otherwise ships of a hostile nation could cut off its food supply and stop its trade with foreign countries, as was attempted during the World War. Many of the people of these islands have been sailors, explorers, and traders in all parts of the world; and even after the destructive World War Great Britain has more ships than any other country.

France is only twenty-one miles from England across the Strait of Dover, and by short voyages from British or Irish ports passengers and goods may reach Norway, Sweden, Denmark, Germany, the Netherlands, and Belgium. It takes but a few days for ships to go from these islands to American or Mediterranean ports. Swift steamers cross the English Channel and the North Sea and connect the railways of the islands with those of the continent. Quick railway journeys to Paris, Rome, Berlin, Constantinople, and Petrograd are thus made possible. Great Britain is centrally located among the great trading nations of the world.




Fig. 389. Windermere, one of the lakes in the English Lake district

GREAT BRITAIN

407. Surface.—England and Wales have highlands in the west and north. Wales is a region of low mountains and of many valleys. The highest point is the top of Mt. Snowdon, 3570 feet above the sea. The peninsula between the English Channel and Bristol Channel is an upland, and the English lake district, in the northwest, on Solway Firth and the Irish Sea, is mountainous (Fig. 389). The Pennine Chain is a range of low mountains running north and south through the middle of northern England. Central and southeastern England is a lowland which is flat in some parts and hilly in others. A part of the lowland between the mouth of the Humber River and the Wash is so low that banks are built to keep out the sea and the area is drained by pumps. The country is small and the rivers are short, but many have been made navigable by dredging and the use of dams and locks.

The Highlands of Scotland are in the central and northern part of that country. As a whole this region is rocky and barren; Ben Nevis, 4406 feet in altitude, is the highest mountain in the British Isles (Fig. 390). The southern part of Scotland also is a highland, but it is not so high or rugged as the northern part. Between the highland in the south and the Highlands of the north is the Scot-

tish lowland. The Firth of Forth and the Firth of Clyde are deep indentations in the east and west, and along their shores and between their heads are fertile lands and large deposits of coal and iron. Here on the river Clyde is Glasgow, the largest city in Scotland and the second largest in Great Britain, and near the Firth of Forth is Edinburgh, the famous old Scottish capital.

408. Climate.—Because of its position. Great Britain has an oceanic climate, with no extremes of temperature (Sec. 385). The winters are not severe, and the snow that falls does not remain long. In fact it is possible to do out-of-door work throughout the year. American visitors find the midsummer days cool enough to be very comfortable, though the Englishmen may call them hot.

On the Scilly Islands, a small group off Lands End, the climate is so mild that the chief business is the raising of flowers, bulbs, and early vegetables for the city markets. In the western highlands of Wales, England, and Scotland the rainfall is heavy and grass grows abundantly. In the Highlands of Scotland especially the rainfall is so frequent and heavy that agriculture is not profitable, but there are fine pasture lands and many of the people are shepherds. In eastern England the rainfall is only about 25 inches a year; and yet the fields and gardens there




Fig. 390. Ben Nevis, Scotland



Fig. 391. Farms in Scotland

are green and fresh through the summer, because there is no great heat to dry the ground and wither the plants.

409. Agriculture.—In spite of the care with which the soil is tilled, British farmers raise only a small part of the food needed by the British people. In the south and east of England, where the rainfall is least abundant and the winters cool, much wheat is grown, an average of 32 bushels per acre being maintained. This is much more than is usually produced on an acre in the United States. Yet the population of Great Britain is so dense that it has to import the greater part of its wheat and flour from the United States, Canada, Argentina, and other lands.

In the more moist portions of England and in the Scottish lowlands, barley and oats and many potatoes are raised because they thrive in a cool, moist climate in which wheat will not ripen (Fig. 391). Immense quantities of garden vegetables are also raised in various parts of the country, and root crops, such as turnips and mangels (a kind of beet), are raised as food for stock. Corn does not thrive, because the summers are too cool.

A considerable part of the more rainy portion of the island is in meadow and pasture. Cattle, sheep, horses, and hogs are numerous.

The dairy industry is very large, but not enough butter and cheese are produced to supply the needs of the population and some must be imported. Young cattle are imported from Ireland to be fattened for market in English pastures. British mutton has a reputation for its excellent quality. English agriculture has improved since the World War, largely because the higher prices of agricultural produce have made it profitable to bring under cultivation land that had been left idle or used only as pasture.

The fields in Great Britain, as in many other parts of Europe, are very carefully cultivated. The roads are narrow and winding, and roads, fields, and railways are commonly bordered by neat hedges. Many trees grow in the meadows and pastures, and buildings and walls are often covered with graceful, luxuriant growths of ivy. The soft, rich green of grass and trees and the well-kept fields and roads make the English countryside (or rural England) very beautiful.

410. Metropolitan and Industrial England.—London is the metropolis of the kingdom and the center of many railways leading to all parts of England, Wales, and Scotland. The district south of a line drawn from the Wash on the east to the Bristol Channel on the west is the great farming region of England; but it is commonly called metropolitan England because its only very large city and trade center is the metropolis London.

North of the line described lies industrial England, so called because the people are mainly devoted to the manufacturing industry. Here are all the very large cities of England except London, and in this district practically all the work in iron, woolen, and cotton is carried on. Great Britain is chiefly known for its manufacturing. If this industry and the income from shipping did not furnish money to buy food and raw materials of many kinds in foreign lands, Great Britain might not be able to support more than a third of its present population.



Fig. 392. Coal fields, and principal industrial centers and ports of Great Britain

411. Iron and Coal.—Great Britain could never have taken such a lead in the world's affairs without its large supplies of coal and iron (Fig. 392). One of the great coal fields of England is about Newcastle, on the Tyne (Fig. 388), in the north of England. This city not only exports coal, but makes iron and steel and builds some of the largest steel ships that cross the oceans. Another great coal field is in Yorkshire, east of the Pennine Chain. This supplies coal for the iron and woolen industries of Sheffield, Leeds, and many other cities. Sheffield has made fine grades of steel for hundreds of years, including the finest pocket knives, shears, and other kinds of cutlery.

Other coal fields are found in central England, near Birmingham. This is one of the chief cities of England, and its special industry is the working of iron. Here and in the neighboring towns there are so many chimneys, coal pits, and heaps of waste that the region is called the "black country." It is very different from the clean and quiet parts of rural England which lie around it. The "forest of Arden" formerly surrounded Birmingham, and the people made charcoal and

used it in little shops, to work the iron. Now most of the work in iron and steel is done in factories which turn out pens, nails, screws, and needles by the million, as well as all kinds of machinery.

There is one other important coal field in England, in the county of Lancashire, west of the Pennine Chain. It is the region about Liverpool, the great port, and Manchester, the chief center of the cotton industry.

A large supply of coal is found in the South Wales coal field. This coal is taken to Cardiff, the principal seaport of Wales, on Bristol Channel; much is used there in the iron furnaces, and much is exported. Cardiff is the principal coal-exporting city of the world. British ships carry coal to sell in France, Italy, Argentina, and many other foreign countries, and to supply coaling stations which Great Britain owns in various parts of the world, including Gibraltar, Malta, the Bermudas, St. Helena, and the Fiji Islands. Such coaling stations are necessary because even the largest ships carry only coal enough to go a few thousand miles.

Coal fields in the Scottish lowlands provide a convenient supply of fuel for Glasgow and other manufacturing cities in Scotland.

Many deposits of iron are close to the coal beds in England and Scotland, and much is brought in ships from Sweden, Spain, and other countries. Modern building, manufacturing, and transportation both by land and by sea, require the use of iron and steel in great quantities. Great Britain has iron for ships, tools, railroads, and machinery, and the coal to work the iron, drive the ships, and run the factories. These two minerals have done much to make Great Britain the greatest manufacturing nation of the world, even in industries for which the raw material must be brought from distant lands.

412. Cotton Manufacture.—The manufacture of cotton goods is the largest industry in Great Britain, and yet every fiber of the raw material must be imported. The United



Fig. 393. Manchester ship canal, bordered by wharves

States supplies more cotton than any other country, though much comes from Egypt and India. Much of the cotton is brought by sea to Liverpool and then sent by rail or boat to the manufacturing towns in Lancashire. Manchester is the greatest city in the cotton district, and is the money and banking center for the cotton trade. The city of Manchester has dug a ship canal $35\frac{1}{2}$ miles long and 28 feet deep from Manchester to the sea (Fig. 393), so that cotton and other freight can reach the city without stopping in Liverpool.

About two fifths of all the cotton spindles of the world are in England, and more than half of the product, in value, is turned out by English mills. There are several reasons for the greatness of the industry.

(1) Englishmen first invented the machinery that was needed. More than one hundred years ago two men, named Hargreaves and Arkwright, invented machines for spinning cotton, which made it possible to turn out more and better goods and thus decrease their cost. In those days woolen manufactures were much more important than those of cotton, but now the cotton industry is much the larger of the two. At first the workmen were very angry over the inventions of Hargreaves and Arkwright, because they feared that the machines would enable a few

men to do the work and that many men would have no employment. The demand for cotton manufactures has so increased in all parts of the world, however, that now far more workmen find employment than before.

(2) Lancashire, the great cotton-spinning region, is in the rain belt of western England (Secs. 385, 408), and the moist air is favorable to working the delicate fibers of the cotton (Fig. 394).

(3) The manufacturing region is favorably located for ocean trade. The estuary of the Mersey allows large ships to reach Liverpool, so that the cotton is brought by water close to the mills, and a short haul carries the cotton goods back to the sea again.

(4) The enterprise of the British people has led to the development of trade with all parts of the world. Even the United States, which raises and manufactures so much cotton, buys some English cotton goods. Raw




Fig. 394. Spinning room in a Lancashire cotton mill

cotton may be sent from Texas fields to England, there made up into cloth, and finally sent back to Mexico, to be sold just across the Rio Grande from the state in which it was grown. At the same time the bread-stuff for the operatives comes to Liverpool from North America, Argentina, Egypt, and other countries, while cattle and beef and dairy supplies are shipped in from Canada, Argentina, Australia, and New Zealand.

413. Woolen and Other Manufactures.—Leeds is the center of woolen manufacture, and other cities near it have a share in the industry. All these cities are near the Yorkshire coal fields, which furnish the power to run the machinery. Woolen manufacture began there because sheep were kept on the pastures of the Pennine Chain. Now, although Great Britain still has many sheep and produces much wool, more than three fourths of the wool needed in its factories is imported. Australia sends the most, while Argentina and South Africa send some.

There is a great demand for British woolen goods. Many kinds of woolen cloth are brought from Great Britain and sold in American stores and tailor shops. One of these is worsted, which took its name from a village of that name in eastern England. Another is the tweeds, which are made at a number of places in the lowlands of Scotland. Broadcloths, cashmeres, merinos, and serges also are made of wool, as are likewise many kinds of the best carpets.

The most important manufactures in Great Britain are those of iron, cotton, and wool; but there are many others. In addition to the making of cotton and woolen cloth, the textile industries of the country include some manufactures of silk and of linen. The making of pottery, including fine china, is another British industry (Fig. 395). There are many breweries, distilleries, and factories for making jams and marmalades, which are favorite articles of diet in Great Britain.




Fig. 395. Shaping pottery by use of the potter's wheel

414. Commerce.—Great Britain usually has a larger foreign commerce than any other country; but since Great Britain is small and has less than half the population of the United States, its internal or domestic trade is much less than ours. Most of the British foreign trade is carried in British ships; and these, as well as many ships for other countries, are built in the shipyards of Great Britain. Newcastle (Sec. 411) has the largest shipyards of England, but Glasgow, together with the

bank of the lower Clyde, is one of the chief shipbuilding districts of the world.

Great Britain has many seaports. Like other parts of Europe, it has an irregular coast line, with numerous bays and tidal rivers or estuaries. The water of a number of these rivers is deep enough for ships to go many miles into the country. No place in the country is more than 70 miles from a seaport. This gives the manufacturers an advantage, for it costs less to carry goods by ship than by rail. In the United States it is not unusual to carry manufactured goods 500, or 1000, or even 2000 miles by railroad.



Fig. 396. Liverpool landing stage



Fig. 397. British shipping at London

There are four principal ports on the west coast. The second in size, but first in commerce, is Liverpool, on the river Mersey (Fig. 396). No other foreign city has so great a trade with the United States. Ships run to Boston, New York, Philadelphia, and many other ports. Cotton ships dock here from Galveston, New Orleans, and Savannah. From Liverpool ships go to all the British colonies and to all other countries. Not only the cotton, but most of the grain and meat from foreign countries enters Great Britain here. The wheat prices for the world are fixed chiefly by the condition of the Liverpool market.

First in size, but second in commerce, of the western ports is Glasgow. It has not only shipyards, but also factories for making locomotives, and is the great center and outlet for the products of the Scottish lowland. Ships sail between Glasgow and American ports, and some of them call at Londonderry, in the north of Ireland.

Bristol and Cardiff are also important seaports, though neither of them ranks with Liverpool or Glasgow.

English mails for America are sent by train to Fishguard on the Welsh coast, or to Holyhead. From Holyhead, they cross the Irish Sea to Dublin and then go by train to Queenstown in the south of Ireland. The ships pick up or leave the mail bags at Fishguard and Queenstown, and the mails thus go more quickly than if they were to go all the way from or to London and Liverpool by ship.

There are three principal ports on the English Channel: Plymouth, Portsmouth, and Southampton. Plymouth has long been a British naval station, Portsmouth has the largest of the government navy yards, and Southampton is a convenient port for London, because it is little more than an hour away by rail. Many English ships sailing from New York have their terminal there, and some ships of other nations call there on voyages to and from America.

England has three first-class ports on its east shores. One is Newcastle on the Tyne (Sec. 411). Another is Hull (Fig. 398), on the Humber, an outlet for the iron and woolen manufactures of Sheffield, Leeds, and other cities, with lines of ships that run to North Sea and Baltic ports and to many other parts of the world. The third and by far the most important port is London (Sec. 416).

415. Fishing.—As Great Britain is surrounded by water, fishing has become an important industry both along the coast and offshore, where such food fish as cod, haddock, and herring are taken in great numbers.



Fig. 398. Fish wharves at Hull

More than 100,000 men from Great Britain are engaged in this occupation. Many seaports share in this industry, though much of it has been concentrated at a few large ports on the North Sea. Among these are Hull (Sec. 414), Grimsby, and London in England, and Aberdeen in Scotland. Fresh fish are carried from these ports to market by fast trains and form a large part of the food supply in many parts of the country (Fig. 399).



Fig. 399. Sorting fish for market

416. London.—London is the capital of Great Britain and of the British Empire, and is the largest city of the Old World. The center of London is on the river Thames, fifty miles from its mouth. The place is an excellent site for a city, because it is at the head of the tidewater, and even before the time of the Romans in Great Britain, it was a convenient place for crossing the river. King Alfred the Great made London the capital of England more than a thousand

years ago. The city has grown up on both sides of the river, though most of the important streets and buildings are on the north side. London Bridge is the oldest of several bridges that now join the two parts of the city.

London is the center of British railways. They run out in all directions to the principal seaports and to Scotland. Trains are swift, and no one is allowed to cross the tracks at stations or to walk on them in the

country. More railroad tickets are sold each year in Great Britain than in the United States, but the average length of each journey is less.

Every British citizen thinks much about London and talks about "going up to London." This is because the city is so great and the land so small. London has about one sixth of the population of Great Britain.

London leads all other cities in its commerce. Its docks stretch down the Thames more than twenty miles, and the cargoes unloaded there come from all parts of the world. They are brought here, not only for use in Great Britain, but to be reshipped to many other ports, for Great Britain is a great trading nation and London a great trading center. Tea, coffee, spices, sugar, petroleum, wool, rubber, and hides are among the imports, some of which are again exported. The export trade is smaller than the import trade, because the chief manufacturing district is in the north of England, nearer Liverpool and




Fig. 400. The central part of London

Hull. London, however, is a great manufacturing center, with automobile works and many factories.

London has long been a money center, not only of the British Empire, but of the world. Much of the business is conducted through the Bank of England. The money transactions of New York, however, now exceed those of London.

London, like other European cities, does not allow very high store or office buildings to be erected, such as we see in some of our own cities. Many of the streets are narrow and crowded and not suited to railroad tracks. Most of the public travel is by taxicabs and huge omnibuses. There are extensive subways also, which the Londoners call "tubes."

Among the great buildings are St. Paul's Cathedral and Westminster Abbey. In the Abbey are buried many famous British statesmen, writers, heroes, and men of science. The Tower is a great square building on the

Thames, in which, in former centuries, many famous men of the kingdom were imprisoned, and some of them executed. The British Museum has vast collections in art and science, and one of the two largest libraries of the world, the other one being the National Library in Paris. In the eastern part of London, on the river Thames, is the Greenwich Royal Observa-



Fig. 401. Greenwich Observatory



Fig. 402. Trafalgar Square, London

tory, from whose meridian longitude is usually reckoned in all countries (Fig. 401).

Only a short journey from London are the largest and most ancient of the British universities, Oxford (Fig. 403) and Cambridge. There are universities also at London, Sheffield, Manchester, Liverpool, Edinburgh, and other places.

417. Government and Colonies.—The form of government in Great

Britain is now such that the people have almost entire control, while the king and the nobles have little power. The House of Commons is made up of members elected by the people, and is the chief source of legislation. The House of Lords is composed of members of the nobility and the bishops of the established church—the Church of England. The two houses



Fig. 403. One of the colleges at Oxford—Christchurch

form the *Parliament* of the kingdom (Fig. 404). The king appoints as *Premier* the leader of the party in power, and the Premier selects a *ministry* of leading statesmen for the management of the departments of government.

In the early days of America Englishmen founded several colonies, including Virginia and Massachusetts. Many Scotch, Irish, and Welsh people also came here in order to have religious freedom, or a better opportunity to earn a living.

At the time of our Revolutionary War Great Britain lost the colonies which formed the United States. But British colonies have at various times been established in other parts of the world, and are still members of the British Empire. While some of these have their own governments and are almost independent, they favor Great Britain in trade and in other ways.

In America, the empire includes Canada, Newfoundland, British Honduras, and British Guiana, besides Jamaica and several smaller islands of the West Indies. There are important British colonies in several parts of Africa, and in southern Asia. Australia and New Zealand and many smaller islands in the Pacific, Atlantic, and Indian oceans are under British rule. British possessions are so extensive (Fig. 350) that it is a common saying that the sun never sets on the British flag. The sons of British families go out and manage the farms, tend the ranches, work the mines, build the cities, and organize the governments of the colonies. For this reason the ideas and books, the commercial enterprise and ingenuity, of the English people are now found in all parts of the world. The English language is spoken by more people than any other European tongue.



Fig. 404. Houses of Parliament, London, where the Parliament meets

Review.—1. What advantage has Great Britain from its island position? 2. Describe its surface and climate.

3. In what parts of Great Britain are wheat and oats chiefly raised? 4. Where is metropolitan England? Why is it so called?

5. Locate the chief coal fields of Great Britain. Name the chief cities which are dependent on them for fuel for their manufactures. 6. What advantages for cotton manufacture has the Lancashire district? What countries supply the raw material for this manufacture? 7. What is the leading city in English woolen manufacture? What countries supply the raw wool?

8. What is the principal center for shipbuilding in England? In Scotland? 9. Give an account of Liverpool; of Southampton; of Hull.

10. Describe the location of London and state its advantages. 11. What is the character of the commerce of London? 12. Why is Westminster Abbey a noteworthy church?

13. Describe the government of Great Britain.

14. What is the extent of the British Empire?

IRELAND

418. Irish Free State, and Northern Ireland.—Most of the people of Ireland have long objected to English rule. In 1922, after conferences between representatives of the Irish people and the British government, it was arranged to divide the island into two parts. A small region in northeastern Ireland remained with Great Britain in the United Kingdom, but the rest of the island was formed into the Irish Free State, with a government like that of Canada or Australia.

Taken as a whole, Ireland has low mountains on its borders, but in the central part there are low plains, suitable for meadows, pasture lands, and for some crops. Some of the best farming land is in Northern Ireland, where crops of hay, oats, barley, flax, potatoes, and roots are large and a fine grade of grass seed is grown.

Northern Ireland is the chief flax-growing region of the island, because the plant thrives in a cool climate. In preparing the flax the plants are pulled, dried, and the seeds removed.

They are then put into pools of soft water to loosen the fibers and make it possible to comb them out and get them ready for weaving. Much of the fiber goes to Belfast, where it is made into linen. The best Irish linens are very beautiful and bring high prices. Belfast is noted also for its great ship yards, where large ocean ships are built (Fig. 405).

The Irish Free State is largely an area of grass land, with grazing and dairying as the chief industries (Fig. 406). It is this region that furnishes the young cattle sent to England to be fattened. There is some farming in the southern section of the country, but much of the land has been impoverished



Fig. 406. Hay field near Killarney, Ireland

by poor farming methods and the returns are not large. In the western part, where the population is dense, most of the land under cultivation has been won from bog or mountain.

There is but little coal in Ireland and therefore but little manufacturing. Many of the people depend upon peat for fuel. In the swampy lands, of which there are many in the low-lying parts of this island with a heavy rainfall, mosses and other plants have grown freely. As the country is never hot or dry, the moisture of the swamps prevents decay, and in time the plants form a brownish vegetable substance called peat. This peat when cut out in blocks and thoroughly dried burns well and is extensively used as a domestic fuel.

Dublin is the chief city of the Irish Free State and has become an important shipbuilding and brewing center. In recent years it has grown rapidly in size, even while the country districts have been gradually losing in population.

Review.—1. What is Northern Ireland? What crops are grown there? 2. How is flax prepared for spinning? 3. In what city is linen chiefly manufactured? 4. What are the chief industries of the Irish Free State? 5. Where is the farming region of the Free State? 6. What is peat and for what is it used? 7. Where is Dublin, and what industries are carried on there?




Fig. 405. Shipbuilding, Belfast. Two vessels on the stocks, in process of building

Fig. 407. Physical and Political

GERMANY POLAND AND OTHER COUNTRIES ON THE NORTH AND BALIC SEAS

Scale of Statute Miles
140 MILES TO ONE INCH
Capitals: ● Railroads: —
ELEVATIONS IN FEET







Fig. 408. Docks at Hamburg, the chief German seaport

GERMANY

About 179,500 sq. mi. POP., about 60,000,000. CAPITAL, Berlin.

Map Study.—1. Name in order the countries that border Germany on the north, west, south, and east. 2. Describe the courses, in Germany, of five important rivers. 3. What are the latitudes of Berlin and of Washington? 4. Name the leading seaport on the Elbe River; three Baltic Sea ports. 5. Locate Breslau, Leipzig, and Dresden. 6. Locate Munich and Nuremberg. 7. What seas are joined by the Kiel Canal?

419. Physical Geography.—Northern Germany is a plain sloping from altitudes of a few hundred feet down to the North and Baltic seas. All the greater rivers of Germany, except the Danube, flow northward across this plain, which extends from the Netherlands on the west through Russia on the east.

Middle Germany consists of hills and low mountains, some of which are covered with forests. In southern Germany the Danube and its branches cross the Bavarian Plateau, while farther west are the Black Forest and the valley of the middle Rhine. On the southern border the country includes a part of the Alps, with summits nine or ten thousand feet high.

Germany has land boundaries on the west, south, and east. On the north is Denmark, but the rest of the northern border is a part of the shore line of the Baltic and North seas.

The climate is not so moist or so even as that of Great Britain, nor is the country so dry or subject to such extremes of heat and cold as Russia. The western parts of Germany have more rain and milder temperatures than the eastern parts. Southern Germany, on account of its greater elevation, is no warmer than the northern half of the country. Like Great Britain and like most of central and northern Europe, Germany is cloudy in winter, while bright days prevail in Italy.

The northern plain, which was covered by the ice-sheet (Sec. 379), has many lakes, sand flats, and moraine hills. As southern Germany was at one time covered by ice moving northward from the Alps, this region also has drift soils and many lakes.

420. History and Government.—For centuries there were many German states, each more or less independent. Some were kingdoms, and others were known as *grand duchies*, *duchies*, *principalities*, and *free cities*. Until 1806 they were loosely banded together in an empire, which at times was too weak to prevent wars among the different states. At length, in 1871, a new German Empire was founded, under a constitution which made the central government strong and powerful. By war with France, it annexed the provinces of Alsace and Lorraine, west of the Rhine.

In the World War Germany again attempted to add to its territory, but was




Fig. 409. States of Germany and territories ceded by treaty of 1919

defeated and lost the territories shown in Fig. 409, including Alsace-Lorraine, which was returned to France. To Poland Germany lost still larger areas, including a large region around the city of Posen, extending northward to the Baltic Sea. The part of Prussia around Königsberg, though still a part of Germany, is thus cut off from the rest of the country. After a plebiscite, or vote of the people, the eastern part of a mining region on the upper Oder River (Fig. 409) was also given to Poland. A part of Schleswig was by vote of its people added to Denmark. A small area on the western border was ceded to Belgium, and the coal beds of the Sarre Basin were turned over to France. Moreover, as security for the carrying out of the treaty, it was agreed that French and other Allied troops should occupy the land west of the Rhine, with small areas east of it.

In 1918 the imperial government of Germany was overthrown and the country adopted a republican form of government, with a president, a Reichstag or legislative assembly, and equal suffrage for all classes and

for both sexes. The country is made up of eighteen states, large and small, each with a republican government.

421. The German People.—After the war of 1870 and the formation of the empire, the population increased rapidly until the opening of the recent war. At present the population is greater than that of any other country in Europe except Russia.

Under the empire the people were trained to industry and strict obedience to law. The royal families, the nobility, and the rich expected service from those who belonged to the laboring classes, who tilled the fields,

worked in the factories, and carried on the small trades. Class feeling was strong and it was rarely possible for a poor or obscure boy or girl to rise to wealth or to important public positions.

The German people did, however, give much care to education. The schools of all grades are taught by well trained teachers. There are more than twenty universities, of which those of Berlin, Leipzig, Munich, and Heidelberg are among the best known.

422. Agriculture.—Rye and barley are the principal grains, for they thrive best in a cool climate, and the poorer people eat a great deal of rye bread. Much wheat is raised and a large amount of wheat flour is manufactured, but not enough to supply the needs of the people; therefore wheat and flour are also imported. Germany surpasses all other countries in the quantity of potatoes raised, and also in the amount of beet sugar made. Much of the sugar is not needed at home, and is sold in other countries. Many of the farms in Germany are small, and the farmers live in villages and go out each day to their work.



Fig. 410. Castle, town, and vineyards on the Rhine

In the Rhine country there are extensive vineyards, the grapes from which are used in making wine. This part of Germany joins France and the Swiss lowland, which are also regions of grape raising. Along the Rhine and the Moselle the people have, with great labor, terraced many of the steeper slopes, so that the soil is held in place and more vines can be grown (Fig. 410). The vineyards of Germany extend farther north than those of any other country of Europe.

Much attention is given to the raising of live stock. Hogs are fed on the ground pulp of sugar beets from which the juice has been extracted, and on nuts from the forest.

423. Forests and Mines.—For many years Germany has given attention to forest development. About one fourth of the surface is covered by forests, which belong partly to the German states and partly to private owners. The private owner, however, cannot cut trees as he may wish, for he is required by law to preserve the woods. This he does by cutting only mature or ripe trees and by replacing them with young ones. A German forest looks like a densely wooded park (Fig.

411). The majority of the trees are ever-green, including many pines. The beech is also common. The woods are cared for by men trained in the profession of forestry.

Germany has many mines and quarries. There are beds of coal and of iron ore in several German states. There are also mines of silver, lead, and zinc, and wonderful deposits of common salt and of potash salts. In the southern part of Germany, near the Danube, are quarries of lithographic stone. This rock is a limestone of very fine grain, which

is cut into smooth slabs and sent to various parts of the world for making plates used in the production of maps and posters.

424. Manufactures.—Germany is a great manufacturing nation and factories are common in all parts of the country. The greatest concentration of industries, however, is found in the basin of the Rhine below Cologne. Here are vast deposits of coal along the Ruhr, a small river



Fig. 411. German fir forest




Fig. 412. Power plant near Berlin. Here an abundance of cheap coal is converted into electrical current



Fig. 413. Shipbuilding at Stettin



Fig. 414. The Reichstag Building, Berlin

flowing into the Rhine from the east. Essen is a center for iron and steel. Some of the iron ore lies close at hand and the rest is brought by ship from Spain and Sweden. It is in this part of Germany that most of the textiles are manufactured, including cotton, woolen, and silk goods.

Outside of the lower Rhine district, Saxony has the most extensive manufactures, including large centers for iron, textile, and printing industries. Industries are also highly developed in and about Berlin. Among German specialties of manufacture are instruments of precision, and drugs, dyes, and a great variety of other chemical products.

In the woodland parts of the country, wood carving is carried on by thousands of peasants and others in their homes, at times when work cannot be done in the fields and vineyards. Toys, clock cases, and carved furniture of all kinds are made.

In many German cities the workmen have acquired skill in making watches, jewelry, and all kinds of gold and silver ornaments and utensils. This work is done especially in Berlin, Nuremberg, Munich, and Augsburg. Fine china is made, the Dresden china being well known. The brewing of beer, a common beverage in Germany, is a large industry.

425. Commerce.—Germany has many states, and its domestic commerce is large.

Railways have been laid out, rivers improved, and canals constructed, so that the cities and people of the interior may trade with one another and may readily reach the seaports. Most of the railroad lines are owned and operated by the German states. The larger rivers improved for navigation have been joined to one another by canals (Sec. 384).

The population of Germany is so large that much foodstuff must be imported. Because there are many factories, raw materials, as cotton, wool, silk fiber, iron ore, and crude rubber, must also be brought in. Before the World War the foreign trade and the shipping of Germany were large. The terms of peace adopted in 1919 compelled the country to surrender most of its merchant ships in compensation for ships which were destroyed in sea warfare. Its carrying trade was therefore for several years much reduced.

The greater part of the overseas trade enters Germany by way of the North Sea; therefore Bremen and Hamburg (Fig. 408) are more important than the ports on the Baltic. These two ports, as well as Stettin and Kiel, are shipbuilding centers (Fig. 413).

426. Chief States and Cities of Germany.—Prussia, somewhat smaller than California, is by far the largest of the German states (Fig. 409). Its capital, Berlin, is also the capital of the country (Fig. 414).

Berlin is one of the three cities of the

world that have more than 3,500,000 people. It is in the midst of the north German plain and lies between the Elbe and Oder rivers. Smaller rivers and canals join it to these rivers and afford navigation for its commerce. Railroads have been built across the lowland and reach out in every direction to the different parts of the country and to all parts of the continent. The manufactures of Berlin are extensive and include the making of machinery, steam engines, and a great variety of woolen goods. The city is also a banking center and has the largest of the German universities and various museums of art and industry.

Breslau is a large city in southeastern Prussia, on the river Oder. It is near coal fields and has important manufactures.

The most western part of Prussia is the country along the Rhine. It is not only noted for the beauty of its scenery and for its ancient castles, but is also known for its manufactures and commerce. Here on the Rhine are Cologne, with its cathedral and its manufactures of Cologne water, sugar, chocolate, and tobacco; and Dusseldorf, a handsome residential city and a center of iron and textile manufacturing. Not far from the Rhine are Essen, the iron-manufacturing center (Sec. 424), and the great textile cities Barmen and Elberfeld. These two cities are so closely connected that they really form one center of population and industry. Frankfort on the Main is a financial and trading center and takes its name from a branch of the Rhine on which it stands.

Saxony is a state south of Prussia, on each side of the Elbe. Its capital is Dresden, where a variety of artistic objects are manufactured, including china, and where there are large art galleries, libraries, and scientific collections; Dresden is a resort for students of music and painting. Leipzig also is in Saxony, and is the most important center in Germany for the printing of books. Chem-



Fig. 415. The heart of Munich

nitz is another large city of Saxony; its chief industries are in iron work and textiles.

The second largest German state is Bavaria, in the south. It is crossed by the Danube and has the Alps on its southern border. Its chief city is the capital, Munich (Fig. 415), which has important collections of pictures and manufactures a variety of artistic objects, including bronzes and stained glass. This city is one of the chief brewing centers of the country. Another great Bavarian city is Nuremberg (Sec. 424).

Hamburg is the second city of Germany, with a population of about one million. Other important cities are Hanover, Stuttgart, and Magdeburg.

Review.—1. Briefly describe the surface of Germany. 2. Compare the climate with that of Great Britain. 3. When was the former German Empire established? 4. Describe the form of government recently adopted. 5. What recent changes have been made in the boundaries of Germany?

6. Name four of the leading products of the soil. 7. Give an account of the care taken of the forests. 8. What useful kind of stone is exported? 9. In what parts of Germany are important concentrations of industry found? 10. What industry is common in the forest regions?

11. Name the largest German state. 12. Give the main facts about Berlin. 13. Name and locate two German cities that have important picture galleries. 14. Locate two important cities on the Rhine, and two leading seaports.

OTHER COUNTRIES ON THE NORTH AND BALTIC SEAS

	AREA, SQ. MI.	POPULATION	CAPITAL
Belgium . .	11,760	7,684,000	Brussels
Netherlands .	12,772	6,841,000	The Hague
Denmark . .	16,585	3,289,000	Copenhagen
Norway . .	124,710	2,646,000	Christiania
Sweden . .	172,928	5,904,000	Stockholm
Poland . .	149,000	27,442,000	Warsaw
Lithuania . .	25,000	2,300,000	Kovno
Latvia . .	24,000	1,503,000	Riga
Esthonia . .	18,500	1,110,000	Reval

Map Study (Fig. 407).—1. Give the boundaries and locate the capital of the Netherlands; of Belgium; of Denmark. 2. In what country is Amsterdam? Antwerp? 3. What river crosses Belgium and the Netherlands? 4. Give the latitude of the North Cape (Fig. 371). 5. What countries occupy the Scandinavian Peninsula? 6. Name and locate the capital of each. 7. What countries are east of the Baltic Sea? 8. Locate Warsaw; Riga.

BELGIUM

427. Size and Population.—Belgium is not very much larger than New Hampshire or Vermont, and yet it has a greater population than all New England, important manufactures, and a very great foreign commerce. There are more than 600 people for each square mile in the kingdom. No other country in Europe is so densely populated.

There are two main languages in Belgium. The people in northern Belgium, next to the Netherlands, use the Flemish language, which is much like the speech of their Dutch neighbors. In southern Belgium the people speak French, as their neighbors do over the border in



Fig. 416. Milk peddler, Belgium



Fig. 417. Lace making, Belgium

France. The Belgian money unit is the franc, as in France.

428. Industries.—Northern Belgium has a low, flat surface; some of it has been made habitable by building embankments to shut out the sea. The natural streams on this lowland, as well as the many canals that have been dug, make it easy to travel and to transport goods by water. Southern and eastern Belgium are hilly, with forests and many mines, and in this respect southern Belgium is like that part of France which borders it.

Valuable deposits of coal, iron, zinc, and lead are found there, and southern Belgium is one of the busiest manufacturing regions in the world. All kinds of glassware and iron and steel goods, as well as cotton, woolen, and linen goods, are made there (Fig. 417).

The people have long been skillful workers in wool; centuries ago Flemish weavers, because of their great skill, were taken to England to improve the woolen industry there. In the early development of the textile manufactures Belgium raised most

of the necessary wool and flax; no cotton goods were made at that time. Now much of the wool and all of the cotton are imported.

The flat lowlands are used mainly for agriculture. The principal crops are hemp, flax, hops, sugar beets, chicory, and a variety of garden vegetables. The farms are small, are worked with great care, and are more like large gardens than like the farms we know. Much food has to be imported, but the manufactures furnish money to pay for it. The foreign trade of Belgium is larger than that of any other small country except the Netherlands.

429. Cities and Commerce.—Brussels is the capital (Fig. 418), and has many manufactures, among which those of lace and carpets are important. Antwerp, on the river Scheldt, is the chief seaport of Belgium. It is one of the greatest seaports of Europe, and its ships go to America and all other parts of the world. Belgium has, through Antwerp, a large transit trade; that is, it receives many foreign goods and sends them on to other countries of Europe. Liege is the important city of the hilly interior, and the chief manufacturing center of Belgium. It is in a region of large coal fields, and manufactures woolen goods and steel goods, including firearms.



Fig. 418. City Hall, Brussels

Belgium controls nearly all of the great Congo River basin in Africa, and trades in its rubber and other products.

THE NETHERLANDS

430. Surface.—The Netherlands is often called *Holland*, the name of one of its provinces. The whole country is a little larger than Belgium, and about one fourth the size of the state of New York. The land is a low plain, like northern Belgium, which adjoins it. Several rivers cross the country, of which

the Rhine is the largest. Much of the southern part of the Netherlands belongs to the delta of this great river. A large bay, the Zuider Zee, deeply indents the northern half of the country.

The name *Netherlands* means that the land is low. Indeed much of it lies lower than the surface of the sea. Several centuries ago the inhabitants, the Dutch people, began to build embankments around the coast swamps. These embankments are called *dikes*, and there are now many hundred miles of them.

In places they are as much as thirty feet high. The lowland within is kept free from water by pumping, and is occupied by farms and towns. For centuries the pumping has been done by means of the large windmills often seen in pic-



Fig. 419. A dike in Holland, used as a roadway



Fig. 420. Windmills in Holland

tures of this country (Fig. 420). Now some of the pumping is done by means of steam. The people are very industrious and determined, and long ago when their liberties were threatened by the armies of Spain, they sometimes opened the dikes and flooded the lands, in order to defeat the enemy. Many canals are needed to drain the lands and to carry away the water, and these form a network over the country and are used by boats. In some cities, as in Amsterdam, there are canals in many of the streets.

431. Industries.—Clay is abundant, and bricks, tiles, and pottery are made in large quantities. There is not much coal or iron in the country, and hence the people are engaged more in farming than in manufacturing. They raise live stock and cultivate many vegetables, fruits, and flowers for home and foreign markets. One of their exports is flower bulbs, of which many are sent to the United States. Many of the tulips, hyacinths, and other flowers seen in American lawns

and gardens are grown from Dutch bulbs (Fig. 421). Other important exports are poultry, eggs, butter, and cheese (Fig. 422).

432. Commerce and Cities.—The Dutch have always been stubborn fighters, good traders, and excellent sailors. Like the early English and Spanish navigators, they helped to find new lands. The Dutch still have rich possessions in the East Indies and some small islands in the West Indies. Java and other islands in the East Indies furnish coffee, spices, and other products, which Dutch merchants carry to Europe and sell in many markets. The Dutch have a greater foreign trade than any other nation except the United States, Great Britain, Germany, and France.

The capital is a city known as the Hague. It has a splendid art gallery. Rotterdam is one of the world's greatest seaports. Its harbor is used not only by many seagoing ships, but also by river steamers that connect it with Dusseldorf, Cologne, and other cities on the Rhine.



Fig. 421. A field of tulips at Haarlem, Holland



Fig. 422. Cheese market

Amsterdam, near the south end of Zuider Zee, is the largest city of the Netherlands. It is built on a number of islands connected by bridges. A canal joins the Zuider Zee and the port of Amsterdam with the North Sea. Thousands of diamond cutters carry on their industry in Amsterdam, and thousands more do the same in Antwerp. The jewels cut in these two great cities of the Netherlands and Belgium find their largest market in the United States.



Fig. 423. Copenhagen, the great port of Denmark

Review.—1. What is the density of population in Belgium? 2. What languages are used there? 3. Name the capital and two other cities of Belgium. 4. Give an account of Antwerp. 5. What are the main industries of Belgium?

6. What part of the Netherlands belongs to the delta of the Rhine? 7. Describe the means by which the Dutch people have reclaimed much of their country from the sea. 8. In what ways has the position or the character of the country affected the occupations of the people? 9. What interesting export of the Netherlands comes to our country? 10. Give an account of the diamond-cutting industry. 11. Where are the colonial possessions of the Dutch people?

DENMARK

433. Land and Industries.—Denmark consists of the larger part of the peninsula of Jutland, and of several large islands in the Baltic Sea. On one of these islands is Copenhagen, the capital, one of the large cities of Europe (Fig. 423). All the shipping that enters or leaves the Baltic Sea must pass Copenhagen, unless it goes by the Kiel Canal.

The land is low

and flat or gently rolling. The soil is not of the best, and the climate is too cool for any but hardy crops. Oats, barley, and rye are the chief cereals, but the main industries are dairying (Fig. 424) and the raising of swine and poultry. There are so many cows that some cattle food is imported, including much cottonseed meal from the United States. The chief export is butter, which is sent to Great Britain. The skimmed milk is fed to poultry and hogs. Pork and eggs are produced in large quantities for export.

There are no minerals of value, except clay. Fuel must be imported, and manufactures cannot be large. There are many peat bogs, as in Ireland, and some fuel is taken from them.

434. Iceland.—The king of Denmark is also the king of Iceland, in the north Atlantic. Iceland is a cold country, especially on the north. Sheep, cattle, and horses are raised, some fish are caught, and the eider duck furnishes eider down for export. In Iceland there are volcanoes and geysers.

Greenland and the Faroe Islands belong to Denmark.



Fig. 424. Danish women carrying pails of milk



Fig. 425. Haying in Norway. Because of the moist climate, the grass is placed on trellises to dry

NORWAY

435. Surface.—The Scandinavian Peninsula is bordered by the Atlantic and Arctic oceans, and by the Baltic Sea and the Gulf of Bothnia. It includes two separate kingdoms, Norway and Sweden. Most of Norway, except in the south, is so mountainous that there is little cultivated land, although there is much pasture. Inlets of the sea, called *fiords*, penetrate deeply into the mountains, and for hundreds of miles the coast is bordered by islands. Ships can go along the coast and far into the interior, in quiet, safe waters.

436. Industries.—There are fewer people in Norway than in Denmark. They get their food and other necessities of life in several ways. They raise many potatoes and other vegetables and a little grain. They keep cattle and produce much milk, butter, and cheese. The grass in the meadows is fine and short, and when it is cut, it is laid on frames or trellises to cure, because in the moist air it would spoil on the ground if the farmers tried to dry it as is done in our country (Fig. 425). In the summer, members of the farmer's household drive the cattle up into the mountains and live there, watching the cattle and making the butter and cheese. Sometimes

they draw up supplies and send down the produce on a long tight wire that reaches from the valley home up to the mountain dairy house.

Lumbering, the manufacture of pulp and paper, condensing milk, and smelting are important industries. Some of the waterfalls are used to develop electricity, and the electrical energy is carried long distances to the mills.

Thousands of Norwegians find work during part or all of the year in the fishing fleets. Like their Viking forefathers, they are good sailors, and Norwegian ships are seen in all parts of the world, carrying the goods of many countries.

437. People and Cities.—Norwegians live among mountains like the Swiss people, but they are also accustomed to the sea, like the Dutch. The hardships of their life are such as to make them a very vigorous people. Many good citizens of the United States, especially west of the Great Lakes, have come from Norway and settled on the fertile prairies. Norwegians speak the same language as the people of Denmark.

Christiania is the capital and the largest city and the chief industrial center. It has nearly one tenth of the total population of Norway. Bergen is the second city and the chief fish market.

SWEDEN

438. Industries.—Sweden is less mountainous than Norway, and has a greater area of fertile soil suitable for grain, hay, and pasture. Dairying is an important industry, and butter is exported to England. More than half of the country is covered with forest. Much wood pulp and paper are made, besides many other wood products. Hundreds of sawmills, planing mills, and furniture factories are kept busy; and the exports of timber and of articles made of wood are far larger than any others. The forests are protected by limiting the amount of timber that may be cut each year.

Sweden has deposits of iron ore that are among the largest and best in Europe, and there are many iron furnaces. Some of the iron ore is sent to other countries, especially to England. The Sheffield factories buy much of it for

cultural land, more timber, and more minerals with which to make their living.

Stockholm is the capital and largest city of Sweden (Fig. 427). It is an important port, although closed by ice in winter. Goteborg, in the southwest, close to Denmark, has an open port and a large trade. Swedes, like Norwegians, have come to our country and are prosperous citizens of many of our states.

439. Climate of Sweden and Norway.—In both the Scandinavian countries the summer season is short, but the summer days are long.

In southern Sweden the midsummer night is only about six hours long. At Trondhjem, the old capital of Norway, a July night lasts about four hours. At the North Cape, for several weeks in the summer, the sun does not set at all, and this is "the land of the mid-night sun."

Although the growing season is short, and wet or cloudy days are frequent, the crops have the benefit of some long sunny days. It is for this reason that grain and vegetables can grow rapidly and ripen quickly so far north.

Review.—1. Where is Copenhagen? Why is its position important? 2. What is the main agricultural interest of Denmark? 3. Give an account of Iceland.

4. Describe the shore line of Norway. 5. How are the farming and dairy industries carried on during the summer? 6. What are the other large industries? 7. What

facts make Bergen an important city? 8. In what respect is Sweden inferior to Norway? 9. In what industries does it surpass Norway? 10. What is the length of midsummer nights in various parts of the Scandinavian Peninsula? 11. State the location and importance of Stockholm; of Goteborg.



Fig. 426. A waterfall in Sweden



Fig. 427. Parliament House, Stockholm

making steel tools. As in Norway, electrical energy is developed at waterfalls (Fig. 426), and this power is used in the wood-working and iron-working industries.

The Swedes do not sail so many ships as the Norwegians; but they have more agri-

POLAND AND THE BALTIC STATES

440. Poland.—Poland became a separate kingdom nearly one thousand years ago. During long periods it embraced large areas in central and eastern Europe. In general the Carpathian range formed the southern boundary and the Baltic shore was the northern limit. More than one hundred years ago the country was divided among the sovereigns of Prussia, Russia, and Austria. Notwithstanding prolonged persecution the Poles kept their language, their national feeling, and their desire for independence.

Following the World War the Polish people gained their freedom and reunited under a republican form of government. The western boundary of Poland was located partly by the treaty of 1919 and partly as the result of a plebiscite (1921) in the rich coal-mining region of upper Silesia (Fig. 409). The eastern boundary was agreed upon after a hard-fought war between Russia and Poland in 1920.

The Vistula is the great river of Poland and most of the country lies in its basin. On its upper waters and not far from the Carpathian Mountains is Krakow, the ancient capital (Fig. 428). Near the middle of the country on the banks of the river is Warsaw, the present capital (Fig. 429). The city has about 900,000 people and is the chief



Fig. 429. Market in the Jewish quarter of Warsaw

railway center. Railway lines connect Warsaw with Krakow and Vienna, Berlin, Danzig and the Baltic Sea, Petrograd, Moscow, and Odessa. Posen is an important city in the region recovered from Germany.

The country is low and flat, except for the foothills of the Carpathians and the glacial hills in the north. In this northern or glacial region there are many lakes and large swamps. A large part of this area is covered with forests.

The leading occupation is agriculture, and the principal crops are rye, oats, wheat, potatoes, and sugar beets. Fine horses, cattle, and sheep are raised. The manufactures include cotton and other textiles, leather, iron, and steel. These industries center



Fig. 428. Bread market in Krakow



Fig. 430. A group of Polish peasant women



Fig. 431. Polish farm house, with roof of thatch

mainly in Warsaw and Lodz. The latter city is especially known for its cotton mills.

Among the mineral resources are coal, iron, zinc, and salt. Not far from Krakow are some of the most remarkable salt mines in the world. The beds of salt are of great thickness and extend for several hundred miles. Like other beds of rock salt they are due to evaporation of sea water in ancient periods of time. Near Krakow is a mine with 48 miles of galleries at different levels down to 900 feet. It has been worked for hundreds of years and is like an underground town. The province of Galicia also has a large output of petroleum.

441. Danzig.—Danzig was for centuries a Polish city but in the dissolution of Poland it came under the rule of Prussia, and it is now peopled mainly by Germans. It is the great seaport at the mouth of the Vistula, and is the chief outlet available for the foreign trade of Poland. At the close of the World War it was internationalized and was made a free city under the care of the League of Nations. Definite privileges in the use of docks and railways are given for the promotion of Polish commerce.

442. Small Baltic States.—Three small countries on the eastern shore of the Baltic Sea have declared their independence of Russian control and have set up republican governments. They are Esthonia, which lies south of the Gulf of Finland; Latvia, on the Gulf of Riga; and Lithuania, which is south of Latvia. Each of these countries is larger than Denmark, but has a smaller population. The Letts and Lithuanians belong to the white race and use kindred forms of speech. The Esthonian language is of Mongolian origin.

Latvia includes the important commercial city of Riga, at the mouth of the Duna, a navigable river flowing out of Russia. The lands of all these countries were covered by the ice sheet of northern Europe, and contain many lakes and swamps and much forest. Lumbering, fishing (Fig. 432), and agriculture are the principal industries.

Review.—1. Outline the history of Poland. 2. Name and locate three important cities on the Vistula River. 3. What is the leading industry of Lodz? 4. What are the chief mineral deposits found in Poland? 5. Give an account of the salt mines. 6. Where is Danzig? 7. Why was this city internationalized at the close of the World War? 8. Name and locate the small Baltic states. 9. What important city is in Latvia? 10. What are important surface features of these countries?



Fig. 432. Fishing boats and sailing vessels at Libau, a Baltic port



Fig. 434. Vineyard in southern France, near Bordeaux. The grapes are used in making wine

FRANCE

AREA, 212,822 sq. mi. POP., 39,210,000. CAPITAL, Paris.

Map Study.—1. What barrier separates France from Spain? From Italy? 2. What countries border France on the east? 3. What waters are on the north, west, and south?

4. Describe the four chief rivers, in respect to their positions and their courses. 5. Locate Havre, Bordeaux, and Marseille. 6. Locate Paris, Lyon, and Lille. 7. With the scale of miles determine the distance between Havre and Marseille. 8. What port of France is opposite Dover in England? 9. Name the westernmost port of France.

PHYSICAL GEOGRAPHY

443. Climate and Rivers.—France is much smaller than the state of Texas. It has little waste land, however, and supports about 40,000,000 people. It is farther south than Great Britain and therefore has a warmer climate, especially in the part that borders the Mediterranean Sea. Paris is in latitude 49° north, the same latitude as the

boundary between western Canada and the United States.

The central and western parts of France slope toward the Atlantic Ocean and the English Channel, and are drained by three large rivers. To the north is the Seine, on which Paris is situated, with Havre at its mouth. Next southward is the Loire, on which are Orleans and Tours, with the ports of Nantes and St. Nazaire near its mouth. In southern France is the Garonne, with Toulouse on its course and Bordeaux near its mouth. Eastern France drains to the south by the Rhone and eastward to the Rhine. On the Rhone, where the Saone flows into it, is Lyon, and near the mouth is Marseille, the second city of France, and its largest seaport. The Rhone has a large delta, whose flat, swampy land is not suitable for a city, and the large Mediterranean seaport of France is located on higher ground to the east.

444. Highlands.—The main highland is in the interior of France, around St. Etienne, and extends to the north, south, and west.

It consists of low, well-worn mountains and hills. France has several uplands on its borders. To the south the high Pyrenees separate it from Spain. They are so high and unbroken that the railways between France and Spain pass around the ends of the range. On the southeast the Alps separate France from Italy. Mont Blanc, the highest peak in Europe, with an altitude of 15,781 feet, is in France (Fig. 435). Between France and Switzerland are the low Jura Mountains, while the Ardennes highlands are on the Belgian border. The Vosges Mountains are in eastern France near the Rhine.



Fig. 435. Mont Blanc

PEOPLE AND INDUSTRIES

445. History and People.—In the time of Julius Cæsar, this region was called Gaul, and he made it part of the Roman Empire (Sec. 387). In modern times it has been sometimes a monarchy and sometimes a re-

public. Under the Emperor Napoleon Bonaparte the country was for a time greatly enlarged. After many other changes, France in 1871 became a republic, as it is to-day. It has a president, a senate, and a chamber of deputies, and thus has a form of government somewhat like ours.

The French language has been derived from the Latin by many centuries of gradual change. It has

long been studied and spoken by educated people in many parts of Europe and in other lands.

The French have good schools, and a great national university which includes many colleges scattered over France. The people are industrious, skillful, thrifty, and patriotic, and are great lovers of all beautiful things. Population has not increased rapidly in recent years, and few French emigrants have gone out to settle in other countries.

446. Alsace-Lorraine.—The provinces of Alsace, on the Rhine, and Lorraine, on the Moselle, were taken by Germany in 1870-1871, but were recovered by France in 1918. They are about as large and as populous as Connecticut and Rhode Island. Their restoration to France is of immense importance because of their mineral resources and manufactures. Lorraine has extensive beds of iron ore. Alsace has great textile industries, vast deposits of potash (Fig. 436), and some salt and petroleum. Its chief city is Strasbourg, which carries on a large trade.

447. Forests and Agriculture.—The French people appreciate the value of trees; they take good care of the forests, plant many young trees, and let no wood go to waste. Even small twigs are cut up and tied in bundles, for kindling.



Fig. 436. Potash mine, Alsace. Most of the potash is used in fertilizers

France is a land of small farms, which are usually owned by the farmers, and not, as so commonly in Great Britain, by the nobility. For this reason the farmers take interest in their land and raise good crops. They raise about one third as much wheat as we do in the entire United States, and, unlike the British, provide nearly all their own bread. The average wheat field in France yields about 20 bushels an acre (Fig. 437). There are many flour mills to prepare the grain for use. The people produce much of their own meat supply and an abundance of fruit and vegetables. They economize carefully and make a small supply go a long way towards a comfortable living. In the fields the peasant women often work beside the men. It is common for the farmers to live in village communities and go out to work in the fields.

Many chestnuts and walnuts are raised, and the walnuts are an export to the United States. We buy them under the name "English walnuts." In the warm southern parts of France olive trees flourish, and the fruit is bottled, or is pressed for the oil. One of the most important products is grapes.

The care of vines, the gathering of the grapes, and the making of wine and raisins are branches of the grape industry. In France the vineyards extend up the Rhone and Saone valleys and into the valleys of the Seine, the

Moselle, and the Rhine. All of France south of Paris has valleys where vineyards abound, especially along the Garonne and its branches (Figs. 434, 438). So much wine is made in this southwestern part of the country that Bordeaux is the most important city in the world for trade in wine.

448. Manufactures.—The French do not manufacture so extensively as do the people of the United States or Great Britain, but they make some things extremely well, especially such artistic things as fine jewelry, dress fabrics, laces, tapestries, gloves, and perfumery. For the operation of their large mills and factories part of the coal must be imported, and in the iron and textile industries France does not take rank with Great Britain, which supplies all its own fuel.

Northern France is the region that includes Paris and extends to the English Channel and the Belgian boundary. It has more factories than any other part of the country. This is because there are coal and iron along the Belgian border as there are in Belgium. There are also iron mines in Lorraine, and France owns the coal mines of the Sarre Basin, north of Lorraine.

Bales of cotton and other raw materials are brought by ship to Havre, and from this port they are taken by rail or by smaller boats up the Seine to Rouen and Paris. Paris manu-



Fig. 437. Harvesting wheat, France



Fig. 438. Young grape pickers

factures clothing and many things that require fine skill and artistic taste. At Rouen and Mulhouse are large cotton mills. It was in Rouen that Joan of Arc, a famous French heroine, met her death. Lille makes textile and iron goods. It gives the name to lisle thread, much used in making gloves and hosiery. Amiens, Reims, and other cities make woollens. These two places and Rouen contain celebrated old cathedrals (Fig. 439).

Lyon and the region near it form the second greatest manufacturing part of France. The silk industry is foremost in Lyon (Sec. 449). Southwest of it is St. Etienne, which is near a coal field and has iron works, but much silk ribbon also is made there. Farther north is Le Creuzot, the chief iron-working city of France. It resembles Pittsburgh in the United States and Birmingham in England, but does not equal either of those cities in the amount of its manufactures. Fine porcelain ware is made at Limoges in south-central France, and at Sevres, a few miles from Paris.

449. Lyon and the Silk Industry.—Lyon is an ancient city at the junction of the Rhone and Saone rivers (Fig. 440). During more than two thousand years the valley of these rivers has afforded a lowland road from the Mediterranean Sea to northern Europe and Great Britain.

All about Lyon are groves of mulberry trees. The leaves are picked and fed to silkworms. When full grown the worms or caterpillars form from their bodies the silk fiber and wind it around themselves, forming cocoons. These very fine fibers are carefully unwound and made into silk thread and



Fig. 440. Factories at Lyon on the Rhone

silk fabrics. Lyon makes more silk goods than any other city in the world, though other cities have large silk industries. Among these are St. Etienne in France, the chief center for the manufacture of ribbons, and also Crefeld in Germany, Milan in northern Italy, and Paterson in New Jersey. Only part of the silk fiber used in Lyon comes from France. Much of the raw silk is produced in Italy, or is brought in by way of Marseille from China and Japan.



Fig. 439. Cathedral at Reims, which was much damaged in the World War

450. Paris.—Paris, on the Seine, is the capital of France. It is the fourth city of the world, with a population of about 3,000,000. It is one of the most beautiful cities in the world, because of its fine buildings, splendid avenues, its parks, and its works of art. It lies on both sides of the river, which is crossed by many bridges. Around it is much of the most fertile land in France, and railroads run from it to all parts of France and most of the other countries of continental Europe. Ex-



Fig. 441. Paris and its seaport, Havre

press trains go to Rome, Constantinople, Berlin, and Moscow, while a few hours of railroad travel and a short passage on the English Channel take the traveler to London.

The cathedral of Notre Dame in Paris is one of the finest in Europe (Fig. 442), and the Louvre, an art gallery, contains many of the world's greatest treasures in painting and sculpture. Among these is the Mona Lisa, a painting by Leonardo da Vinci, and the Venus de Milo, one of the beautiful Greek statues of an earlier time. Many articles of dress and ornament are made and sold in Paris, which is the world's center for fashionable dress. The exports from Paris to the United States are very large.

451. Waterways and Sea-ports.—The main rivers have been deepened in places to fit them for navigation, and the larger rivers have been joined to one another by canals (Secs. 383, 384). Freight can thus be taken from Paris northward to

Brussels and Antwerp; or eastward to Strasbourg on the Rhine; or southward to Lyon and Marseille. In like manner boats go from Bordeaux up the Garonne River and to Marseille. Starting from the mouth of the Rhone, one could go by boat to Bordeaux; to Nantes by the Loire; to Havre; to Antwerp or to Rotterdam by way of Lyon, Strasbourg, and the Rhine.

Marseille (Fig. 443), Havre, and Bordeaux are the most important seaports. Cherbourg, Boulogne, and Brest are other ports much used in trade with the United States, while Calais and Dieppe are the chief ports of departure for England.



Fig. 442. Cathedral of Notre Dame, Paris

452. The Riviera and Small States on the French Border.—The word Riviera means shore line, but it is especially applied to the coast of southeastern France and northwestern Italy. The region is protected from north winds by high mountains, and it is so warm that palms and oranges grow there, although in the latitude of our northern states. It is a winter resort for Europeans and Americans (Fig. 444).



Fig. 443. Wharf at Marseille




Fig. 444. The Riviera, near the boundary between France and Italy

On this shore is the independent principality of Monaco, containing only eight square miles, and best known because of the resort called Monte Carlo.

At the point where France, Belgium, and Germany come together is the grand duchy of Luxemburg, a hilly region of about 1000 square miles, with a population of about 260,000. It supplies much iron ore to the adjoining manufacturing districts.

The Sarre Basin, between France and Germany, is a little smaller than Luxemburg. It is controlled by the League of Nations, but its rich coal mines belong to France.

The republic of Andorra, in the Pyrenees, is under the protection of France and Spain. It has a territory of 175 square miles, and about 5000 inhabitants.

453. French Foreign Possessions.—The French possessions include parts of Africa, Asia, and South America, and a number of islands (Fig. 350). Algeria and Tunis in north Africa are the most important, and France controls much of the Sahara and Sudan and part of the Congo River region. Other possessions are in Indo-China in south-eastern Asia, the island of Madagascar off the east coast of Africa, St. Pierre and Miquelon near Newfoundland, Guadeloupe and Martinique in the West Indies, French

Guiana in South America, and many islands in the Pacific Ocean.

Review.—1. Give the size and population of France. 2. Name the highlands on the south and east borders of the country. 3. When did France finally adopt its present form of government?

4. What difference exists between the farms of France and of Great Britain? 5. Give an account of wheat raising in France. 6. Where are the grape districts of the country? 7. Name and locate the chief trading center for wine.

8. Name the chief centers and kinds of manufacture in northern

France. 9. Explain why the possession of Alsace-Lorraine is important. 10. Name two cities not far from Lyon, and give their industries. 11. How is silk fiber obtained? 12. What countries produce the most of it? 13. What cities are centers of silk manufacture?

14. Name some interesting buildings in Paris.

15. What are the railway facilities of the city?

16. Describe five routes by which a boat may go by river and canal from the Mediterranean Sea to the Atlantic Ocean, the English Channel, or the North Sea.

17. Where is Andorra? Monaco? The grand duchy of Luxemburg? The Sarre Basin?

18. Name the foreign possessions of France.

SPAIN AND PORTUGAL

	AREA, SQ. MI.	POPULATION	CAPITAL
Spain	192,000	20,784,000	Madrid
Portugal . . .	34,264	5,546,000	Lisbon

Map Study (Fig. 433).—1. Give the land and water boundaries of the Iberian Peninsula. 2. What three rivers have their courses partly in Spain and partly in Portugal? 3. What cities are at the mouths of two of these rivers? 4. What is the chief river of southern Spain? 5. What river of northern Spain flows into the Mediterranean? 6. Name and locate the capitals of the two countries. 7. What group of islands is near Spain on the east? 8. What mountains are in the northern part of Spain? In southern Spain?

454. Physical Geography.—The Iberian Peninsula, including Spain and Portugal, is a little larger than France, and contains about 25,000,000 people. The greater part of the peninsula is a plateau 2000 feet or more above the sea. The lowlands are found in a narrow strip along the coasts and in the valleys of the larger rivers. Above the plateau rise a number of east and west mountain ranges. The highest of these ranges, the Pyrenees and Cantabrian Mountains in the north, and the Sierra Nevada in the south, carry snow on their upper slopes throughout the year. One can stand on the shores of the warm Mediterranean and see the eternal snow fields of the Sierra Nevada.

In the winter the peninsula is in the track of the westerly winds, and the lands near the Atlantic receive rains; but the rainfall in the interior is small. In the summer the northeast trade winds cross the peninsula (Sec. 386), and the rainfall is small. The interior is so far from the sea that its climate is continental, being cold in winter and hot in summer.

The coast line is regular, and there are few good harbors. The rivers do not afford much navigation, both because they flow mainly on the interior uplands, and because the country is too dry to furnish much water.

455. History and People.—At the time of the discovery of America, Spain and Portugal were among the strongest countries in Europe, and they gained great possessions in the New World. They have from time to time lost these, but Spain still holds the Canary Islands and parts of western Africa. Portugal has the Azores Islands and the Madeira Islands (Fig. 350); also large territories in the eastern and western parts of southern Africa, and some small possessions in southern Asia.

Spain is a monarchy, but Portugal in 1910 passed through a revolution and adopted the republican form of government. The Span-

ish and the Portuguese people have lived from generation to generation without much change of any kind. More than half of the people cannot read or write. There is now some desire to improve, to have better education, better homes, and more liberty. This is shown by the change of government in Portugal, and by the growth of modern industries in some parts of Spain.

The Spanish and Portuguese languages, like the French, are derived from the Latin tongue, and the countries belong with France and Italy among the Latin countries of Europe.

456. Agriculture.—Much of the interior is not suited to crops (Sec. 454), but is used for pasture, especially for sheep, of which many are kept in Spain. It was from the flocks of Spain that the well-known Merino sheep were taken to start flocks in the United States and other countries.

Wheat is the principal grain, and is raised in the north of Spain around Valladolid, and



Fig. 445. Sorting oranges for shipment, near Valencia, Spain

in the basin of the Ebro. All along the coast, from Barcelona to Oporto, orange trees flourish, especially north and south of Valencia, a seaport that exports oranges (Fig. 445). The olive grows in the same belt, and farther north on both coasts. In the interior irrigation is extensively used in raising these fruits. The vine is cultivated also on all the coasts and far up the valleys of the main rivers.




Fig. 446. Cork oak

Like France and Italy, the peninsula produces and exports large quantities of wine. Port wine derives its name from Oporto in Portugal. Another important export is cork (Fig. 446), from the bark of the

principal center of manufacturing in Spain, especially of textiles. Valencia is another important seaport because it is in the center of a large irrigated orange region, and ships thousands of boxes of this fruit to foreign countries. It also exports great quantities of onions, raisins, and almonds, which are raised in that part of Spain.

Iron, copper, and lead ores are found in large quantities in Spain. They are shipped from Cartagena and several smaller seaports on the south shore. The greatest port for iron, however, is Bilbao in northern Spain, on the Bay of Biscay (Fig. 448). Much ore is shipped from this place to Great Britain and Germany. As there is coal also not far away, Bilbao has furnaces for separating the iron from the ore and for making steel. Spain is

cork oak, which grows in both countries.

457. Cities and Trade.—Spain and Portugal are backward in manufactures, and their chief exports consist of fruits and fruit products and minerals. The railroads are poorly developed, and the rivers are only in a small degree navigable. Most of the commercial centers, therefore, are near the sea.

The chief seaport, and the second city of Spain, is Barcelona, on the Mediterranean. It is also the

exceeded only by Italy as a producer of the curious but important metal known as mercury, or quicksilver. It is found around Almaden, south of the center of the country.

Lisbon (Fig. 447) and Oporto are the chief seaports of Portugal. They export wine, cork, olive oil, and fruit.



Fig. 447. Avenue in Lisbon, Portugal



Fig. 448. Loading iron ore at Bilbao. The cables carry the small cars from shore to ship

Madrid is the capital and the largest city of Spain, with a population of more than half a million. It is on the interior plateau, surrounded by a dry and barren region that is cold in winter and hot in summer. It has fine streets, magnificent palaces (Fig. 449), and a splendid gallery of pictures. It is a railway center and has some manufactures of porcelain, glass, and metal ware, and is especially important as the home of the rich and ruling classes.

458. Moors in Spain.—Many hundreds of years ago much of southern Spain was conquered and held for a long time by Moors, a Mohammedan people that came from Africa. Their chief city was Granada, on the north of




Fig. 450. The Rock of Gibraltar

great fortress, one of the strongest in the world. Its guns command the entrance to the Mediterranean Sea, and some British warships are always to be found there. Between Gibraltar and Spain is a narrow strip of flat land that is unoccupied and is considered as neutral ground; that is, belonging to neither.



Fig. 449. The Royal Palace, Madrid

the Sierra Nevada. Here is the Alhambra, a palace that is a wonderful example of Moorish skill in building. It is described in Washington Irving's book of that name.

459. Gibraltar.—Just inside the Strait of Gibraltar on the European side is a peninsula from which rises the great rocky height with steep sides, known as Gibraltar (Fig. 450). The rock, with its sloping base, covers an area of nearly two square miles, and is occupied by a population of about 25,000, many of whom are soldiers. The British people, who own Gibraltar, have made it a

Review.—1. How do the countries of the Iberian Peninsula compare with France in area and population? 2. Give a general description of the surface. 3. Why does most of the peninsula have little rain? 4. How does the coast line differ from that of Great Britain?

5. What are the foreign possessions of Spain? Of Portugal?

6. When did Portugal adopt its

present form of government? 7. What is the condition of the Spanish and Portuguese peoples?

8. What kind of live stock is kept in Spain?

9. What is the principal grain? In what part of Spain is it most raised? 10. Where are oranges produced? Olives? Grapes?

11. Name and locate the chief commercial city of Spain. 12. What kind of manufacture is important there?

13. What seaport is the chief Spanish place for trade in oranges and onions?

14. Locate Bilbao and explain its importance.

15. Where is mercury mined? 16. Give some important facts about Madrid.

17. Name and locate the chief Moorish city of Spain. 18. What is the Alhambra?

Fig 451. Physical and Political
ITALY, ROMANIA
 AND OTHER COUNTRIES OF
SOUTHERN EUROPE

Scale of Statute Miles
 0 50 100 150
 0 50 100 150 MILES TO ONE INCH

Capitals of Countries: ○
 Principal Railroads: —
 ELEVATIONS IN FEET
 OVER 5000
 2000 TO 5000
 1000 TO 2000
 500 TO 1000
 SEA LEVEL TO 500





Fig. 452. A Swiss farmhouse in a valley of the Alps in summer

SWITZERLAND AND ITALY

	AREA, SQUARE MILES	POPULATION	CAPITAL
Switzerland .	15,956	3,880,000	Bern
Italy . . .	123,000	40,070,000	Rome

Map Study.—1. What countries border Switzerland? 2. What countries border Italy? 3. What large islands are a part of Italy? 4. Trace the course of the two chief rivers of Italy. 5. Locate Mt. Vesuvius and Mt. Etna. 6. Where is the island of Elba?

7. What is the capital of Switzerland? 8. Locate Zurich and Geneva. 9. Locate Milan and Turin, in Italy. 10. Locate Genoa and Venice. 11. Locate Florence, Leghorn, and Naples. 12. Where is the Strait of Messina? Locate Palermo.

SWITZERLAND

460. The Swiss Land.—Switzerland is only about one third as large as the state of New York. Although much of its surface is too high and rocky for farms and homes, the population is on the average about 240 people for every square mile. Here, as in Belgium and in England, many people are able to live in a small country because they are enterprising and produce a variety of manufactures which they sell to buy food and clothing.

Switzerland includes the central parts of the Alps, with hundreds of mountain peaks and hundreds of snow fields and glaciers (Fig. 452). In the lower valleys are vineyards, gardens, and fields of grain. On the lower

slopes of the mountains are the common trees with broad leaves such as beech and maple. Higher up are evergreen forests and grassy pastures, and above these are snow and rocks. Far above the tree limit, wild flowers of many colors bloom in summer on the stony slopes.

On the higher mountains the air is cold and the snows remain year after year. We call the lower limit of snow the *snow line*. On steep slopes the snows

sometimes slide down in great masses, destroying trees and houses. Such a slide is an *avalanche*. When the snows pack together in the high valleys and change to ice, the ice may form a slowly moving glacier (Fig. 374).

Among the celebrated peaks of the Swiss Alps are the Matterhorn and the Jungfrau.

The northern part of Switzerland is a hilly plateau, 1000 to 2000 feet above the sea. Here are most of the farms and all the cities and largest towns. This region is sometimes called the Swiss lowland, because it is low as compared with the mountains. There are several large lakes. The most important are the Lake of Lucerne, Lake of Geneva (Fig. 453), and Lake of Constance. The Lake of Constance is on the boundary between Switzerland and Germany, and the Lake of Geneva is partly in France.

Switzerland is in the track of the westerly winds, and as it has so many high mountain ranges, much rain and snow fall, the fields are well watered, and the mountain snows are the source of great rivers (Sec. 383). Because the country is inland, it has a continental climate. Even among the snow-capped mountains, the valleys are warm in summer, and the whole country is cold in winter.

461. The Swiss People.—Life in the mountains tends to make people independent, strong, and home loving. Such a country is easier to defend than a flat and open region.



Fig. 453. Lake of Geneva, seen from the city of Geneva

For centuries the Swiss have been a brave and independent people. Whether William Tell ever really shot the apple from the head of his son, or not, the story gives a true idea of the people. They could not be easily subdued, and the greater powers of Europe have agreed to guarantee the independence of this little country.

The country is divided into a number of small states called *cantons*. These are united into a republic, at the head of which is a president, who is elected annually. Three principal languages are spoken. In the east and north, bordering Germany, most of the Swiss speak German. In the west, they speak French, and in the south, Italian.

On the farms and in the villages the Swiss build most of their houses of wood, because it is plentiful. Some of the houses are large and have several stories. They often include barn room also, the cattle and other stock, with the hay and grain, being under the same roof with the family. The roofs project far over the sides of the house, or *chalet*, giving it a homelike and graceful appearance (Fig. 452).

462. Swiss Industries.—The farmers raise the common grains and vegetables, and there are many vineyards in the warmer lowlands, and on the steep slopes around the Lake of Geneva. In the mountain valleys the chief industry is dairying. The thrifty farmers



Fig. 454. Swiss farm yard

save every bit of grass that they can gather for hay, and they drive the cattle to the upper pastures in the summer, somewhat as the Norwegians do (Sec. 436). The hay and wood from the higher fields and forests are dragged down the mountain side; and even young boys carry milk on their backs in large casks which are flat on the side that rests against the back.

The Swiss are skillful in making things in their homes. Many of them spend the winter days and evenings carving ornaments and trinkets from wood, which they sell to the next summer's tourists. In the cities the Swiss artisans are very skillful. They make silk, cotton, and other textiles, and also many million dollars' worth of embroidery each year. Much of this embroidery is sold in America. The Swiss also make jewelry and an immense

number of watches. Many Americans have seen, or perhaps carry every day, a watch made in Geneva or Neuchatel. The Swiss make many kinds of cheese for home use and for export. Zurich (Fig. 455) is an important trade center and manufactures both silk and cotton goods.

Switzerland has no good coal, but it imports some, and also uses the water of its streams and waterfalls to furnish power. Because the Swiss are so thrifty and skillful, they have a foreign trade that amounts each year to much more than that of Spain, a country with a population nearly five times as large.

463. Travel in Switzerland.—Switzerland has been called the “playground of Europe.” British people are fond of going there for their summer “holiday,”—a word which they use to mean vacation. Thousands of Germans and Austrians also love to tramp among the mountains, and in the summer American tourists are seen in all the hotels and on all the roads. The Swiss mountaineers spend most of their summers keeping boarders, supplying vegetables, or acting as guides to visitors.

Alpine guides are daring but trustworthy, and with their aid many travelers climb the various summits of the Alps every summer. Sometimes these guides are taken to Asia or South America to help mountain climbers in those lands.



Fig. 455. Lake front of Zurich, the largest city in Switzerland

The roads of Switzerland are well built, and many of them are made by blasting the rock from the mountain side. Stages, known as *diligences*, carry people over many of the roads. Switzerland has a good railroad system. The Swiss have built mountain railroads by which they carry passengers up steep slopes (Fig. 456), and even to the tops of several of the high peaks. Many people

Long tunnels have been made under some of the ranges, so that railroad trains can go through without climbing to the top; also the trains can pass through in winter as well as in summer. The Simplon tunnel is the longest of the great tunnels on railroads that connect Switzerland and Italy. It is about twelve miles long, and a train passes through it in about twenty minutes. In the tunnel trains are moved by electricity, so that the air is kept free from steam and smoke. It required great engineering skill to construct so long a tunnel. The work was carried on from both sides of the mountain range at the same time until the two parts met.



Fig. 456. Electric railway up the Jungfrau, an Alpine peak in Switzerland

are thus enabled to have splendid views from mountain tops.

464. Passes and Tunnels.—High valleys leading from one side of a mountain range to the other are known as *passes*. They are of far greater importance to the student of geography than are the most wonderful mountain peaks. This is true because of the influence of passes upon the location of routes of trade and travel. There are many passes in the Alps, and at the summits of a number of them were formerly built refuges, or hospices (Fig. 457), where devoted monks lived to help travelers in the cold and storms. The St. Bernard monks and their dogs still do this work.

Review.—1. Give the size and population of Switzerland. 2. Define avalanche; the snow line. 3. What is a Swiss state called? What is the Swiss form of government? 4. What are the principal languages of the country? 5. What are the chief manufactures of Switzerland? 6. Define diligence, pass, hospice. 7. Describe the Simplon tunnel.



Fig. 457. Hospice at the Great St. Bernard Pass, on the southwestern border of Switzerland



Fig. 458. Bellagio, a town at the junction of the two southern arms of Lake Como

ITALY

465. Physical Geography.—The most northern parts of Italy are among the southern slopes and peaks of the Alps. Many rivers rise in the glaciers and snow fields, and flow down the slopes and across the plain into the river Po. On their way, some of them pass through beautiful lakes bordered by mountains (Fig. 458). These Italian Lakes are much visited for pleasure and recreation. Several railroads come through long tunnels or across passes and connect Italy with the rest of Europe.

The Po is the chief river of Italy, and it is bordered by fertile plains. It spreads the fine rock waste of the Alps over these plains in time of flood. It has built its delta out into the Adriatic Sea so rapidly that some towns that were on the sea border two thousand years ago are now several miles inland. Smaller tributaries flow into the Po from the Apennines on the south.

In the west, the main Alpine range bends to the south, and joins the Apennines. The

Apennines extend the whole length of the peninsula of Italy, and in parts of the peninsula the mountains and hills occupy nearly its entire width. There are small lowlands on some parts of the shore and along the rivers, among which are the Arno and the Tiber. There are also small basins of flat and rich land high among the mountains. The largest river, next to the Po, is the Tiber, on which stands the city of Rome. The ancient Romans called it the "yellow Tiber," because it was muddy and discolored, as it is now, by the land waste brought from the mountains of the interior.

Much of the island of Sicily, which belongs to Italy, is mountainous, but owing to good soil and a warm climate, the small lowlands are very productive. The island of Sardinia, which also belongs to Italy, is very rugged and is unproductive except in minerals.

466. Climate.—Italy is as far north as our northern states, and yet it has a mild climate, and in the south is so warm that many tropical fruits and palms flourish. The basin of the Po is well protected from cold north winds




Fig. 459. View from Naples, showing part of the city and the bay, and Mt. Vesuvius in eruption

by the great Alpine mountains. The shores of the peninsula and the islands are washed by the warm Mediterranean waters. Winds from these waters blow inland, and except in the higher mountains there is rarely frost.

Most of the rainfall is in the winter, when it is not helpful to crops. In the summer the peninsula is in the belt of the northeast trade winds and has little rain. Hence irrigation is much used. In the Po basin there is more rain, but the plentiful water of the rivers also is employed to irrigate the fields, because in this way two or more crops can be raised in one season.

467. Volcanoes and Earthquakes.—A few miles from Naples is Vesuvius, a volcanic mountain (Fig. 459). Through the crater in the center and top of the mountain, melted rock or lava sometimes pours out and flows down the slopes. At times there are explosions in the crater, and clouds of dust and of larger fragments are hurled out. These darken the sky, and the stones and dust fall on the mountain slopes and build them up. Lavas and volcanic dust soon break up and make fertile soils, and people have gardens and vineyards and

build large towns all around the foot of the mountain. Sometimes a town is partly or wholly destroyed and the people are compelled to leave, but they soon return and build homes again. In the year 79 A.D. a great eruption completely buried two cities, Pompeii and Herculaneum, and in time they were entirely forgotten. After many centuries Pompeii and a part of Herculaneum have been uncovered, the volcanic earth shoveled away, and the streets and many buildings, statues, and even pictures painted on the walls have been found well preserved (Fig. 460).

Vesuvius is a small mountain, only about 4000 feet high, but Etna on the island of Sicily is about two miles high. At its foot are

palms and orange trees, on its slopes are oaks and chestnuts, farther up are evergreen trees, and around the top are perpetual snows. Sometimes eruptions melt the snows, and send down streams of lava that endanger the towns and cities near the mountain.

In the Mediterranean, not far from Sicily, is Stromboli, an island volcano that is always sending out steam and other gases. In much of Italy are found volcanic rocks of former ages.



Fig. 460. House in Pompeii

A valuable product of the volcanoes and of the volcanic rocks of Italy, especially in Sicily, is sulphur. Italy produces also about half of the world's quicksilver, as well as some zinc, lead, and iron.

In southern Italy earthquakes are common. In the year 1908 the large cities of Messina and Reggio were almost completely destroyed, and thousands of people were killed by the falling walls.

468. Italian Farming.—The plains of the Po furnish the largest area of good land in Italy. The soil is rich, level, and well watered. Wheat, corn, and rice are the principal Italian grains. The Italians grow large crops of wheat, and make much use of corn, which the poorer classes eat in the form of thick corn-meal mush. Much rice is grown in the Po Valley, where the fields can be easily leveled and the crops flooded when necessary. Italy is the leading European country in the growing of rice, although some is produced also in other countries of the Mediterranean slope, notably in Spain.

Mulberry trees are grown in many parts of Italy, especially on the plains of the Po; and Italy produces more raw silk than France, though it does not manufacture so much. Grapes are almost as abundant as in France, olives are widely raised (Fig. 461), and oranges and lemons are especially abundant in the southern end of the peninsula and in Sicily (Fig. 462). Nuts are extensively grown. About a million acres are covered with chestnut trees, and the people eat the nuts, boiled or roasted, in place of the potato. Nut meal is also used for making bread. Walnuts and hazelnuts are used at home and also exported. The Italians make large use of vegetables, which grow abundantly in their warm climate.



Fig. 461. Olive orchard, Italy. Sheep grazing

More than half of the Italian people are engaged in agriculture. Many of them do a great amount of hand work, turning the soil by hand and beating out wheat with a flail. For centuries they expended an enormous amount of time and labor in building walls and terracing mountain sides for grapes, oranges, and other fruits. White oxen, large and sleek, with long horns, are often seen at work on Italian farms, or drawing wagons in the streets of the cities (Fig. 464).




Fig. 462. Loading ships with lemons, at a wharf in Palermo




Fig. 463. Macaroni factory, Palermo. The macaroni is hung over frames to dry

469. Manufactures.—The Italians have always made certain things by simple processes, but have also begun to manufacture articles, like textiles and airplanes, that require much skill and the use of complicated machinery. Among the simple manufactures are macaroni and similar bread pastes, made from wheat flour (Fig. 463). The people have long been skillful in plaiting straw, and Florence has been a center for making and selling articles of straw for many hundred years. Thousands of women and children engage in this work. Italians also are expert jewelers, and skillful makers of gloves and lace.

All the salt and tobacco are manufactured and sold by the government. One cannot buy salt at a grocery, as we do in our country, because the government has its own stores for the sale of salt and tobacco, from which it gets a revenue.

Wine is made in immense quantities. Much is used at home, and much is exported. More olive oil is manufactured than in any other country, and

the Italians use it in place of butter. The poorer people still use olive oil in their lamps, as all the people did for hundreds and even thousands of years.

Red coral is obtained on some parts of the coast by diving, or by the use of drag-nets. It is used in Naples, Genoa, and other cities, in making beads and other ornaments. Some Italians, especially at Rome and Florence, are very skillful in fine metal work, and in making mosaics.

Fine marble is quarried in the mountains around Carrara (Fig. 464), and is exported to many countries and also wrought into building stones, statues, and many kinds of ornamental carved work. Superior work in glass is done near Venice and elsewhere.

Silk is manufactured in Milan and in other parts of the kingdom. Much raw cotton for manufacture is imported from the United States, and the industry is growing. Excellent automobiles are made at Turin.

470. History.—Several centuries before Christ the Greeks founded colonies and built cities in southern Italy. Long before the



Fig. 464. Long-horned oxen used in hauling marble from the quarries at Carrara

Greeks came, however, there were people who had learned the arts of civilization. Later, in central Italy, the Roman dominion was founded, and at the time of Christ it embraced the civilized world of that period. Still later Italy was divided among various independent king-

doms and republics. Among the independent republics were Venice, Genoa, and Pisa, which sent their trading ships to all parts of the Mediterranean and even to the Black Sea.

Italy remained divided until, about sixty years ago, the various parts joined together as the Kingdom of Italy. Some territory also was added after the World War. Italy has several colonies in Africa.

Within the peninsula of Italy is the little independent republic of San Marino, protected by Italy, as Andorra is held neutral by France and Spain. South of Sicily is Malta, a strongly fortified island owned by Great Britain.

471. Cities.—In Rome is the Forum, the market place of ancient Rome. Here may be seen the remains of temples and other public buildings. The rubbish of the old city has




Fig. 465. Rome and vicinity

been removed from the Forum, and it is fenced in and opened to visitors. Near it are the ruins of the Colosseum, a vast amphitheater, seating thousands of people, who in ancient times gathered there to see contests of men and wild animals (Fig. 466). There are many

beautiful churches of more modern times, of which the greatest is St. Peter's (Fig. 382). The Vatican adjoins St. Peter's church. It is a group of buildings in which the Pope resides and in which are galleries of painting and sculpture.

Milan is on the lowland of northern Italy, surrounded by rich land, and on the route southward from two of the great railroad tunnels through the Alps. It is the most important manufacturing and trading city of Italy, and contains one of the most beautiful cathedrals of Europe (Fig. 467). In this city, in the dining room of what was once a monastery, Leonardo da Vinci painted on the wall the well-known picture "The Last Supper." Turin also is in the Po Valley. It is joined to the rest of Europe through another of the great Alpine tunnels.



Fig. 466. Colosseum and Arch of Constantine, Rome



Fig. 467. The cathedral at Milan



Fig. 468. Harbor of Trieste

There are four important seaports in northern Italy,—Genoa, Venice, Trieste (Fig. 468), and Fiume. Genoa has a larger commerce than any other Italian coast city. Goods are landed here for Italy and for other countries. Venice is built on many low, flat islands, in a lagoon, or lake, that is separated from the Adriatic Sea by a sand beach. Canals take the place of streets, and boats, including steam and naphtha launches, are used instead of horses or trolley cars. In visiting a hotel or a gallery or house, one lands from a boat and goes into the building, which looks as if it stood in the water. Some of the boats, called gondolas, are propelled by oarsmen who stand as they row. There are many palaces, art galleries, and churches in Venice.

Another important seaport is Leghorn. Near Leghorn is Pisa, an ancient city in which the Leaning Tower still forms one of a group of remarkable buildings. Florence, in the interior of central Italy, is visited by thousands from all parts of the world, because its art galleries and churches contain many of the world's most notable paintings and other works of art.

Naples, the largest city of Italy, is

an important seaport, and is visited by many tourists. Palermo is the chief center for the foreign trade of Sicily.

Review. 1. Why has the Po many large tributaries? 2. Where are the "Italian Lakes"? 3. How extensive are the Apennines? 4. What facts can you give about the Tiber? 5. Why has Italy a mild climate? 6. What is the cause of the small rainfall in summer? 7. Tell the story of Pompeii. 8. Name the chief agricultural products of Italy. 9. What is the mode of carrying on the trade in salt? 10. What celebrated places and buildings are in Rome? 11. What are the chief seaports of Italy?



Fig. 469. Transfers of territory in southern Europe

AUSTRIA, HUNGARY, AND CZECHOSLOVAKIA

	AREA, SQ. MI.	POPULATION	CAPITAL
Austria	30,700	6,131,000	Vienna
Hungary	36,000	7,841,000	Budapest
Czechoslovakia	54,700	13,596,000	Prague

Map Study (Figs. 371, 451).—1. Locate Vienna with relation to the Alps and the Carpathians. 2. What river drains nearly all of Bohemia? 3. To what extent is Bohemia bordered by mountains? 4. What city of Czechoslovakia is on the Danube? 5. What countries does the Danube cross? 6. What countries have the Danube as a part of their boundaries? 7. Name two rivers which drain the plains of Hungary. 8. In what respect do the three countries here studied resemble Switzerland? 9. Locate Karlsbad; Innsbruck; Budapest.

472. History.—The former dual monarchy of Austria-Hungary, consisting of two monarchies under the same ruler, extended from the eastern boundary of Germany to the Iron Gate and the Transylvanian Alps; and from the plains north of the Carpathians to the Adriatic Sea. After the World War Austria, Hungary, and Czechoslovakia became independent countries (Fig. 469), and large sections formerly subject to Austria-Hungary became parts of Poland, Roumania, Yugoslavia, and Italy. The new boundaries were determined for the most part on the basis of racial kinship.

473. Austria.—Austria is now reduced to a belt of territory along the Danube, and a part of the eastern Alps. The provinces of Upper and Lower Austria extend along both sides of the Danube from Bavaria to a point eastward from Vienna. The Alpine region includes the Tyrol and other provinces. Trentino in the southern Alps, drained by a branch of the Po River, becomes a part of Italy, as do Trieste and the region bordering the head of the Adriatic Sea.



Fig. 470. Street in Vienna. Billboards like the one shown are common in European cities

The lowlands are not extensive and they lie mainly along the Danube. The Alpine region has many high peaks, deep and narrow valleys, snow fields and glaciers. Innsbruck is a city in the Austrian Alps, much frequented by tourists. From Innsbruck a railway leads into Italy by the Brenner Pass, one of the ancient gateways across the Alps.

The mineral wealth of Austria is not great. Iron is found, especially at Eisenerz in the Alps, where a mountain about a mile high contains much ore. Some coal is mined. The greatest mineral resources, as well as the best agricultural lands of the former Austrian Empire, belong now to other countries.

Austria is now smaller than Pennsylvania in area and population. Most of the people are of German blood and speak the German language. The majority are of the Roman Catholic faith.

At the point where the Danube passes between the east end of the Alps and the west end of the Carpathians stands Vienna, the capital, formerly the capital of the empire (Fig. 470). It is a very large city, but its trade and industries were cut down by the loss of its tributary territory.

West of Austria is the independent principality of Liechtenstein, which has a population of about 10,000.

474. Hungary.—Like Austria, Hungary, the other member of the former dual monarchy, has lost large areas, in the north, the east, and the south. The old Hungary included 125,000 square miles of territory; it was larger and had a greater population than our Middle Atlantic States. The present Hungary, like Austria, is smaller than Pennsylvania. Most of its people are true Hungarians or Magyars, descendants of Asiatic people who came to Hungary many centuries ago.

Hungary consists mainly of two plains. The greater plain lies along the Danube in its southward course below Budapest, and along the Tisza, a large tributary of the Danube, which flows from the Carpathians southward and enters the main stream above Belgrade. The smaller plain borders the Danube between Budapest and Vienna.

There is some coal, but the other mineral resources are small. The principal industries are stock raising and agriculture. Wheat and maize are extensively raised on the great central plains, and grapes and tobacco are products of some importance.

The manufactures reflect the agricultural character of the country. Flour milling is

highly developed at Budapest, and other industries are brewing and distilling, tobacco curing, the making of beet sugar, and the manufacture of agricultural implements.

Budapest, the capital, is a large and well-built city. Its two parts, Buda and Pest, stand on opposite sides of the Danube (Fig. 471).

475. Czechoslovakia.—Czechoslovakia is the land of the Czechs and Slovaks, two closely related branches of the Slavic race. Though long subject to Austria-Hungary, they preserved their national traditions, held to their own forms of speech, and developed their literature.

The country embraces Bohemia, Moravia, and Austrian Silesia, all former provinces of Austria and inhabited mainly by Czechs. It also includes a large section of northern Hungary, on the slopes of the Carpathians, occupied by the Slovaks. Between Vienna and Budapest the new country extends southward, taking in the former Hungarian city of Pressburg and a section of the Danube plains. Altogether, Czechoslovakia is nearly as large as Austria and Hungary together.

Bohemia, the western part of Czechoslovakia, is bordered by mountainous and hilly uplands. A mountain range, under various names, bends around the province on the west, north, and northeast, while on the south-east a hilly region leads into the province of Moravia. The river Elbe rises in Bohemia and passes through the mountain range on the north, afterwards crossing Saxony and Prussia. Thus Prague and other cities of Bohemia communicate by water as well as by rail with Dresden and Hamburg in Germany.

Moravia lies between Bohemia and the Slovak section of the Carpathians. From the watershed in Moravia the river Oder



Fig. 471. Airplane view of the Hungarian Parliament House at Budapest, overlooking the Danube River

flows northward through Germany, and a smaller river, flows south to the Danube. Along these valleys is the "Moravian Gateway," a notable route of traffic leading from the Adriatic Sea and the Danube to the Baltic Sea, and much used in ancient as well as in modern times.

The new nation has chosen a republican form of government, and its capital is Prague, the ancient capital of Bohemia. It is a splendid city on a branch of the river Elbe.

476. Industries of Czechoslovakia.—Bohemia has long been the principal manufacturing district of Austria-Hungary. It has abundant coal to supply power for its iron and textile industries. The streams flowing from the forested upland borders supply much water power. Here is made the celebrated Bohemian glass, and in this province also are the breweries of Pilsen and other places for which the Bohemian farms furnish the necessary hops and barley. In Bohemia are health resorts such as Karlsbad and Marienbad, with mineral springs and hot baths to which people of many countries go for medical treatment. There is kaolin for porcelain, and paper mills utilize the wood from the forests. Silver, radium, and graphite, as well as iron and abundant coal, are found in various sections of the country. Iron and steel are important products of western Czechoslovakia (Fig. 472). The textile industries, including the manufacture of cotton, woolen, and linens, are carried on both in Bohemia and in Moravia.

In the agricultural regions of the country the variety of products is large. Cereals, potatoes, sugar beets, tobacco, hops, and fruits are raised.



Fig. 472. Steel mills in Czechoslovakia

477. The Danube River.—The Danube and the Rhine are the chief international rivers of Europe. The Rhine furnishes a trade route for Switzerland, Germany, France, and the Netherlands. The Danube crosses Germany, Austria, Hungary, Yugoslavia, and Roumania, and for long distances forms the southern border of Czechoslovakia and the northern border of Bulgaria. It flows between the Alps and Carpathians at Vienna, and between the Transylvanian Alps and the Balkan Mountains at the Iron Gate. As the waters connecting the Black Sea and the Mediterranean have been internationalized, the Danube has become one of the most important routes of interior navigation in the world.

Review.—1. What changes have taken place in the former Austria-Hungary? 2. Name a tourist center and an important pass in the Austrian Alps. 3. What changes have taken place in the area and population of Hungary? 4. What are the manufactures of Hungary? 5. What parts of the former monarchy of Austria-Hungary are included in Czechoslovakia? 6. Describe the boundaries and drainage of Bohemia. 7. What are the manufactures of Bohemia? 8. For what countries does the Danube afford a trade route? 9. What is the Iron Gate?

THE BALKAN COUNTRIES

	AREA, Sq. Mi.	POPULATION	CAPITAL
Yugoslavia . .	95,000	12,017,000	Belgrade
Roumania . .	116,000	17,393,000	Bucharest
Bulgaria . .	40,000	4,910,000	Sofia
Albania . .	11,000	832,000	Tirana
Greece . .	42,000	4,932,000	Athens
Turkey in Eur.	10,000	1,800,000	Constantinople

Map Study (Figs. 371, 451).—1. Bound Bulgaria; Greece; Roumania. 2. Locate the capital of Roumania; of Yugoslavia. 3. Locate the Bosphorus; the Sea of Marmora; the Dardanelles. 4. Locate Athens; Salonica; Constantinople; Sofia; Belgrade. 5. Where, on the Danube, is the Iron Gate? 6. State an important difference between the Balkan and the Italian coast lines of the Adriatic Sea. 7. What is the character of the surface and of the shore line of Greece? 8. Compare Yugoslavia, in size, with Roumania; with Czechoslovakia; with Bulgaria.

478. Physical Features.—The Balkan Peninsula is sometimes likened to a bridge joining Europe to Asia. It faces Asia across three seas—the Black Sea, the Sea of Marmora, and the Aegean—and is bordered also by the Adriatic Sea and the Mediterranean. Its northern boundary is vague, but may be described as extending from Fiume on the northern Adriatic, eastward along the Save and Danube rivers, to the Black Sea.

The land is mountainous, but among the mountains there are many beautiful valleys and old lake basins. In the west are the Dinaric Alps. This range of highlands continues the folds of the Alps southeastward into Greece. The Balkan Mountains are in the northern and eastern part of the peninsula, in Bulgaria and eastern Yugoslavia. Extending south and east from the Iron Gate (Sec. 383), they may be regarded as a continuation of the great Carpathian range.

479. History of the Balkan Region.—This part of Europe has been for thousands of years in close relation to Asia. Across

the narrow waters that join the Black and Aegean seas, men have gone for trade, for settlement, and for war and conquest. The land route from southern Europe to southwestern Asia leads through the Balkans, and a trunk railroad connects Constantinople with the Danube trade route at Belgrade. A branch line joins Nish and Salonica.

The whole Balkan region fell under the control of the Turks several hundred years ago, but the cruelty of their rule caused one group of people after another to rebel and set up independent governments. A further blow to the Turkish power in Europe came in a war with the adjacent countries of the peninsula in 1912–1913. The Turks were then compelled to give up about five sixths of their European possessions, retaining only a small area in the east. The greater part of the conquered territory was divided among Greece, Serbia, Montenegro, and Bulgaria, the four kingdoms that had carried on the war. A small region on the Adriatic Sea was given an independent existence as Albania.

As a result of the World War, the kingdom of Yugoslavia was formed, including Serbia, Montenegro, and several southern provinces of the former Austria-Hungary. Roumania was doubled in size, and Greece gained territory from Bulgaria and from Turkey.

480. Yugoslavia.—This is the kingdom of Serbs, Croats, and Slovenes, and is some-



Fig. 473. Town in Bosnia, Yugoslavia

times referred to as the greater Serbia. These three peoples are, as the name Yugoslavia indicates, Slavs of the southern or Balkan region, thus contrasting with the northern Slavs of Czechoslovakia, Poland, and Russia. The Serbs live in the eastern part of the country, not only in the old Serbia but also in Montenegro, Bosnia, and other provinces. The Croats and Slovenes, in Croatia and other western provinces, are closely akin to the Serbs in blood and in language.

The northern boundaries of Yugoslavia are mainly on the plains north of the Drave and Danube rivers. The country has a considerable section of the Dalmatian coastline between Albania and the upper Adriatic region of Italy. Most of the ports on the Adriatic, however, are difficult of access from the interior, because the rugged ridges of the Dinaric range everywhere follow the coast line. The railroads of the peninsula already referred to furnish overland trade routes through the Morava and Vardar valleys to Constantinople and Salonica. Other railroads lead across the Dinaric Alps to the port of Fiume.

Much of Yugoslavia is a tangle of mountains and valleys, and has no natural center from which all parts are easily reached. Its material resources have remained largely undeveloped because of the oppression to which the people have been subjected under the rule of both Turkey and Austria-Hungary.

The people are mainly devoted to agriculture, for which the soils and climate of the mountain valleys are well suited. Wheat and corn are important crops, and there is much fruit, especially grapes and plums. Plum marmalade and the dried plums or prunes are exported. Many hogs are raised.

Coal and copper are important mineral products, and the mountain regions of the greater Serbia will, no doubt, when explored and developed, yield a large output of mineral wealth. Carpet weaving and flour milling are the chief manufacturing industries.



Fig. 474. Threshing wheat in Roumania

481. Roumania.—The kingdom of Roumania is usually called one of the Balkan countries, although only a small part of it, in the southeast, is in the Balkan Peninsula. Prior to the World War Roumania was a little larger than the state of Pennsylvania and had about an equal number of people. Other millions of Roumanians, however, were subjects of Austria-Hungary and Russia, and after the war the adjoining regions, where Roumanians predominate, were added to Roumania. From the tables on pages 321, 324, compare Roumania in size and population with other countries of southern Europe.

The old Roumania was mainly a plain on the north bank of the Danube, rising in the north to the crest of the Carpathians, there known as the Transylvanian Alps. This plain bordered in the east on the Black Sea and on Russia, from which it was separated by the Pruth River. By the new arrangement Roumania acquires the old Hungarian mountain region of Transylvania and reaches westward into the Hungarian plain. It also acquires the Russian province of Bessarabia, and Bukowina, a former province of Austria lying on the north-eastern slope of the Carpathians.

The Roumanians, although partly Slav by race, claim to be descendants of ancient



Fig. 475. Market day in Sofia

Roman colonists; they speak a language derived largely from Latin.

The Roumanian plain has hot summers and cold winters, with a rainfall of about 20 inches. It is therefore continental in climate, like Russia. There are extensive forests, especially in the Bukowina and Transylvanian highlands. They include oak, beech, plane, and ash. Lignite is mined, some salt is produced, and much petroleum is exported. Glass making is an industry of importance, and in Bukowina and Transylvania there are paper and leather industries.

The plains of Roumania are very productive and, as in Hungary and Russia, the crops of wheat, corn, and other grains are large. In normal times much wheat is exported to Great Britain and Belgium. Galatz on the Danube is a wheat-exporting city. Bucharest is the capital and largest city. Transportation is afforded by extensive railroad lines and by means of ships on the Danube River and on the Black Sea.

482. Bulgaria.—Before 1908 Bulgaria was a principality tributary to Turkey. In that year an independent kingdom of Bulgaria was established. Sofia, the capital (Fig. 475), has about 150,000 inhabitants. The country is nearly as large as Ohio. It has ports on the Black Sea, and is crossed by the trunk railroad leading to Constantinople.

The population includes, in addition to Bulgarians, many Turks, Roumanians, Greeks, and Gypsies. Such a mixture of races is common in all the Balkan countries, and in connection with Turkish misrule has been the cause of much disorder. Education has been generally neglected, and modern industry has made little progress.

Three fourths of the people in Bulgaria till the soil, and live on farms of a few acres each. Wheat and corn are the leading grains. Tobacco, silk, and sugar beets are produced. The climate south of the Balkan range is mild, and favors the growth of rice and especially of roses, used in making the perfume attar of roses. Coal and iron are mined, and there are some manufactures of cotton and wool.

483. Albania.—The new country of Albania, formed from Turkish territory in 1912, has been the home of the Albanian people for many centuries. The people are divided in religious faith, some being Mohammedans and some Christians. Tirana is the capital. There is little or no manufacturing, agriculture is of the most primitive kind, and there are no railroads, though certain lines are projected. Large deposits of platinum have been discovered.

484. Greece.—The republic of Greece is larger than the state of Ohio, but has a smaller population.

The ancient Greeks were the leaders of the world in poetry, philosophy, science, architecture, and sculpture. They founded colonies in other Mediterranean lands, and taught the ruder Roman people much that made them great.

Athens, an ancient city, is the capital of modern Greece. It still possesses the ruins of the Parthenon (Fig. 476), one of the most beautiful of ancient temples. The city is several miles inland, and its port is Piraeus. Salonica, the Thessalonica of the Bible, is a large and important seaport; it was acquired as a result of the recent Balkan wars. After

the World War, Greece gained further territory in the northeast. Elementary education is compulsory, and the University of Athens enrolls several thousand students.

Greece is a land of mountains and valleys, much broken by inlets of the sea. The Isthmus of Corinth is but a few miles wide, and a ship canal has been cut across this neck of land.

Only about one fifth of the land surface is capable of cultivation. The climate is dry, and in some districts irrigation is necessary. The small dried grapes known as "currants" are the leading product and the chief export. Olives are next in importance. Figs and tobacco are also raised, and several million bushels of wheat; but much wheat is imported.

The country has a variety of metals, including iron, copper, zinc, and lead.

Greeks own much shipping in the Mediterranean Sea and control a line of steamships to New York.

485. Turkey.—European Turkey is but a small remnant of the great territory which the Turks once controlled in Europe. Most of the territory lost was lost because of the harsh treatment of the native people. According to recent treaties the waterway from the Black Sea to the Mediterranean will be open to all, under international control.

Constantinople, on the Bosphorus, is by far the largest city of the Balkan Peninsula, and is one of the most ancient and celebrated cities of Europe (Fig. 451). Here the Greeks

founded a city 700 years before Christ, and called it Byzantium. The name was changed to Constantinople by the Roman emperor Constantine, and he made it the capital of the Roman Empire. Its best-known buildings are the great Mohammedan mosques, or places of worship (Fig. 477), and the palace of the Sultans, the former rulers of the country. The population includes people of many races.

Turkish industries and trade are in a backward condition. Large numbers of ships enter and clear from the harbor of Constantinople each year, but their trade is largely with ports situated on the Black Sea. There are large fisheries in the Bosphorus.

Review.—1. What Balkan countries have the Danube as part of their boundaries? 2. What are the chief products of Yugoslavia? 3. What are the industries of Roumania? 4. Tell the recent history of Bulgaria. 5. In what did the ancient Greeks excel? 6. Give an account of the Greek population and industries at the present time. 7. Give some facts about the history of Constantinople. 8. Why is its situation important?




Fig. 476. The Acropolis, Athens



Fig. 477. Mosque of Suleiman, Constantinople





Fig. 479. The Kremlin, a walled area in the center of Moscow, containing many public buildings

EASTERN EUROPE

	AREA, SQ. MI.	POPULATION	CAPITAL
Russia, etc. .	1,716,500	93,782,000	Moscow
Finland . .	130,000	3,367,000	Helsingfors

Map Study.—1. How many degrees of longitude are covered by Russia? How many degrees of latitude? 2. What countries border Russia on the west? 3. What ocean and what seas and gulfs are on the boundary?

4. Using the scale of miles, determine the width of the Caspian Sea. 5. What long river flows into it? 6. What city is at the mouth of this river? 7. What river flows into the Sea of Azof? 8. What large river flows into the Black Sea?

9. Locate Moscow; Nizhni Novgorod; Petrograd. 10. Name the chief seaport on the Black Sea. 11. Where is the peninsula called Crimea?

12. What part of Russia has many lakes?

13. Compare the latitude of Russia with that of the United States; with that of Canada. 14. How do most of the rivers flow with reference to the center of the country?

15. What waters border Finland? 16. Locate the capital of Finland.

486. Physical Geography.—East of Germany, the central plain of Europe widens and embraces the eastern half of the continent. The greater part of this eastern plain belongs to Russia. The highest land is in the center, where the rivers rise. But even this region is flat and less than 1100 feet above the sea.

The rivers are long and descend very slowly to the sea. For this reason Russia has many thousands of miles of interior navigation (Fig. 480). The Volga, which flows into the Caspian Sea, is one of the world's greatest rivers. In its lower course it flows through a large region that is below the level of the ocean.

The Ural Mountains are on the east border, but they are so low and have such gentle slopes that they do not form a real barrier. No mountains are visible in crossing by rail from Russia to Siberia. Some geographers

consider the Caucasus Mountains as part of the southern boundary of Europe. Others place that boundary between the Caspian Sea and the Sea of Azof, at the valley of the Manich, as shown in this book (Figs. 371, 478).



Fig. 480. Boat on the Dnieper River at Smolensk



Fig. 481. Sledge and ponies in a North Russian village

Although the Caspian Sea receives the water of the longest river of Europe, the region is so dry that few other streams enter the sea, and its surface is kept by evaporation 85 feet below the level of the ocean. It has no outlet, and its waters are salt like those of Great Salt Lake. The Black Sea receives large rivers, and is connected with the Mediterranean Sea. Its waters are brackish.

As in Scandinavia and north Germany, so in Finland and in northern and western Russia, an ancient ice sheet swept over the surface. By this agency thousands of lakes were formed.

487. Climate and Vegetation.—The range of latitude is so great that eastern Europe is cold in the north, temperate in the middle, and warm-temperate in the south. The climate is continental, for the land is far from the Atlantic, and the westerly winds do not give even temperatures as they do in western Europe. The winters are cold, and the summers are hot. The rainfall varies greatly in different parts of Russia; it is moderate in the central and western parts, and lighter—less than 20 inches—in the north, east, and south. But in most of Russia there is usually enough moisture for good crops because the rains fall mainly in the summer.

In the north is a belt of tundra or Arctic plains. Farther south is an extensive forest belt, of birch, beech, oak, fir, and pine. This belt is so extensive that lumber interests in Russia and Finland are large.

In central and southern Russia is the fertile region of the so-called "black earth." This is a deep and rich soil, resembling that of our prairies, and especially suitable for raising wheat and other grains. Here the population is dense. In the southeast, around the Caspian Sea, is the steppe

region, where the land is too dry for farming; some parts of it are below sea level. The population of this region is sparse.

488. Russia.—Before the World War European Russia had about 140,000,000 people. The Russian Empire included also Siberia, Turkestan, Caucasus, and some other regions in Asia; the total population was 175,000,000 and the area larger than that of the mainland of North America. As a result of the war the monarchical government was overthrown and the western parts of the old empire became independent countries.

The greater part of Russia fell under the control of extreme radicals, who framed for it a government by soviets, or councils of union workmen. It is the largest country of Europe. Most of its inhabitants are Great Russians, the most numerous people of the Slavic group. Many parts of Russia occupied by other peoples—such as Ukraine, White Russia, Karelia, etc. (Fig. 478)—were given local governments of their own, under soviet control.

Russia is a backward country, and until about sixty years ago many of its peasants were serfs. The roads and the schools are poor. The ways of living are very simple and rude (Figs. 481, 482).

The prevailing worship is in the forms of the Orthodox Church.

489. Russian Agriculture.—

Russia is primarily an agricultural country and most of its people are engaged in farming.

During the long Russian winters there is not much work on the farms, and some of the land owners live in the cities or carry on industries and trade. Farm produce is often marketed by means of sledges which can be easily drawn over the snow-covered ground.

Wheat is grown in the "black-earth" region of Russia. Much rye is raised, and the peasants use rye bread. Barley, oats, and flax also are leading crops. The flax is grown both for fiber and for making linseed oil. Hemp, another and taller fiber plant, is an important product. Potatoes and sugar beets are the most common vegetables.

The farmers generally use primitive methods and rude tools, but in many places modern agricultural tools and machines have been introduced. The modern implements have come partly from the United States.

490. Mines and Manufactures.—Iron and coal are found in several parts of Russia



Fig. 482. Russian farmers in a sugar beet field

and considerable iron is manufactured. In the Ural Mountains many metals are mined, including the very hard and valuable metal, platinum, of which Russia furnishes an important part of the world's supply.

The largest manufacturing center of Russia is in and near Moscow. The use of manufacturing machinery is very limited, and, as in other backward countries, many things are still made by hand. But in Moscow and Petrograd, and to a lesser extent elsewhere, machinery has been introduced, and before the World War the textile industries had reached a flourishing condition. One of the largest of these was cotton manufacturing, for which Russia imported much raw cotton from our southern states. The war and ensuing difficulties brought most of the Russian factories to a standstill; but the country has so many people and can supply so much cheap labor that manufactures are likely to increase.

491. Cities and Routes of Trade.—Moscow, the capital of Russia, is in the central part of the country and is the chief railroad center. Railroads lead north to Archangel, northwest to Petrograd and thence to Murmansk, west to Warsaw and Berlin, and south to Odessa and Sebastopol. Another line extends eastward into Asia, and crosses Siberia to Vladivostok on the Pacific. Not far from Moscow are ports on the Volga, which is navigable to its mouth. The Orthodox Church,



Fig. 483. St. Basil's Church, Moscow



Fig. 484. Shipping on the Neva River, in Petrograd

which is the national church of Russia, has its principal seat in Moscow, and this city is known as the "holy city" of the empire (Figs. 479, 483). It has many palaces and a large university.

Petrograd, formerly named St. Petersburg, is at the mouth of a short river called the Neva (Fig. 484). It was the capital of the old Russian Empire. It is second only to Moscow as a manufacturing center. Petrograd and other ports on the Baltic are closed by ice for many weeks of the winter; for the shallow, brackish water (Sec. 382) is easily frozen.

Nizhni Novgorod, east of Moscow, has every year the greatest of the Russian fairs. These are not, as in our country, places for showing fine products for which prizes may be awarded, but places where, for centuries, people have come from all parts of the country bringing their goods for sale. We should call them markets. Astrakhan is a center for fisheries and a starting point for Persian trade. Archangel receives and sends out the natural products of the colder parts of Russia, lumber, flax, and some kinds of grain. It is icebound for several months of each year. Murmansk, the terminus of a Russian railroad built during the World War, is a port open all the year.

Kief, an ancient city on the Dnieper River, is a center for linen and woolen manufactures and for the wine trade. Odessa, on the Black Sea, is the chief southern seaport. It receives much of the Russian wheat crop and exports both grain and flour. Taganrog, on the Sea of Azof, also ships much wheat.

Although Russia has several seaports it is not well situated for trade by ocean ships. The open Arctic Ocean at Murmansk is reached only by a long railroad through barren country. Both the White and Baltic seas are closed by ice for a long time during the winter months. The Black Sea ports can be reached only by way of narrow straits



Fig. 485. Bridge across the Volga, Nizhni Novgorod



Fig. 486. Cutting seed potatoes, Ukraine



Fig. 487. Market boats, Helsingfors, Finland

through which freedom of trade is impossible when they are held by unfriendly powers. But with its enormous size, its multitude of people, and its varied resources, a well-governed Russia should have a great future.

492. Ukraine.—The southern part of Russia, known as Ukraine, gained temporary independence but in 1920 fell under the soviet government of Russia. This region embraces a large part of the plains of southern Russia and includes most of the “black earth,” which in richness and fertility is like the prairie soils of America. These lands produce large crops of wheat and other cereals and of vegetables (Fig. 486). In the valley of the Donetz are rich mines of coal and iron. The people of Ukraine, differing slightly from the Great Russians in race and language, are known as Little Russians.

493. Finland.—Finland lies north of the Gulf of Finland, and is separated from Sweden on the west by the Gulf of Bothnia.

The Finns are Asiatic in race and in their speech, and were for several centuries subject to Sweden. Finland was ceded to Russia in 1809, but enjoyed a good degree of self-government until 1898. Oppression by Russia followed, until the World War gave the Finns opportunity to declare their independence.

They have now adopted a republican form of government. The people are advanced in education and industry. There is some mixture of Swedes in the population, and nearly all the people are Protestant.

Helsingfors (Fig. 487) is the capital and the largest city. Lumbering, farming, and dairying are leading industries, and the large forest resources have led to woodworking and paper making.

Review. — 1. Describe the surface of eastern Europe, from the Arctic Ocean to the Black Sea. 2. Describe the seas on the southern border.

3. What part of our country resembles Russia in climate? 4. Where are the principal forests? 5. Where is the black-earth region?

6. Who are the principal people of Russia in Europe? 7. Give an account of the government.

8. What grains are raised in Russia? 9. What grain is used in making the bread of the working people? 10. What vegetables are raised? 11. What valuable metal is found chiefly in Russia? In what part? 12. Name the leading manufacturing cities. 13. Why are manufactures likely to increase?

14. Name three Russian seaports. 15. Name the leading railroad center and the cities to which the principal lines extend. 16. What city is the capital of Russia?

17. Who are the principal people of Ukraine? 18. What are the chief industries?

19. What are the leading industries of Finland?



ASIA

	AREA, Sq. Mi.	POPULATION	CAPITAL
Turkey in Asia	295,000	10,000,000	Angora
Syria	80,000	3,000,000	
Palestine	9,000	757,000	Jerusalem
Iraq	140,000	2,850,000	Bagdad
Hedjaz	140,000	600,000	Mekka
Aden, etc.	15,870	177,000	Aden
Oman	75,000	500,000	Maskat
Arabia (interior)	906,500	2,000,000	
Persia	635,000	9,500,000	Teheran
Afghanistan	240,900	6,380,000	Kabul
Indian Empire . . .	1,856,500	319,075,000	Delhi
Nepal	54,000	5,600,000	Khatmandu
Bhutan	18,600	250,000	Punakha
Ceylon, etc.	25,500	4,568,000	Colombo
Siam	245,000	8,266,000	Bangkok
Fr. Indo-China . . .	256,500	17,269,000	Hanoi
Straits Settlements, etc.	35,600	2,377,000	Singapore
East Indies	788,000	60,694,000	
China, etc.	4,300,000	320,880,000	Peking
Japanese Empire . .	261,300	77,606,000	Tokyo
Russia in Asia . . .	6,721,500	41,037,000	

Map Study.—1. What is the latitude of Singapore, at the southern end of the Malay Peninsula? Of Cape Chelyuskin? 2. What is the difference in longitude between Smyrna in Asia Minor, and Bering Strait?

3. Where has Asia a land communication with Africa? 4. Name three great peninsulas on the south border of Asia (Fig. 489). 5. Give the water boundaries of the most westerly of these; of the middle one; of the most easterly. 6. Name and give the water boundaries of two peninsulas on the east border of Asia. 7. Beginning with the Caspian Sea, name in order the principal seas, gulfs, and bays along the border of the continent.

8. Through how many degrees of latitude does the island group of the Empire of Japan extend? 9. Locate Ceylon, Sumatra, Borneo, and the Philippine Islands.

10. Name in their order from east to west the three principal rivers that flow into the Arctic Ocean. 11. Describe the course of the Amur River, the Hwang, and the Yangtze. 12. Name two rivers that flow southward in Burma. 13. Name two rivers whose waters

join before they enter the Bay of Bengal. 14. Describe the course of the Indus. Into what sea does it flow? 15. Name two rivers whose waters join before they enter the Persian Gulf.

16. Locate the Himalaya Mountains; the Tien Shan; the Altai Mountains; the Caucasus Mountains. 17. Compare, as regards rivers, the interior of Asia with the interior of North America. 18. Name and locate three large lakes in Asiatic Russia.

19. What countries border Asiatic Russia on the south? 20. What countries border British India? 21. Locate French Indo-China; the Straits Settlements; Oman; Aden. 22. Locate Manchuria; Mongolia; Tibet. 23. What two regions bear the name Turkestan?


24. Locate the capitals of China, Persia, British India, Siam, and the Empire of Japan. 25. Locate Jerusalem, Mekka, and Damascus in southwestern Asia. 26. Name and locate two important seaports of India. 27. Locate Hongkong, Canton, Shanghai, and Hankow in eastern Asia. 28. Locate Tomsk and Vladivostok in Asiatic Russia.

29. What countries of Asia are wholly or partly south of the Tropic of Cancer?

PHYSICAL GEOGRAPHY

494. Asia as a Continent.—Asia is nearly twice as large as North America and more than four times as large as Europe. Asia and Europe belong together when we think of them as a land surface, for they have a long land boundary in common; and they are sometimes included together under the name Eurasia. But when we consider their history, their people, and their trade, they may rightly be called separate continents.

Asia is more distinct from Africa than from Europe, being joined to Africa only by the Isthmus of Suez. But the peoples of Asia and those of northern Africa have had much intercourse with each other for thousands of






Fig. 490. Snow and glaciers on the Himalayas

years, because it has been easy for them either to pass over the Isthmus of Suez or to cross the Mediterranean or the Red Sea by boat.

In northern Asia are the vast plains of Siberia, but these plains are not so valuable as those of North America, South America, or Europe, because a large part of the region is so far north. In Asia there are large areas in the North Temperate Zone, but excepting eastern China, this region is generally either very dry or too high and cold for agriculture. The hot lands of Asia, however, have much greater area and are more important than those in the hot belt of North America.

495. Surface and Rivers.—The surface is high in the interior and, as a rule, low near the borders. Asia thus differs from Europe and North America, which have their large lowlands in the interior and their mountains on or near the borders.

The Himalaya Mountains (Fig. 490) extend east and west and contain the highest peaks on the globe. Hundreds of peaks, and even some ranges, are more than 20,000 feet high, and Mount Everest, believed to be the highest in the world, is

about 29,000 feet in altitude. The Himalayas have many glaciers and snow fields, and in these mountains two of the great rivers of India, the Ganges and the Indus, have their headwaters. Under other names, the same system of mountains extends westward through Afghanistan, Persia, Caucasus, and Asia Minor, and is continued in the southern ranges of Europe. We may, therefore, think of one great line of elevations as reaching from the Pyrenees in western Europe to the southeastern parts of Asia.

North of the Himalayas, occupying all central Asia, is a vast region of plateaus and mountain ranges, of great height. The plateaus of Tibet, Turkestan, and Mongolia are very large. Tibet and Pamir have an altitude of more than 15,000 feet, or about three miles. Because the Pamir Plateau is so high, it is sometimes called "the roof of the world." Rising above the plateaus are many ranges of high mountains. They run in a general east and west direction, and are thus roughly parallel to the Himalayas. Among them are the Hindu Kush, Kuenlun, Tien Shan, and Altai ranges.




Fig. 491. Drainage basins of Asia

Out of the eastern parts of the central highland flow the headwaters of the Yangtze, the Hwang, and the Amur rivers. On the north slopes of the central highland the rivers of Siberia have their sources. They flow across the vast Siberian plains and enter the Arctic Ocean. They are navigable, but are not of much value for this purpose, because the Arctic Ocean is generally covered with ice, and is far from the commercial countries. The rivers also are so long from south to north that their northern courses are often frozen when the southern parts are open. This results in ice blockades and causes great floods. The rivers of China and of southern Asia are important for commerce, because they are large, are open to the sea, and flow through densely populated countries. Name six of them (Fig. 488).

The surface, climate, and drainage of Asia are such that the most people and the greatest trade must always be within 500 or at most 1000 miles of its borders. The shore line of Asia is irregular, though not so irregular as that of Europe. Some parts of the pen-

insulas of eastern and southern Asia are mountainous. These regions have many volcanoes and are shaken by violent earthquakes.

496. Climate.—Asia lies in the same zones as the continent of North America. The northern part of Siberia is intensely cold in winter, and the region where the Lena River crosses the Arctic Circle is one of the coldest places known in the world, having an average temperature in January of 60° below zero. The southern part of the Siberian plain has a cold-temperate climate, somewhat like that along the boundary between our western states and the Dominion

of Canada. As the westerly winds first cross Europe and then pass for thousands of miles over the long stretches of Siberia, all the moderating effect of the Atlantic Ocean is lost. The climate of central Asia is continental: the summers are warm, and the winters are bitterly cold.

We have already learned that Russia in Europe, on its southeast border, is a steppe. The dry grasslands continue eastward over Turkestan and among the high plateaus of central Asia. Little moisture can come from the Atlantic or the Indian Ocean, and the central and west-central parts of Asia are mainly desert (Fig. 367).

The countries of southwestern Asia are largely desert because they are in the belt of the northeast trades, and these winds have moved for long distances across the inland parts of the continent. They have, therefore, gathered but little moisture, and they descend into the warmer lands of southwestern Asia as drying winds. They continue across Egypt and the Sahara in the same condition. Hence we find a desert stretching from

eastern central Asia across Asia and Africa to the Atlantic Ocean. This is by far the greatest desert area in the world. We know from the historical books of the Bible and from other ancient and modern writings that in all this region springs, wells, and rivers have always had the greatest value, in the raising of crops and in the locating of homes and routes of travel (Fig. 492).

The northern part of Asia is cold, and the central and western parts are dry; but the southeastern parts are wet and hot, and they contain about four fifths of the population of the continent. Southeastern Asia has about 700,000,000 people, and is far more densely populated than any other region of equal area in the world. This is due partly to its great and fertile plains, partly to climate, and partly to ample facilities for trade.

The climate is warm in the southern lowlands, because they are south of the Tropic of Cancer; and in eastern China the climate is tempered from the neighboring ocean. The rainfall of southern Asia (Fig. 493) is brought chiefly by the summer monsoons (Sec. 373).



Fig. 492. A well at Nazareth, in Palestine

PLANTS AND ANIMALS

497. Vegetation.—Along the Arctic border the plains are tundras, frozen in winter, and thawing to a depth of a few feet during the short summer. Only grasses and other small plants flourish there. Southward there are heat and moisture enough for a belt of forest, in which evergreen trees, larches, and birches are common. South of the forest the dry region begins, first the steppes and then the mountains and plateaus, which are too high, dry, and cold for much vegetation. In south-western Asia, wherever there is sufficient rain, or wherever irrigation is used, the vegetation, like that of southern Europe, is subtropical. In India, Indo-China, and the East Indies is the truly tropical country, with rank forests, dense jungles, and fields that produce several crops a year, because growth takes place throughout the twelve months.

498. Animals.—Most kinds of animals can move from one region to another while plants cannot, but still animals depend on climate, for they become accustomed to certain temperatures and suitable kinds of vegetable food. Thus we find that the reindeer is the important animal in northern Siberia. In winter it lives upon the mosses of the tun-




Fig. 493. Average annual rainfall in India



Fig. 494. Tiger

dra, which it reaches by pawing away the snow. In the forest belt are fur-bearing animals, — otter, beaver, sable, ermine, — whose pelts are taken to the fur markets of Russia, to the German fur center, Leipzig, and to other countries and cities. In the arid parts of Asia, sheep, goats, cattle, and horses are kept by the wandering tribes. In these regions the camel is one of the important beasts of burden, because of its ability to live for days without water.

In India elephants are found wild in the jungle, and are also domesticated and used to carry people, to haul heavy loads of merchandise, and even to pile timber. Lions, tigers, apes, and monkeys are found in the jungles, and crocodiles and numerous serpents live in the waters and the forests. Insects of all kinds abound, and some, as, for instance, certain species of ants, are very destructive. Boring worms destroy timber, and the people have to take many precautions to preserve health and property. The tropical belt, especially in the East Indies, has many birds of brilliant plumage.

Review.—1. How does the general surface of Asia differ from that of Europe, or of North America? 2. Give the name, altitude, and location of the highest

mountain peak. 3. What is the height of the central plateaus? 4. Why are the Siberian rivers of small commercial value?

5. Describe the climate of Siberia; of western Asia. 6. Why is central Asia arid? Southwestern Asia? 7. What regions are included in the greatest desert of the world? 8. Where do most of the people of Asia live? 9. What are the monsoon winds? 10. What effect do they have on the climate of India and other parts of southern Asia? 11. Where is the heaviest rainfall in the world?

12. What kind of country is northern Siberia? 13. Where is the temperate forest area of Asia? 14. What are some of the domestic animals of Asia? 15. Name some of the important animals of tropical Asia.

PEOPLE AND INDUSTRIES

499. Races.—The majority of the inhabitants of Asia are *Mongolians*, and because of the color of their skin they are said to belong to the yellow race of mankind. To this race belong the Chinese, the Japanese, the people of the Indo-Chinese peninsula, and many of the people of the East Indies. Among the Mongolians who have settled in Europe are the Finns and others in the north, the Magyars




Fig. 495. Distribution of population in Asia

of Hungary, and the Turks of the Balkan Peninsula. The people of the yellow race are short and have black hair, high cheek bones, and narrow, oblique eyes; the men have scanty beards.

Many of the people of Asia are *Caucasians*, but this race is more numerous and more scattered in all parts of the world than the Mongolian race. We see, every day, that some members of the white race are light in the color of eyes, skin, and hair. We call these blondes. Others are dark in skin, eyes, and hair, and are called brunettes. These differences are found especially in America and between northern and southern Europe. The French, Spaniards, and Italians are usually dark. There are many million people in Asia belonging to the so-called white race, but they are usually of the dark kind, and some of them are almost as dark as negroes. People that have lived, as their ancestors have lived, for thousands of years under a hot sun, are darker than people whose ancestors have lived in a cooler climate, and under a dull sky, as in northern Europe.

Among the people of the white race are most of the inhabitants of India and a large part of the population of Asiatic Russia, Persia, Arabia, and neighboring lands. The Semitic people are white; the Jews and Arabs are branches of this people, as were also the ancient Babylonians and Assyrians of Mesopotamia.

In small parts of southeastern Asia are some groups of the black or *negro* race. In the northeast, near Bering Strait, are a few Eskimos, who, according to some scholars, belong to the red or *Indian* race.

500. Religion.—There are several kinds of religious belief in Asia. They all had their beginnings in Asia, and some of them have spread widely over other parts of the world.

Christianity had its origin among the Jewish people, in the life and teachings of Jesus. Christians believe in one God, in Jesus as the Savior of men, and in the Bible as the




Fig. 496. Hindu temple at Benares, India

greatest source of religious and moral teaching. This faith has many followers in western Asia, and is the principal religion of Europe and the New World. It embraces most of the white race, and the most enlightened and progressive countries.

Brahmanism is the religion of the Hindus, or most of the people of India. Their name for God, or the Universal Spirit, is Brahma; but they worship many gods. The people are divided into classes or castes, and the members of one caste will have nothing to do with members of another. People of the lowest class are considered as outcasts. Modern government and schools and the teachings of missionaries are slowly breaking down the cruel caste system.

Buddhism was founded on the teachings of an ancient prince in northern India who was given the title of Buddha. He rejected the idea of castes and taught a life of purity

and kindness. His followers are Buddhists. They are not numerous in his native country, but are counted by hundreds of millions in other countries, mainly in China, Japan, and Indo-China.

The Chinese are devoted to the worship of their ancestors, and nearly all—whether Buddhists or not—accept the moral teachings of Confucius, who lived and taught at the end of the sixth and the beginning of the fifth century before Christ.

Mohammedanism is the religion founded by Mohammed, a religious teacher who lived in Arabia about six hundred years after Christ. His followers are called Mohammedans. Their creed is, "there is one God, and Mohammed is his prophet." Their sacred book is the Koran. In past centuries they often compelled people by the sword to accept their faith, and they are numerous in southwestern Asia, India, and north Africa. At one time they conquered much of Spain (Sec. 458). Their sacred city is Mekka, and a railroad is being extended from the north to that city, chiefly to accommodate Mohammedan pilgrims.

The *Hebrews* of the present day receive their faith from the ancient Jewish people. They believe in one God, and accept the Old Testament as their Bible. They reject the New Testament as not being a part of the Bible, and do not believe that Jesus was the Messiah or Savior. They have been much persecuted and are now widely scattered among the countries of Europe and America.

In addition to the forms of religion already described, many savages and rude tribes in various parts of the world scarcely have a religion, and

are called *pagans*. They believe in many gods, or good and evil spirits, and worship images or idols.

501. Agriculture.—Agriculture in Asia goes back to times so ancient that we have no record of its beginnings. No one knows when the chief grains and fruits were improved from wild plants, and no one knows when or where cattle, horses, dogs, camels, and other animals were domesticated and made to serve man.

More of the people of Asia are engaged in cultivating the soil than in any other occupation. This is especially true in eastern and southeastern Asia, where the climate is warm and rain plentiful. It is because of these conditions that so many people can live in those parts of Asia. Nearly half the human race live on the warm and fertile side of this one continent. They are overcrowded there, and when a crop fails or is short, famine follows and thousands die of starvation.

In the central, northern, and western parts of Asia the country is generally too cold or too dry for agriculture. Near springs of water and along streams, the water has been used for centuries to irrigate the fields, and some crops are raised. A place in the desert that is naturally or artificially watered and made green and fruitful is called an *oasis*. At such a place a village

usually grows up, and here caravans stop on their journeys across the desert.

502. Nomadic Peoples.—Many of the people do not try to live by agriculture, but wander from place to place. They are called *nomads*, and they look down on farmers as inferior people.



Fig. 497. A nomad family, Persia

The natives of northern Siberia live in the far north only in the short summer. The reindeer is their beast of burden and is useful for its milk, its hide, and its bones, which are used for making tools. In summer the natives gather wild berries, and catch fish for summer food and to dry for winter use. In the winter they move southward into the edge of the Siberian forests. They live in rude tents, and the women stay at home and prepare the food, make the clothing out of skins, and care for the animals. The men go out in the forest and hunt for animals that yield furs. When summer comes they go back again to the tundra.

The people of the deserts and steppes also are nomads. They have many horses, camels, cattle, and sheep. These require pasture, and as grass is scattered or in patches, the family must move, sometimes every day, sometimes at greater intervals, depending on how long the pasturage holds out. Not only one family, but the sons and their families, and the servants as well, stay together, and thus the family becomes a tribe. The men of the steppe are expert horsemen from childhood, and wealth consists in owning many horses and other animals. Here, as in the tundra, the women do most of the drudgery of the camp. The customs of these people make them independent and brave. Many pictures of life such as theirs are found in the historical books and poems of the Old Testament. The desert people do not change their habits, and we find them to-day living much as they lived in the days of Abraham.

503. Fishing.—Among the tribes in the northern and northeastern parts of the continent, fishing and hunting furnish a large part

of the food. Fishing is also an important industry among the Japanese and Chinese.

504. Mining and Manufactures.—The mineral wealth of Asia is enormous, but only a small part of the mineral riches of the continent have been worked in any systematic way.

Manufactures are not so extensive or so greatly varied in Asia as they are in Eu-

rope or North America, for the people are not so progressive. They have never invented fine machinery, and their chief products are made by hand and in their homes. Nevertheless, many of them are skillful and show much taste in making objects of beautiful forms and colors. The Chinese



Fig. 498. Stamping the pattern on cloth in India

and Japanese make silks and pottery that win the admiration of the world, and the people of the drier lands of western Asia have for hundreds of years made the finest and rarest rugs and carpets. These are woven on hand looms, and months and sometimes years are spent on a single piece. The fibers are from the wool and hair of sheep, goats, and other animals, and are colored with dyes made from plants. In recent years these rugs have been much sought by people in Europe and America, and the demand has led to the building of factories and to the making of many rugs of poorer quality.

505. Ancient Routes of Trade.—Long before the time of Christ the Asiatic peoples traded with one another. They followed well-beaten trails, and their caravans went between China and India on the east, across the plateaus and over the mountain passes to Persia, to the regions along the Euphrates, and to the shores of the Mediterranean. It was also before the Christian era that the people of Europe began to want the tea,

the fabrics, the jewels, and the spices of the East. Much of this trade was carried on by the Phœnicians, who lived in Tyre and Sidon, ancient cities at the east end of the Mediterranean Sea. They received the goods from the caravans and took them westward in their ships. After a time the Roman people controlled the trade, and later the citizens of Venice and Genoa, great commercial cities of Italy, were the chief traders. About the time America was discovered, a way was found to the East around the Cape of Good Hope, and the land routes of Asia became of less importance. Many of them, however, are still used.

506. The Awakening of Asia.—Most of the people of Asia have been satisfied to do the same things in the same ways for thousands of years. This is shown in the worship of ancestors in China, the caste system of India, and the ways of life in the desert. But many changes are now taking place. Foreign nations have pressed into Asia for conquest, for commerce, and for missionary work.

Many years ago the Japanese opened some of their ports to foreign trade. Gradually China has pursued the same course. Great Britain founded a great commercial city on the island of Hongkong just off the shores of China. The British have also for a long time ruled the three hundred million

people of India. They have built railroads, founded schools, introduced machinery, and developed agriculture. The Russians have extended their control over northern Asia, and have built several railroads. Japan is one of the most progressive nations, and China is building railroads and modern factories.

Indian, Chinese, and Japanese young men and women study in the schools of Europe and America. Some of them have been sent by their governments to learn the ways of the West so that they may introduce them into the Orient. In southwestern Asia, rapid changes are resulting from the World War. The ending of Turkish misrule made it possible for Syria, Palestine, and other lands to progress in agriculture, manufacturing, commerce, and education. The entire continent is rapidly advancing and taking its place as a part of the modern world.

Review.—1. Give an account of the distribution of the yellow race. 2. Where, in Asia, are people of the white race found?

3. Name and briefly describe each of the chief forms of religion in Asia. 4. What is a pagan?

5. In what part of Asia is agriculture chiefly pursued? 6. Describe the life of the northern nomads; of the desert nomads. 7. Name some of the chief articles manufactured by Asiatic people. 8. Give an account of the Phœnicians. 9. What changes show that Asia is becoming more modern and enlightened?



Fig. 499. School in Persia



Fig. 500. Railroad station, Bombay




Fig. 501. Western Asia

THE COUNTRIES OF SOUTH-WESTERN ASIA

507. Turkey.—The westernmost country of Asia is Turkey. It occupies Asia Minor, the peninsula that has the Black Sea on the north, the Aegean Sea on the west, and the Mediterranean Sea on the south. It is a rugged plateau bordered by ranges of mountains on the north and south.

Centuries of misrule have kept the people in ignorance and poverty. Turkish industry, therefore, is very primitive. Cereals, tobacco, cotton, fruits, and nuts are, with wool and mohair, the principal products. The country is rich in petroleum and minerals, and the fisheries are important. Textile manufactures are increasing.

The chief seaport is Smyrna. Trebizond has for many centuries been the starting point of caravans going to Persia.

Northeastern Turkey includes most of Armenia, which for a short time after the




Fig. 502. A mound of wheat in an Armenian market

World War was an independent country. It is a mountainous land where the chief industries are farming and grazing. The Armenians are of the white race and hold the Christian faith. For a long time they have been bitterly persecuted by the Turks and by savage tribesmen known as Kurds. The small part of Armenia that is not in Turkey is a republic under the control of Russia.

508. Syria and Palestine.—Syria lies east of the Mediterranean Sea. In Syria, north of Palestine, is the Lebanon mountain range, still bearing such giant cedars as are mentioned in the Bible. Aleppo is a commercial center in northern Syria. Damascus, in an oasis, is the chief city of the country. In the World War, French forces occupied the Syrian coast, and after the war Syria was made a French protectorate.

Near Syria is the large island of Cyprus. It was occupied by the Phœnicians three thousand years ago. It has since had many rulers, but is now governed by Great Britain.

Fig. 503
PALESTINE

Scale of Statute Miles

0 5 10 20
12 MILES TO ONE INCH

Main Highways:
Railroads in operation: ————
Proposed Railroads: - - - - -

ELEVATIONS IN FEET



All place names are Biblical or Historical except those in parenthesis (Acre), which are Modern place names.



In the World War Palestine, the "Holy Land," was wrested from the Turk after centuries of corrupt rule. Many Jews plan to go there to set up a new Zionist Republic, under British protection.

Palestine is a small country, but is of great interest because here the most important events of Hebrew history took place. Here Jesus lived, and the Christian church was founded. On the Mediterranean side is a coastal plain, the land of the ancient Philistines. Here is Jaffa, the seaport of Jerusalem. Back of the plain is a range of low limestone mountains. On the top of this range is Jerusalem, the Holy City (Fig. 504), and a few miles south is Bethlehem, the birthplace of Jesus.

East of this ridge is the deep valley of the Jordan and the Dead Sea. The Jordan rises in a great spring south of Mount Hermon, flows through the Sea of Galilee and down to the Dead Sea. This latter sea is in so hot a region, and the rainfall is so small, that it has no outlet and is a salt lake. Its surface is 1292 feet below sea level, and it is so salt that no fish can live in it. The southern part of Palestine was the ancient Judea, and the northern part was Galilee, containing Nazareth, the home of Jesus.

Palestine is called in the Old Testament a land flowing with milk and honey, but this statement is far from being true now. Since those early days the country has been sadly neglected, its trees have been cut away, and the soil has been washed from the hillsides. At the present time it is beginning to prosper again under modern enterprise.

A railroad extends from Jaffa to Jerusalem. Another runs from Damascus to the sea at



Fig. 504. Jerusalem. The large dome at the far left is on the Church of the Holy Sepulcher

Beirut, and a long line, nearly completed, extends from Smyrna to Damascus, and far southward. It will be continued to the outskirts of Mekka, the sacred city of the Mohammedans. Another railroad is planned to cross Syria and Mesopotamia from the Mediterranean Sea to the Persian Gulf.

509. Iraq and Arabia.—Iraq, also called Mesopotamia ("be-

tween the rivers"), is the region of lowland along the Tigris and Euphrates rivers. It was the seat of ancient empires and of the cities of Nineveh and Babylon. Here, as in Egypt, irrigation was practiced in ancient times and its use is again increasing with the revival of agriculture. One of the chief resources is petroleum, of which large amounts are obtained. Bagdad is the principal city. Goods and passengers are carried on the rivers by rafts and steamboats.

Iraq is an Arab kingdom under the protection of Great Britain.

Arabia is an immense peninsula, one third the size of the United States. It is widest at the south, and is bordered on the west by the Red Sea, on the south by the Arabian Sea, and on the east by the Persian Gulf. It is mainly a high plateau with a very dry climate. Much of it has never been explored.

The kingdom of Hedjaz, with British aid, threw off the Turkish yoke in 1916. This small country on the eastern shore of the Red Sea contains the important Mohammedan cities of Mekka and Medina, and aims to become the nucleus of a greater Arabia.

The future of Asir and Yemen, former Turkish provinces southward from Hedjaz, is yet to be determined.



Fig. 505. Plowing in Persia. The plow is drawn by eight buffaloes

Aden, at the southwest end of the peninsula, is owned by Great Britain and is an important coaling station.

Oman is an independent state. Its seaport is Maskat, from which many dates are sent to the United States. In the Persian Gulf are important pearl fisheries.

The interior of Arabia has no single government. Its wandering Arab inhabitants are called Bedouins, and the tribes are under native chiefs called sheiks. The people are few, and only small districts can be cultivated.

The Red Sea on the one side, and the Persian Gulf on the other, were important routes of commerce in ancient times, and since the Suez Canal was constructed the Red Sea has again become a great trade route.

510. Persia.—Persia is an ancient country, and many centuries ago it was very large, reaching from the Mediterranean Sea to India. It is now a country nearly three times as large as France, but has less than one fourth as many people. So much of it is desert or barren mountain side that food for a large population cannot be raised. Much more of everything could be produced, however, if the people had the skill and the machinery that are common in Europe and

America. Figure 505 shows the clumsy Persian method of plowing.

The surface of Persia is a plateau with many mountains and valleys. Over much of the area the rainfall averages only about five inches a year. There are few rivers and many deserts. The streams usually disappear in the desert sands. The snow and rain of the mountains supply such streams as the country has, and the water is used in the valleys for irrigation. The northern part of the country, around the Caspian Sea, has a more moist climate and considerable forest, but it is unhealthful. Silk, wool, cotton, tobacco, wheat, and barley are common products of Persia, as are fruits and gums.

Many sheep and cattle are raised. Much of the wool is used in making beautiful rugs and shawls. They are among the finest of those produced in Asia. The rugs (Fig. 506) are known by the name of the city or province in which they were made, each district having had for hundreds of years its favorite colors and designs. Many of these rugs are sold in America.

The mineral wealth of Persia is undeveloped, but there is evidence that the country is rich in petroleum. Many borings have



Fig. 506. A rug being made by hand in Persia

already been made and oil is being shipped in increasing quantities.

Nearly all the Persians are Mohammedans in faith. The greater number lead a settled life in towns and cities, but there are many tribes of nomads or wanderers (Fig. 497).

In 1906 a constitution was granted to the people by the Shah, as the ruler is called, and a government was organized to meet the desires of the more intelligent Persians.

The cities have fine mosques and some beautiful shops (Fig. 507). The houses are usually made of dried mud and the windows face an inner court, leaving the street blank and unattractive. Teheran, the capital and largest city, has made much progress. Ispahan was formerly the capital.

By the Persian Gulf the country communicates with Bombay and other ports of India. On the west, caravan routes lead to the Black and Mediterranean seas. On the north, the Russians have built a railroad to the boundary.

The roads in Persia are poor. Travel has always been by means of animals, but recently automobiles have been introduced.

511. Afghanistan.—Afghanistan lies between Persia and India. It is nearly as large as the state of Texas, or the Canadian province of Saskatchewan. There are about six million people. The ruler is called the Ameer.

Most of the country is mountainous. In the fertile plains and valleys grain and many varieties of fruit are grown in abundance. Preserved fruits are exported.

Review.—1. Describe the surface of Palestine.

2. Give an account of the Jordan and the Dead Sea. 3. Locate Jerusalem, Bethlehem, and Jaffa.

4. What changes have taken place in Palestine?

5. What country governs Cyprus? 6. Where is Iraq? Syria? Armenia? Turkey?

7. Give an account of Hedjaz and its capital.

8. Where are Oman and Aden?

9. What is the ruler of Persia called?

10. Compare Persia with France as to size and population. 11. How do the Persian rugs compare with those made in other parts of Asia?

Where are many of them sold? 12. What is the condition of transportation in Persia?

13. Describe Afghanistan.



Fig. 507. Mosque in a Persian city


Fig. 508

Physical and Political

INDIA AND INDO-CHINA

Scale of Statute Miles

Capitals: © Railroads: ©



INDIA

512. Size.—India proper occupies the central peninsula of southern Asia, together with large regions to the north. Bordering it on the west is the desert country of Baluchistan. The Indian Empire under British control includes India proper and Baluchistan, and also Burma, which extends over the west side of the Indo-Chinese peninsula. The total area of this greater India is only three fifths that of the United States, but it contains more than 300,000,000 people. Besides the Hindus, there are in India many different peoples speaking various languages.

513. Surface.—The surface of India may be divided into three main parts, — mountain, lowland, and plateau.

The first region is the southern portion of the Himalaya Mountains. Even the passes over these mountain ranges are from 16,000 to 19,000 feet above the sea, or higher than the highest peaks of the Alps. Here are the sources of the two principal rivers of India, the Ganges and the Indus. The Indus flows southwest and enters the head of the Arabian Sea. The Ganges receives many rivers from the mountains, flows southeast, and enters the Bay of Bengal. Near its mouth it is joined by the Brahmaputra, which is 1800 miles long, or longer than the Ganges itself. This river comes from Tibet, north of the Himalayas. The combined rivers have built a very large delta.

The second region consists of the lowlands of both the Indus and the Ganges. These rivers and their tributaries have spread out the waste from the mountains into wide flood plains, which make up the lowland of India, extending from the Arabian Sea across to the Bay of Bengal. Except some desert ground near the Indus, this plain is densely populated and has many cities.

The third region is the central and southern part of the peninsula, which is a plateau called the Dekkan. Much of this upland is

a half mile above the sea, and the larger part of it is covered by ancient lavas, which in some places are more than a mile thick. The surface long ago weathered into soil. There are many mountains in the Dekkan.

The coast line of India is little broken, and there are but few good harbors.

514. Irrigation.—The lower Ganges flows through a region of heavy rains (Sec. 373). During the summer monsoons the western coast of India from Bombay southward is well watered. The winter monsoons give rain in Ceylon and the adjacent parts of the mainland coast. But much of India is so dry, at least a part of the year, that irrigation is needed. The natives dug irrigation canals centuries ago, but the British people have greatly extended irrigation, and have made India the first country in the world in this respect. In years of serious drought, however, the people of a large part of India are in danger of starvation. There has been much loss of life in this way, in spite of help from the government and of gifts of private charity from other lands.



Fig. 509. Shore of the Ganges River at Benares

515. Agriculture.—The three principal grains raised in India are wheat, millet, and rice. Wheat is raised in the lowlands of the northwest, also in the Dekkan Plateau, and some of the crop is exported. Much of it is taken to Karachi, near the mouth of the Indus, and much goes to Bombay, and is there made into flour. Most of the people are too poor to eat wheat bread, and many use millet. In the lowlands of the lower Ganges, where the fields can be easily flooded, is one of the great rice regions of the world. Two crops a year are usually raised. Not much of the rice that we buy comes from this part of India, for most of the crops there are needed at home. Burma exports more rice than any other region. One third of the people of the globe—including many of the people of India and China—find in rice their chief food.

Much cotton is raised in the central parts of India. Some of it is sent to English factories and some is spun and woven in the cotton mills of India. Jute, a tall plant, yields a silky fiber used in adulterating fine woven goods of many kinds, as well as in making ropes and bagging. Silk is produced, but not so extensively as in China. Cinnamon and pepper are among the spices raised in India. Sugar cane and oil seeds, including flax, are important crops.

Tea is one of the chief products. It is grown especially in the lower valley of the Brahmaputra. Much tea is exported from this part of India.

516. Lumbering and Other Industries.—Teak is a hard and durable wood that grows in several parts of India and is valuable for shipbuilding and for furniture. It is not

usually attacked by the insects that destroy softer woods. Some teak trees are 200 feet high. They are generally girdled, and killed, two years before they are cut, so that the wood may season while standing. Teak leaves furnish a purple dye for silk and cotton goods. The bamboo (Fig. 530) is used for many implements and in the construction of the light, simple houses of the natives. The banyan is

a curious, spreading tree with many trunks (Fig. 510). Palms and coconut trees furnish drink and food.

Many cattle are raised, but chiefly for domestic use. Hides and skins, however, are exported in large numbers.

The mineral deposits are valuable and include coal, iron, petroleum, and gold.

517. Government.—Three hundred years ago Great Britain, France, and Portugal began to trade with India, and the British after a time gained control of nearly all the country. Many native states still have their own governments, under British influence, but since 1858 most of the land has been directly under British rule. The king of Great Britain now has the title emperor of India, and the British government appoints a viceroy who is the actual ruler. In 1912 the capital was removed from Calcutta to Delhi, the ancient capital of a former native empire.

It is the policy of the government to give the natives a gradually increasing share in the management of affairs. Much has been done for India by British rule. Irrigation has been extended, better and cleaner ways of living promoted, schools supported, and more than 30,000 miles of railroad have been built. Before 1858 there were less than 1000 post-offices, while now there are about 70,000.



Fig. 510. A banyan tree



Fig. 511. Bombay, India

518. Cities.—Calcutta is the largest city of India, with about 1,300,000 people. It is on the delta of the Ganges and is a great commercial city in spite of its poor harbor. Bombay (Fig. 511) is the second city. Since it has been possible for ships to come from Europe to Asia by the Mediterranean Sea, the Suez Canal, and the Red Sea, Bombay has become an important seaport. Madras is a port in southern India. Hyderabad is the largest city of the interior. Benares is on the Ganges (Fig. 509), and both the river and the city are regarded as holy by the Hindu people. They believe that they receive blessing by drinking or bathing in the water of the river, or by making pilgrimages to the city.

519. Burma.—Burma is a large province with more than 13,000,000 people of various races. Only a small part of the country is under cultivation, but under British control conditions are improving. Rangoon is the largest city and chief seaport (Fig. 512). It exports much teakwood and rice. Mandalay is the chief city of the interior. On what river is it (Fig. 508)?



Fig. 512. A street in Rangoon, Burma

rubber, coconuts, and other tropical products. Sapphires and other gems are found, and there are pearl fisheries. Much graphite is mined and exported. The main port, Colombo, is one of the great coaling places for ships engaged in Asiatic trade (Fig. 513).



Fig. 513. Port of Colombo, Ceylon

520. Nepal and Bhutan.—The small countries of Nepal and Bhutan, in the mountains north of India, are called independent; but they are under British protection. Nepal has several million inhabitants. Most of them are people called Gurkhas, and many of the men are soldiers in the British army.

521. Ceylon.—The island of Ceylon has been for a hundred years under British rule. It is a colony by itself, not part of British India. The area and population are nearly as great as those of Ireland. It is one of the three largest tea-raising regions in the world, and raises



Fig. 514. Rubber plantation near Singapore

SOUTHEASTERN ASIA

522. Indo-China.—The peninsula of Indo-China includes Burma (Sec. 519) and the countries southeast of it.

The Malay Peninsula, narrow and mountainous, stretches far southward from Burma. The southern end of the peninsula is known as the Straits Settlements, because bordered by the Strait of Malakka, which separates the mainland from Sumatra. The Settlements form a British colony, and connected with it are a number of Malay states that are under the protection of the British government. This region produces a great variety of tropical gums, spices, fruits, and grains, but the best-known exports are rubber and tin, of which a large part of the world's supply comes from this region. The barbarous natives have become orderly and somewhat civilized through steady employment in producing tin and rubber.

Singapore, on an island near the end of the peninsula, is a large city founded by the English, and is a very important

port, because it is on the route of all ships sailing around the south shore of Asia.

East of Burma are two countries, Siam and French Indo-China. In both of them, mountain ranges run from north to south. The Mekong is a great river on the boundary of the two countries.

Siam is not quite so large as Texas, but has nearly twice as many people. As in India, rice and millet are important crops, and tin, gold, and gems are among the minerals found.

Here also teakwood is one of the most valuable products. The government is an absolute monarchy — one of the few still existing. The capital is Bangkok (Fig. 515), a city intersected by the Menam River and by many canals. On these waters thousands of the inhabitants live in floating homes or houseboats.

The French possessions are about as large as Texas, and have nearly four times as many people. The products are like those of other countries of southern Asia, including teakwood, millet and rice, spices, tea, cotton, and silk. Hanoi, the capital of French Indo-China, and Saigon, near the sea, are important cities.



Fig. 515. Bangkok. Notice the houseboats along the shore



Fig. 516. Irrigating rice terraces in Java

523. East Indies.—The East Indies (or Malay Archipelago) are the islands lying between Asia and Australia. All except certain islands that are close to Australia are considered as belonging to Asia. The waters about them are not so deep as in most parts of the ocean. These islands are largely of volcanic origin. Active volcanoes are numerous and earthquakes occur frequently. The vegetable and mineral products are like those of the neighboring parts of the mainland.

More of these islands belong to the Netherlands than to any other country. They are known as the Dutch East Indies. All together they have a surface almost one fourth as large as the United States, and contain nearly 50,000,000 people. The most important of the Dutch possessions, though not the largest, is the island of Java, which has 35,000,000 people, and exports tea, rubber, tobacco, tin, copra, coffee, sugar, and cinchona (quinine). Most of these commodities are taken to the Netherlands and are then distributed to other countries. Rice is the chief food crop (Fig. 516). Batavia is the capital of Java.

Sumatra is much larger, but has fewer

people. It produces tobacco and many tropical products. Near it are two small islands, Banka and Billiton, which have rich tin mines. Borneo is the largest island of the group. It is divided between the Netherlands and Great Britain. The Dutch also hold Celebes, part of New Guinea, and a large number of smaller islands, while the Philippines belong to the United States. The islands resemble one another in soils and climate, are rich in minerals, and abound in every kind of tropical product.

Review.—1. What regions are included in British India? 2. Where are the principal lowlands of India? 3. Give an account of the Dekkan.

4. Give the chief facts about rice production in India. What other grains are raised? 5. For what is teakwood used?

6. How is India governed? 7. Name the principal cities of India. 8. Name and locate the principal rivers and cities of Burma.

9. What are the products of Ceylon?

10. What name is given to the southern part of the Malay Peninsula? 11. State the location and importance of Singapore. 12. What are the products of Siam? Of French Indo-China?

13. What parts of the East Indies belong to the Netherlands? 14. What localities furnish much tin? 15. How does the population of Java compare with that of the Netherlands?

CHINA

524. Chinese Provinces.—In addition to China proper, the Chinese government claims authority over four provinces on the west and north: Tibet, Sinkiang, Mongolia, and Manchuria. All together these five regions are about half as large as North America.

Tibet is a high and mountainous plateau. The western part of the plateau is from 14,000 to 16,000 feet above sea level, and surrounding mountains rise much higher. It is very cold and very dry, and yet it contains many lakes. These have no outlets and are therefore salt. The eastern parts of Tibet are lower. The people and the cultivated lands are mainly in the drainage basin of the Brahmaputra River. Barley thrives there, and it is the chief grain and the most important food of the people. The herdsmen keep sheep, goats, and yaks, which can live on the scanty pasturage.

Yaks are much like cattle, but are usually black or white and have coats of long, soft hair. Yak's milk is rich, and is made into curds, which are a favorite food of the Tibetans. Ropes and tent coverings are made of the hair, the flesh is good for food, and the animals are used to carry loads, but not to draw wagons or plows. Thus the yak is as useful in this high, cold region as the reindeer is on the Arctic plains.

Cashmere wool, clipped from goats, is an important export, and brick tea is brought in from China proper.

The Tibetans are so isolated by mountains and so far from the main Chinese nation that they are but little controlled by the central government. Lassa is the capital and is regarded by the people as a sacred

city. They try to shut out all foreigners from the place, and only a few have ever succeeded in entering it.

The province of *Sinkiang* includes Chinese Turkestan and other districts northwest of Tibet. It lies largely in the basin of the Tarim River, and is much lower than Tibet. Nearly all the province is a sandy desert, and the river ends its course in a salt lake. There are a few oases, where towns have stood for many hundred years. The most impor-

tant of these are Yarkand and Kashgar. Through Sinkiang runs an ancient caravan route, by which China has carried on trade with western Asia and Europe.

Between China proper and Siberia is the vast province of *Mongolia*. It is occu-

pied by the Desert of Gobi and by ranges of high mountains. The people are nomadic and devote themselves mainly to the keeping of camels, horses, and sheep. The Chinese call the desert "the Sea of Sand." A great trade route leads from northern China across Mongolia by way of Urga to Siberia.

Manchuria is on the Pacific Coast, east of Mongolia. It has extensive plains, is well watered, has good soil and a favorable climate, and produces large crops of beans and wheat. It has more people than all the three provinces already described. The Russians laid a railroad across it from Siberia to Port Arthur, where they built a great fortress, on ground leased from China. In a war with Russia in 1905, Japan captured this fortress, and these two countries now exercise much influence over Manchuria, though the province is considered as belonging to China. Mukden is the capital. Dairen, the chief port, is under Japanese rule.




Fig. 518. Yaks



Fig. 519. Coolies unloading tea at Hankow

525. China Proper.—China proper is less than half as large as the United States, but has about three times as many people. A complete census is not taken and we do not know the population accurately. The country is mountainous in the west, where it joins Tibet, and in the south, where it borders the Indo-Chinese region. The main lowlands are along the great rivers.

The largest of the rivers is the Yangtze, which to the Chinese is "the great river." It is 3100 miles long and is the main commercial river of China. Ocean vessels ascend to Hankow, 680 miles from the sea (Fig. 519). River

steamers go 370 miles farther, and native boats, pulled in some places by means of ropes, by runners on the banks, reach a point 1750 miles from the ocean. Several large cities are on the Yangtze, and the adjoining country has a dense population.

The Hwang is the main river of northern China. Like the Yangtze, it rises in Tibet. After making a great bend northward in Mongolia, it crosses the plains to the Gulf of Pechili. It sometimes rises in terrible floods over these plains, and in 1887 no less than 1,000,000 people thus lost their lives. It is not strange that the people refer to it as "China's sorrow." It has shifted its course as much as 300 miles, and for a time it flowed into the Yellow Sea instead of the Gulf of Pechili.

Much of the interior of northern China is covered with a fine, yellowish soil known as *loess*. This is in places hundreds or even thousands of

feet deep. Streams and rains have washed it and cut it into many hilly surfaces. As it is easily dug, and the country is dry, thousands of Chinese families cut out rooms in the

banks and cliffs and use them for houses. This material is extensively washed away by the Hwang, or *Yellow River*, so called because discolored by the land waste that it carries.

526. Climate.—The climate of China and its provinces varies greatly in different sections, for the land lies across much of the temperate belt, and its southern parts are south of the Tropic of Cancer. Part of it is low and near the ocean, and the interior is high and far removed from the influence of the sea.



Fig. 520. Road cut in loess

Little moisture can reach the high interior provinces, for most of their area is in the course of the westerly winds, which have moved across Europe and western Asia before they reach the provinces of China. The high wall of the Himalayas shuts off moisture derived from the Indian Ocean.

China proper and Manchuria have much more rain. All the southern parts are in the course of the monsoon winds that bring so much rain to India (Sec. 373). The south coasts often have as much as 100 inches of rainfall a year. The rainfall is less in the north, and at Peking the amount is about 24 inches.

Violent storms sometimes start in the East Indies and sweep the Chinese coasts, doing great damage. They are called *typhoons*, and are like the West Indian hurricanes.

527. People of China.—This section refers only to the people of China proper, who number more than 300,000,000. They have tilled the soil, built cities, and have been a civilized people from very ancient times. Until the middle of the nineteenth century they lived almost by themselves. The mountains and deserts of the western provinces shut them away from western Asia and Europe. Siberia was a wilderness until the Russians built a railroad through it. The Himalayas and other mountains separated the Chinese people from India, Burma, and Siam. On the ocean it took months for a European sailing vessel to reach them, and they did not allow foreigners to trade in their coast cities. They thought they had the best institutions, learning, and arts, and they did not want to have anything to do with other nations.

They knew how to make the finest silk goods, and fine china ware. They manufactured paper and published books long before



Fig. 521. Great Wall of China; view along the top

Europeans invented printing. Instead of using type, however, they printed from blocks of hard wood, each containing the engraved words for a whole page. Twelve hundred years ago they built a canal 700 miles long which is still used. Two hundred years before Christ they began to build the Great Wall, which still stands to show their skill and industry. It extends more than 1200 miles from east to west, across hills and valleys, and has many watchtowers. It was constructed as a defense against Mongolian invaders from the north, and it served its purpose, for these wild enemies were horsemen, and a small Chinese army could defend the wall against them (Fig. 521).

While the Chinese people have thus been for many centuries capable of great achievements, they have been slow to adopt new customs. They show great deference to parents. They have an excessive reverence for the past, and do not readily change from the habits and mode of life of their forefathers. They are disposed to think the old way is best, and they also fear that they will lose their work when railroads take the



Fig. 522. Cutting off the queue, in China

place of porters and junks, and when machines replace labor by hand. And yet the Chinese people have always shown great skill and industry and they are coming gradually to appreciate the modern point of view and the ways of western nations.

Woman has been in a low position in China, and many girl babies were formerly sold or put to death, because they were not wanted. The feet of girls were bound in infancy, so that they could not grow, and many women could hardly walk. This is changed now, foot-binding is no longer lawful, and women begin to have advantages that they have not had before.

For nearly three centuries the Chinese men shaved part of their heads and allowed the rest of the hair to grow, to be braided into a "queue" or "pigtail," as a sign of submission to the ruling dynasty of emperors. But since the downfall of those emperors the queue has become very unpopular.

The homes of most of the people are poor, being made of bamboo or of dried mud. Little fuel is used,

although China has much coal, and modern mines are in operation. Many of the people try to keep warm in padded cotton garments. The roads are very bad, and only recently have attempts been made to improve city streets, or to build sewers to carry off the filth of the cities. Goods are carried on the backs of men and animals, or pulled along the streams and canals in boats. Both goods and men are transported on a kind of wheelbarrow

with a large wheel in the center. In recent years, however, several important railroads have been built, and others are under construction.

528. Government.

—About three hundred years ago the Manchu race, coming from the north, conquered China; and from that time on,

until recently, the reigning sovereigns belonged to the Manchu dynasty. In modern times foreign nations, desiring Chinese trade, have gained permission to visit and settle in certain ports and in other cities. The

Chinese have learned the value of foreign manufactures, such as cotton goods from our own country. Missionaries and teachers, especially from America and Great Britain, have introduced foreign ideas. The Manchu emperor was deposed in 1912, and a republic proclaimed; but there was long delay in adopting a constitution for the new government.



Fig. 523. Chinese passenger wheelbarrow



Fig. 524. Chinese house boat



Fig. 525. Cells formerly used for examinations in China



Fig. 526. A Chinese school supplied with modern books

529. Agriculture.—To till the soil is thought highly honorable by the Chinese. The farms are small and are tilled with all the care usually bestowed on a garden. The Chinese farmers have long known that it is useful to change or rotate the crops. They save everything that can possibly be useful as a fertilizer; otherwise they could not have raised crops on the same ground for thousands of years. On the steep slopes they have made many terraces, as the farmers have in Italy and Germany, to prevent the washing away of the soil (Fig. 527). Even on the rivers, rafts are built and covered with soil for making gardens. Thousands of people have their little homes on such rafts, for every foot of space is precious where such a multitude must have homes and get a living.

The natural rainfall does not always provide moisture enough for the crops. In the plains, especially in central and southern China, water is laboriously raised from the rivers for irrigation, and for flooding the fields in raising the immense crops of rice that constitute a large part of the people's food. Two crops a year of rice and other products are commonly grown. The Chinese raise fish

in the irrigating ditches and plant mulberry trees along the banks to feed silkworms. China is one of the leading countries of the world in the production of raw silk. This is largely because it has the cheap labor necessary for feeding the worms and unwinding the silk fibers from the cocoons (Sec. 449). Cotton is raised and is

mainly consumed in home manufactures.

530. Tea.—China supplies a large part of the world's tea. The plant or bush needs a warm climate, but will endure some frost. It requires plenty of moisture, but the water must not stand around the roots. Hence the warm, well-watered hillsides in much of China are good ground for the tea crop. Three times a year the leaves are picked, dried in the sun, heated, rolled in the hand, and then baked over fires of charcoal. This process, which causes fermentation, makes "black tea." In making "green tea," the leaves are roasted without being fermented. Some of the tea is pressed into "bricks," for convenience in packing in small



Fig. 527. Terraces built to save the soil, northern China




Fig. 528. Harbor of Hongkong

compass, and in carrying a great distance on pack animals. The cheaper bricks are made from the poorer leaves and small twigs.

531. Forests and Minerals of China.—The country is so old and so populous that most of the trees were cut down centuries ago. For this reason there is but little wood for use, and the soil on the hills has been subjected to great washing and loss. There are some forests in southern China and in the outlying provinces, but the people have yet to learn the practice of forestry.

The coal and iron deposits of China are among the most extensive in the world. There are also rich deposits of copper, gold, silver, tin, mercury, lead, and antimony. Much tin and antimony are exported.

532. Chinese Cities and Routes of Trade.—China has not many good seaports. Shanghai is by far the most important. Behind it is the vast and fertile Yangtze Valley, with many cities along the Yangtze River. Hankow, on this river, is the most important interior city of China (Fig. 519). Waterways bring it into communication with many rich provinces. The principal railroad of China runs north to Peking, and a connecting line is under construction from Hankow to Canton.

This will furnish a trunk line for traffic from north to south through the richest part of the country. Far in the interior on the Yangtze is Chungking, the commercial center of western China.

In northern China are Peking, the capital, and Tientsin, the port of Peking. The seaport is a large city, commercially more important than the capital. These cities are joined by railroad with Siberia, by way of Manchuria.

The port of Kiaochow, greatly improved as a German possession before the World War, has been returned to China.

Canton is the chief city of the southern regions. It is one of the large cities of China and is a center of the silk trade.

Not far from Canton is the island of Hongkong, which belongs to Great Britain, although the largest part of its population is Chinese. The seaport of Hongkong is one of the greatest in the world, and rivals Shanghai as a place for Chinese trade.

Review.—1. Describe the physical geography of Tibet. 2. In what ways is the yak useful? 3. Name the chief river and principal cities of Sinkiang. 4. What desert is in Mongolia? 5. Why is Manchuria an important province? 6. Describe the Yangtze River and give the facts about its navigation. 7. Give an account of the Hwang River. 8. What is the loess? 9. Explain the differences of rainfall in the different parts of the country.

10. How were the Chinese long separated from other peoples? 11. In what industries have the Chinese people shown skill?

12. What are the leading agricultural products of China? 13. What conditions are best for raising tea? 14. In what minerals is China very rich? 15. Draw a map of China showing the chief rivers and cities.



Fig. 529. A valley in central Japan. Much of Japan is mountainous

EMPIRE OF JAPAN

533. Physical Geography.—The Japanese Empire embraces a chain of islands extending from the south end of the peninsula of Kamchatka almost to the Philippine Islands. In the central part is the main Japanese group of islands, of which Honshu is the largest and most important. To the north-east are the Kuril Islands, of volcanic origin, and containing several active volcanoes. These islands are small and barren. The south half of the large island of Sakhalin has belonged to Japan since the close of its war with Russia in 1905. To the southwest is another chain of small islands,—the Nansei group,—and southwest of these is the island of Taiwan, or Formosa. The ancient country of Korea, occupying a peninsula of Asia, has been made a part of the Japanese Empire, and is now called Chosen.

The main islands are mountainous (Fig. 529), and are partly of volcanic origin. They contain several active volcanoes, one of which is Fujiyama, with an altitude of over 12,000 feet. Earthquakes occur frequently,

and some of them are very destructive. The houses are built low, so that they may withstand the strain of the shocks.

The empire ranges in latitude from 22° to about 51° north. The southern part of Formosa is south of the Tropic of Cancer. Because of such differences of latitude the climate varies from tropical in the south to cold in the north. A warm ocean current, known as the Japan current, flows northward along the coast. The rainfall is heavy, and in the north and on the higher mountains there is much snow. The forests, by reason of the moisture, are luxuriant and show a great variety of trees. Much forest growth has been preserved because most of the surface is hilly or mountainous and there is less temptation to cut away the trees on steep slopes in order to cultivate the land.

534. People of Japan.—On the Japanese islands there are about 55,000,000 of the Japanese people, and their country is so small that only their industry and skill enable them to support themselves. They belong to the yellow, or Mongolian, race. They are somewhat like the Chinese, but are smaller in

stature, and more keen and active. Some are trained from infancy to be athletes, and they perform wonderful acrobatic feats. As in China, the civilization is very ancient, and the people kept foreigners away until modern times. The head of the nation is the Emperor (sometimes called the Mikado), whom the Japanese regard with feelings close to those of worship. There are two assemblies, or legislative bodies, one consisting of



Fig. 530. Bamboo forest, Japan



Fig. 531. Bamboo baskets

the nobility, and the other of representatives chosen by the people. Not all the people, however, are allowed to vote.

The Japanese are intensely patriotic. They are very brave, and very willing to lay down their lives in battle. In the war with Russia, which closed in 1905, they

showed great military skill. They had accurate knowledge of the country, provided ample food and pure water for their soldiers, showed skill in preventing disease and in surgical operations and nursing, and won great victories on sea and land.

535. Industries.—The Japanese have for many hundred years been skillful in many arts. Among these is the weaving of silk and the making of mattings. Their fine porcelain and glass ware are greatly

admired, and are seen in the museums, art stores, and homes of people in Europe and America. The Japanese also excel all others in the art of lacquering. From the sap of a kind of sumac they make the lac, which is a varnish. They inlay woods in beautiful patterns, and then apply the lac, which when dried is given a high polish. As in India and China, many useful objects are made from bamboo (Fig. 531).

The progress of Japan during the past fifty years has been wonderful. The people are

quick to learn, and they readily adopt or imitate the customs and industries of others. They have had a great desire to adopt the inventions and modern ways of Europe and the United States. They send many young men to foreign universities and engineering schools to study modern industries in the western



Fig. 532. Picking tea in Japan

world. When they return they can set up cotton-mill machinery and build ships or railroads as well as any other trained engineers. They also have large and well equipped universities of their own, and only a few of the professors in these schools are men from other nations.

There are more than 8000 miles of railway in Japan, a large mileage in view of the fact that the country is mountainous, and has few places that are as much as seventy-five miles from the sea.

Rice is the main crop and, as in China and India, it is one of the principal foods. Barley and other grains also are raised. Japan produces a very large part of the world's supply of silk. Tea also is grown, as in China, India, and Ceylon. Some cotton is raised, but the main supply for Japan's numerous cotton mills is imported from the United States.

The waters about the islands abound in fish, and the fishing industry is very large, for the population must seek food of all kinds, when the area of tillable land is small.

Iron and coal are among the important minerals of Japan, and this is fortunate for the people, as they are establishing mills, building railroads, constructing ships, and engaging in commerce. The deposits of copper are large, and this metal also is of great value now that electrical power is much used. New manufactures, new openings for trade, new lines of steamships—all these are promoted with tireless energy by the wide-awake Japanese people.



Fig. 533. Street decorated for a festival, Yokohama

536. Cities.—Tokyo, the capital, has over two million people. Yokohama is the port for Tokyo, and although much smaller than the capital city, it is the chief center of foreign trade. The principal Pacific steamships from Canada and the United States call at Yokohama. In September, 1923, these two cities and the surrounding region were greatly damaged by earthquake and fire. Osaka, the second city of Japan in population, has many cotton factories.

537. Chosen.—Chosen, formerly called Korea, occupies a large peninsula of the mainland of Asia across the Japan Sea from the island of Honshu. It was annexed to Japan in 1910, but for several years before that date Japan had exercised large influence in its affairs.

Most of the people of Chosen are engaged in agriculture. The most important crops are rice, wheat, beans, tobacco, and cotton. Live stock is raised chiefly for home use, and some whale fishing is carried on. The mineral wealth of the country includes copper, iron,



Fig. 534. Station at Vladivostok, terminus of the Siberian railroad



Fig. 535. Cotton warehouse, Bokhara

and coal, all of which are found in abundance, and also some graphite and mica. Seoul is the chief city.

Review.—1. What is the range of latitude in the Japanese Empire? 2. Name the more important islands and island groups. 3. Give facts about rainfall and forests. 4. Compare the Japanese with the Chinese people. 5. In what kinds of manufacture are the Japanese skillful? 6. What recent advances have they made? 7. Name the chief cities of Japan. 8. Where is Chosen, and what are its resources?

ASIATIC RUSSIA

538. Russia in Asia.—The former Russian Empire included Siberia, Caucasus, Turkestan, and other provinces, with a total area almost equal to that of South America and a population much smaller. After the World War these provinces declared themselves independent republics, but they soon fell again under Russian influence or control.

539. Siberia.—Siberia was once known as a cold, barren wilderness to which Russian convicts were sent for exile. Thousands of these people had committed no worse crime than to criticize the government, or in some way to seek the reasonable liberty for themselves and their fellow-Russians that the

citizens of all well-governed countries have enjoyed for many years. It gradually came to be known that the Siberian country had good soils, much timber, and many minerals. The Russian government gained control of some of the Pacific coast of Asia, and built the Siberian railroad, which extends from Petrograd to Port Arthur and Vladivostok, a distance of almost 6000 miles (Fig. 534).

After the Siberian railroad was finished, the country through which it passes was settled by more and more people from European Russia. They found it profitable to raise wheat, rye, oats, and other crops, to keep live stock, and to open mines, because the products could now be carried to people who would buy them. Not only the products of Siberia, but tea from China and other goods go overland from eastern Asia to Europe.

Among the chief cities of the interior are Tomsk and Irkutsk, the latter near Lake Baikal, a large, deep body of fresh water.

Along the Siberian railroad in the far east Russian settlers have established the semi-independent Far Eastern Republic. It is for the most part a region of forest-covered mountains. The natives are chiefly nomads; the Russians are engaged in farming and stock raising.

540. Kirghiz, Turkestan, etc.—In Turkestan, Kirghiz, and Bokhara, semi-independent countries east of Caspian Sea, deserts and mountains occupy most of the land, and there are few cities. In this region is Lake Aral, which, like Great Salt Lake and the Dead Sea, is a body of salt water. The Russians have built a railroad southeast into the interior of Asia, with a branch leading westward to the frontier of Persia, and extending to the Caspian Sea. Some grain is raised, and the Russians have also promoted the raising of cotton in this region (Fig. 535), so that they need not import so much from the United States and other countries. The wool of sheep, goats, and other animals is woven by the natives into rugs, many of which are sold in the United States.

541. The Caucasus Republics.—In the region that lies south of European Russia, between the Caspian and Black seas, are a number of republics under Russian control,




Fig. 536. Oil well, Baku, before the flow was brought under control

including Azerbaijan, Georgia, and Armenia (Fig. 501). The Caucasus Mountains run through the region from east to west. South of them the climate is suited to grapes, corn, cotton, and other products of temperate and subtropical latitudes.

A large amount of petroleum is obtained in a small district at Baku on the Caspian Sea (Fig. 536). Much of the oil is transported by rail to Batum on the Black Sea, and thence is taken by ships to many lands. It is also used as a fuel by steamers on the

Caspian Sea and on the Volga River. Tiflis (Fig. 537), the largest city of the Caucasus region, is an ancient center of trade.

Review.—1. For what was Siberia formerly used? 2. What are its chief resources? 3. Give an account of the Siberian railroad. 4. Locate Lake Baikal and name a city near it.

5. Where is Lake Aral? What is its character? 6. Describe the lands near it.

7. In which republic is Tiflis (Fig. 501)? 8. What is the great industry of Baku?



Fig. 537. Tiflis, the capital of Georgia





Fig. 539. Lifting water from the Nile, for irrigation, by means of jars on the vertical wheel at the right

AFRICA

	AREA, SQ. MI.	POPULATION	CAPITAL
Abyssinia	312,000	8,000,000	Adis Abeba
Liberia	36,800	1,500,000	Monrovia
Egypt	400,000	13,387,000	Cairo
British Possessions .	3,848,100	46,042,000	
French Possessions .	4,287,400	40,728,000	
Portuguese Posses. .	801,500	8,150,000	
Italian Possessions .	774,500	1,675,000	
Spanish Possessions .	106,240	1,330,000	
Belgian Congo . . .	947,200	15,400,000	Boma

Map Study.—1. Compare the coast lines of Africa and Europe. 2. How many degrees south of the Tropic of Capricorn is the Cape of Good Hope? 3. How many degrees does Africa extend north of the Tropic of Cancer? 4. From the map, estimate the part of the continent that is in the Torrid Zone.

5. Locate the Atlas Mountains; the Ruwenzori Mountains. 6. Locate the Sahara; the Libyan Desert; the Kalahari Desert.

7. What sea is between Africa and Asia? 8. Locate the Gulf of Aden.

9. Describe the course of the Nile; the Niger; the Congo; the Zambezi. 10. Where is Lake Chad? 11. In what respect is it like the Caspian Sea? 12. Locate Lake Tanganyika; Lake Nyasa; Lake Victoria.

13. What three groups of islands are west of Africa and north of the Equator? (See Fig. 350.) 14. Allowing sixty-nine miles for a de-

gree of latitude, how long is the island of Madagascar?

15. What parts of Africa belong to France? To Great Britain? To Italy? To Belgium? To Portugal? (Fig. 350.) 16. What city is at the head of the Nile delta? At one of the mouths of the Nile? 17. Name three other important cities on the north coast. 18. What city is at the union of the White Nile and the Blue Nile? 19. Where on the east coast is Mombasa? Lourenço Marques? 20. Find the following cities of South Africa: Cape Town; Johannesburg; Kimberley. 21. Find Monrovia and Freetown on the west coast, and Leopoldville on the Congo. 22. Locate Walfisch Bay and name the European nation that controls it.

PHYSICAL GEOGRAPHY

542. Coast Line and Surface.—Africa is three times as large as Europe, and yet it has a shorter coast line. The outline is very regular, and there is not a single deep indentation like the Adriatic Sea or the Baltic Sea. Around almost the whole continent there is a narrow lowland, which in many parts is so hot and unhealthful that white men cannot live upon it. Back of this low coast strip the surface rises, and becomes a




Fig. 541. A snow-covered peak of the Ruwenzori Mountains, near the Equator in Africa

plateau over most of the continent. Much of the interior plateau is from 2000 to 4000 feet in altitude, and all the great rivers descend from the upland to the coastal lowland by a series of rapids or falls. Above these falls the larger rivers are navigable for hundreds of miles into the interior of the continent.

Africa has fewer high mountains than any other continent except Australia. The range known as the Atlas Mountains extends through northern Africa about 1400 miles, from the Atlantic Ocean to the eastern part of Tunis. The highest point in these mountains has an altitude of nearly 15,000 feet. The Ruwenzori Mountains are a short, high range in central Africa, whose tops are covered with snow and glaciers, the highest peak rising to 16,600 feet (Fig. 541). Eastern Africa has a highland that extends from the Zambezi River to the Red Sea. Upon it, near Lake Victoria, is the volcanic peak Kilimanjaro, rising to 19,720 feet. Abyssinia occupies a lofty plateau, above which volcanic peaks reach to a height of about 15,000 feet above sea level. But Africa has no mountain range equal in size to the Himalayas, the Andes, or the mountains of western North America.

543. Rivers and Lakes.—Africa has four great rivers. The longest of these is the Nile,

which rises in the region of the great lakes of east-central Africa, and flows northward to the Mediterranean. On the way, it receives the Blue Nile, which descends from the Plateau of Abyssinia on the east. The Nile is 3700 miles long. Its headwaters are in the region of large rainfall along the Equator and in Abyssinia, and the supply of water is so great that it flows for hundreds of miles through a desert and enters the sea as a large stream.

The Congo River is somewhat shorter, but has a still larger volume of water. Some of its headwaters are near the sources of the Nile, but it flows westward, and hence, all the way to the sea, is in a region of plentiful rain, and receives large tributaries. Its falls are below Leopoldville. Above that place it is navigable for 1000 miles, and steamboats traverse also many of its larger tributaries. From the lower part of the river, which is navigable, a railroad has been built around the falls to Leopoldville. From the mouth of the Congo, therefore, freight may be carried, first by boat, then by rail, and again by boat, to the interior of the continent.

The Niger is the great river of that part of western Africa north of the Equator. It flows northeast for a long distance, and then turns to the southeast and finally enters

The greater part of northern Africa is always in the course of the northeast trade winds, and hence is a desert (Fig. 367). This is true of the Sahara, of the Libyan Desert, and of Egypt except where it is irrigated. The Sahara extends westward to the shores of the Atlantic, because the winds come from the land and not from the water. Morocco, Algeria, and Tunis have more rain than the regions to the southward, especially in the winter, for at that time of the year these countries are in the belt of the westerly winds.

Southern Africa is across the track of the southeast trade winds. Hence the east coast is well watered, but the interior and the west coast are for the greater part dry. The Kalahari Desert is in this part of the continent.

As a whole, Africa is more in the tropics and has higher temperatures than even South America. It is drier also, because it is mostly a plateau and has no great mountain ranges, like the Andes, to condense the moisture brought by the winds.

545. Forests and Animal Life.—As the climate of most of Africa is either hot or subtropical, the vegetation is mostly such as is found in warm countries. The largest trees and heaviest forests are in the hot, rainy region near the Equator, especially in the basin of the Congo River. These forests, like those of the Amazon, are tangled and dense, with trees, shrubs, and vines,

which shield most of the ground so completely that the sun's rays do not reach it.

North and south of this forest belt are *savannas*, or grasslands, with trees in the river valleys and reeds in the marshes. Trees do not flourish in the savannas, because rain

falls only part of the year, by reason of the northward and southward movement of the equatorial calm belt. They are like the llanos of Venezuela and the campos of Brazil (Sec. 314). In the deserts of the trade wind belts are many oases with groves of date palms, which supply an important article of food. In the Mediterranean belt, which is more temperate, the vegetation is much like that of southern Europe, including palms, oaks, the olive, and the vine.

Many large wild animals are found in



Fig. 544. Lion



Fig. 545. Hippopotamuses, mother and young

Africa, such as the elephant, rhinoceros, giraffe, leopard, lion (Fig. 544), and hippopotamus (Fig. 545). Camels are much used as beasts of burden in the deserts of northern Africa. The quagga and zebra, animals of the horse family, are numerous in the grasslands. Among other African animals are apes, chimpanzees, gorillas, baboons, and monkeys. In the tropical forests, as in those of other continents, there are many venomous reptiles, and many birds with brilliant plumage. The ostrich of southern Africa is raised for its feathers. Ants are numerous and build mounds ten or fifteen feet high. The white ants destroy almost anything made of wood.



© Valentine & Sons

Fig. 546. Zulu warriors, negroes of southern Africa

Review.—1. What is peculiar about the great rivers of Africa? 2. Where are the sources of the Nile? The Congo?

3. Why does the Sudan have a wet and a dry season each year? 4. Where are the trade wind deserts of Africa? 5. Why is one so much larger than the other? 6. What is the vegetation of the African savannas? 7. Why do they have few forests? 8. What are the principal wild animals of the continent?

PEOPLE AND HISTORY


546. The People.—The countries along the Mediterranean are occupied almost entirely by people of the white race. Some of them are called Berbers. They have lived in North Africa since ancient times. They are a wandering or nomadic people, and inhabit the mountain districts. Others are Arabs, or Moors, descendants of the men who, 1200 years ago, overran north Africa and conquered it for the Mohammedan faith. It was then and in the period following that the Moors crossed the Strait of Gibraltar, and ruled much of Spain (Sec. 458). The Mohammedans have planted their faith even south of the Sahara, and about a third of the people of Africa are believers in their prophet. There are some Jews also in the Mediterranean parts of Africa, and some who hold to ancient forms of Christianity. There are a few Italians, Frenchmen, and other Europeans, especially in the cities along the coast.

Central and southern Africa have always been the home of the black, or negro, race (Fig. 546). There are innumerable tribes of them, and the white man found most of them living in dense ignorance and darkest savagery. For several hundred years the white foreigner only made these conditions worse, for he came to Africa for little else than to hunt down the negroes in the forest, lead them in gangs to the seacoast, shut them up in terrible confinement in slave ships, and sell them into bondage in America and other lands. If he found them making slaves of one another, offering human sacrifices, killing a chief's wives after his death, or shooting their enemies with poisoned arrows, he had no excuse for finding fault with them, for he treated them worse than they treated one another.

Great changes have been made within the last fifty years, for civilized nations no longer sanction the slave trade. The natives are being kept in order by foreign powers, and many of them are learning how to labor. Missions and mission schools are teaching them the lessons of civilized life. It is not easy for some of the natives to learn to work, for they live in a warm region where they can get along with little clothing and shelter, and where the forest provides food.



Fig. 547. Kraal, or village, of negroes in southern Africa



For more than 3000 years northern Africa has been known to history, but central and southern Africa have been largely unknown until within sixty years. Hence Africa has been called the "dark continent." There are several reasons why it has been backward. The coast is regular, and has few good harbors. The coast lands are low, hot, and so unhealthful that the region is called the "white man's grave." The rivers are interrupted by falls, so that boats cannot go from the sea to the interior. Unlike America, with its small original population, Africa had many millions of savages, ready to attack foreigners who ventured into her wild forests or over her savannas and deserts. Until recent years the white man went to Africa for slaves, and for ivory supplied by the tusks of elephants, and for little else.

547. Exploration.—The entire Mediterranean and Red Sea coasts were known by the people of Asia and Europe long before the time of Christ. The early narratives of the Bible have much to say about Egypt. The Phœnicians and the Greeks had colonies on

the southern shore of the Mediterranean from Egypt to Gibraltar. They had some commerce in ivory and ostrich feathers, which must have come from the interior. But Africa beyond the Sahara was little known to the ancients, who called it Ethiopia. It is believed by some that one of the ancient navigators sailed around Africa. If this is true, the people had lost the knowledge of it, for when Vasco da Gama, a Portuguese navigator, in 1497 sailed around the Cape of Good Hope, he was regarded as having made a great discovery. He went to India and returned safely to Lisbon in 1499.

In the last century two British explorers more than any others made the "dark continent" known to the world. The first was David Livingstone, a Scotchman, who went to southern Africa as a medical missionary in 1840, and worked as a missionary and explorer until his death in 1873. He learned much about the Zambezi and the region of the great lakes at the sources of the Nile and Congo. The other was Henry M. Stanley, who was sent by a New York newspaper in 1869 to find Dr. Livingstone. He made great discoveries in central Africa, especially in the Congo basin.

548. The Cape-to-Cairo Railroad.—All the European countries that own parts of Africa are active in building railroads. One great plan will be described here and reference made to others in our study of African countries. The British control the greater part of the basin of the Nile. They have already built a railroad from Alexandria and Cairo to Khartum and beyond. They also control much of eastern and southern Africa. They have built a railroad from Cape Town 2000 miles northward, far across the Zambezi River. They expect to join these two lines and make the "Cape-to-Cairo" railroad, nearly 7000 miles long. New lines are under construction by the British and others, to connect this road with the shores of the Indian and Atlantic oceans.

549. Partition of Africa.—Europe is made up of large and small countries, most of which are independent. In Asia large sections are controlled by European nations, but there are also important countries, as Japan and China, that are self-governing. With but few exceptions, the countries of the Western Hemisphere are republics. Canada is a part of the British Empire, but its people are as free as those of any republic. Africa differs from the other continents by reason of the fact that nearly all of its territory has been divided among European powers. Liberia, Abyssinia, and Egypt are the only countries that are independent.

The countries that control most of Africa are Great Britain, France, Belgium, Italy, and Portugal. All these are small countries with a dense population. Portugal has had her African colonies since the days of early discovery, but the others have taken possession of parts of Africa within recent times. One reason for this "partition," or dividing, of Africa is that the European powers want land where some of their people can find new homes.

Another reason is that they want more raw materials for the factories at home. They hope to raise much cotton, for example, and not to be compelled to buy so much cotton from the planters of our southern states. They desire to find precious metals, as the British have found gold and diamonds in South Africa. They seek the forest wealth, just as Belgium makes much money from the rubber of Congo forests.

They also desire new markets for the steel, textiles, and other things which are made in European factories. If they can train the African negro to work, and produce things needed in Europe, and

at the same time to desire things made in Europe, then commerce will be established and both the Europeans and the Africans will be benefited. It is, therefore, the growth of European nations and the desire for expansion of territory and trade that have led to the partition of Africa.

The interest of European nations in owning land in Africa became so strong that in 1885 a conference was held in Berlin, and many questions were settled, which helped to a peaceful division of the continent, by treaties. Germany soon gained nearly one tenth of Africa; but in the World War she lost most of Cameroon and Togo to the French, a small part of East Africa to the Belgians, and the rest of her African colonies to the British.

France and Great Britain together hold three fourths of all African territory. On the whole the British possessions are of the greater importance because of good soils and favorable climate. Among the regions in the British Empire are South Africa, Rhodesia, East Africa, and much of eastern Sudan. In western Africa, Nigeria on the lower Niger, Gold Coast, and Sierra Leone are under British control (Fig. 350).

France has Algeria and Tunis, on the Mediterranean, most of Morocco, most of the Sahara, French West Africa, Dahomey, French Equatorial Africa, and the island of Madagascar. Italy holds Eritrea on the Red Sea, Italian Somaliland, and Tripoli or Libia on the Mediterranean. Portugal retains from



Fig. 549. Algiers, the chief city of French Africa

its provinces held by right of discovery, Mozambique, Angola, and Portuguese Guinea. Spain holds two small territories on the west coast, and controls part of Morocco. Belgium holds most of the Congo basin.

Review.—1. What races of people are found in northern Africa? 2. Give an account of the slave trade. 3. What improvements are taking place in the life of the negro tribes? 4. Why has Africa been a backward continent?

5. What nations explored the coasts of Africa in ancient times? 6. Give the name of the first modern sailor who went around the Cape of Good Hope to India, and the date. 7. Give an account of David Livingstone; of Henry M. Stanley.

8. Describe the Cape-to-Cairo railroad.

9. What is meant by the partition of Africa? 10. What are the principal parts of Africa belonging to Great Britain? To France? To Portugal? To Belgium? 11. For what reasons have European nations been eager to possess African territory?



Fig. 550. Pyramids in Egypt

COUNTRIES OF AFRICA

550. Egypt.—Civilized people lived in Egypt and maintained a strong kingdom for thousands of years before the time of Christ. Much of their ancient history has been learned in recent years by scholars who have translated the inscriptions and other writings that have been discovered. These have been preserved in Egypt, an arid country, while they would have been destroyed in a land with a moist climate and severe changes of temperature. The Egyptians took great care in embalming and wrapping the bodies of the



Fig. 551. Columns in the temple at Karnak, Egypt

dead, which are known as mummies. The mummies of some of the ancient kings have been discovered and identified.

The pyramids of Egypt, built of blocks of stone, were erected as burial places for kings (Fig. 550). The building of such pyramids required the work of thousands of men for many years. The largest of them are about 450 feet high. Temples with huge columns were made in the same way (Fig. 551). Single blocks of stone of great size were quarried, carved with inscriptions, and set up as monuments. These are known as obelisks, and some have been removed and set up in foreign cities, as in Rome, in London, and in Central Park, New York. The Sphinx is a giant statue carved out of rock.

Egypt was badly governed for a long time as a part of the Turkish Empire. Later it became a nearly independent monarchy, and was for many years under British control. The people prospered under British rule, because



Fig. 552. Part of the Assuan dam

they were justly taxed and were taught to cultivate their fields by good methods. In 1922 the British protectorate was ended and Egypt became a sovereign state under its own king.

Egypt is several times as large as the British Isles, but most of it is a desert like the Sahara. The Nile flows through it from south to north, and for thousands of years the people have lifted or pumped the water out over the flood plain and the great delta at its northern end (Fig. 539). About 12,000 square miles are thus cultivated, and this area is the real Egypt. When the rains come along the upper Nile, and particularly in the Plateau of Abyssinia, the river rises many feet and floods the lowlands, giving them water and leaving a cover of fine, rich soil. Under British direction a dam about 6400 feet long was built at Assuan (Fig. 552), setting back the water and forming a lake or reservoir 200 miles long. This water is distributed over the fields, and increases the amount of land that can be cultivated.

Two or three crops are raised each year, and Egyptian agriculture is now very prosperous. Many crops of both temperate and hot climates are raised, including a large amount of wheat and other grains. The Egypt-

tian cotton is of excellent quality, and the country stands next to the United States and India in the export of this fiber. Some Egyptian cotton is used in American mills for making special kinds of goods, but most of it goes to England.

There are more than 13,000,000 people in Egypt, and more than nine tenths of them are of the Mohammedan faith. Cairo (Fig. 553), at the head of the Nile delta, is the capital, and is the largest city in Africa, with a population of more than 750,000. In its museum is a remarkable collection of Egyptian antiquities. Its streets are full of quaint Oriental people of many kinds. Its dry and healthful air and its historical interest attract people of many lands, who make it a resort for the winter months. Alexandria still remains the chief seaport of Egypt, as it was in ancient times.

The Suez Canal extends from Port Said, on the Mediterranean, 103 miles to Suez at the head of the Red Sea. Of this distance true canals cover 76 miles, and lakes 27 miles. The canal was completed in 1869 after ten years of work. It is 35 feet deep, and accommodates all but very large ocean vessels. Before it was dug, Mediterranean commerce was much less important than now, for all European ships bound for the

East were compelled to go around the Cape of Good Hope. Now they may go direct from London and other European ports by the Suez route to Bombay, Calcutta, Singapore, Hongkong, and the ports of Australia and New Zealand. In normal times about 5000 ships pass through the canal each year, with a tonnage of 20,000,000. The majority of the ships are British, but there are many under the French, Dutch, Japanese, Italian, and other flags.



Fig. 553. A street in Cairo



Fig. 554. Camel ready for a caravan journey

551. Tripoli, or Libia.—Tripoli was formerly part of the Turkish Empire, but is now controlled by the Italians, who have renamed it Libia. The country has a long shore line on the Mediterranean, but is mainly a desert with a scattering population of Berbers, Arabs, Jews, and desert tribes. The chief city is Tripoli. The harbor is poor and the approach difficult. The sands and shoals of this part of the Mediterranean were dreaded by ancient seamen, and navigation is still dangerous. Along this shore the Greek sponge divers come with ships to gather sponges from the sea bottom.

In the deserts of Libia and in other parts of northern Africa a plant known as esparto grass is found. It has strong fibers. The stems are gathered, bound into huge bundles, and carried by camels to the sea, where they are put on ships and sent to England for making paper.

Tripoli has always been a center for the caravan trade. The trails reach across the Sahara to Timbuktu, Lake Chad, and all parts of the Sudan country. Some caravans are small, and some have thousands of camels with their drivers and guards, and carry goods

having a value of hundreds of thousands of dollars. A caravan journey across the Sahara takes several months, and is full of danger, for bands of robbers are common in the desert. They know where all the wells and springs are, and often exact tribute from passing caravans even when they do not plunder them. Camels (Fig. 554) are the only animals that can carry burdens across the desert, because they can go five days or more, if necessary, without drinking. Each animal carries a load of about 300 pounds, and a day's march lasts sixteen hours.

The caravans bring from central Africa or the Sudan region, ivory, ostrich feathers, and skins, and carry back to the natives various products of Europe, such as cloths of cotton and wool, beads, paper, drugs, and sugar. The largest item is cotton goods from Great Britain. The caravan trade is not so large as it was, for railroads are being built in the countries south of the Sahara.



Fig. 555. Date palms, Algeria

552. Tunis and Algeria.—

Tunis and Algeria are under the control of France. They are more progressive countries than Tripoli. There are more railroads in these countries than in most parts of Africa, and there are thousands of miles of telegraph and telephone lines. Tunis and Algiers are the two capitals. They are well-governed cities, and are visited every winter by many Americans and other tourists. Much wheat is raised in Algeria and sent to France. Barley, oats, and corn also are large crops. Grapes and many tropical fruits, such as oranges, bananas, figs, olives, and dates (Fig. 555), are raised. Much wine is made and exported. Cork oaks yield an important export of cork bark. Esparto grass is gathered and exported, as in Tripoli. Sheep and other live stock are kept.



Fig. 556. Nile steamboat landing, at Khartum

553. Morocco.—Morocco has been until recently an entirely independent country, ruled by an absolute monarch called the Sultan. Its resources are like those of other north African countries, but most of its people live in ignorance and barbarism, and it is not yet an orderly or safe country. France has recently gained some control over most of the country, and may in time give Morocco as good government as Algiers and Tunis now have. Spain controls a small part of Morocco. Tangier, in an “international zone,” is the principal city and seaport.

554. Sudan Countries and Abyssinia.—The Sudan is the region extending across Africa, south of the Sahara, from the Atlantic Ocean to Abyssinia and the Red Sea. On the south are the Gulf of Guinea and the watersheds between Lake Chad and the Congo River system. As we have learned (Sec. 544), it is intermediate in heat and rainfall between the tropical forests and the Sahara. Many of the negroes of the Sudan, west of Lake Chad, belong to the Hausa tribes, which are among the best and most prosperous people of the African black race.

France governs the central and much of the western part of the Sudan. In the west the chief center for trade between the Sudan and the Sahara is the ancient city of Timbuktu on the northern bend of the Niger. It is the center of many caravan trails, and the French plan to connect it by a railroad with their

possessions in northern Africa. On the Gulf of Guinea are Nigeria and the Gold Coast, under British rule, and Dahomey and the Ivory Coast, under French rule. These are tropical countries with a hot climate, unhealthful near the coast, but with large resources of mine, forest, and field. The Gold Coast produces more cacao than any other country in the world.

In the western part of the Sudan are the small republic of Liberia and the British colony and protectorate of Sierra Leone. Liberia was founded as a home for freed American slaves. All industries are in a backward state. Monrovia is the chief city. Sierra Leone exports palm oil and kola nuts. Freetown is the greatest seaport in west Africa.

East of French Sudan is Anglo-Egyptian Sudan, which nominally belongs to Egypt and Great Britain, and is being developed under British control. The capital is Khartum, on the Nile (Fig. 556). The fierce natives were subdued by a British-Egyptian army in 1898, and order was established, opening the way for agriculture and civilized life. The Cape-to-Cairo Railroad (Sec. 548) has been finished to a point some distance south of Khartum, and a branch line extends to the Red Sea.

To the east is Abyssinia, a region of plateaus and mountains, which still remains under a native ruler. Most of the inhabitants accept an ancient form of Christianity. The country has many mineral and other resources, but it has made little progress in modern methods of industry.

555. Countries along the Equator.—Among the countries crossed by the Equator are French Equatorial Africa, Belgian Congo, Uganda, and Kenya, the two last named being British possessions.

Following the journeys of Livingstone and Stanley, there was new interest in the Congo region, and the Berlin Conference in 1885 agreed that the Congo Free State should be

formed, and placed under the care of the King of Belgium. In 1908 it was formally annexed to the kingdom of Belgium and is now known as the Belgian Congo. Railroads and steamboats, traders and missionaries, have done much to open this tropical forest, and to improve the condition of its native negro tribes. A railroad runs around the falls of the lower Congo, and, above these, boats can go hundreds of miles on the great river and its tributaries (Fig. 557). The greatest native product is rubber. Much ivory (Fig. 558) has been obtained here and carried out to all parts of the world, both by the river and by caravan across the Sahara, but the supply is giving out. Other products are palm nuts, palm oil, white copal, cacao, and gold. The largest import is cotton goods, showing that the native negroes, of whom there are many millions, are learning to wear clothes.

French Equatorial Africa and the former German protectorate of Cameroon are northwest of the Belgian Congo, and have similar resources.

British colonies in eastern Africa extend



Fig. 557. Steamboat on the Congo River at Leopoldville

from the Belgian Congo eastward to the Indian Ocean. In the northern parts are some of the sources of the Nile. The region includes Uganda and the colony of Kenya, with Mombasa the chief seaport. A railroad has been built from this city to the shores of Lake Victoria.

South of the region just described is Tanganyika Territory, the part of German East Africa taken by Great Britain in the World War. It has millions of native people, a great variety of tropical products, a railroad from lake to ocean, and is being developed by European money and skill. Off the coast are the island and city of Zanzibar, which have long been under British control.

556. Countries of Southern Africa.—Portugal has colonies both on the west and on the east coast of southern Africa. In the eastern colony there is valuable territory along the Zambezi River, and there are two important ports, Beira and Lourenço Marques.

Most of the richer parts of southern Africa are under the British flag. The oldest towns are in the province of Cape of Good Hope, which was first settled by the Dutch and afterward occupied by the English. Then many of the Dutch, or *Boer* farmers, as they were called, "trekked," that is, they moved on to the north, or into the interior. They founded the Orange Free State and the Transvaal Republic. But when much gold was discovered in the Transvaal, many British and



Fig. 558. Arab trader buying ivory in central Africa



Fig. 559. Cape Town, South Africa

© Valentine & Sons

other gold seekers went in and there were disputes that finally led to the Boer War and the conquest of both republics by Great Britain. They are now provinces in the Union of South Africa, which has a government somewhat like that of Canada. The other two provinces of the Union are Natal and Cape of Good Hope. Natal is a province on the east coast with Durban as its seaport. The principal city and seaport of Cape of Good Hope is Cape Town (Fig. 559).

To the north, Rhodesia, named for Cecil Rhodes, who did much to develop South

Africa, stretches northward to Belgian Congo and East Africa.

Southwest Africa, a former German colony, has been placed under the control of the Union of South Africa. It is largely a desert region, with a small population.

South Africa produces grain, and supports many sheep and cattle. A large amount of wool is exported, and there are many ostrich farms (Fig. 560). Gold is mined near Johannesburg (Fig. 561) in the Transvaal, and this locality is by far the greatest gold producer of the world.



© Valentine & Sons

Fig. 560. Ostriches, mother and young



© Valentine & Sons

Fig. 561. A gold mine at Johannesburg, South Africa



Fig. 562. Bottom of a diamond mine, Kimberley

At Kimberley in Cape of Good Hope are the largest diamond mines in the world. The gems are dug in a rough state out of masses of partly decayed volcanic rock (Fig. 562). The native laborers are watched and searched to see that they do not steal these precious stones. When sold, most of the diamonds go to Antwerp or Amsterdam to be cut and polished, after which they find their largest market in the United States.

557. African Islands.—The Madeira (Fig. 563) and Cape Verde Islands (Fig. 350) belong to Portugal, as do also the Azores, but the last are too far away to be called African islands. St. Helena is a small island off the southwest coast, chiefly known as the place to which Great Britain exiled Napoleon Bonaparte several years before his death. The Canary Islands belong to Spain.

The largest of African islands is Madagascar. It is larger than France or Germany, and is under French rule. It has a population of about 3,000,000, mostly natives descended from the Negro and Mongolian

races (Fig. 564). Agriculture and cattle raising are the main industries, but the island has graphite and other minerals.

The islands of Reunion and Mauritius, in the Indian Ocean, are ruled by France and Great Britain respectively.

Review.—1. What are some of the great architectural works of the ancient Egyptians? 2. How is Egypt now governed? 3. How has the agricultural capacity of the country been increased? 4. Give an account of the Suez Canal.

5. Describe the caravan trade. 6. Name the countries of northern Africa.

7. What countries belong to the Sudan region? 8. How far south from Cairo has the Cape-to-Cairo Railroad been built?

9. What facilities for transportation are found in the Belgian Congo? 10. What bodies of water are joined by the chief railroad of British East Africa (Fig. 538)?

11. Give the history of German occupation in Africa; of Dutch occupation in southern Africa. 12. Name the chief seaport of Cape of Good Hope. 13. Where are the chief gold and diamond deposits of South Africa? 14. What are the other important products of South Africa?



Fig. 563. Funchal, the seaport of the Madeira Islands



Fig. 564. Water carriers, Madagascar

AUSTRALIA AND PACIFIC ISLANDS

	AREA, SQ. MI.	POPULATION	CAPITAL
Australia	2,972,866	5,437,000	Melbourne
New Zealand	104,663	1,221,000	Wellington
New Guinea group . .	311,000	1,000,000	
Other Pacific islands	68,850	1,100,000	

Map Study.—1. Give the latitudes of Melbourne and Cape York. 2. How many degrees of longitude are covered by Australia? 3. What large island is north of it? 4. What is the location of Tasmania? 5. Using the scale of miles, determine the distance from Sydney to Perth; from Sydney to Wellington in New Zealand.

6. Name and bound the five states and one territory of the Australian continent. 7. Name and locate the capital of each state. 8. Describe the courses of the Murray and Darling rivers. 9. Give the name of the chief mountain range of Australia and describe its position (Fig. 566).

10. From the map estimate what share of the surface of Australia lies in the Torrid Zone. 11. Compare the latitude of Auckland, in New Zealand, with that of Buenos Aires. 12. Compare the latitude and longitude of Auckland with those of London.

13. What group of islands in the Pacific Ocean is in longitude 180°? 14. Locate the Samoa group of islands; the New Hebrides; New Caledonia; the Solomon Islands.

558. Physical Geography of Australia.—Australia has sometimes been called an island, but it is so large and so far from other large lands that it may properly be called a continent. It is more than 2000 miles across from east to west, and it averages more than 1000 miles in width from north to south. The area is nearly 3,000,000 square miles, making it three fourths as large as Europe.

Every other inhabited continent is crossed either by the Arctic Circle or by the Equator, but Australia is between 10° and 40° south latitude. It is 4500 miles from Africa, and 7500

miles from South America. It is about 2000 miles by sea from Australia to Asia, though the journey lies among the East Indies. Even New Zealand, which we often name with Australia as being in the same part of the world, is 1000 miles away.

The coast line of Australia is somewhat like that of Africa, for it is but little broken by bays, and hence has but few natural harbors. Much of the interior is so dry that there are few rivers. Along some parts of the shore one might travel for hundreds of miles without crossing a river. Thirty miles or more off the northeast coast, the Great Barrier Reef, a coral formation, extends for about 1000 miles.

In surface, Australia consists of a central plain, bordered by mountains on all sides except on the south. There are, however, no very high mountains on the continent. The largest and highest mountains make up the Great Dividing Range, which follows the east coast, and is not very far from it. The highest parts are toward the south, where the range is sometimes called the Australian Alps, and has peaks more than 7000 feet in altitude. The mountains of the northern and western borders are lower.

The interior plain has many hills or low mountains. Most of the streams dry away or enter lakes which on account of the dry climate have no outlets. The largest rivers, however, the Murray and its tributary the Darling, flow westward from the Great Divide and carry their waters to the sea on the south. On the east, north, and west borders, short rivers flow from the mountains to the ocean.

The southeast trade winds bring ample moisture to the eastern parts of Australia, where they rise in crossing the slopes of the Dividing Range and are chilled as a result of



the greater elevation. It is in these mountains that the Murray and Darling rivers have their origin. The conditions are the same as in eastern Brazil and southeastern Africa. In the Australian summer, which occurs during our winter, the belt of equatorial calms and heat moves

southward over northern Australia, and gives ample rain. In the Australian winter, occurring at the time of our summer, when the equatorial heat belt and the wind belts move northward, southwestern Australia gets some moisture from the prevailing westerlies of the Southern Hemisphere. In the summer, the westerly winds are too far south to touch Australia.

The interior and the south-central coast of the continent are dry, and much of the land is a desert (Fig. 367). The climate is continental, hot in summer and cold in winter. Much of the interior has as little as five inches of rainfall a year. Parts of the east and north coasts have more than fifty inches.

The animals and plants of Australia are very different from those of other continents. The kangaroo (Fig. 567) is one of the peculiar native animals. Like many of the other Australian animals, it carries its young in a fold of its skin. Its front legs are short, but the hind legs and tail are long and strong. In leaping over the ground the animal stands nearly upright and uses its hind legs and tail. The common domestic animals have been introduced from other countries.

559. People of Australia.—The natives of the continent (Fig. 568) are a very dark-skinned people, who in many ways, however, are unlike the negro. They are thin and



Fig. 567. Kangaroo



Fig. 568. Australian natives, with spears and boomerangs

muscular, with heavy beards and straight or wavy hair. When the white man first came to Australia, these natives, or aborigines, were rude savages. Some of them are still wild men, but there are not nearly so many as when they had the land to themselves.

Soon after the time of the American Revolution, Great Britain began to settle Australia. Many of the first white inhabitants were convicts, sent out to Australia instead of being shut up in British prisons. Then a better class of people began to go in search of homes and of new chances to make a living. Thus Australia was occupied by several British colonies, including New South Wales, Victoria, Queensland, and others. In 1901 all these colonies, now called states, together with Tasmania, the large island south of the continent, were united to form the Commonwealth of Australia. Like Canada, this part of the British Empire is self-governing, but works in harmony with Great Britain in foreign affairs. Melbourne is the temporary capital, but the site for a permanent capital has been laid out at Canberra. Australia has made many laws in favor of laborers. The people believe in a "white Australia," and prevent the immigration of the black or yellow races.

The population is less than that of London. About two thirds of the people are in the states



Fig. 569. Sheep at a watering place, New South Wales, Australia

of New South Wales and Victoria, leaving only a sparse population in the remainder of the continent.

560. Products and Industries of Australia.

—Agriculture and grazing are the main occupations in Australia. The same is true of Canada, Argentina, Siberia, and the newer parts of the United States. This is the rule in large countries that are young in development, and have broad plains suited for fields and pastures. The principal grain of Australia is wheat, and some wheat is sent abroad, particularly to Liverpool. Much fruit is raised, especially grapes, and much wine is made. In Queensland, where the climate is moist and hot, sugar cane is the leading product, and tropical fruits flourish.

Australia has about 85,000,000 sheep, and sends to the world's markets more wool than any other country. As merino sheep were taken from Spain to America, so they were carried to South Africa and Australia. The climate, and the grasses and other wild plants of the region, aid in producing wool of excellent quality, and

there is room on the ranches for large flocks (Fig. 569). The event of the year is sheep shearing. The wool goes to one of the seaports and is transported to the mills of England and other countries.

Cattle also are raised, and hides, tallow, butter, and frozen beef, as well as frozen mutton, are shipped to Great Britain. Dairy supplies

produced during the southern summer may in a few weeks reach England in the northern winter, when the cattle of Europe are living under cover on dry food.

Gold to the value of many hundred million dollars has been taken from Australian mines, and the country still ranks next after South Africa and the United States among the gold producers of the world. Silver, lead, copper, tin, and coal are found.

The Australians have most of the raw materials to make a rich and populous country, although manufacturing has not yet been extensively developed.

561. Cities and Routes of Australia.—

There are two great cities in the Commonwealth, each with more than 700,000 people.



Fig. 570. Melbourne, Victoria



Fig. 571. Harbor at Sydney, New South Wales

One is Melbourne, the capital of the state of Victoria (Fig. 570). The other is Sydney, the capital of New South Wales (Fig. 571). Adelaide is the capital of South Australia (Fig. 572). Other important cities are Brisbane, the capital of Queensland (Fig. 573), Perth, the capital of Western Australia, and Hobart, the capital of Tasmania. Ballarat and Bendigo are mining towns in Victoria. As the interior is so dry, all the large cities are on the seacoast.

Most of the railroads are in New South Wales, Victoria, and Queensland. A railroad has been built near the south coast, across Australia from east to west, and another has been proposed which will run through the center of the country across the great desert, from the southern seaports to the northern shore.

A great sea route to Australia

from Europe is by way of the Suez Canal and Aden to Adelaide and Melbourne. Another route runs from Colombo in Ceylon to Singapore and Sydney. To Sydney, steamships make regular trips from Vancouver and San Francisco. The route from London to Sydney by way of the Panama Canal is shorter than by way of the Suez Canal. Other sea routes pass around the Cape of Good Hope and Cape Horn, and many steamships ply between Australia and New Zealand. There is cable communication with southern Asia and with Vancouver. Many ships going between Australia, or New Zealand, and the western coast of North America, call at Honolulu in the Hawaiian Islands.



Fig. 572. Street in Adelaide

562. New Zealand.—The Dominion of New Zealand is part of the British Empire. There are two principal islands, separated by Cook Strait, and many small islands. The group is 1000 miles long, and contains a little more than 100,000 square miles. It is thus about as large as the state of Colorado. The population is somewhat over 1,000,000, including about 50,000 Maoris. These are the native people of the islands. They are a strong race, and many are now civilized and intelligent citizens of the British Empire.



Fig. 573. Brisbane, Queensland



Fig. 574. Lake and mountains in southern New Zealand

Much of the surface is mountainous, and has magnificent scenery (Fig. 574). Deep bays penetrate the shores among lofty peaks. Mountain ranges form the backbone of both the large islands, and there are regions of glaciers and perpetual snow, as well as active volcanoes, geysers, and other hot springs. There are many rivers, but most of them are short mountain torrents. There are also fertile plains. The industries are much like

those of Australia. Except in the high mountains, the climate is mild. The rainfall is greatest on the west side, because the islands are in the course of the westerly winds. Wheat and oats are the leading field crops, and wool, frozen meat, butter, and hides and skins are the leading exports. Most of these go to Great Britain. Auckland and Wellington (Fig. 575) are the principal cities.

563. Islands of the Pacific Ocean.—

Thousands of islands are scattered over the Pacific, but only a few of the larger groups are important. Most of the East Indies are considered as belonging with Asia (Sec. 523). New Guinea, however, is near Australia and is somewhat like it as to its animals and plants. It is a vast island, with an area of more than 300,000 square miles. It has mountains which rise more than 15,000 feet above the sea. Australia and the Netherlands each control parts of the island. Near New Guinea, on the east, are the Bismarck Archipelago and the Solomon Islands.



Fig. 575. Wharves at Wellington, New Zealand

The New Hebrides, New Caledonia, the Fiji, the Tonga (Fig. 576), and the Samoa islands (Fig. 577), are south of the Equator. New Caledonia is governed by France, and the New Hebrides jointly by France and Great Britain. There are 200 islands of the Fiji group alone, all belonging to Great Britain. The Samoa Islands are divided between the United States and New Zealand.

Some of the Pacific Islands are of volcanic origin, consisting of mountains and hills, and in some, as in Hawaii, active volcanoes are still found. These volcanic islands are sometimes referred to as the "high islands." In contrast are many "low," or flat islands due to coral growth (Fig. 578). The hard or stony parts of the corals are broken and worn by the waves into small bits. These accumulate and the waves push them above the surface of the ocean, forming islands.

The natives of most of the islands were originally savages, often cruel and degraded. By the heroic work of missionaries, and by the aid of foreign governments, most of the people have now come to an orderly and more or less civilized mode of life.

The principal value of the smaller islands to the United States, and to the nations of Europe, is as coaling stations, and as harbors for warships and the ships of commerce.

Review.—1. Describe the surface of Australia. 2. Explain the rainfall of the



Fig. 576. Native children, Tonga Islands



Fig. 577. Native hut, Samoa

several parts of Australia. 3. Describe one of the native animals.

4. Describe the native people of Australia. 5. How did the British people first make use of the country? 6. What is meant by a "white Australia"? 7. When was the Commonwealth of Australia formed?

8. What are the chief agricultural products? 9. Give an account of sheep raising.

10. What are the principal seaports? 11. Name the two leading cities of Australia. 12. What railroad is planned? 13. Name the chief sea routes to other countries.

14. How far is New Zealand from Australia? 15. What is the length of the New Zealand group?

The area? 16. Name some of the principal physical features. 17. What products are common to New Zealand and Australia?

18. Give an account of New Guinea. 19. What nation controls New Caledonia? The Fiji Islands? 20. Name two classes of islands, according to their surface. 21. What is the main value of the smaller islands to the nations that control them?



Fig. 578. Coral growing on a reef along the coast of Australia

THE EARTH AS A WHOLE

564. Size of the Earth.—The earth is a ball or globe, and its diameter, or the greatest distance through it, is nearly 8000 miles. The circumference is a little more than three times as great, or nearly 25,000 miles. It is not easy to imagine how large the earth is, although it does not seem so large as it did to our forefathers, because we can travel more swiftly than they, and can send messages by telegraph. Even now, a swift passenger ship would take about seven weeks to sail around the earth. If there were lands on which a railroad could be built at the Equator, a train moving forty miles an hour would require twenty-six days to make the journey.

565. Shape of the Earth.—The earth is not a perfect sphere, for it is flattened at each pole so that the polar diameter is about 26 miles shorter than the diameter at the Equator. But if a baseball or a school globe were flattened in this proportion the difference would be so small that we should fail to notice that it was not a perfect sphere.

Long before the time of Christ a few men believed the earth to be round. But most persons did not believe it until about four hundred years ago. They thought the earth was flat, and they had curious ideas as to what held it up.

If the earth were flat, the hull of a ship would be the last part to disappear from sight as the ship leaves a port, for it is the biggest part. But in reality the hull goes out of sight first, then the rigging, then the smoke, showing that the ocean has a curved surface. We know the ocean has a curved surface for the further reason that we can sail around the world and come back to the place we left.

When the earth's shadow falls on the moon, the edge of the shadow is always part of a circle. No object but a sphere will always cast a circular shadow. When we go from the

Northern Hemisphere to the Southern, or from the Southern Hemisphere to the Northern, some stars go out of sight and others come into view. If the earth were flat, we should see the same stars wherever we went. In all these ways we know that the earth has a curved surface, and since the amount of curvature has been measured, it has been found that the curved surface is that of a sphere.

In former times men could not easily believe in a round earth, because they thought people would fall off from the other side of it. They thought people on the other side of the world would have their feet up and their heads down. But the only *down* is toward the center of the earth, and the only *up* is away from the center of the earth. Men and all objects are held to the earth by an invisible force called gravitation. For this reason any object thrown into the air falls again toward the earth's center. The attraction is what gives objects weight. It is not the earth's center, however, that exerts the force, but the whole mass of the earth. The gases that make up the atmosphere are bound to the earth in the same way. There is less air at the tops of high mountains than on low plains. We say that the air there is rare, and people have difficulty in breathing. The waters of the earth are gathered into the low parts, but they are spread over nearly three fourths of the earth's surface, because the surface is so nearly round.

566. Surface and Materials of the Earth.—We have already learned that the land surfaces are uneven, but the height of mountains is small compared with the diameter of the earth. The highest mountains rise less than six miles above sea level, while the earth's diameter is nearly 8000 miles.

The earth is everywhere surrounded by the atmosphere, which extends many miles

above the highest mountains. Below the atmosphere, the surface is made up of land and water. The land is nearly everywhere covered with soil, and under the sea almost everywhere are layers of mud. Under the soils of the land and the muds of the sea are the rocks that make up most of the globe. The rocks deep in the interior of the earth are believed to be very hot. One reason for thinking this is that the rocks increase in temperature the deeper we go down a mine shaft. We do not believe that the earth's interior is liquid rock, for it is all under such vast pressure that it would remain solid even if intensely hot.

567. The Rotation of the Earth.—The earth always turns or spins in the same direction. The line around which it turns we call the earth's *axis* (Fig. 579). One end of this line we call the *North Pole*, and the other end we call the *South Pole* of the earth. The motion is like that of a spinning top. We can think of a line passing through the center of the top, around which it turns. The Pole Star, or North Star, is so called because it is almost in line with the earth's axis. It is always above the North Pole.

We can also think of a line running around the earth, just halfway between the poles. This circle we call the *Equator*, because it divides the earth into two equal parts or hemispheres. North of the Equator is the Northern Hemisphere, and south of the Equator is the Southern Hemisphere (Fig. 580).

The earth makes a complete turn on its axis once in twenty-four hours. This move-

ment is toward the east, where the sun rises, or comes into view in the morning. At the Equator, any person or thing at the surface of the earth travels in one complete rotation about 25,000 miles, or more than 1000 miles an hour. A person is not blown away and does not feel the motion, because the air and everything else around him is moving as fast as he is moving.

568. Directions and the Compass.—Toward the North Pole is north, and toward the South Pole is south. At the North Pole one could not face in any direction but south, and in moving away from the Pole one must go south. At the South Pole the observer faces north, and could not move away from the Pole in any

direction but north. The earth turns toward the east and from the west. These four main directions are the *cardinal points*. We also name intermediate directions, such as northeast, southeast, south-southeast.

A compass consists of a magnetic needle mounted on a pivot, so that it will turn freely (Figs. 581, 582). In the mariner's com-




Fig. 579. Axis and poles




Fig. 580. Equator




Fig. 581. Engineer's compass




Fig. 582. Mariner's compass

pass the needle carries with it a card showing the directions (Fig. 583). It does not point exactly north except in a few places, but points in general toward a locality in the north of Canada called the North Magnetic Pole. In some parts of the land and sea the needle points west of north, in others east of north.




Fig. 583. Card of mariner's compass

Maps are prepared showing how much the needle varies from true north, and thus the sailor or the explorer can allow for the compass variation.

569. Latitude.—Every circle is divided into 360 equal parts, and one of these parts is a degree; 360 degrees is written 360° . Each degree is divided into 60 minutes, written $60'$, and each minute into 60 seconds, written $60''$.

Since a whole circle is 360° , a quarter of a circle is 90° . From pole to pole is 180° on a great circle drawn around the earth through both poles. Angular distance from the Equator to the poles, measured on such a great circle, is called *latitude*,—north latitude, if measured from the Equator north; south latitude, if measured south. One degree of latitude covers about 69 miles of distance. A circle running around the earth parallel to the Equator is a *parallel of latitude* (Fig. 584). All points on such a circle are at equal distances from the Equator. We can draw as many parallels as we like, but it is common to draw them on maps at intervals of 5° , 10° , or 20° . The parallels on a globe are shorter as we go away from the Equator.

If a person were at the North Pole, the Pole Star would be nearly overhead, or in the zenith. If he were at the Equator, it would be on the horizon. If he moved north from the Equator, for every degree he traveled, the North Star would rise one degree above the horizon. Hence the angular distance of the star above the horizon anywhere is nearly the latitude of that place.

Sailors often wish to know the latitude when they cannot see the star. They use an instrument called a

sextant, and find out the height of the sun at noon (Fig. 362). Astronomers furnish tables by which the traveler or sea captain can reckon his latitude from the facts learned by using the sextant.

570. Longitude.—Angular distance around the earth from east to west, or west to east, is called *longitude*. If it is noon at any place, it is noon at all places directly north and south on a line running from pole to pole through the place. Such a line is called a *meridian*, or midday line (Fig. 584). We can imagine as many meridians as we like. In giving longitude it is customary to choose one meridian as the starting place from which to measure. This is called the *prime meridian*. The one commonly used is the meridian




Fig. 584. Parallels and meridians

of the national observatory at Greenwich, in the eastern part of London. From that meridian, most nations speak of all points eastward up to 180° , as in east longitude, and all points westward up to 180° , as in west longitude. A degree of longitude on the Equator measures about 69 miles. North or south of the Equator any two meridians, a

degree apart, gradually approach each other until they come together at the poles. Hence the length of a degree of longitude, measured on circles that constantly decrease in size from the Equator toward the poles, diminishes from 69 miles at the Equator to zero at either pole.

When a ship captain sails from London to New York, he carries a chronometer, — which is a good watch or clock, — keeping Greenwich time. Every 15° of longitude makes an hour's difference in time (for 15° is one twenty-fourth of 360°). Hence if the chronometer indicates 3 o'clock P.M. Greenwich time, when it is only noon where the ship is, the captain knows he is 45° west of Greenwich, or in west longitude, 45° . On land, people in different places are able to get each other's local or sun time by telegraph, and, by reckoning 15° difference for every hour's difference in time, to find the difference in longitude.

We could not sail the ocean, explore the wilderness, or make accurate and useful maps, if we did not have the system of locating places by their latitude and longitude.

571. The Sun.—Without the sun it would be impossible for animals and plants to live on the earth. Although but a slight part of the sun's heat and light falls on the earth, it makes all the difference between a dead and frozen world, with endless night, and an earth covered with seas and fertile soils, with grasses, flowers, forests, and animals.

When we shrink from the heat of the sun on a summer day, it is hard to believe that




Fig. 585. An ellipse may be drawn by aid of a cord attached to two points called foci

the sun is so far away. We can go within a short distance of the hottest bonfire, but we seek a shade tree or a porch to shield ourselves from rays of heat that have traveled 93,000,000 miles, a distance which is too great for us to comprehend.

The sun is more than a million times as large as the earth, and more than 300,000

times as heavy. We cannot understand such size any more than we can realize the sun's distance. The outer parts of the sun are made up of hot gases, and glowing tongues of these gases leap out for thousands of miles.

572. The Revolution of the Earth.—The earth moves around the sun once each year. The curve or track which it follows is called its *orbit*. As the earth is about 93,000,000 miles from the sun, the distance across the orbit is about 186,000,000 miles. This orbit, or track, is not quite a circle, but is drawn out very slightly in the form of an ellipse (Fig. 585). The sun is at one focus of the ellipse. The exact shape of the earth's orbit is shown in Figure 592. For this reason the earth is about 3,000,000 miles nearer the sun at one time in the year than at another.

The earth has kept its place in the orbit, and for ages it has made its journeys around the sun, because of the attraction of gravitation. If there were no attraction of gravitation, the earth would not follow its track but would fly off into space.

We may think of the orbit as in a plane surface like the top of a table. The axis of the earth is not at right angles (90°) with the plane of the orbit, but is inclined $23\frac{1}{2}^\circ$ away from that position (Figs. 579, 589, 592). So the earth goes around the sun once in a year and its axis is all the time inclined in one direction. Hence during part of each year the North Pole is turned a little away from the sun, and the South Pole toward the sun;

and during another part of the year the North Pole is turned a little toward the sun, and the South Pole away from the sun.

573. The Solar System.—The earth is not the only body that revolves around the sun. There are seven other large bodies, and many smaller bodies, of the same kind, and these with the earth are called *planets*. The planets shine because the light of the sun is reflected from them, for they are not, like the sun and stars, balls of hot and glowing substances. Two of the large planets, Mercury and Venus, are nearer the sun than the earth, and hence go around the sun in smaller orbits and in shorter time. They are also smaller than the earth.

The other five large planets are Mars, Jupiter, Saturn, Uranus, and Neptune. They are all farther from the sun than the earth is, and hence move around the sun in larger orbits. All except Mars are much larger than the earth.

All the planets spin, or rotate, on their axes. Some turn in less than one of our days, and others turn so slowly that many days are required to complete a rotation. Some of the planets require a period equaling many years to finish a revolution in their orbits around the sun.

Some of the planets have small bodies that revolve around them. Our earth has one, the moon. Such smaller bodies, revolving around the planets as the planets revolve around the sun, are called *satellites*. The planet Saturn has ten satellites.

All these bodies, the sun, the planets, and the satellites, make up the solar system, that is, the family of spheres or bodies that belong with the sun.

There are many millions of stars in the heavens and they are much farther from us than any part of the solar system. Some of them are much larger than our sun. Each of the stars is a sun and may have many planets of its own, which are too far away to be seen through a telescope.

574. The Moon.—The moon is the earth's satellite. It revolves around the earth at a distance of about 240,000 miles. The period of revolution is a little less than a month. It also turns once around on its axis in the same period of time. The result is that we have always the same face of the moon toward us.

The moon shines because the sun's light is reflected from it to us. When it is between us and the sun its dark side is toward us. When it passes a little beyond this point, we see it as a narrow curved band of light, and call it the *new moon*. The belt of light increases until the moon is *full*. It then shows an entire half lighted because it is on the opposite side of the earth from the sun.




Fig. 586. Eclipses of sun and moon

The moon has a rough and rocky surface, but it has no atmosphere, no soil, and no plants or animals. The attraction which it exerts on the waters of the earth is the main cause of the tides (Sec. 352), and it gives useful light during some of the evenings of each month.

When the moon comes exactly between us and the sun, it shuts off part or all of the sun from view. This is an *eclipse* of the sun, which is either *partial* or *total* (Fig. 586, A). When the earth comes exactly between the sun and the moon, it shuts off the light from the moon, and thus causes an eclipse of the moon (Fig. 586, C).

575. Time.—The rotation of the earth through one full turn takes 24 hours, or a day. This is one unit for measuring time.

One full revolution of the earth about the sun requires a few hours more than 365 days, and affords a natural measure for the period that we call one year. Both the rotation and the revolution of the moon require nearly a month, and furnish another natural division of time.

For centuries, many ingenious devices have been made for showing the time by the position of the sun, and the shadow that it casts. Such a device is called a sundial (Fig. 587). In the old days hourglasses were used for measuring time. They were so arranged that a given amount of sand would run from one part of a glass to another through a narrow neck in a given time, usually one hour. Now watches and clocks are commonly used. They are machines that cause one hand, the hour hand, to go around a dial in twelve hours, while the minute hand goes around in one hour. Thousands of regulator clocks are set to true time every day, by a telegraphic signal sent from Washington, D. C., at noon to all parts of the United States.

576. Standard Time.—As it is noon in any place when the sun is highest in the sky, local time is different for all places of different longitude. When it is noon in Greenwich, it is afternoon at all places east of Greenwich, and before noon at all places west of Greenwich. Trains have to be run on schedule time so that they may keep from collision, and so that all may know when they are due to




Fig. 587. Sundial

arrive at a given place, or to depart from it. It would be difficult to do this if local, or sun, time were used in every place through which the road runs. Hence it is agreed to use *standard time*. In the United States, for a distance of about $7\frac{1}{2}^\circ$ both east and west of the meridian of 75° west longitude,

the people use the local time of that meridian. Similarly, the local time of the meridians of 90° , 105° , and 120° is used. These belts of about $7\frac{1}{2}^\circ$ on each side of a meridian, making about 15° in all, are called *standard time belts*. In going west on a through train, the watch is put back an hour every time we pass from one belt to another. In going east the watch is in like manner put ahead one hour. The time belts in the United States have eastern, central, mountain, and Pacific time.

In practice, the belts are in places less or more than 15° wide, as seen in Figure 588.

577. International Date Line.—If we go around the world by ship, or by ship and train, each day, as marked by the sun, is a little longer or shorter than 24 hours. If we go east, we meet the sun, and it requires less than 24 hours to go from noon of one




Fig. 588. Standard time belts of the United States

day to noon of the next. In going entirely around the world we should thus reckon one day too many to correspond with the actual days of 24 hours each. If we go around the world to the west, we are going away from the sun, and when it overtakes us at noon, we have gone a little more than 24 hours since the sun marked noon for us the day before. We should thus reckon one day too few in a journey around the world.

Hence the nations have agreed to adopt the meridian of 180° as an *International Date Line*. A ship crossing this line to the east goes back one day in its calendar, while a ship crossing it to the west goes ahead one day. The line is chosen in the Pacific Ocean because the changes in time would be inconvenient if made on land where many people live. (See Fig. 360.)

578. The Zones.—In studying the zones refer constantly to Figure 589, which shows the June position of the earth in relation to the sun in *A*, and the December position in *B*. The two positions of the earth's axis are parallel to each other. For convenience, the sun is represented as small, while in reality it is vastly larger than the earth (Sec. 571). It is also shown as near, though it is really very far away. In *A* the inclination of the earth's axis to the plane of the orbit causes the North Pole, on June 21, to be turned $23\frac{1}{2}^\circ$ directly toward the sun. Hence a ray of light from the sun, *a*, shines $23\frac{1}{2}^\circ$ beyond the pole. This is the position of the Arctic Circle.

The ray of light *c* falls on the earth vertically at an angle of 90° with the surface, and the latitude at which it falls determines the position of the Tropic of Cancer, which is $23\frac{1}{2}^\circ$ from the Equator. The ray *f* reaches a point $23\frac{1}{2}^\circ$ from the South Pole. This is the position of the Antarctic Circle.


In *B*, representing the earth December 21, or six months later, the ray of light *g* reaches the Arctic Circle. The ray *j* is vertical $23\frac{1}{2}^\circ$ south of the Equator and thus determines the position of the Tropic of Capricorn. The

ray *l* shines $23\frac{1}{2}^\circ$ past the South Pole, as in *A* ray *a* shines $23\frac{1}{2}^\circ$ past the North Pole.

All the surface north of the Arctic Circle we call the Arctic, or North Frigid, Zone. The belt between the Arctic Circle and the Tropic of Cancer is the North Temperate Zone. The belt between the Antarctic Circle and the Tropic of Capricorn is the South Temperate Zone. All the surface south of the Antarctic Circle is the South Frigid Zone. The belt between the two Tropics is the Torrid Zone, divided into halves by the Equator. The sun shines either very obliquely or not at all in the Frigid Zones, and they are very cold. It shines less obliquely on the Temperate Zones, and they have a moderate amount of heat. It is always directly overhead somewhere within the Torrid Zone, and hence this zone is hot.

579. Summer and Winter.—On June 21 the North Pole is turned more toward the sun than at any other time (Fig. 589). The South Pole is turned more from the sun than at any other time. The sun's rays fall everywhere in the North Frigid Zone. In the North Temperate Zone the rays at noon are from 47° to 90° above the horizon. They are vertical at the Tropic of Cancer, and at the Equator they are $66\frac{1}{2}^\circ$ above the horizon, or $23\frac{1}{2}^\circ$ north of the zenith, the point directly overhead. Hence the whole Northern Hemisphere is then warm, and has its summer. At the same time no sunlight falls in the South Frigid Zone, the sun's rays fall very obliquely on the South Temperate Zone, and the Southern Hemisphere has winter. The summer (Northern Hemisphere) is warmer also because it has long days and short nights, and the winter (Southern Hemisphere) is colder because it has short days (Sec. 580).

On December 21 these conditions are exactly reversed, as shown in *B*. The sun's rays fall obliquely, and the days are short, in the Northern Hemisphere, and hence it has winter. On that date, the sun does not shine anywhere north of the Arctic Circle. At the



same time, in the Southern Hemisphere the sun rises high in the sky and the days are long. Hence that hemisphere then has its summer. On December 21, the sun shines everywhere south of the Antarctic Circle.

580. Day and Night.—Figure 589 illustrates the different lengths of day and night. A person at the Equator would be in the sunlight during half of one rotation of the earth, and in the shadow during one half a rotation. Hence day and night there would be equal. In the Northern Hemisphere in summer (A, Fig. 589) daylight everywhere lasts longer than darkness. A person living at *n*, for example, and going around with the earth as it turns on its axis, is longer in the sunlight than in the shadow. A person at *m*, on the Arctic Circle, would be in daylight for the full period of rotation, or 24 hours, and he would see the sun at midnight, on the horizon in the north. This is the “midnight sun,” which many people go to North Cape in Norway to see. Within the Arctic Circle, daylight is everywhere long in summer, and at the North Pole there is daylight for six months, or while the earth is passing from C around to D; that is, from March 21 to September 22 (Fig. 592).

During this period south of the Equator the night is everywhere longer than the day, for

winter there is at the same time as summer in the Northern Hemisphere. A person at *o* (Fig. 589) is longer in the shadow than in the sunlight, as the earth turns. At *p*, on the Antarctic Circle, one would see the sun on the horizon at noon in the north, but it would be night all the rest of the 24 hours. Within the Antarctic Circle night everywhere is long in winter, and at the South Pole it lasts six months.

Near the Arctic Circle the summer is cool and short, because the sun's rays are very oblique, and less heat comes through the atmosphere to the ground. But the days are very long, and the nights short. For this reason vegetables, grasses, and even hardy grains may ripen during the short summer.

Referring now to B in Figure 589, we can see that the conditions of day and night are reversed. It is now winter in the Northern Hemisphere, and the days are shorter as we go north, until at the Arctic Circle the sun is seen only at noon, on the southern horizon. The night lengthens as we approach the Pole, where it lasts six months.

The Southern Hemisphere is in its summer and has daylight increasing from a period of twelve hours at the Equator to six months at the South Pole.



581. Spring and Autumn.—

In Figure 592 we imagine that we see the sun and the earth's orbit from such a position that we observe the North Pole, and the earth in its position for each month. The position for June 21 corresponds to *A* in Figure 589, but now we look down on the North Pole, while in *A* we look across it. In like manner, the position for December 21 corresponds with *B* in Figure 589.

Look now at the earth as it is related to the sun on March 21. The North Pole is not turned at all toward the sun, and the South Pole is not turned toward it. The sun's rays reach both poles, though we see only one in the diagram. At this time all people on earth, wherever they may be, have day and night of equal length; each is twelve hours long. Hence this date is called the *equinox*, or the time when night equals day. As the season is spring, this is the *spring*, or *vernal*, equinox.

Look now at the diagram for September 22. The conditions are the same as for March 21, and we call the time the *autumnal* equinox.

By looking at other parts of the diagram we can see that the days in the Northern Hemisphere are longer as we are nearer June, and the nights are longer as we are nearer December.

MEAN ANNUAL TEMPERATURE AND HEAT BELTS

582. Mean Annual Temperature.—Among the facts shown by the daily weather maps issued by the Weather Bureau of the national government none are more interesting than the records of temperature and the changes which they show for each place from day to



Fig. 592. Earth in relation to the sun each month of the year

day. On such maps the influence of elevation upon temperature is very clearly shown. In studying the causes which lead to temperature differences on land and sea, as well as for other purposes, it is often desirable to know what the temperature of all places would be if they were at sea level. This is usually found by adding to the temperature as recorded by the thermometer one degree for every three hundred feet of elevation.

It is sometimes desirable also to be able to compare the average temperatures of places for a month or year or for a much longer time.

Figure 590 is a map of the kind described; it shows sea level temperatures, as averaged for a long period of years.

583. Heat Belts.—As we have seen (Sec. 578), the boundaries of the zones are fixed by the way the sun shines at different places and at different times. The zones are really light zones, although named as if they were

heat zones. The distribution of heat, as shown by Figure 590, is affected by winds and other causes besides sunshine.

Figure 591 shows the true heat belts, corresponding in a rough way with the zones. The hot belt is bounded by lines of mean annual temperature; but the temperate belts extend poleward to the line of 50° average temperature for the hottest month.

The hot belt is on both sides of the Equator, but more in the Northern Hemisphere than in the Southern. The north temperate belt is much broader than the south temperate belt and more irregular in outline; it includes nearly half of the land surface of the earth. The temperate belts include some regions of mild temperature and some regions of cold winters and warm summers. In them live the progressive peoples of the world.

We began the studies of this book with the ways of living in the cold north, in the heated tropics, in temperate latitudes, and in desert regions. We have now seen in this chapter that these ways of living depend in great part upon the relations which our earth bears to the sun. The sun makes life on the earth possible and it shapes in many ways the lives of plants, animals, and men.

Review.—1. How large is the earth? 2. How much shorter is the polar diameter than the equatorial? 3. Give reasons for thinking that the earth is nearly a sphere. 4. What is meant by gravitation? What results from it?

5. By what is the earth surrounded? 6. Describe the earth's surface.

7. Define the axis of the earth; the poles. 8. What are the cardinal points? 9. Where is the North Magnetic Pole? 10. What is meant by the variation of the magnetic needle?

11. What is latitude? What is a parallel of latitude? 12. How long is a degree of latitude? 13. What is longitude? What is the prime meridian? 14. How does the length of a degree of longitude vary?

15. Compare the size and weight of the sun with those of the earth. 16. What is the earth's orbit? What is the shape of the orbit? 17. How much is the earth's axis inclined?

18. What is the solar system? 19. What planets are nearer than the earth to the sun? 20. What are satellites?

21. How far is the moon from the earth?

22. How does the moon differ from the earth?

23. How is an eclipse of the moon caused?

24. How do we get the length of our day?

25. What is local time? 26. Define standard time. What names are given to the standard time belts in the United States? 27. What is the International Date Line?

28. What determines the position of the Arctic and Antarctic Circles? Of the Tropic of Cancer? The Tropic of Capricorn? 29. Name the zones.

30. What causes summer in the Northern Hemisphere? 31. What part of the earth has summer about December 21?

32. Why are summer days longer than winter days? 33. What makes it possible to raise some crops in regions far north, where summer is very short? 34. What is the "midnight sun"? 35. What places have day and night six months long?

36. What are the equinoxes? 37. What seasons occur at the time of the equinoxes?

38. Make from memory a sketch map of North America, including the following features: Great Lakes; Mississippi, Colorado, Columbia, Nelson, Mackenzie, and Yukon river systems; Montreal, Vancouver, Seattle, San Francisco, Chicago, New Orleans, New York, Philadelphia, and Washington.

39. Make a sketch map of Europe and include five important rivers, seven national capitals, and the following mountain ranges: Alps, Pyrenees, Apennines, Carpathians. 40. Name the largest island of Europe and the largest island in the temperate latitudes of North America, and compare them as to latitude, area, climate, population, and products.

41. Make a sketch map of your own state, including the capital, the chief cities, your home town, the chief rivers, and leading agricultural and manufactured products. 42. Name the European country whose area is approximately equal to that of your own state. 43. Compare the areas of Massachusetts and Belgium; of Colorado and the British Isles; of Texas and France.

44. Name five important agricultural countries; four important manufacturing countries. 45. What important imports do we receive from South America? What are our leading exports to Europe? 46. Name four important seaports in the United States, two in South America, one in Australia, three in Asia, one in Africa, and seven in Europe.

REVIEW OF IMPORTANT PRODUCTS

WHEAT

(Five-year averages)

World's annual production, 3,440,000,000 bushels.

Leading wheat-growing countries, with percentages of the world crop:

United States	24%
India	10%
Russia (estimated)	8%
Canada	7%
France	6%
Argentina	5%

Average annual production in the United States, 830,000,000 bushels. (In 1915, over 1,000,000,000 bushels.)

Leading wheat-growing states, with percentages of United States crop:

Kansas	13½%	Nebraska	5½%
North Dakota	9%	Oklahoma	5½%
Illinois	6%	Minnesota	5½%

Leading wheat-exporting countries: United States, Argentina, Canada.

Reading References.—Sections 182–186, 108, 252, 292, 326, 492 of this book. Carpenter's "How the World is Fed" (American Book Company). Smith's "The World's Food Resources" (Holt). Rutter's "Wheat Growing in Canada, the United States, and the Argentine" (Macmillan Company).

CORN

(Five-year averages)

World's annual production, 3,880,000,000 bushels.

Leading corn-growing countries, with percentages of the world crop:

United States	76%
Argentina	5%
Roumania	4%
Mexico	3%
Italy	2½%
Hungary	2%




Fig. 593. Wheat-producing regions

Average annual production of corn in the United States, 2,945,000,000 bushels.

Leading corn-growing states, with percentages of United States crop:

Iowa	14%	Indiana	6%
Illinois	11½%	Ohio	5½%
Nebraska	7%	Texas	4%
Missouri	6½%	Kansas	3%

Leading corn-exporting countries, Argentina, United States.

Reading References.—Sections 187, 190, 110, 326. Carpenter's "How the World is Fed," pp. 44–55. Brooks's "The Story of Corn and the Westward Migration" (Rand, McNally & Co.). Myrick's "Book of Corn" (Judd).




Fig. 594. Corn-producing regions

RICE

(Five-year averages)

World's annual production, 155,000,000,000 pounds.

Leading rice-growing countries, with percentages of world crop:

India	46%
China (three provinces)	30%
Japanese Empire	15%

The United States produces less than one per cent of the world total, although the production has considerably increased in recent years.

Leading rice-exporting countries, with percentages of the world's exports of rice:

India	42%
French Indo-China	18%
Siam	15%

Leading rice-growing states in the United States: Louisiana, Texas, Arkansas, California.

Reading References.—Sections 165, 468, 515, 523, 529. Carpenter's "How the World is Fed," pp. 56-66. Gannett, Garrison, and Houston's "Commercial Geography"—see index for various countries (American Book Company). Freeman and Chandler's "The World's Commercial Products," pp. 27-49 (Ginn & Co.). King's "Farmers of Forty Centuries" (Mrs. F. H. King, 1540 University Ave., Madison, Wisconsin).

SUGAR

(Five-year averages)

World's annual crop:

Cane	11,600,000 tons
Beet	8,800,000 tons

Leading cane-sugar countries, with percentages of the world's cane-sugar crop:

Cuba	29%
India	26%
U. S. and dependencies	15%
Java	14%



Fig. 595. Rice-producing regions

Leading beet-sugar countries are Germany, France, Russia, Poland, Czechoslovakia, and Belgium, for which recent statistics are not available because of the World War.

The crop of cane sugar in the main body of the United States, of which Louisiana produces the greater part, averages nearly 300,000 tons a year. This is about 2½% of the world's total.

The leading beet-sugar states, with percentages of United States production, are Colorado 30%, California 25%, Michigan 13%, Utah 12%.

Reading References.—Sections 164, 422. Surface's "Story of Sugar" (Appleton). Carpenter's "How the World is Fed," pp. 328-345. Wiles's "Cuban Cane Sugar" (Bobbs-Merrill Co.). Geerligs's "The World's Cane Sugar Industry" (Van Nostrand Co.).



Fig. 596. Sugar-producing regions

TEA

(Five-year averages)

The total production of tea in some countries is not reported. The world's annual exports of tea amount to 773,000,000 pounds.

Leading tea-exporting countries, with percentages of the world's exports of tea:

India	35%
China	26%
Ceylon	25%
Japan, etc.	8%

Among the leading tea-consuming countries Australia uses each year about seven pounds per person, Great Britain six pounds, and Canada five pounds. The United States uses only a little more than one pound per inhabitant.

Reading References.—Sections 515, 521, 530. Carpenter's "How the World is Fed," pp. 308-316. Gannett, Garrison, and Houston's "Commercial Geography," pp. 97-98. Ibbetson's "Tea from Grower to Consumer" (Sir Isaac Pitman and Sons).

COFFEE (Five-year averages)

World's annual production, about 3,000,000,000 pounds (Fig. 334); annual exports, 2,600,000,000 pounds.

Leading coffee-exporting countries, with percentages of the world's exports of coffee:

Brazil	63%
Central America	9%
Dutch East Indies	5%
Venezuela	4%
Colombia	4%

Among the coffee-importing countries the United States leads, taking about one third of the world crop. Germany in normal times is second, taking less than half as much as the United States. Netherlands and France come next, each taking about one fourth as much as the United States.




Fig. 597. Tea-producing regions and cacao-producing regions

Reading References.—Section 321. Carpenter's "South America" (American Book Company). Keable's "Coffee from Grower to Consumer" (Sir Isaac Pitman and Sons).

CATTLE

World's total (excepting China), 500,000,000. The leading cattle-raising countries are:

India	26%	Germany	4%
United States	12%	Russia in Asia	4%
Argentina	6%	France	3%
Brazil	6%	Australia	2%
European Russia	4%	Great Britain	2%

Reading References.—Sections 192-196, 326. Carpenter's "North America," pp. 252-258 (American Book Company). Brigham's "Commercial Geography," pp. 40-57 (Ginn & Co.).




Fig. 598. Cattle-raising regions

COTTON

(Five-year averages)

World's annual production, 22,000,000 bales of 500 pounds each.

Leading cotton-growing countries, with percentages of world production:

United States	65%
India	17%
Egypt	6%
China (estimated)	6%

World's annual imports, about 14,000,000 bales, of which Great Britain takes about one third, and France and Japan each about one ninth. Before the World War Germany imported about half as much as Great Britain.

Average annual cotton production of the United States, 14,260,000 bales.

Leading cotton-producing states, with percentages of United States crop:

Texas	30%	South Carolina	9%
Georgia	15%	Mississippi	8%
Alabama	9%		

Reading References.—Sections 88, 141-143, 163, 412, 550. Carpenter's "How the World is Clothed" (American Book Company). Chamberlain's "How We are Clothed" (Macmillan Co.). Bigwood's "Cotton" (Holt). Scherer's "Cotton as a World Power" (F. A. Stokes Co.).

WOOL

(Five-year averages)

Annual exports of wool reported from all countries, 2,200,000,000 pounds.

Leading wool-exporting countries, with percentages of exports reported for all countries:

Australia	30%
Argentina	15%
New Zealand	9%
British South Africa	8%
Uruguay	7%




Fig. 599. Cotton-producing regions

Among the wool-importing countries, France and Great Britain lead, each taking about one fourth of the world's imports. Germany before the war imported less than either France or Great Britain, but twice as much as the United States.

The scoured wool produced in the United States averages 122,000,000 pounds a year.

Leading wool-producing states, with percentages of United States production:

Wyoming	11%	Idaho	6%
Montana	9%	Utah	5½%
Ohio	7%	Oregon	5%
New Mexico	7%		

Reading References.—Sections 226, 89, 413, 560. Carpenter's "How the World is Clothed," pp. 73-90. Ormerod's "Wool" (Holt).




Fig. 600. Wool-producing regions

RAW SILK

(Five-year averages)

It is impossible to obtain accurate figures of the world production of raw silk, as the records of production in the Oriental countries are not complete. In the following table, therefore, the figures for Japan and China are for exports only.

World's annual production, more than 55,000,000 pounds.

Leading silk-producing countries, with percentages of the world average given above:

Japan	50%
China	29%
Italy	14%

These three countries lead also in the exportation of raw silk to the United States.

Leading countries exporting manufactured silk to the United States: France, Japan, Switzerland, Great Britain, Italy, and China.

Reading References.—Sections 449, 469, 529. Carpenter's "Asia," pp. 50-52 (American Book Company). Carpenter's "How the World is Clothed," pp. 105-127.

RUBBER (Three-year averages)

World's annual production, 600,000,000 pounds.

Leading sources of rubber, with percentages of world production:

Plantation . . .	84%
Brazil	12½%
Other sources . .	3½%

Most of the world's rubber is now grown on plantations in the far East. Plantations have been developed in the Federated Malay States, Straits Settlements, Java, Sumatra, Ceylon, southern India, Borneo, and Dutch and British Guiana.




Fig. 601. Silk-producing regions

Some rubber is also produced in the various colonies of west and central Africa, Philippine Islands, and Trinidad.

Leading rubber-importing countries (chiefly for home consumption):

United States . .	400,000,000 pounds
Great Britain . .	75,000,000 pounds
France	45,000,000 pounds
Canada	15,000,000 pounds
Italy	15,000,000 pounds

Reading References.—Section 322. Carpenter's "South America," pp. 312-320. Carpenter's "How the World is Clothed," pp. 240-261. Freeman and Chandler's "The World's Commercial Products," pp. 278-297. Lock's "Rubber and Rubber Planting" (Cambridge University Press).




Fig. 602. Rubber-producing regions

FLAX (FIBER)

World's production, about 1,400,000,000 pounds a year. Reliable statistics are not now available. Before the World War, about 80% of the world's flax fiber was grown in European Russia, and 7% in Austria-Hungary. France, Belgium, Ireland, and Netherlands each produce a small part of the world's crop.




Fig. 603. Flax-producing regions

FLAXSEED (Five-year averages)

World's annual production, 110,000,000 bushels. Countries leading in the production of flaxseed, with percentages of world production:

Argentina	32%	United States	13%
India	18%	Canada	9%
Russia	about 15%		

Average annual production of flaxseed in United States, 13,800,000 bushels.

Leading flax-growing states, with percentages of United States production:

North Dakota	47%	Montana	17%
Minnesota	20%	South Dakota	11%

Reading References.—Sections 189, 399, 418, 489, of this book. Carpenter's "How the World is Clothed," pp. 50-59. Freeman and Chandler's "The World's Commercial Products," pp. 313-315.

COAL

World's annual production, 1,350,000,000 short tons.

Leading coal-producing countries, with percentages of world production:

United States	44%
Great Britain	22%
Germany	about 15%

Russia	about 7%
France	about 4%

Of the coal mined in the United States (532,000,000 short tons), only 89,000,000 tons, or less than 17%, is anthracite, and of this amount the state of Pennsylvania produces over 99%.

Leading coal-producing states, with percentages of United States production:

Pennsylvania	44%	Kentucky	4%
West Virginia	15%	Indiana	3%
Illinois	11%	Alabama	3%
Ohio	6%		

Reading References.—Sections III, II2, I 9, 411. Martin's "Story of a Piece of Coal" (Appleton). Brigham's "Commercial Geography," pp. 79-91. Carpenter's "North America," pp. 211-218.




Fig. 604. Coal-producing regions

IRON

World's annual production of pig iron, 70,000,000 long tons.

Countries leading in the production of pig iron, with percentages of world production:

United States . . .	57%
Great Britain . . .	20%
Germany . . .	about 12%
France	7%
Russia	6%
Czechoslovakia . .	3%
Belgium	2%

Annual production of pig iron in the United States, 40,000,000 tons.

States leading in the production of pig iron, with percentages of United States production:

Pennsylvania	41%
Ohio	22%
Illinois	10%
Alabama	7%
New York	6%

Annual production of iron ore in the United States, about 75,000,000 long tons.

States leading in the mining of iron ore:

Minnesota	60%
Michigan	24%
Alabama	9%

Reading References.—Sections 127, 5, 169, 198, 411. Smith's "Story of Iron and Steel" (Appleton). Brigham's "Commercial Geography," pp. 58-78. Carpenter's "How the World is Housed," pp. 142-163 (American Book Company).

COPPER

World's annual production, 3,100,000,000 pounds.

Leading copper-producing countries, with percentages of world production:

United States . . .	62%
Japan	6%
Chile	5%
Canada	4%




Fig. 605. Regions producing iron ore

Mexico	4%
Spain	4%
Peru	3%
Australia	2½%

Annual production of copper in the United States, 1,930,000,000 pounds.

Leading copper-producing states, with percentages of United States production:

Arizona	36%
Montana	18%
Michigan	14%
Utah	12%
Alaska	6%
Nevada	5%

Reading References.—Sections 237, 200. Carpenter's "North America," pp. 182-184. Carpenter's "How the World is Housed," pp. 180-188.




Fig. 606. Copper-mining regions

PETROLEUM

World's annual production, 450,000,000 barrels of 42 gallons each.

Leading petroleum-producing countries, with percentages of world production:

United States	66%
Mexico	15%
Caucasus	13%
Roumania	3%
Dutch East Indies	3%
Poland	2%
India	2%

Petroleum production of the United States, 300,000,000 barrels a year.

Leading petroleum-producing states, with percentages of United States production:

Oklahoma	38%
California	33%
Texas	9%
Illinois	7%
Louisiana	6%

Reading References.—Sections 113, 171, 255, 541. Tower's "Story of Oil" (Appleton). Carpenter's "North America," pp. 203-207. Carpenter's "How the World is Housed," pp. 286-290.

GOLD AND SILVER

World's annual production of gold, \$457,000,000.


Leading gold-producing regions, with percentages of world production:

Africa	49%
United States	20%
Australia	9%
Russia	about 6%
Canada	4%
India	2½%
Mexico	2%

World's annual production of silver, \$107,000,000.

Leading silver-producing regions, with percentages of world production:


United States	50%
Mexico	16%



Canada	16%
Peru	6½%
Japan	3%

Reading References.—Sections 235, 236, 261, 291, 556, 560. Mead's "Story of Gold" (Appleton). Carpenter's "Africa," pp. 303-309; "Australia," pp. 39-44; "North America," pp. 266-273.

General References.—Some mineral industries (notably petroleum) are subject to rapid changes because of the discovery of new fields and the decreased production of old fields, and for other reasons. For recent information, consult "Mineral Resources of the United States" (annual, United States Geological Survey), or Roush's "The Mineral Industry" (annual, McGraw-Hill Book Company).



BOOKS FOR REFERENCE READING

The books in the following list present in greater detail many of the topics and regions treated in this textbook. They are chosen for their excellence; but some care will be necessary in assigning passages for the pupils' reading. Reference should be made to definite pages, and the children should be asked to read independently only such portions of a book as are reasonably simple and clear.

The following abbreviations are used: American Book Company, New York (A. B. C.); D. Appleton and Company, New York (D. Ap.); The Century Company, New York (Cent.); Ginn and Company, Boston (Ginn); Henry Holt and Company, New York (H. H.); Orange Judd Company, New York (Judd); J. B. Lippincott Company, Philadelphia (Lip.); The Macmillan Company, New York (Mac.); G. P. Putnam's Sons, New York (Put.); Charles Scribner's Sons, New York (Scrib.).

General.—Geographical Readers, especially suitable for the pupils' reading; Carpenter's "North America," "South America," "Europe," "Asia," "Africa," "Australia, Our Colonies, and Other Islands of the Sea" (A. B. C.). Chamberlain and Chamberlain's "North America," "South America," "Europe," "Asia," "Africa," "Australia" (Mac.).

Standard Works of Reference.—Any good modern Encyclopedia. Stanford's "Compendium of Geography and Travel," North America 2 v., Central and South America 2 v., Europe 2 v., Asia 2 v., Africa 2 v., Australasia 2 v. (Lip.). "Cyclopedia of Names" (Cent.). "The Statesman's Year-Book," an annual (Mac.). Dryer's "High School Geography" (A. B. C.). Mill's "International Geography" (D. Ap.). McFarlane's "Economic Geography" (Mac.). Smith's "Industrial and Commercial Geography" (H. H.). Talbot's "Railway Conquest of the World" (Lip.). Freeman and Chandler's "The World's Commercial Products" (Ginn). The Century "Atlas" (Cent.). Stieler's "Hand Atlas" (G. E. Stechert & Co., N. Y.). "National Geographic Magazine" (National Geographic Society, Washington, D. C.).

Sections 11-39. North America.¹—Russell's "North America" (D. Ap.), "Rivers of North America" (Put.), "Lakes of North America" (Ginn), "Glaciers of North America" (Ginn), "Volcanoes of North America" (Mac.). Brigham's "Geographic Influences in American History" (Ginn). Semple's "American History and its Geographic Conditions" (Houghton, Mifflin & Company, Boston).

40-282. The United States.¹—Shaler's "United States of America" 3 v. (D. Ap.). Ward's "Climate" (Put.). Fiske's "How the United States Became a Nation" (Ginn). Powell's and others'

"National Geographic Monographs" (A. B. C.). Dondlinger's "Book of Wheat" (Judd). Myrick's "American Sugar Industry" (Judd). Oemler's "Truck Farming at the South" (Judd). Thompson's "From the Cotton Field to the Cotton Mill" (Mac.). Todd's "The World's Cotton Crops" (Mac.). Bean's "On the Wool Track" (John Lane Company, New York). Additional references on pages 403-410.

283-308. Other Countries of North America.¹—Hayden's "Canada: Britain's Largest Colony" (Cassell, London). Bradley's "Canada" (H. H.). Enock's "Mexico" (Scrib.). Carson's "Mexico, the Wonderland of the South" (Mac.). Martin's "Mexico of the Twentieth Century" 2 v. (Dodd Mead and Company, New York).

309-335. South America.¹—Bowman's "South America: a Geography Reader" (Rand McNally and Co., Chicago). Bryce's "South America" (Mac.). Buley's "Brazil (northern)" "Brazil (southern)" (D. Ap.). Koebel's "Uruguay" (Scrib.). Hardy's "Paraguay" (Scrib.). Martinez and Lewandowski's "The Argentine in the Twentieth Century" (Scrib.). Elliott's "Chile" (Scrib.). Walle's "Bolivia" (Scrib.). Vivian's "Peru" (D. Ap.). Enock's "Peru" (Scrib.). Enock's "Ecuador" (Scrib.). Levine's "Colombia" (D. Ap.). Dalton's "Venezuela" (Scrib.). Rodway's "Guiana: British, French, and Dutch" (Scrib.).

336-374. The Ocean and the World Winds.—Murray's "Ocean" (H. H.). Johnson's "Ocean and Inland Water Transportation" (D. Ap.). Smith's "The Organization of Ocean Commerce" (University of Pennsylvania). Ward's "Climate" (Put.).

375-493. Europe.¹—Lyde's "The Continent of Europe" (Mac.). Mackinder's "Britain and the British Seas" (D. Ap.). Dawson's "German Life in Town and Country" (Put.). Partsch's "Central Europe" (D. Ap.). Lynch's "French Life in Town and Country" (Put.). Deecke's "Italy" (Mac.). Drage's "Austria-Hungary" (E. P. Dutton and Company, New York). Palmer's "Russian Life in Town and Country" (Put.). Wallace's "Russia" 2 v. (Cassell, London). Leroy-Beaulieu's "Empire of the Tsars and the Russians" 3 v. (Put.).

494-563. Asia, Africa, and Australia.¹—Holdich's "India" (D. Ap.). Hogarth's "The Nearer East" (D. Ap.). Little's "The Far East" (Oxford University Press, London). Turner's "Siberia" (Scrib.). Willis's "Agriculture in the Tropics" (Put.). White's "Development of Africa" (Philip, London). Gregory's "The Dead Heart of Australia" (Murray, London).

564-583. The Earth as a Whole.—Johnson's "Mathematical Geography" (A. B. C.).

¹ In addition to those given in the general list above.

TABLES

1. AREA AND POPULATION OF THE WORLD

SUMMARY

Length of earth's axis (miles)	7,900
Length of equator (miles)	24,900
Earth's Surface (sq. mi.)	196,900,000
Pacific Ocean (sq. mi.)	71,000,000
Atlantic Ocean (sq. mi.)	34,000,000
Indian Ocean (sq. mi.)	28,000,000
Arctic Ocean (sq. mi.)	4,000,000
Antarctic Ocean (sq. mi.)	2,700,000
The Sea (sq. mi.)	139,700,000

	Sq. MILES	POPULATION
North America	9,392,000	146,126,000
South America	6,856,000	63,850,000
Europe	3,794,000	443,972,000
Asia	17,143,000	895,118,000
Africa	11,514,000	136,272,000
Australia, etc.	3,457,000	8,758,000
Antarctic Cont.	5,000,000	

The Land. 57,156,000 1,694,096,000

NORTH AMERICA

United States	3,088,519	105,711,000
(States in Table No. 6)		
Alaska	590,884	55,000
Dom. of Canada	3,759,365	8,788,000
Nova Scotia	21,428	524,000
N. Brunswick	27,985	388,000
Prince Edw. I.	2,184	89,000
Quebec	706,834	2,361,000
Ontario	376,722	2,934,000
Manitoba	251,832	610,000
Saskatchewan	251,700	757,000
Alberta	255,285	588,000
Brit. Columbia	355,855	525,000
Territories	1,479,000	12,000
Part Gt. Lakes	30,540	
Newf'dland, etc.	49,680	268,000
Newfoundland	42,730	264,000
Labrador	6,950	4,000
St. Pierre, etc.	93	5,000
Greenland	838,000	14,000
Mexico	767,300	15,503,000
Central America	206,753	5,813,000
Guatemala	43,640	2,100,000
Brit. Honduras	8,600	45,000
Honduras	44,276	637,000
Salvador	8,170	1,501,000
Nicaragua	49,550	638,000
Costa Rica	18,690	468,000
Panama	33,300	401,000
Canal Zone	527	23,000
West Indies	91,400	9,947,000
Cuba	44,000	2,889,000
Haiti, Rep. of	11,070	2,500,000
Dominican Rep.	18,750	897,000
Jamaica	4,840	858,000
Porto Rico	3,435	1,300,000
Bahama Is.	4,400	53,000
Lesser Antilles	4,905	1,450,000
Bermuda Is.	19	22,000

SOUTH AMERICA

Brazil	3,300,000	30,645,000
Argentina	1,084,000	8,699,000
Paraguay	100,000	1,050,000
Uruguay	69,000	1,495,000
Chile	293,000	3,755,000
Bolivia	440,000	2,890,000
Peru	440,000	4,586,000
Ecuador	118,000	2,000,000

	Sq. MILES	POPULATION
Colombia	466,000	5,855,000
Venezuela	364,000	2,412,000
Guiana, British	95,000	298,000
Guiana, Dutch	50,000	113,000
Guiana, French	30,500	49,000
Falkland Is., etc.	6,570	3,000

EUROPE

United Kingdom	94,350	44,168,000
England	50,850	35,679,000
Wales	7,473	2,207,000
Scotland	30,405	4,882,000
N. Ireland	5,320	1,250,000
Small islands	302	150,000
Irish Free St.	27,040	3,140,000
Germany	179,500	59,857,000
Prussia	109,600	37,075,000
Bavaria	29,180	7,140,000
Saxony	5,789	4,670,000
Other states	34,931	10,972,000
Belgium	11,760	7,684,000
Netherlands	12,772	6,841,000
Denmark	16,585	3,289,000
Iceland	39,770	95,000
Faroe Islands	540	21,000
Norway	124,710	2,646,000
Sweden	172,928	5,904,000
Poland	149,000	27,442,000
Danzig	600	365,000
Lithuania	25,000	2,300,000
Latvia	24,000	1,503,000
Estonia	18,500	1,110,000
Monaco	8	23,000
Luxemburg	999	264,000
Sarre Basin	750	658,000
Andorra	175	5,000
France	212,822	39,210,000
Spain	192,000	20,784,000
Gibraltar	2	25,000
Portugal	34,264	5,546,000
Azores	922	243,000
Switzerland	15,956	3,880,000
Italy	123,000	40,120,000
San Marino	24	12,000
Malta	124	225,000
Liechtenstein	61	11,000
Austria	30,700	6,131,000
Hungary	36,000	7,841,000
Czechoslovakia	54,700	13,596,000
Yugoslavia	95,000	12,017,000
Roumania	116,000	17,393,000
Bulgaria	40,000	4,910,000
Albania	11,000	832,000
Greece	42,000	4,932,000
Turkey in Eur.	10,000	1,800,000
Russia in Eur.	1,716,500	93,782,000
Russia proper	1,125,000	58,924,000
Ukraine	173,000	25,605,000
Other areas	418,500	9,253,000
Finland	130,000	3,367,000
Arctic islands	33,500	

ASIA

Turkey in Asia	295,000	10,000,000
Syria	80,000	3,000,000
Iraq	140,000	2,850,000
Palestine	9,000	757,000
Cyprus	3,580	311,000
Sinai (Egypt)	22,800	26,000
Hedjaz	140,000	600,000

	Sq. MILES	POPULATION
Aden, etc.	15,870	177,000
Oman	75,000	500,000
Other Arabia	906,500	2,000,000
Persia	635,000	9,500,000
Afghanistan	240,900	6,380,000
Portug. India	1,400	548,000
Indian Empire	1,856,500	319,075,000
India proper	1,446,200	305,069,000
Burma	268,700	13,206,000
Baluchistan	141,600	800,000
Nepal	54,000	5,600,000
Bhutan	18,600	250,000
Ceylon, etc.	25,500	4,568,000
Straits Sttl's, etc.	35,600	2,377,000
Siam	245,000	8,266,000
French Indo-China, etc.	256,500	17,269,000
East Indies	788,000	60,694,000
Philippine Is.	115,000	10,351,000
Java	51,000	35,017,000
Sumatra, etc.	185,000	6,295,000
Borneo	290,000	2,459,000
Other islands	147,000	6,572,000
China, etc.	4,300,000	320,880,000
China proper	1,497,000	302,340,000
Tibet	814,000	2,000,000
Sinkiang	550,000	2,000,000
Mongolia	1,076,000	1,800,000
Manchuria	363,000	12,740,000
Hongkong	400	625,000
Weihaiwei	280	147,000
Macao	4	75,000
Japanese Empire	261,300	77,606,000
Japan	147,750	55,961,000
S. Sakhalin	14,700	106,000
Taiwan, etc.	13,400	3,654,000
Chosen	84,250	17,284,000
Dairen, etc.	1,200	601,000
Russia in Asia	6,721,500	41,037,000
Siberia	4,162,000	9,349,000
Far East. Rep.	645,000	1,812,000
Kirghiz in Asia	780,000	4,546,000
Turkestan	570,000	7,202,000
Khiva	23,200	519,000
Bokhara	79,200	3,000,000
Azerbaijan	34,000	2,097,000
Georgia	26,000	2,372,000
Armenia	15,000	1,214,000
Russia proper, etc.	191,500	8,926,000
Lake Aral and Caspian Sea	195,600	
Arctic islands	14,900	

AFRICA

Egypt	400,000	13,387,000
Libia	542,000	525,000
Tunis	64,600	2,094,000
Algeria	343,600	5,801,000
Morocco	176,000	5,000,000
Fr. Morocco	154,570	4,340,000
Sp. Morocco	21,200	600,000
Tangier (Int.)	230	60,000
Sahara, remain- ing part	1,944,000	695,000
Rio de Oro, etc.	82,100	224,000
Fr. West Africa	704,000	12,284,000
Gambia	3,700	248,000
Port. Guinea	13,100	289,000
Sierra Leone	26,900	1,403,000
Liberia	36,800	1,500,000

AFRICA (continued)

	SQ. MILES	POPULATION
Gold Coast, etc..	88,800	2,430,000
Nigeria, etc....	394,000	17,300,000
Anglo-Eg. Sudan	1,014,400	3,400,000
Abyssinia.....	312,000	8,000,000
Eritrea.....	42,500	450,000
French Somali..	6,000	208,000
British Somali..	59,800	300,000
Italian Somali..	190,000	700,000
Uganda.....	111,000	3,072,000
Kenya.....	247,000	2,630,000
Zanzibar.....	1,000	197,000
Tanganyika Ter.	384,200	4,000,000
Belgian Congo, etc.	947,200	15,400,000
Fr. Equatorial Af.	680,600	10,000,000
Fr. Cameroon...	160,000	1,500,000
Angola, etc....	490,800	4,120,000
Mozambique....	295,800	3,120,000
Union of S. Af..	792,340	6,926,000
C. of Gd. Hope.	277,000	2,781,000
Natal.....	34,710	1,194,000
Or. Free State..	48,340	628,000
Transvaal.....	114,290	2,086,000
S. W. Africa..	318,000	237,000
Rhodesia.....	408,500	1,735,000
Other Brit. S. Af.	313,900	1,989,000
Madagascar....	228,600	3,545,000
Other islands....	8,730	1,800,000

AUSTRALIA, ETC.

Com. of Australia	2,972,866	5,437,000
Victoria.....	87,884	1,532,000
New S. Wales...	310,660	2,100,000
Queensland....	668,497	758,000
South Australia	380,070	495,000
Western Austr..	975,920	332,000
Tasmania.....	26,215	214,000
Northern Ter...	523,620	4,000
New Zealand....	104,663	1,221,000
New Guinea Gr.	311,000	1,000,000
Bismarck Arch...	18,190	188,000
Solomon Islands	16,950	200,000
New Caledonia..	7,650	51,000
New Hebrides...	5,100	60,000
Fiji Islands....	8,050	140,000
Samoa Islands..	1,076	45,000
Hawaiian Is....	6,449	256,000
Other Pacific Is..	5,385	160,000

2. LAKES

	AREA, SQ. MILES	ALTITUDE, FEET	DEPTH, FEET
Caspian.....	169,400 ±	—85 ±	3,600 ±
Superior.....	31,200	603	1,008
Victoria.....	27,000 ±	3,720	270
Aral.....	26,200 ±	155 ±	220 ±
Huron.....	23,200	580	800
Michigan.....	22,400	581	870
Baikal.....	13,200	1,680	4,900
Tanganyika..	12,700	2,600	2,000
Great Bear L.	11,200	200	270
Nyasa.....	11,000	1,650	2,316
Chad.....	10,000 +	850 ±	24 ±
Erie.....	10,000	573	200
Winnipeg....	8,550	710	70
Balkash.....	8,400	780 ±	135 ±
Ontario.....	7,260	247	738
Ladoga.....	7,000	55	730
Titicaca.....	4,000	13,860	984
Nicaragua....	2,970	135	260
Great Salt L.	1,750 ±	4,218 ±	40 ±
Dead Sea...	350 ±	—1,292 ±	1,280 ±

3. RACES OF MANKIND

Caucasian, or white.....	860,000,000
Mongolian, or yellow.....	650,000,000
Negro, or black.....	155,000,000
Indian, or red.....	30,000,000

4. RIVERS AND RIVER BASINS

RIVER	AREA OF BASIN, SQ. MILES	LONGEST STREAM, MILES	NAVIGABLE, MILES
Amazon.....	2,320,000	3,500	2,686
Amur.....	780,000	2,700	2,400
Colorado.....	230,000	1,000	500
Columbia.....	290,000	1,400	200
Congo.....	1,500,000	2,800	1,100
Danube.....	320,000	1,800	1,700
Dnieper.....	197,000	1,300	1,200
Elbe.....	55,340	612	525
Euphrates....	490,000	2,000	550
Ganges.....	600,000	1,800	1,300
Brahmaputra	390,000	2,800	800
Hwang.....	360,000	1,900	400
Indus.....	180,000	1,200	900
Irrawaddy....	900,000	2,800	2,500
Lena.....	46,755	543	Little
Loire.....	680,000	2,100	1,800
Mackenzie....	90,000	1,100	600
Magdalena....	280,000	2,600	1,200
Mekong.....	1,250,000	4,200	2,000
Mississippi..	350,000	1,100	2,400
Missouri.....	470,000	1,900	230
Murray.....	1,000,000	2,600	2,250
Nelson.....	1,300,000	3,700	2,900
Saskatchewan..	1,100,000	3,000	2,000
Niger.....	270,000	1,200	40
Nile.....	425,000	1,500	870
Ob.....	1,150,000	2,500	1,600
Orange.....	27,000	460	337
Orinoco.....	63,265	709	550
Plata.....	38,180	447	200
Po.....	230,000	1,800	460
Rhine.....	565,000	2,100	2,000
Rhone.....	210,000	1,800	1,100
Rio Grande....	590,000	2,300	2,100
St. Lawrence..	690,000	3,100	1,050
São Francisco.	1,500,000	3,000	1,840
Volga.....	380,000	1,865	1,600
Yangtze.....	580,000	2,200	1,620
Yenisei.....			
Yukon.....			
Zambezi.....			

5. GREAT SHIP CANALS

CANAL AND YEAR WHEN OPENED	CONNECTIONS	LENGTH, MILES	DEPTH, FEET
Welland.....	Lake Erie	26 $\frac{3}{4}$	14
1833.....	Lake Ontario		
Soo (U. S.)..	Lake Superior	1 $\frac{1}{2}$	25
1855.....	Lake Huron		
Suez, 1869..	Mediterranean	103	35
	Sea, Red Sea		
Corinth.....	G. of Corinth	4	26
1893.....	Aegean Sea		
Manches- ter, 1894..	Liverpool	35 $\frac{1}{2}$	28
Kiel, 1895..	Manchester		
	North Sea	61	36
	Baltic Sea		
Soo (Cana- dian), 1895	Lake Superior	1 $\frac{1}{2}$	22
	Lake Huron		
Cape Cod, 1914	Cape Cod Bay	8	25
	Buzzards Bay		
Panama, 1915	Caribbean Sea	50	41
	Pacific Ocean		

6. THE UNITED STATES

	SQ. MILES	POPULATION, 1920
Alabama.....	51,998	2,348,174
Arizona.....	113,956	334,162
Arkansas.....	53,335	1,752,204
California.....	158,297	3,426,861
Colorado.....	103,948	939,629
Connecticut....	4,965	1,380,631
Delaware.....	2,370	223,003
Dist. of Columbia	70	437,571
Florida.....	58,666	968,470
Georgia.....	59,265	2,895,832
Idaho.....	83,888	431,866
Illinois.....	56,665	6,485,280
Indiana.....	36,354	2,930,390
Iowa.....	56,147	2,404,021
Kansas.....	82,158	1,769,257
Kentucky.....	40,598	2,416,630
Louisiana.....	48,506	1,798,509
Maine.....	33,040	768,014
Maryland.....	12,327	1,449,661
Massachusetts...	8,266	3,852,356
Michigan.....	57,980	3,668,412
Minnesota.....	84,682	2,387,125
Mississippi....	46,865	1,790,618
Missouri.....	69,420	3,404,055
Montana.....	146,997	548,889
Nebraska.....	77,520	1,296,372
Nevada.....	110,690	77,407
New Hampshire...	9,341	443,083
New Jersey.....	8,224	3,155,900
New Mexico....	122,634	360,350
New York.....	49,204	10,385,227
North Carolina...	54,426	2,559,123
North Dakota...	70,837	646,872
Ohio.....	41,040	5,759,394
Oklahoma.....	70,057	2,028,283
Oregon.....	96,699	783,389
Pennsylvania....	45,126	8,720,017
Rhode Island....	1,248	604,397
South Carolina...	30,989	1,683,724
South Dakota....	77,615	636,547
Tennessee.....	42,022	2,337,885
Texas.....	265,896	4,663,228
Utah.....	84,990	449,396
Vermont.....	9,564	352,428
Virginia.....	42,627	2,309,187
Washington.....	69,127	1,356,621
West Virginia...	24,170	1,463,701
Wisconsin.....	56,066	2,632,067
Wyoming.....	97,914	194,402
Part of the Great Lakes.....	61,730	

Main Body..... 3,088,519 105,710,620

Outlying Territory, etc.

Alaska Territory..	590,884	55,036
Hawaii Territory..	6,449	255,912
Porto Rico.....	3,435	1,299,809
Virgin Islands of the United States ('17)....	132	26,051
Philippine Is. ('18)	115,026	10,350,640
Tutuila, etc.....	77	8,056
Guam.....	210	13,275
Panama Canal Zone.....	527	22,858
Soldiers and sailors stationed abroad		117,238
Total Outlying....	716,740	12,148,875
Grand Total.....	3,805,259	117,859,495

7. COMMERCIAL STATISTICS OF THE

COUNTRIES	CHIEF PRODUCTS	CHIEF EXPORTS	TOTAL VALUE OF EXPORTS
Alaska . . .	Salmon, sealskins, copper, gold, and silver	Fish, sealskins, copper, gold	\$38,362,000
Algeria . . .	Wine, cereals, animals, fruits, cork bark	Wine, wheat, figs, sheep, cork	231,338,000
Argentina . . .	Corn, wheat, livestock, wine, flax	Corn, wheat, meat, flaxseed	1,020,841,000
Australia . . .	Wool, cereals, animal products, minerals	Wool, wheat, meat, butter, minerals, hides	545,084,000
Austria . . .	Cereals, timber, minerals	Chemicals, ores, sugar beets, timber	"
Belgium . . .	Manufactures of cotton, wool, iron, and steel	Textiles, manufactures of iron and steel	531,639,000
Bolivia . . .	Silver, tin, rubber, coca, coffee	Silver, tin, rubber	45,307,000
Brazil . . .	Coffee, rubber, cotton, cacao, tobacco, cattle	Coffee, sugar, leather, hides, meat, cotton	394,520,000
Bulgaria . . .	Cereals, wine, tobacco	Tobacco, cereals, hides, attar of roses	27,783,000
Canada . . .	Agricultural products, manufactures of iron	Wheat and flour, wood and wood pulp	1,057,333,000
Ceylon . . .	Rice, tea, coconuts, rubber	Rubber, tea, coconuts, oil, graphite	124,708,000
Chile . . .	Nitrate, copper, silver	Nitrate, copper, wool	282,675,000
China . . .	Cereals, silk, cotton, soya beans, minerals	Silk and silk goods, beans, tin, antimony	666,207,000
Colombia . . .	Coffee, bananas, minerals, cattle	Coffee, hides, platinum, bananas	70,372,000
Costa Rica . . .	Coffee, bananas, gold, silver	Coffee, bananas, gold, silver, sugar	9,606,000
Cuba . . .	Tobacco, sugar, fruits	Sugar, tobacco, fruits	855,138,000
Czechoslovakia . . .	Sugar beet, potatoes, coal, iron, fruit	Glass, sugar, fruit, iron, timber, coal	428,900,000
Denmark . . .	Cereals, potatoes, fish, dairy products	Dairy products, animals, cereals	250,990,000
Dominican Rep. . .	Sugar, cacao, tobacco, fruit	Sugar, cacao, limes	58,399,000
Dutch E. Indies . . .	Rice, tea, rubber, tobacco, tin, coconuts	Tobacco, rubber, tea, copra, tin	838,260,000
Ecuador . . .	Cacao, coffee, ivory, nuts	Cacao, ivory nuts, coffee, Panama hats	20,314,000
Estonia . . .	Cereals, potatoes, flax, timber, animals	Flax, timber, potatoes, meat	*
Egypt . . .	Cotton, cereals, vegetables	Cotton, cereals	153,183,000
Finland . . .	Cereals, timber, wood pulp, animal products	Timber, wood pulp, paper, meats	96,126,000
France . . .	Textiles, wine, cereals, potatoes	Textiles, clothing, automobiles, chemicals	1,606,870,000
Germany . . .	Coal, iron, potatoes, cereals, textiles, sugar	Textiles, fish, ironwork	1,206,902,000
Great Britain . . .	Textiles, coal, iron and steel goods	Textiles, yarns, coal, iron and steel goods	2,706,638,000
Greece . . .	Currants, olives, cereals, tobacco	Currants, olives, tobacco	309,088,000
Guatemala . . .	Coffee, sugar, bananas, animals, dye woods	Coffee, sugar, bananas, timber, hides	18,103,000
Haiti . . .	Coffee, cotton, cacao, logwood	Coffee, cotton, cacao	18,990,000
Hawaii . . .	Sugar, pineapples, coffee, honey	Sugar, pineapples, coffee, honey	73,020,000
Honduras . . .	Bananas, sugar, coconuts	Bananas, sugar, coconuts	5,429,000
Hungary . . .	Cereals, fruit, animals, coal	Flour, animal products	*
India . . .	Rice, wheat, tea, cotton, jute, cattle	Jute, etc., cotton, rice, tea, oil seeds	787,879,000
Irish Free State . . .	Potatoes, turnips, animals	Horses, meats	*
Italy . . .	Raw silk, cereals, fruit, wine	Cotton goods, silk and silk manufactures	887,213,000
Japan . . .	Cereals, raw silk, cotton and silk goods, coal	Silk, cotton and silk goods, cotton yarn	999,600,000
Latvia . . .	Cereals, potatoes, timber, flax	Flax, timber	9,679,000
Lithuania . . .	Cereals, potatoes, timber, animals	Animal products, timber, flax, hides, wool	*
Mexico . . .	Silver, gold, copper, petroleum, cotton, henequen	Metals, petroleum, cotton, henequen	202,664,000
Morocco . . .	Cereals, flaxseed, nuts	Beans, eggs, flaxseed, barley, almonds	33,662,000
Netherlands . . .	Cereals, dairy products, potatoes, sugar beets	Dairy products, potatoes, bulbs	460,829,000
Newfoundland . . .	Fish, iron and copper ore, wood pulp, paper	Fish, pulp and paper, iron ore	19,459,000
New Zealand . . .	Wool, meat, dairy products, metals	Wool, meat, dairy products, hides, skins	164,756,000
Nicaragua . . .	Coffee, sugar, fruit, timber	Coffee, sugar, timber, bananas	10,787,000
Norway . . .	Fish, timber, wood pulp, animal products	Fish, timber, paper, animal products	181,697,000
Panama . . .	Fruits, coconuts, balata, cattle, gum	Bananas, coconuts, balata, hides, gum	3,552,000
Paraguay . . .	Cattle, maté, tobacco, quebracho extract	Hides, maté, meat, tobacco, quebracho ext.	6,839,000
Persia . . .	Cereals, fruits, petroleum, rugs, cotton	Fruits, petroleum, cotton, rugs	58,791,000
Peru . . .	Sugar, cotton, coffee, copper, petroleum	Sugar, cotton, copper, petroleum	170,519,000
Philippines . . .	Rice, manila hemp, coconuts, sugar cane	Manila hemp, sugar, copra, cigars	88,115,000
Poland . . .	Cereals, potatoes, sugar beet, salt, coal	Cereals, sugar, textiles, salt	*
Porto Rico . . .	Sugar, tobacco, fruit, coffee, sea island cotton	Sugar, tobacco, coffee, cigars, cigarettes	78,742,000
Portugal . . .	Cereals, fruits, animals, wine, cork	Rawhides, sardines, cork, wine	35,873,000
Roumania . . .	Cereals, livestock, petroleum, metals	Petroleum, oil seeds, grain, wood	8,311,000
Russia, etc. . .	Potatoes, flax, cereals, animals	Timber, flax, paper, tobacco, wheat	152,696,000
Salvador . . .	Coffee, rubber, sugar, tobacco	Coffee, sugar, indigo	18,000,000
Siam . . .	Rice, tin, teakwood	Rice, tin, teakwood	25,042,000
Spain . . .	Cereals, wine, iron and coal, fruit	Wine, fruit, olive oil, metals	239,414,000
Sweden . . .	Iron ore, timber, cereals	Metal goods, wood pulp, paper, timber	402,464,000
Switzerland . . .	Textiles, dairy products, salt, clocks, watches	Dairy products, embroideries, watches	371,399,000
Turkey . . .	Tobacco, cereals, fruit, wool, carpets	Fruit, gum, wool, carpets	48,158,000
Union of So. Afr. . .	Animals, animal products, gold, diamonds	Gold, wool, diamonds	154,823,000
United States . . .	Cereals, cotton, minerals, animals, food products, textiles, iron and steel goods	Cotton, iron and steel goods, breadstuffs, meat and dairy products	3,888,073,000
Uruguay . . .	Animal products, cereals	Hides, wool, live animals	48,061,000
Venezuela . . .	Coffee, cacao, animal products, rubber	Coffee, cocoa, hides, balata and rubber	13,652,000
Yugoslavia . . .	Cereals, fruits, livestock, timber	Corn, wheat, timber, prunes, animal prod.	*

* No reliable statistics available.

PRINCIPAL COUNTRIES OF THE WORLD

COUNTRIES	CHIEF IMPORTS	TOTAL VALUE OF IMPORTS	RAILROAD MILEAGE	CHIEF SEAPORTS
Alaska . . .	Food, clothing, machinery	\$20,209,000	818	
Algeria . . .	Clothing, automobiles, cotton, sugar, petroleum	185,739,000	2,203	Algiers
Argentina . .	Textiles, foodstuffs, iron, chemicals, oils, glassware	649,333,000	22,587	Buenos Aires
Australia . .	Textiles, clothing, machinery, metal manufactures	390,711,000	25,657	Sydney, Melbourne
Austria . . .	Cereals, flour, textiles	*	2,570	
Belgium . . .	Wool, wheat, cotton, machinery, iron, and steel	748,440,000	5,451	Antwerp
Bolivia . . .	Textiles, foodstuffs, hardware	19,544,000	1,354	
Brazil	Foodstuffs, coal, machinery, manufactured goods	470,664,000	18,662	Santos, Rio de Janeiro
Bulgaria . . .	Textiles, metals, oils, skins	37,436,000	1,824	Varna
Canada	Manufactures of iron and steel, textiles, coal, sugar	1,102,675,000	39,058	Montreal, Vancouver
Ceylon	Rice, cotton goods, coal and coke, manures	127,356,000	731	Colombo
Chile	Textiles, metals and machinery, chemical products	160,807,000	5,102	Valparaíso, Antofagasta
China	Cotton goods, metals, cigarettes, coal, fish	937,568,000	6,836	Shanghai, Canton
Colombia . . .	Cotton goods, metals, foodstuffs, drugs	34,225,000	688	Barranquilla
Costa Rica . .	Flour, cotton goods, cattle, bags, drugs	14,389,000	501	Limon
Cuba	Foodstuffs, textiles, machinery	434,189,000	3,200	Havana
Czechoslovakia	Cotton and woolen goods, cereals	363,400,000	8,303	
Denmark . . .	Coal, metals and hardware, textiles	511,706,000	2,668	Copenhagen
Dominican Rep.	Cotton goods, foodstuffs, iron and steel goods	46,526,000	408	Santo Domingo
Dutch E. Ind.	Cotton goods, machinery	249,780,000	1,969	Batavia
Ecuador	Textiles, foodstuffs, machinery, clothing	11,248,000	365	Guayaquil
Estonia	Salt, coal, fertilizers, sugar	*	1,120	Reval
Egypt	Textiles and yarns, metals and metal manufactures	222,512,000	3,065	Alexandria
Finland	Metals and machinery, cereals, coffee, tea, sugar	120,678,000	2,611	Helsingfors
France	Coal and coke, cereals, wool, machinery	1,755,633,000	31,958	Marseille, Havre
Germany	Cotton, wool, copper, skins and hides	1,708,722,000	37,627	Hamburg, Bremen
Great Britain	Cotton, wool, cereals, meats, petroleum	4,182,713,000	21,057	Liverpool, London
Greece	Yarns and textiles, minerals, cereals	235,650,000	1,460	Piræus, Salonica
Guatemala . . .	Cotton goods, iron and steel goods, foodstuffs	18,344,000	439	Puerto Barrios
Haiti	Cotton goods, sacks, machinery	27,398,000	114	Port au Prince
Hawaii	Foodstuffs, clothing, machinery	73,976,000	969	Honolulu
Honduras	Cotton goods, foodstuffs, machinery	16,723,000	360	Puerto Cortes
Hungary	Textiles, clothing, machinery	*	4,493	
India	Cotton goods, metals and ores, machinery, sugar	1,109,569,000	36,735	Caleutta, Bombay
Irish Free St.	Textiles, machinery	*	2,677	Dublin
Italy	Wheat, cotton, coal and coke, wool and woollens	1,803,366,000	11,891	Genoa, Naples, Trieste
Japan	Cotton, machinery, iron bars and plates, sugar	1,209,511,000	8,166	Yokohama, Kobe
Latvia	Textiles, foodstuffs, machinery, coal	18,550,000	1,829	Riga
Lithuania . . .	Manufactured goods, fertilizers, agr. machinery	*	1,550	Memel
Mexico	Textiles, machinery, hardware	178,239,000	15,840	Vera Cruz, Tampico
Morocco	Sugar, cotton goods, machinery	77,994,000	704	Tangier
Netherlands . .	Textiles, cereals, flour, iron, steel, wood and coal	753,767,000	2,144	Rotterdam, Amsterdam
Newfoundland	Flour, textiles, hardware, coal, pork, machinery	18,192,000	951	St. Johns
New Zealand	Clothing, textiles, iron and steel goods, motor cars	227,270,000	3,134	Auckland, Wellington
Nicaragua . . .	Cotton goods, iron and steel, flour, chemicals	13,864,000	209	Corinto
Norway	Foodstuffs, textiles, minerals, machinery	634,981,000	2,019	Christiania, Bergen
Panama	Cotton goods, foodstuffs, machinery	17,161,000	301	Colon
Paraguay	Textiles, provisions, hardware	5,908,000	266	
Persia	Cotton goods, sugar, tea, minerals	98,300,000	97	Bushire
Peru	Coal, wheat, bags, lumber	88,670,000	1,889	Callao
Philippines . .	Cotton goods, iron and steel goods, rice, meat	115,839,000	778	Manila
Poland	Foodstuffs, textiles, machinery	*	9,849	Danzig (free city)
Porto Rico . . .	Cotton goods, machinery	68,354,000	339	San Juan
Portugal	Coal, codfish, rubber, cotton, rice	89,313,000	2,047	Lisbon, Oporto
Roumania	Textiles, clothing, machinery	286,636,000	2,382	Galatz
Russia, etc. . .	Agricultural machinery, drugs, cloth, foodstuffs	432,654,000	29,996	Petrograd, Vladivostok
Salvador	Cotton goods, hardware, flour, drugs, chemicals	13,541,000	241	Acajutla
Siam	Cotton goods, metal manufactures, tobacco	55,677,000	1,333	Bangkok
Spain	Machinery, vehicles, cotton	141,256,000	9,455	Barcelona, Valencia
Sweden	Coal, textiles, fibers, machinery	647,228,000	9,416	Göteborg, Stockholm
Switzerland . .	Foodstuffs, textiles, metals	398,498,000	3,250	
Turkey	Sugar, petroleum, cotton, woolen and iron goods	39,580,000	3,842	Constantinople
Un. of So. Af.	Textiles, foodstuffs, machinery	342,261,000	10,049	Cape Town
United States	Sugar, silk, hides and skins, coffee, rubber, wool	2,186,995,000	263,707	New York, New Orleans Philadelphia
Uruguay	Textiles, machinery, foodstuffs	65,218,000	1,621	Montevideo
Venezuela . . .	Textiles, machinery, foodstuffs	24,464,000	535	La Guaira
Yugoslavia . . .	Chemicals, metals, machinery	*	3,390	Fiume (free city)

* No reliable statistics available.

8. POPULATION OF CITIES IN THE UNITED STATES AND ITS DEPENDENCIES

Cities having more than 25,000 People, together with Others Mentioned in the Text.

	Pop. 1920	Pop. 1910		Pop. 1920	Pop. 1910		Pop. 1920	Pop. 1910
Akron, Ohio	208,435	69,067	Columbus, Ga.	31,125	20,554	Jackson, Mich.	48,374	31,433
Alameda, Calif.	28,806	23,383	Columbus, Ohio.	237,031	181,511	Jackson, Miss.	22,817	21,262
Albany, N.Y.	113,344	100,253	Concord, N.H.	22,167	21,497	Jacksonville, Fla. .	91,558	57,699
Albuquerque, N.Mex. .	15,157	11,020	Council Bluffs, Iowa	36,162	29,292	Jamestown, N.Y.	38,917	31,297
Allentown, Pa.	73,502	51,913	Covington, Ky.	57,121	53,270	Jefferson City, Mo. .	14,490	11,850
Altoona, Pa.	60,331	52,127	Cranston, R.I.	29,407	21,107	Jersey City, N.J. ...	298,103	267,779
Amsterdam, N.Y. . .	33,524	31,267	Cumberland, Md.	29,837	21,839	Johnstown, N.Y. ...	10,908	10,447
Anaconda, Mont.	11,668	10,134	Dallas, Tex.	158,976	92,104	Johnstown, Pa.	67,327	55,482
Anderson, Ind.	29,767	22,476	Danville, Ill.	33,776	27,871	Joliet, Ill.	38,442	34,670
Annapolis, Md.	11,214	8,609	Danville, Va.	21,539	19,020	Joplin, Mo.	29,902	32,073
Ann Arbor, Mich.	19,516	14,817	Davenport, Iowa ...	56,727	43,028	Kalamazoo, Mich. ..	48,487	39,437
Asheville, N.C.	28,504	18,762	Dayton, Ohio.	152,559	116,577	Kansas City, Kans. .	101,177	82,331
Astoria, Oregon	14,027	9,599	Decatur, Ill.	43,818	31,140	Kansas City, Mo.	324,410	248,381
Atlanta, Ga.	200,616	154,839	Denver, Colo.	256,491	213,381	Kearney, N. J.	26,724	18,659
Atlantic City, N.J. .	50,707	46,150	Des Moines, Iowa ...	126,468	86,368	Kenosha, Wis.	40,472	21,371
Attleboro, Mass.	19,731	16,215	Detroit, Mich.	993,678	465,766	Key West, Fla.	18,749	19,945
Auburn, N.Y.	36,192	34,668	Dover, Del.	4,042	3,720	Kingston, N.Y.	26,688	25,908
Augusta, Ga.	52,548	41,040	Dubuque, Iowa	39,141	38,494	Knoxville, Tenn. ...	77,818	36,346
Augusta, Maine	14,114	13,211	Duluth, Minn.	98,917	78,466	Kokomo, Ind.	30,067	17,010
Aurora, Ill.	36,397	29,807	Durham, N.C.	21,719	18,241	Lackawanna, N.Y. ...	17,918	14,549
Austin, Tex.	34,876	29,860	East Chicago, Ind. .	35,967	19,098	La Crosse, Wis.	30,421	30,417
Baltimore, Md.	733,826	558,485	East Cleveland, Ohio	27,292	9,179	Lakewood, Ohio.	41,732	15,181
Bangor, Maine	25,978	24,803	East Liverpool, Ohio	21,411	20,387	Lancaster, Pa.	53,150	47,227
Baton Rouge, La. ...	21,782	14,897	Easton, Pa.	33,813	28,523	Lansing, Mich.	57,327	31,229
Battle Creek, Mich. .	36,164	25,267	East Orange, N.J. .	50,710	34,371	Lawrence, Mass.	94,270	85,892
Bay City, Mich.	47,554	45,166	East St. Louis, Ill. .	66,767	58,547	Lewiston, Maine ...	31,791	26,247
Bayonne, N.J.	76,754	55,545	Elgin, Ill.	27,454	25,976	Lexington, Ky.	41,534	35,099
Beaumont, Tex.	40,422	20,640	Elizabeth, N.J.	95,783	73,409	Lima, Ohio	41,326	30,508
Bellingham, Wash. .	25,585	24,298	Elmira, N.Y.	45,393	37,176	Lincoln, Nebr.	54,948	43,973
Berkeley, Calif.	56,036	40,434	El Paso, Tex.	77,560	39,279	Little Rock, Ark. ...	65,142	45,941
Bethlehem, Pa.	50,358	12,837	Erie, Pa.	93,372	66,525	Long Beach, Calif. .	55,593	17,809
Billings, Mont.	15,100	10,031	Evanston, Ill.	37,234	24,978	Lorain, Ohio.	37,295	28,883
Binghamton, N.Y. ...	66,800	48,443	Evansville, Ind.	85,264	69,647	Los Angeles, Calif. .	576,673	319,198
Birmingham, Ala. .	178,806	132,685	Everett, Mass.	40,120	33,484	Louisville, Ky.	234,891	223,928
Bisbee, Ariz.	9,205	9,019	Everett, Wash.	27,644	24,814	Lowell, Mass.	112,759	106,294
Bismarck, N. Dak. ...	7,122	5,443	Fall River, Mass. ...	120,485	119,295	Lynchburg, Va.	30,070	29,494
Bloomington, Ill.	28,725	25,768	Fargo, N. Dak.	21,961	14,331	Lynn, Mass.	99,148	89,336
Boise, Idaho	21,393	17,358	Fitchburg, Mass.	41,029	37,826	McKeesport, Pa.	46,781	42,694
Boston, Mass.	748,060	670,585	Flint, Mich.	91,599	38,550	Macon, Ga.	52,995	40,665
Braddock, Pa.	20,879	19,357	Fort Smith, Ark. ...	28,870	23,975	Madison, Wis.	38,378	25,531
Bridgeport, Conn. .	143,555	102,054	Fort Wayne, Ind. ...	86,549	63,933	Malden, Mass.	49,103	44,404
Brockton, Mass.	66,254	56,878	Fort Worth, Tex. ...	106,482	73,312	Manchester, N.H. ...	78,384	70,063
Brookline, Mass.	37,748	27,792	Frankfort, Ky.	9,805	10,465	Manila, P. I. ('19, '03)	283,613	219,928
Buffalo, N.Y.	506,775	423,715	Fresno, Calif.	45,086	24,892	Mansfield, Ohio	27,824	20,768
Burlington, Iowa	24,057	24,324	Galveston, Tex.	44,255	36,981	Marion, Ohio	27,891	18,232
Burlington, Vt.	22,779	20,468	Gary, Ind.	55,378	16,802	Medford, Mass.	39,038	23,150
Butte, Mont.	41,611	39,165	Glens Falls, N.Y. ...	16,638	15,243	Memphis, Tenn.	162,351	131,105
Cambridge, Mass.	109,694	104,839	Gloucester, Mass. ...	22,947	24,398	Meriden, Conn.	29,867	27,265
Camden, N.J.	116,309	94,538	Gloversville, N.Y. .	22,075	20,642	Meridian, Miss.	23,399	23,285
Canton, Ohio	87,091	50,217	Grand Rapids, Mich. .	137,634	112,571	Miami, Fla.	29,571	5,471
Carson City, Nev. .	1,685	2,466	Great Falls, Mont. .	24,121	13,948	Milwaukee, Wis.	457,147	373,857
Casper, Wyo.	11,447	2,639	Green Bay, Wis. ...	31,017	25,236	Minneapolis, Minn. .	380,582	301,408
Cedar Rapids, Iowa .	45,566	32,811	Hagerstown, Md. ...	28,064	16,507	Missoula, Mont.	12,668	12,869
Charleston, S.C.	67,957	58,833	Hamilton, Ohio	39,675	35,279	Mobile, Ala.	60,777	51,521
Charleston, W. Va. .	39,608	22,996	Hammond, Ind.	36,004	20,925	Moline, Ill.	30,734	24,199
Charlotte, N.C.	46,338	34,014	Hamtramck, Mich. ...	48,615	3,559	Montclair, N.J.	28,810	21,550
Chattanooga, Tenn. .	57,895	44,604	Harrisburg, Pa.	75,917	64,186	Montgomery, Ala. ...	43,464	38,136
Chelsea, Mass.	43,184	32,452	Hartford, Conn.	138,036	98,915	Montpelier, Vt.	7,125	7,856
Chester, Pa.	58,030	38,537	Haverhill, Mass.	53,884	44,115	Mount Vernon, N.Y. .	42,726	30,919
Cheyenne, Wyo.	13,829	11,320	Hazleton, Pa.	32,277	25,452	Muncie, Ind.	36,524	24,005
Chicago, Ill.	2,701,705	2,185,283	Helena, Mont.	12,037	12,515	Muskegon, Mich. ...	36,570	24,062
Chicopee, Mass.	36,214	25,401	Highland Park, Mich.	46,499	4,120	Muskogee, Okla.	30,277	25,278
Cicero, Ill.	44,995	14,557	Hoboken, N.J.	68,166	70,324	Nashua, N. H.	28,379	26,005
Cincinnati, Ohio	401,247	363,591	Holyoke, Mass.	60,203	57,730	Nashville, Tenn. ...	118,342	110,364
Clarksburg, W. Va. .	27,869	9,201	Homestead, Pa.	20,452	18,713	Natchez, Miss.	12,608	11,791
Cleveland, Ohio	796,841	560,663	Honolulu, Hawaii ...	83,327	52,183	Newark, N.J.	414,524	347,469
Clifton, N. J.	26,470	11,869	Houston, Tex.	138,276	78,800	Newark, Ohio.	26,718	25,404
Clinton, Iowa	24,151	25,577	Huntington, W. Va. .	50,177	31,161	New Bedford, Mass. .	121,217	96,652
Cohoes, N.Y.	22,987	24,709	Indianapolis, Ind. ...	314,194	233,650	New Britain, Conn. .	59,316	43,916
Colorado Spr's, Colo.	30,105	29,078	Irvington, N.J.	25,480	11,877	New Brunswick, N.J.	32,779	23,388
Columbia, S.C.	37,524	26,319	Ithaca, N.Y.	17,004	14,802	Newburgh, N.Y.	30,366	27,805

POPULATION OF CITIES

417

	POP. 1920	POP. 1910		POP. 1920	POP. 1910		POP. 1920	POP. 1910
New Castle, Pa.	44,938	36,280	Portsmouth, N. H. ...	13,569	11,269	Spartanburg, S. C.	22,638	17,517
New Haven, Conn. ...	162,537	133,605	Portsmouth, Ohio. ...	33,011	23,481	Spokane, Wash.	104,437	104,402
New London, Conn. ...	25,688	19,659	Portsmouth, Va.	54,387	33,190	Springfield, Ill.	59,183	51,678
New Orleans, La.	387,219	339,075	Pottsville, Pa.	21,876	20,236	Springfield, Mass.	129,614	88,926
Newport, Ky.	29,317	30,309	Poughkeepsie, N. Y. ...	35,000	27,936	Springfield, Mo.	39,631	35,201
Newport, R. I.	30,255	27,149	Providence, R. I.	237,595	224,326	Springfield, Ohio.	60,840	46,921
Newport News, Va. ...	35,596	20,205	Pueblo, Colo.	43,050	41,747	Stamford, Conn.	35,096	25,138
New Rochelle, N. Y. ...	36,213	28,867	Quincy, Ill.	35,978	36,587	Steubenville, Ohio. ...	28,508	22,391
Newton, Mass.	46,054	39,806	Quincy, Mass.	47,876	32,642	Stockton, Calif.	40,296	23,253
New York, N. Y.	5,620,048	4,766,883	Racine, Wis.	58,593	38,002	Superior, Wis.	39,671	40,384
Manhattan Boro. ...	2,284,103	2,331,542	Raleigh, N. C.	24,418	19,218	Syracuse, N. Y.	171,717	137,249
Brooklyn " " ...	2,018,356	1,634,351	Reading, Pa.	107,784	96,071	Tacoma, Wash.	96,965	83,743
Bronx " " ...	732,016	430,980	Reno, Nev.	12,016	10,867	Tallahassee, Fla.	5,637	5,018
Queens " " ...	469,042	284,041	Revere, Mass.	28,823	18,219	Tampa, Fla.	51,608	37,782
Richmond " " ...	116,531	85,969	Richmond, Ind.	26,765	22,324	Taunton, Mass.	37,137	34,259
Niagara Falls, N. Y. ...	50,760	30,445	Richmond, Va.	171,667	127,628	Terre Haute, Ind.	66,083	58,157
Norfolk, Va.	115,777	67,452	Riverside, Calif.	19,341	15,212	Toledo, Ohio.	243,164	168,497
Norristown, Pa.	32,319	27,875	Roanoke, Va.	50,842	34,874	Topeka, Kans.	50,022	43,684
Norwalk, Conn.	27,743	24,211	Reno, N. Y.	295,750	218,149	Trenton, N. J.	119,289	96,815
Oakland, Calif.	216,261	150,174	Rockford, Ill.	65,651	45,401	Trinidad, Colo.	10,906	10,204
Oak Park, Ill.	39,858	19,444	Rock Island, Ill.	35,177	24,335	Troy, N. Y.	72,013	76,813
Ogden, Utah.	32,804	25,580	Rome, N. Y.	26,341	20,497	Tucson, Ariz.	20,292	13,193
Ogdensburg, N. Y.	14,609	15,933	Rutland, Vt.	14,954	13,546	Tulsa, Okla.	72,075	18,182
Oklahoma City, Okla. ...	91,295	64,205	Sacramento, Calif. ...	65,908	44,696	Utica, N. Y.	94,156	74,419
Olympia, Wash.	7,795	6,996	Saginaw, Mich.	61,903	50,510	Vicksburg, Miss.	18,072	20,814
Omaha, Nebr.	191,601	124,096	St. Augustine, Fla.	6,192	5,494	Waco, Tex.	38,500	26,425
Orange, N. J.	33,268	29,630	St. Joseph, Mo.	77,939	77,403	Walla Walla, Wash. ...	15,503	19,364
Oshkosh, Wis.	33,162	33,062	St. Louis, Mo.	772,897	687,029	Waltham, Mass.	30,915	27,834
Oswego, N. Y.	23,626	23,368	St. Paul, Minn.	234,698	214,744	Warren, Ohio.	27,050	11,081
Paducah, Ky.	24,735	22,760	Salem, Mass.	42,529	43,697	Washington, D. C. ...	437,571	331,069
Pasadena, Calif.	45,354	30,291	Salem, Oregon.	17,679	14,094	Waterbury, Conn.	91,715	73,141
Passaic, N. J.	63,841	54,773	Salt Lake City, Utah ...	118,110	92,777	Waterloo, Iowa.	36,230	26,693
Paterson, N. J.	135,875	125,600	San Antonio, Tex.	161,379	96,614	Watertown, N. Y.	31,285	26,730
Pawtucket, R. I.	64,248	51,622	San Diego, Calif.	74,683	39,578	West Hoboken, N. J. ...	40,074	35,403
Pensacola, Fla.	31,035	22,982	San Francisco, Calif. ...	506,676	416,912	West New York, N. J. ...	29,926	13,560
Peoria, Ill.	76,121	66,950	San Jose, Calif.	39,642	28,946	Wheeling, W. Va.	56,208	41,641
Perth Amboy, N. J. ...	41,707	32,121	San Juan, P. R.	70,707	49,000	Wichita, Kans.	72,217	52,450
Petersburg, Va.	31,012	24,127	Santa Barbara, Calif. ...	19,441	11,659	Wichita Falls, Tex. ...	40,079	8,200
Philadelphia, Pa.	1,823,779	1,549,008	Santa Fe, N. Mex.	7,236	5,072	Wilkes-Barre, Pa.	73,833	67,105
Phoenix, Ariz.	29,053	11,134	Savannah, Ga.	83,252	65,064	Williamsport, Pa. ...	36,198	31,860
Pierre, S. Dak.	3,209	3,656	Schenectady, N. Y. ...	88,723	72,826	Wilmington, Del.	110,168	87,411
Pittsburgh, Pa.	588,343	533,905	Scranton, Pa.	137,783	129,867	Wilmington, N. C. ...	33,372	25,748
Pittsfield, Mass.	41,763	32,121	Seattle, Wash.	315,312	237,194	Winston-Salem, N. C. ...	48,395	22,700
Plainfield, N. J.	27,700	20,550	Sheboygan, Wis.	30,955	26,398	Woonsocket, R. I. ...	43,496	38,125
Pocatello, Idaho.	15,001	9,110	Sheridan, Wyo.	9,175	8,408	Worcester, Mass.	179,754	145,986
Ponce, P. R.	41,561	35,027	Shreveport, La.	43,874	28,015	Yakima, Wash.	18,539	14,082
Pontiac, Mich.	34,273	14,532	Sioux City, Iowa.	71,227	47,828	Yankers, N. Y.	100,176	79,803
Port Huron, Mich. ...	25,944	18,863	Sioux Falls, S. Dak. ...	25,202	14,094	York, Pa.	47,512	44,750
Portland, Maine.	69,272	58,571	Somerville, Mass.	93,091	77,236	Youngstown, Ohio. ...	132,358	79,066
Portland, Oregon. ...	258,288	207,214	South Bend, Ind.	70,983	53,684	Zanesville, Ohio.	29,569	28,026

9. POPULATION OF CITIES IN FOREIGN COUNTRIES

Cities having more than 250,000 People, together with Others Mentioned in the Text

Aberdeen, Scotland. . .	159,000	('21)	Barcelona, Spain.	710,000	('20)	Breslau, Germany.	528,000	('19)
Adelaide, Australia. . .	261,000	('21)	Barmen, Germany.	156,000	('19)	Brest, France.	74,000	('21)
Alleppe, Syria.	140,000		Barranquilla, Colombia	65,000	('21)	Brisbane, Australia. . .	210,000	('21)
Alexandria, Egypt.	445,000	('17)	Basel, Switzerland.	136,000	('20)	Bristol, England.	377,000	('21)
Algiers, Algeria.	207,000	('21)	Batavia, Java.	139,000	('20)	Brussels, Belgium.	775,000	('21)
Amiens, France.	93,000	('21)	Beirut, Syria.	80,000		Bucharest, Roumania. .	309,000	('17)
Amsterdam, Neth.	647,000	('20)	Belfast, Ireland.	425,000	('22)	Budapest, Hungary. ...	1,185,000	('21)
Antwerp, Belgium.	304,000	('21)	Belgrade, Yugoslavia. .	120,000	('19)	Buenos Aires, Argent. .	1,720,000	('22)
Archangel, Russia.	45,000	('21)	Benares, India.	198,000	('21)	Cairo, Egypt.	791,000	('17)
Arequipa, Peru.	35,000	('20)	Bergen, Norway.	91,000	('20)	Calais, France.	73,000	('21)
Astrakhan, Russia.	123,000	('21)	Berlin, Germany.	3,804,000	('19)	Calcutta, India.	1,328,000	('21)
Asuncion, Paraguay. . .	100,000	('20)	Bern, Switzerland.	105,000	('20)	Calgary, Canada.	63,000	('21)
Athens, Greece.	293,000	('20)	Bilbao, Spain.	113,000	('20)	Callao, Peru.	53,000	('20)
Auckland, New Zealand	164,000	('22)	Birmingham, England	919,000	('21)	Canton, China.	900,000	('21)
Augsburg, Germany. . .	155,000	('19)	Bogota, Colombia.	160,000	('21)	Cape Town, S. Africa. .	207,000	('21)
Bagdad, Iraq.	250,000	('20)	Bombay, India.	1,174,000	('21)	Caracas, Venezuela. ...	92,000	('20)
Bahia, Brazil.	283,000	('20)	Bordeaux, France.	267,000	('21)	Cardiff, Wales.	200,000	('21)
Baku, Azerbaijan.	263,000	('21)	Boulogne, France.	55,000	('21)	Cartagena, Spain.	97,000	('20)
Ballarat, Australia. . .	39,000	('21)	Bradford, England.	286,000	('21)	Catania, Italy.	255,000	('21)
Bangkok, Siam.	630,000	('20)	Bremen, Germany.	270,000	('19)	Changsha, China.	536,000	('21)

POPULATION OF FOREIGN CITIES

Chemnitz, Germany...	304,000	('19)	Le Creuzot, France...	38,000	('21)	Reims, France.....	77,000	('21)
Cherbourg, France...	38,000	('21)	Leeds, England.....	458,000	('21)	Reval, Esthonia.....	123,000	('22)
Christiania, Norway...	258,000	('20)	Leghorn, Italy.....	115,000	('21)	Riga, Latvia.....	185,000	('20)
Chungking, China....	497,000	('21)	Leicester, England...	234,000	('21)	Rio de Janeiro, Brazil.	1,158,000	('20)
Cologne, Germany...	634,000	('19)	Leipzig, Germany...	604,000	('19)	Rome, Italy.....	691,000	('21)
Colombo, Ceylon.....	244,000	('21)	Lemberg, Poland.....	219,000	('21)	Rosario, Argentina...	265,000	('22)
Colon, Panama.....	31,000	('20)	Liege, Belgium.....	165,000	('21)	Rotterdam, Netherl'ds	516,000	('20)
Constantinople, Turk.	1,000,000		Lille, France.....	201,000	('21)	Rouen, France.....	124,000	('21)
Copenhagen, Denmark	561,000	('16)	Lima, Peru.....	176,000	('20)	Saigon, Fr. Indo-China	83,000	('21)
Crefeld, Germany....	124,000	('19)	Limoges, France.....	90,000	('21)	St. Etienne, France...	168,000	('21)
Dairen, Manchuria...	239,000	('20)	Lisbon, Portugal.....	490,000	('20)	St. John, Canada.....	47,000	('21)
Damascus, Syria.....	170,000		Liverpool, England...	803,000	('21)	St. Johns, Newfoundland	34,000	('18)
Danzig, Danzig.....	195,000	('23)	Lodz, Poland.....	452,000	('21)	Salonica, Greece.....	170,000	('20)
Delhi, India.....	304,000	('21)	London, England.....	7,476,000	('21)	San Luis Potosi, Mexico	68,000	('10)
Dortmund, Germany...	295,000	('19)	Lucknow, India.....	241,000	('21)	San Salvador, Salvador	81,000	('22)
Dresden, Germany...	529,000	('19)	Lyon, France.....	562,000	('21)	Santiago, Chile.....	507,000	('20)
Dublin, Ireland.....	427,000	('22)	Madras, India.....	527,000	('21)	Santiago de Cuba, Cuba	70,000	('20)
Durban, South Africa.	146,000	('21)	Madrid, Spain.....	751,000	('20)	Santo Domingo, Dom. R.	31,000	('21)
Dusseldorf, Germany...	407,000	('19)	Magdeburg, Germany	286,000	('19)	Santos, Brazil.....	103,000	('20)
Edinburgh, Scotland...	420,000	('21)	Manaos, Brazil.....	76,000	('20)	São Paulo, Brazil.....	579,000	('20)
Edmonton, Canada...	59,000	('21)	Manchester, England...	731,000	('21)	Sebastopol, Russia...	73,000	('21)
Elberfeld, Germany...	157,000	('19)	Mandalay, Burma.....	149,000	('21)	Seoul, Chosen.....	250,000	('20)
Essen, Germany.....	439,000	('19)	Maracaibo, Venezuela	47,000	('20)	Shanghai, China.....	1,500,000	('21)
Florence, Italy.....	254,000	('21)	Marseille, France...	586,000	('21)	Sheffield, England...	491,000	('21)
Foochow, China.....	320,000	('21)	Mekka, Hedjaz.....	70,000		Singapore, Straits Set.	387,000	('19)
Frankfort on Main, Ger.	433,000	('19)	Melbourne, Australia.	795,000	('21)	Smyrna, Asia Minor...	375,000	('12)
Freetown, Sierra Leone	44,000	('21)	Messina, Italy.....	177,000	('21)	Sofia, Bulgaria.....	154,000	('20)
Galatz, Roumania....	74,000	('17)	Mexico, Mexico.....	1,080,000	('10)	Soochow, China.....	500,000	('21)
Geneva, Switzerland..	135,000	('20)	Milan, Italy.....	718,000	('21)	Southampton, Eng...	161,000	('21)
Genoa, Italy.....	301,000	('21)	Mombasa, Kenya...	40,000	('21)	Stettin, Germany...	233,000	('19)
Georgetown, Br. Guiana	55,000	('21)	Monterey, Mexico....	74,000	('10)	Stockholm, Sweden...	422,000	('22)
Glasgow, Scotland....	1,034,000	('21)	Montevideo, Uruguay	351,000	('22)	Stoke upon Trent, Eng.	240,000	('21)
Göteborg, Sweden....	227,000	('22)	Montreal, Canada....	619,000	('21)	Strasbourg, France...	167,000	('21)
Grimsby, England....	82,000	('21)	Moscow, Russia.....	1,028,000	('21)	Stuttgart, Germany...	309,000	('19)
Guadalajara, Mexico.	119,000	('10)	Mukden, Manchuria...	158,000		Sydney, Australia....	898,000	('21)
Guatemala, Guatemala	91,000	('21)	Mulhouse, France....	99,000	('21)	Sydney, Canada.....	23,000	('21)
Guayaquil, Ecuador...	100,000	('19)	Munich, Germany....	631,000	('19)	Tabriz, Persia.....	200,000	
Hague, Netherlands...	355,000	('19)	Nagoya, Japan.....	430,000	('20)	Taganrog, Russia....	68,000	('13)
Halifax, Canada.....	58,000	('21)	Nanking, China.....	380,000	('21)	Tampico, Mexico.....	18,000	
Hamburg, Germany...	986,000	('19)	Nantes, France.....	184,000	('21)	Tananarivo, Madagascar	63,000	('11)
Hamilton, Canada....	114,000	('21)	Naples, Italy.....	780,000	('21)	Tangier, Morocco....	50,000	('21)
Hangchow, China.....	892,000	('21)	Newcastle, England...	275,000	('21)	Tashkent, Turkestan.	245,000	('21)
Hankow, China.....	1,468,000	('20)	Nice, France.....	156,000	('21)	Teheran, Persia.....	220,000	
Hanoi, Fr. Indo-China	119,000	('21)	Ningpo, China.....	271,000	('21)	Tientsin, China.....	800,000	('21)
Hanover, Germany...	393,000	('19)	Nizhni Novgorod, Russia	88,000	('21)	Tiflis, Georgia.....	347,000	('15)
Harbin, Manchuria...	156,000	('21)	Nottingham, England	263,000	('21)	Tokyo, Japan.....	2,173,000	('20)
Havana, Cuba.....	364,000	('20)	Nuremberg, Germany	353,000	('19)	Tomsk, Siberia.....	119,000	('21)
Havre, France.....	163,000	('21)	Odessa, Russia.....	432,000	('21)	Toronto, Canada.....	522,000	('21)
Heidelberg, Germany.	70,000	('19)	Oporto, Portugal.....	203,000	('20)	Toulouse, France....	175,000	('21)
Helsingfors, Finland..	198,000	('20)	Osaka, Japan.....	1,253,000	('20)	Tours, France.....	75,000	('21)
Hobart, Tasmania....	52,000	('21)	Ottawa, Canada.....	108,000	('21)	Trebizond, Turkey...	55,000	
Hull, England.....	287,000	('21)	Palermo, Italy.....	400,000	('21)	Trieste, Italy.....	239,000	('21)
Hyderabad, India....	404,000	('21)	Panama, Panama....	67,000	('20)	Tripoli, Libia.....	73,000	
Innsbruck, Austria...	56,000	('20)	Para, Brazil.....	236,000	('20)	Trondhjem, Norway...	55,000	('20)
Iquique, Chile.....	37,000	('20)	Paris, France.....	2,906,000	('21)	Tucuman, Argentina...	91,000	('14)
Irkutsk, Siberia....	104,000	('21)	Peking, China.....	1,300,000	('21)	Tunis, Tunis.....	172,000	('21)
Jerusalem, Palestine.	63,000	('22)	Pernambuco, Brazil..	239,000	('20)	Turin, Italy.....	502,000	('21)
Johannesburg, S. Af...	284,000	('21)	Perth, Australia....	155,000	('21)	Valencia, Spain.....	244,000	('20)
Kabul, Afghanistan...	150,000		Petrograd, Russia...	706,000	('21)	Valladolid, Spain....	71,000	('18)
Karachi, India.....	217,000	('21)	Pilsen, Czechoslovakia	88,000	('21)	Valparaiso, Chile....	182,000	('20)
Kashgar, Sinkiang...	60,000		Piræus, Greece.....	131,000	('20)	Vancouver, Canada...	117,000	('21)
Kharkof, Russia....	284,000	('21)	Pisa, Italy.....	68,000	('21)	Venice, Italy.....	172,000	('21)
Khartum, Ang.-Eg. Sud.	31,000		Plymouth, England...	210,000	('21)	Vera Cruz, Mexico...	49,000	('10)
Kief, Russia.....	366,000	('21)	Port Arthur, Canada.	15,000	('21)	Victoria, Canada.....	39,000	('21)
Kiel, Germany.....	205,000	('19)	Port au Prince, Haiti.	120,000		Vienna, Austria.....	1,841,000	('20)
Kimberley, S. Africa...	39,000	('21)	Porto Alegre, Brazil..	179,000	('20)	Vilna, Poland.....	215,000	('14)
Kingston, Jamaica...	63,000	('21)	Port Said, Egypt....	91,000	('17)	Vladivostok, Far E. Rep.	90,000	
Kobe, Japan.....	609,000	('20)	Portsmouth, England.	247,000	('21)	Warsaw, Poland.....	931,000	('21)
Königsberg, Germany	261,000	('19)	Prague, Czechoslovakia	676,000	('21)	Wellington, New Zeal'd	111,000	('22)
Kovno, Lithuania...	90,000	('14)	Puebla, Mexico.....	96,000	('10)	West Ham, England...	301,000	('21)
Krakow, Poland.....	181,000	('21)	Quebec, Canada.....	95,000	('21)	Winnipeg, Canada...	179,000	('21)
Kyoto, Japan.....	591,000	('20)	Quito, Ecuador.....	81,000	('19)	Yarkand, Sinkiang...	60,000	
La Paz, Bolivia.....	107,000	('18)	Rangoon, Burma.....	342,000	('21)	Yokohama, Japan....	423,000	('20)
La Plata, Argentina...	90,000	('14)	Reggio, Italy.....	83,000	('21)	Zanzibar, Zanzibar...	35,000	
Lassa, Tibet.....	20,000		Regina, Canada.....	34,000	('21)	Zürich, Switzerland...	207,000	('20)

INDEX AND PRONUNCIATIONS

MARKINGS: *ā* in *lāte*, *ǎ* in *făt*, *â* in *câre*, *ä* in *fär*, *à* in *lást*, *a* in *fall*, *à* in *sofà*, *au* in *author*; *e* in *can*, *ç=s*, *ch=sh*; *ē* in *mē*, *ē* in *réturñ*, *ē* in *mét*, *berry*, *e* in *veil*, *e* in *térñ*; *ġ* in *ġem*, *ġ* in *ġet*; *ī* in *fine*, *ī* in *tín*. *ŷ* in *police*; *k* = German *ch*; *n* = *ng*, *N* = *ng* in its effect (nasal) on the preceding vowel, but is not itself sounded; *ō* in *uôte*, *ō* in *ōbey*, *ō* in *nôt*, *ō* in *sôft*, *ō* in *fôr*, *ô* in *sôn*, *o* in *wôlf*, *o* in *dô*, *oo* in *schôol*, *oo* in *wôol*; *ş* = *z*; *th* in *thine*; *ū* in *tūne*, *ū* in *nūt*, *û* in *bûrn*, *u* in *full*, *u* in *rude* (= *o*), *ü* = French *u*, *ua* = *wa*, *ue* = *we*; *x* = *gz*; *ÿ* in *mÿ*, *ÿ* in *hÿmn*. *Italic letters are silent.*

Ab-er-deen', Scotland 282
Abruzzi (ä-brööt'se), Duke of 251
Ab-ys-sin'i-ä 371, 376, 380
A-côn-cä'guä (ä-kôn-) 221
Ad'e-laide 389
Aden (ä'den) 348
Ad-i-ron/dacks 36, 41, 74, 78
Adis Abeba (ä'dis ä-bä'bä) 369
a-do'bë 22, 172, 213
Ad-ri-an-o'ple 310
A-dri-at'ic Sea 264
Äë-ġe'an Sea 324
Af-ġhan-is-tän' 349
Af'ri-cä 369
climate 372, 20
countries 377-383
forests and animals 373
partition of 376
people and history 374
physical geography 369
Aġaġa (ä-ġän'yä) 185
a-ġä'vë 213
agricultural implements 145
agriculture, aided by machines 61
dry farming 167
farming in China 361
scientific farming 107
See also names of crops
air 16, 392
Ak'ron, Ohio 150
Al-a-bä'ma 116
climate 119
products 120, 123, 124, 104
Al-a-me'da 183
A-las'ka 185-189, 19, 24, 47
Al-rä'bi-ä 347, 348
Albany (äl'bä-ni) 89
Al'be-marle Sound 99
Al-bër'ta 201-208
Al-bu-quë'r/quë 172
A-lep'po 345
Aleutian (ä-lü'shan) Is. 187
Al-eġ-an'dri-ä, Egypt 378
Alexandria, Va. 100
Al-ġë'ri-ä 379, 373
Al-ġiër's' 379
Al-le-ġhe'ny Plateau 37, 75
Alleġheny River 75
Al'len-town, Pa. 94
Almaden (äl-mä-thän') 308
al-pac'a 224
Alps, glaciers in 263, 264
in Switzerland 311, 312, 314
Mont Blanc 302
Al-säġe' 302, 287-288
Altai (äl-ti') Mts. 337
al'ti-tude, and climate 17
Al-töö'na 93
a-lü'mi-num 91
Am'a-zon River 221, 249
A-meer' 349

Amiens (ä-myän') 304
Am'ster-dam, Holland 295
Amsterdam, N.Y. 89
Amundsen (ä'mün-sën), Ro'-äld, explorer 253
Amur (ä-möör') R. 338
An-a-con'da 171
An'dës Mountains 221
Andorra (än-dör'rä) 306
An-dros-cog'gin River 56
An'ġlo-E-ġyp'tian Sq-dän' 380
Anglo-Sax'on, name 269
An-go'la 377
An-ġo'rä 335
animals, of Africa 373
of Asia 339, 340
of Australia 387
of North America 162, 205
of South America 224
An-nap'o-lis, Md. 110
Ann Ar'bor, Mich. 150
Ant-arc'tic Circle 398, 399
Antarctic Continent 253, 20
Antarctic Ocean 253
an'thra-cite 81
anti-trade winds 259
An-tö-fä-ġäs'tä (än-) 238
Ant'werp 293, 295
Ap'en-nines 263
Ap-pa-läch'i-an Forest Reser-vation 103
Appalachian Mountains 36, 10, 74, 101
climate 41, 43
Appalachian Plateau 37, 74
apples 79, 178
A-rä'bi-ä 347, 348
Arabs (är'abz) 348, 341, 374
Aral (är'al), Lake 367
Areh'an'ġel 332, 265, 266
Arc'tic Ar-ehi-pel'a-go 9
Arctic Circle 398, 399
Arctic Current 246
Arctic Ocean 251
Ardennes (är-dën') Moun-tains 302
Arequipa (ä-rä-kë'pä) 237
Ar-ġen-ti'na 233-234, 226
Arica (ä-rë'kä) 238
är'id regions 43
Arizona (är-i-zö'nä) 157
climate 158, 41, 43
products 163, 167, 169, 170
surface 157, 39
Ar'kan-säs 116
products 120, 122-125
surface 119
ar-ma-dil'lo 224
Ar-me'ni-ä 367, 345
Ar'no River 315
A-shän'ti 368
Ash'e'ville 101
Ash'land, Wis. 143
Ash-ta-bü'la 143

Asia (ä'shä) 335
awakening of 344
climate 338, 19
countries 345-367
industries 342
life and people 339-344
physical geography 335
Asia Mi'nor 345
Asir (ä-sër') 347
äs'phält 217
As-sin'i-boine River 208
Assuan (äs-swän') 378
As-to'ri-ä 181
As-tra-khan' 332, 266
Asuncion (ä-soon-syön') 234
Ath-a-bas'ka, Lake 198
Ath'en's 326
At-lan'ta 110, 125
At-lan'tic City 74, 95
Atlantic coastal plain 35, 99
Atlantic Lowland 11, 34, 73
Atlantic Ocean, currents 246
At'las Mountains 371
atmosphere 16, 392
At'tle-bör-o 63
Au'burn, N.Y. 90
Auck'land 390
Augsburg (ouks'böörk) 290
Au-gus'ta, Ga. 111
Augusta, Maine 66
Au-ro'ra, Ill. 150
Aus'tin, Texas 127
Aus-trä'li-ä 385
cities 388
industries 388
people 387
physical geography 385
rainfall 257
Aus-tra'li-an Alps 385
Aus'tri-ä 321
Austria-Hun'ga-ry 321, 270
automobiles 147
autumn 401
av'a-lanche 312
axis, earth's 393, 395, 398
A-zër-bäi-jän' (ä-) 367
Azof (ä'zöf), Sea of 333
A-zöres' 307, 383
Az'tec Indians 22, 212
Bab'y-lon 347
Bad Lands 134
Bäġ-däd' 347
Ba-hä'mas 217, 23
Bä-hi'ä 233
Bäi-käl', Lake 366
Bä'kers-field 181
Bä-ky' 367
Bal-e-är'ic Isles 300
Bal'kan countries 324
Balkan Mountains 324
Balkan Peninsula 324
Bäl-käsh', Lake 334
Bal-la-rat' 389
Bal'tic Sea 265; states 299
Bal'ti-more 109

Ba-lŷ-chis-tän' 351
bam-boo' 352, 364
bananas 215, 217
Bang-kok' 354
Ban'ġôr 66, 57
Ban'ka 355
Banks of Newfoundland 204
ban'yan tree 352
Bar-bä'dös 217
Bar-ce-lo'na 308
Barge Canal 88
Bar Harbor 67
barley 139
Bar'men 291
Bär-rän-quil'la (-kël'yä) 238
Bär'rë 66
Bar'ren Lands 201
barrier beaches 100, 245
Bär'röw, Point 187, 188
basin of a river 15
Ba-tä'vi-ä 355
Bat'on Rouge (rööz'h') 116
Battle Creek 138
Bä-tum' 367
Ba-vä'ri-ä 291
Bay City 147
Bä-yönne' 95
bay'ou's 117
beach, formation of 245
Beaumont (bö'mönt) 125
Bed'ou-in's 348
Bë'i-rä 381
Be'i'rt' 347
Bel-fäst' 285
Bel'ġi-an Congo 380
Bel'ġi-um 292, 272, 273, 288
Bel-grade' 324
Bë-lize' 211
Bel'ling-ham 181, 184, 179
Ben-ä'rës 341, 353
Ben'di-go 389
Ben-ġal', Bay 351
Ben Ne'vis 276
Ber'bers 374
Bër'gen 296
Be'ring Strait 251
Berke'ley, Calif. 183
Berk'shire Hills 36, 55, 66
Ber-lin' 290-291
Ber-mü'das 6, 278
Bërn 311, 270
Bes-sa-rä'bi-ä 325
Bëth'lë-hem 94
Bhŷ-tän' 353
Bil-bä'o 308
Bil'lings 164
Bil-li-tön' 355
Bing'ham-ton, N.Y. 91
Bir'ming-ham, Ala. 118, 125
Birmingham, Eng. 278
Biş'bee 170
Biş'cay, Bay of 265
Biş'marck, N.Dak. 132
Biş'marck Ar-ehi-pel'a-go 390
bi-tu'mi-nous coal 81

- "black earth" region 330
 Black Forest 287
 Black Hills 38, 134
 black race 374
 Black River, water power 84
 Black Sea 330
 Bloom'ing-ton 150
 Blue-grass region 119
 Blue Ridge 36, 101, 118
 Bqerş 381
 Bo-go-tă' 239
 Bo-he-mi-ă 322, 323
 Boi'se 171
 Bo-khă/ră 367
 Bol'i-văr, General 237
 Bo-liv'i-ă 237, 221
 Bo-mă 369
 Bom-bay' 353, 352
 boots and shoes 62
 Bordeaux (bôr-dô') 303, 305
 bore, tidal wave 249
 Bor'ne-o 355
 Bos'ni-ă 325
 Bos'po-rus 264
 Bôs'ton 69, 60, 62, 67
 Bôth'ni-ă, Gulf of 333
 bottom lands 13
 Boulogne (bôo-lôn'y') 305
 boundaries, kinds of 24
 bowlders 59
 brackish water 244
 Brad'dock, Pa. 94
 Brăh'man-ism 341
 Brăh-ma-pu'tra R. 351, 357
 Bra-zil' 231, 225-229, 234
 Bra-zil'ian mountains 221, 222
 Bră-zôs River 114
 Brēm'en 290
 Breslau (brēs'lou) 291
 Brēst 305
 Bridge'port 63, 70
 Briş'bane 389
 Bris'tol 281
 Bristol Channel 249
 Brit'ish Columbia 201-209
 British Empire 284
 British Honduras 215, 25
 British Isles 265; see Great Britain
 Brit'ta-ny 265
 Brock'ton 62
 Bronx 86
 Brook'line 69
 Brook'lyn 86
 Brus'sel's 293
 Bū-cha-rest' 326
 Bū'da-pest 322
 Bud'dhişm 341
 Bue'nôs A'i'res 234
 Buf'fa-lo 90, 83, 143
 routes of trade 85, 88, 153
 buffalo 162; water 196
 building stone 66
 Bū-ko-wi-nă(-vê-) 325, 326
 Būl-gă'ri-ă 326, 324
 Băr'ling-ton, Vt. 70
 Bur'ma 353, 351, 352
 Bütte 169
 Buz'zards Bay 69
 Bý-zăn'tium (-shi-um) 327
 Cab'ot, explorer 23
 ca-că'o 231, 238, 380, 405
 Cairo (kī'rô) 378
 Cal'ais 305
 Cal-cut'ta 353, 352
 Cal'ga-ry 208
 Cal-i-for'ni-ă 174
 climate 177, 17, 41
 history 47, 48, 173
 products 178-184, 163, 167
 surface 175, 40
 Callao (kăl-yă'o) 237
 Căm'bridge, Mass. 68, 69
 Cam'den 95
 camels 340, 379
 Că-me-rôon' 376, 381
 căm'pôs 222, 223, 231
 Can'a-dă 199-209, 24
 cities 208
 climate 202, 16-19, 44
 government 203
 history 203, 23
 products 203-207
 surface and provinces 199
 transportation 207
 Ca-nă'di-an Rockies 201
 canals in Europe 266
 Canal Zone 190, 215, 25, 47
 Ca-nă'ry Islands 307, 383
 Căn'bér-ră 387
 Can'cer, Tropic of 398
 cañon (kăn'yun) 12
 Can-tă'bri-an Mountains 307
 Can-tôn', China 362
 Can'ton, Ohio 144
 can'tons, Swiss 312
 can'yon 12
 Cape Breton (brît'un) I. 205
 Cape of Good Hope 381-383
 Cape-to-Cairo Railroad 375
 Cape Town 382
 Cape Verde Islands 383
 Cap'ri-corn, Tropic of 398
 Că-ră'căs 239
 căr'a-vanş 379
 Căr'diff 278, 281
 cardinal points 393
 cargadors (kăr-gă-fhöz'r') 213
 Căr-ib-be'an Sea 23
 Căr-pă'thi-an Mts. 263, 322
 Car-ră'ră 318
 Căr'son City 157
 Căr-ta-ge'na 308
 Cas-căde' Range 175, 201, 43
 Cas'co Bay 55
 cash'mère wool 357
 Cas'per 170
 Cas'pi-an Sea 330
 Cats'kill Mountains 37, 74
 cattle 80, 141, 234, 405
 Cauca (kou'ka) River 239
 Cau-că'sian (-shan) race 341
 Cau'ca-sus 367
 Caucasus Mountains 329, 367
 caverns 101, 119
 Căy-en-ne' 239
 Că-yū'ga Lake 74, 91
 Cedar Rapids 139
 Cel'e-bēs 355
 Celts, people 269
 cement industry 83, 144
 census 47
 Central America 215, 23, 25
 cereals 138
 Cetinje (tsēt'ên-yă) 310
 Cey-lôn' 353, 229
 Chăd, Lake 372
 Chă'grēs River 190
 Champlain (shăm-plăn'), ex-
 plorer 23, 25
 Champlain, Lake 70
 channel of a stream 13
 Charles'ton, S.C. 109, 106
 Charleston, W. Va. 110
 Charlotte (shăr'lôt'), N.C. 110
 Charlotte A-mă'li-ă 185
 Char'lôtte-ville (shăr'-) 110
 Char'lôtte-town (shăr'-) 201
 Chat-ta-hoo'chee River 115
 Chat-ta-noo'ga 125, 118
 Chau-tău'qua (shă-) Lake 91
 Chel'sea, Mass. 69
 Chel-yus'kin, Cape 335
 Chemnitz (kēm'nits) 291
 Chemung (shē-mung') R. 91
 Cherbourg (shēr-boor') 305
 Ches'a-peake Bay 99, 108, 9
 Ches'ter, Pa. 94
 chestnuts in Italy 317
 Cheyenne (shī-ên'), Wyo. 171
 Chi-ca'go (shī-) 146, 142, 143
 character of site 5
 transportation 146, 152, 153
 Chī'le 235, 223-227, 239
 Chim-bo-ră'zo, volcano 221
 Chī'na 357-362, 339, 342-344
 Chinese Turkestan 357
 chi-nōōks' 202
 Cho'sen 365, 363
 Chris-ti-ă'ni-a 296
 Chri's-ti-an'i-ty 341
 Chung'king' 362
 cin-cho'na tree 237
 Cin-cin-nat'i 150, 62, 126, 152
 cities, life in 88
 Clarks'burg 110
 clay 83
 Cleve'land 148, 143, 152, 153
 climate 16, 41, 254-259, 401
 cloudbursts 159
 clouds 11
 Clyde, Firth of 276; R. 280
 coal, main account 81, 408
 in Great Britain 278
 in United States 81, 82
 (map), 60, 103, 124
 coastal plain 35, 242
 coast forms 245
 Coast Ranges 40, 176, 43
 Co'balt 205
 Cod, Cape 57, 60, 69
 codfish 205, 67
 Cœur d'Alene (kūr dă-lăn')
 district 169
 coffee 227, 405
 Co-hōes', N.Y. 89
 cold wave 44
 Co-lōgne' 291
 Co-lōm'bi-ă 238, 222, 223, 227
 Co-lōm'bo 335, 353
 Co-lōn' 190
 Col-o-ră'do 157
 climate 158, 17
 irrigation in 165
 products 163, 166, 169, 170,
 122, 141
 surface 157, 38, 39
 Colorado City 169
 Colorado Plateaus 39
 Colorado River 161, 16, 39
 Colorado Springs 172
 Col-os-sē'um 319
 Co-lum'bi-ă, S.C. 99, 100, 35
 Columbia Plateaus 39, 176
 Columbia R. 10, 16, 173, 180
 Co-lum'bus, explorer 21, 23,
 71, 105, 256
 Columbus, Ga. 111
 Columbus, Ohio 150
 commerce, in general 4
 compass 393-394
 Con'cord, N.H. 66
 cones, volcanic 39
 Con-fū'ci-us (-shi-us) 342
 Cōn'go Free State 380
 Congo River 371, 373, 381
 Con-ne-aut' 143
 Con-nect'i-cut 55
 products 60, 62, 63, 66
 Connecticut River 16, 56, 57
 Valley 59, 60, 66, 70
 Con'nells-ville, Pa. 94
 Con'stance, Lake of 312
 Con-stan-ti-nô'ple 327
 constitutional monarchy 270
 con-ti-nen'tal climate 17, 18
 continental divide 157
 continental shelf 242
 con'tour map 29
 Coop'ers-town 74
 Co-pen-hă'gen 295
 copper 144, 168, 170, 181, 409
 copra 196
 cor'al islands 243, 391
 coral reef 243, 385
 Cordilleras (côr-dil-yă'răz)
 10, 38
 Cōr'inth, Isthmus of 327
 cork 308, 379
 corn 137-138, 403
 native to America 22, 225
 use of 140, 80
 Cōr-vă'l'is, Oregon 184
 Cōs'ta Ri'ca 215
 Co-to-pax'i, volcano 221
 cotton 105, 120, 167, 179, 378,
 406
 manufacture 61, 106, 278
 cotton gin 105
 cottonseed oil 106
 Council Bluffs 149
 Cōv'ing-ton 128
 cowboys 141, 142
 cranberries 60
 Crater Lake 177
 Crefeld (kră'fêlt) 304
 Cre'oles 126
 cre-vâsse', defined 117
 Cri-me'ă 329
 Cripple Creek 170
 Crô-ă'ti-a (-shī-ă) 325
 Crô'ats 325
 crop-growing period 43
 Cro'ton River 84
 Că'ba 216, 23, 25, 122
 Cum'ber-land, Md. 110
 Cumberland Gap 113
 Cumberland Plateau 37, 118
 Cū-ră-ă'ă'o 217
 currants 327
 Cuzco (kū'skô) 225
 cŷ'clōnes 44, 255
 Cŷ'prus 345
 Czech'ô-slô-văk'i-ă (chĕk'-)
 322
 Czechs (chĕks) 322
 Dă-ho'mey 376, 380
 Dă'i'ren' 357
 dairying 80, 140, 295, 296, 313
 Dal'las 127
 Dal-mă'ti-a (-shī-ă) 325
 Dal'ton, Mass. 64
 Da-mas'cus 345
 Danes 269, 295

- Dan'ube River 265, 323
Dan'ville, Ill. 150
Danville, Va. 110
Danzig (dän'tsik) 299
Där-da-něles' 264
Dar'ling River 385
Däv'en-port 149
Daw'son 206, 187
day 397, 399
Day'ton 150
Dead Sea 347, 39
De-cä'tur 150
degree, defined 394
Dēk'kan Plateau 351
Del'a-ware 99, 109
Delaware Bay 9
Delaware River 16, 75
Del'hī 352
del'tas 14
Den'mark 295, 273, 288
den-si-ty of population 49
Den'ver 172, 152
des'erts, life in 343
Des Moines' 150
De-troit' 147, 152, 153
diamonds 383
Di-ēppe' 305
dikes 293
Dī-nār'ic Alps 324
directions 393
Dis'mal Swamp 100
dis-trib'u-ta-ries 14
District of Co-lum'bi-ā 99, 111
divide 15
Dnieper (nē'pēr) R. 266, 329
dōl'drums 257
Dom-i-ni'cā 217
Do-min'i-can Republic 217
Donetz (dō-nyēs') R. 333
Doū'las fir 180
Dōu'rō R. 300
Do'ver, Del. 99
Dover, Strait of 275
Drainage Canal 146
Drä'vē River 310
Dres'den 290, 291
drowned valleys 58
drum'lin's 20
dry farming 167
Dub'lin 285, 281
Dū-būque' 149
Dū-lyth' 147, 137, 145, 153
Dū'nā River 266
dūñes 57, 159
Dū-rān'go 214
Durazzo (dōō-rāt'sō) 310
Dur'ban 382
Dur'ham 104
Dūs'sel-dorf 291
Dutch 269, 293, 71, 381
Dvi-nā' River 266
earth, as a whole 392-402
 motions 393, 395
 size and shape 392
 surface 392; altered 5, 13
earthquakes 238, 317, 363
 waves caused by 245, 249
east, defined 393
East In'dies 355
East Liv'er-pool 145
East'on, Pa. 94
East River 85
East St. Loy'is 148, 142
E'bro River 307
e-clipse' 396
Ee'ua-dor 238, 221, 239
Ed'in-burgh (-būr-ō) 276, 283
Ed'mon-ton 208
E'gypt 377, 373
Eisenerz (i'zen-erts) 321
El-ber-feld' (-fēlt') 291
El'bē River 266, 322
El-bur'z', Mt. 336
elephants 340, 375
elevator, grain 90, 137
El'gin, Ill. 150
E-liz'a-beth, N.J. 95
El-mi'ra 91
El Pās'o 127
England 269, 275, 284
E-quā'tor 393
e-qu-a-to'ri-al calms 257
e'qui-nox 401
Er'e-bus (ēr'-), Mt. 253
E'rie, Lake 37, 75
Erie, Pa. 94, 143
Erie Canal 88, 152
Eritrea (ā-rī-trē'ā) 376
Erzerum (ēr-zrōm') 334
Es-ca-nā'ba 143
Es'ki-mōs 1, 4, 201, 209, 341
Es'sen 290
Es-thō'ni-ā 299
es'tū-a-ries 265
E-thi-o'pi-ā 375
Et'na, Mt. 316
Eñ-gēne', Oregon 184
Eñ-phrā'tēs River 347
Eñ-r'a'sia (-shā) 335
Eñ-rōpe 261
 climate 267
 coast line 264
 countries 275-333
 glaciers 264
 history and people 268-270
 industries 271
 rivers and canals 265-266
 roads 271
 surface 263
Ev'ans-ton, Ill. 150
Ev'ans-ville, Ind. 150
e-vap-o-ra'tion 11
Ev'er-est, Mt. 337
Ev'er-ett, Mass. 69
Everett, Wash. 184, 179
Ev'er-glādes 100
Fair'banks 188, 189
Fā'k'land Islands 239
Fall Line 35
Fall River 70, 60, 61
Far'go, N. Dak. 149
Fār'ōe Islands 295
fertilizers 103, 143, 164
Fī'ji Islands 391, 243
Fil-i-pi'nōs 196
Fin'land 333, 329, 330
Fin'ns 333
fiords (fyōrdz) 187, 296
Firth of Forth 276
Fish'guard 281
fishing 3, 9, 249, 272
 in Canada 204-205
 in Great Britain 281
 in United States 49, 67, 108, 180, 188
Fitch'burg 70
Fiume (fyōō'mā) 320
flax 139, 272, 285, 331, 408
Flem'ish 292
Flint, Mich. 147
floe ice 244, 251
flood plains 13
floods 13, 103, 117
Flor'ence 318, 320
Flor'i-dā 99
 climate 102
 history 23, 47, 97
 products 103, 104, 105, 107
forest rangers 162
forest reserves 162, 180, 103
forests, in Canada 203-204
 in Europe 273, 289, 297, 302
 in South America 223
 in United States 64, 103, 162, 179
 national 162
 tropical 223
För-mo'sa 363
Fort Smith 124
Fort Wāyne 150
Fort William 208, 137
Fort Worth 127
France 301-306, 267-273
 colonies 306, 376, 380
Frank'fort, Ky. 116
Frank'fort on the Māin 291
Frā'ser River 201, 180
Fred'er-ic-ton 203
free port 235
Free'town 380
French Equatorial Africa 381
French Indo-China 354
Fres'no 179
Frig'id Zones 398
fruit, in Europe 272
 in United States 49, 79, 107, 167, 178, 179
Fū'ji-yā'mā 363
Fūn-chāl' 383
Gā-lā'pā-gōs Islands 239
Gā'lāt'z 326
Galicia (gā-lish'i-ā) 299
Gal'i-lee, Sea of 347
Gallinas (gāl-yē'nās), Pt. 218
Gal'ves-ton 127, 120
Gā'mā, Vās'co dā 375
Gan'gēs River 337, 351
Ga-rōñne' River 266, 301, 305
Gā'ry 147, 143
gasoline 82
Gā-tūn' Dam 190
Gen-e-see' (jēn) River 79
Ge-ne'va 313; L. of 265, 312
Ge'n-o-ā 320, 318, 319, 267
geography 5, 24
George'town 239
Geōr'gi-ā 99
 physical features 99
 products 103-107, 121
Georgia, in Asia 367
Ger'man East Africa 376
German Empire 287, 288
Germans 288
 in Austria 321
 in South America 226, 231
German Southwest Africa 382
Ger'ma-ny 287-291, 269-273
gē'y'sers 161, 295, 390
Gibraltar (jī-brōl'tēr) 309, 278
Gibraltar, Strait of 264
Gila (hē'lā) River 167
ginger 217
glā'cial (-shāl) period 20
glacial soils 77
glacial waste 56
Glā'cier (-shēr) National Park 162
glaciers (glā'shēr'z) 19-21
 in Canada 19, 201
 in Europe 264, 19
 in United States 19, 56-59, 77, 134
Glās'gōw 276, 280, 281
glass, manufacture of 94
Glens Falls 91
Glen'wood Springs 161
Glōuces'ter 67
Glōv'ers-ville 89
Go'bī Desert 357
gold 168, 410, 188, 206, 382
Gold Coast 380
Golden Gate 176
Gold'field 170
gorge 12
Goteborg (yū-tē-bōr'y') 297
Gra-nā'da 309
Grand Canyon 39, 161
Grand Rapids 145
granite 66
grapefruit 107
grapes 80, 179, 272
graph'ite 353, 383
gravitation 392, 395
grazing 141, 163, 343, 388
Great American Desert 170
Great Appalachian Valley 36, 101, 118
Great Barrier Reef 385
Great Basin 158, 30, 41, 43
Great Britain (brit'n) 275-284, 269-273
 colonies 284, 276
Great Dividing Range 385
Greater An-ti'l'ēs 216
Great Falls 171
Great Lakes 37, 249
 navigation of 9, 153
Great Plains 38, 134, 157
Great Salt Lake 39, 158
Great Smoky Mts. 36, 118
Great Wall of China 359
Greece 326, 268-273, 324
Greeks 268-270, 326
Green'land 209, 19, 21, 269
Green Mts. 36, 55, 64, 66
Greenwich (grin'ij) 283, 395
Gre-nā'da 217
Grims'by 282
Guadalajara (gwā-thā-lā-hā'rā) 215
Guā-dal-quiv'ir River 300
Guā-da-lupe' River 114
Guā-dē-loppe' 217
Guā-di-ā'nā (-thē-) River 300
Guām 197, 47
Guā-te-mā'lā 215, 216
Guayaquil (gwī-ā-kēl') 238
Guiana (gē-ā'nā) 239
Guiana Highlands 221, 222
Guinea (gin't), Gulf of 380
gulf, defined 242
Gulf Plains 38, 116
Gulf Stream 246
gullies 12, 78, 103
Gun'ni-son River 159, 166
Gur'khās 353
Hār'lem 294
hā-čhūres' 28
Hāg'ue, the 294
Hā'i-ti 216, 217
hāl'i-but 67
Hal'i-fax 201, 204, 207
Ham'burg 290, 291

- Ham'il-ton, Canada 208
 Hamilton, Ohio 150
 Hamp/ton, Va. 108
 Hampton Roads 109
 Ham-trām'ck (-ik) 147
 Hān'kōw' 358, 362
 Hā-noi' 335, 354
 Hā'ris-burg 92
 Hart/ford 63, 70, 57
 Hat/ter-as, Cape 100
 Hausa (hou'sā) tribes 380
 Ha-vān'ā 217
 Hā'vēr-hill 62
 Havre (hā'vēr) 301, 303, 305
 Hā-wai'i 193
 Hā-wai'an Is. 193, 47, 243
 hay 80, 139
 Hā'zle-ton 81
 head of navigation 57
 heat belts 401-402
 He'brews, religion of 342
 Hēdj-āz' 347
 Hē'del-bērg 288
 He'l'e-nā, Mont. 171
 Hēl-sīng-fōrs' 333
 hemp 123, 196
 hen'e-quēn 214
 Her-cu-lā-ne-um 316
 Highland Park 147
 Highlands of Scotland 276
 Highlands of the Hudson 74
 Hī'lo 195
 Hī-mā'lā-yā Mts. 337, 351
 Hīn'du-Kūsh' 337
 Hīn'dūs 341, 353
 hip-po-pot'a-mus 373
 Hō'bārt 389
 Hō'bo-ken 95
 hogs 140
 Hol'land 293, 273
 colonies 217, 239, 355
 Hōl'y-hēad 281
 Holy Land 347
 Hōl'yoke 64
 Home'stead, Pa. 94
 Hon-dū'ras 215
 Hōng'kōng' 362
 Hō-nō-lū'lu 195, 389
 Hōn'shū 363
 Hoo'sac tunnel 69
 horse latitudes 259
 Hot Springs, Ark. 128, 161
 Hōus'ton 127, 120
 Hudson, Henry 71
 Hudson Bay 9, 202, 207
 Hudson River 16, 75-77, 85
 Hudson's Bay Company 203
 Hull 281, 282
 Hum'ber River 281
 Hum'bōldt Current 247
 hū'mid air 44
 Hūn'ga-ry 322, 321, 269, 272
 Hunt'ing-ton 110
 Hū'ron, Lake 37
 hur'ri-canes 102, 216
 Hwāng River 338, 358
 Hū-der-ā-bād' 353
 hū-drau'lic mining 168
 I-bē'ri-an Peninsula 307, 264
 icebergs 19, 20, 246
 Ice'land 295, 269
 ice pack 251
 ice sheet 19, 20
 I'da-ho 157
 products 163, 166, 169, 122
 surface 157, 39
 i'lex trees 231
 Il-li-nois' 132
 climate 135
 electric railroads 153
 products 136-145
 surface 132-135, 38
 Illinois river system 15
 Iloilo (ē-lō-ē'lō) 197
 In'cas 225
 In'di-ā 351-353, 341-344
 climate 339, 258
 In'di-ān'ā 132
 climate 135
 electric railroads 153
 products 136-141, 144, 145
 surface 132-135
 In-di-an-āp'o-lis 150, 152, 142
 In'di-ans 21-23
 in Canada 202
 in South America 225, 226
 Indian Territory 113
 In'do-Chi'na 354, 242
 In'dus River 337, 351
 Inns'brūck 321
 International Date Line 397
 Interurban railroads 153
 I'o-wā 132
 products 138-141, 144, 145
 surface 132-135, 38
 Iquique (ē-kē'kā) 235
 Iraq (ē-rāk') 347
 Ire'land 275, 284, 269, 272
 Irkutsk (ir-kōōtsk') 366
 iron 2, 93, 124, 143, 168, 409
 in Great Britain 278
 Iron Gate 265
 Irrawaddy (ir-ā-wōd'i) R. 350
 irrigation 164-167
 islands 243
 Is-pā-hān' 349
 I-tal'ians 317-320
 in Africa 374
 in South America 231, 233
 It'a-ly 315-319, 267-273
 colonies 319, 376
 Ith'a-cā 91
 ivory 375, 381
 Ivory Coast 380
 Jack'son, Mich. 147
 Jackson, Miss. 127, 116
 Jack'son-ville 102, 109
 Jaffa (yā'fā) 347
 jāg'uār 224
 Ja-māi'ca 216, 217
 James River 16, 35, 100
 Jamestown, N. Y. 91
 Jamestown, Va. 23, 109
 Ja-pan' 363-365, 342-344
 in Manchuria 357
 Japan Current 247
 Jap-a-nēse' 363
 in Hawaii 193
 Japanese Empire 363
 Jā'va 355
 Jefferson City 132
 Je-rome', Ariz. 170
 Jer'sey City 95, 87
 Je-rū'sa-lem 347
 jet'ties 118
 Jews 341, 342
 in Africa 374
 in Palestine 347
 Jo-hān'nes-būrg (yō-) 382
 Johns'town, N.Y. 89
 Johnstown, Pa. 93
 Jo'li-et, Ill. 144
 Jop'lin 145
 Jor'dan River 347
 Jorullo (hō-rōōl'yō) Mt. 212
 Juan (hwān) de Fu'cā 174
 Juan Fernandez (hwān fēr-nān'dāth) 239
 Jū-de'a 347
 Jugoslavia (yōō-gō-slā'vī-ā), 324-325
 Jujuy (hōō-hwē') 234
 Juneau (jōō'nō) 188
 Jungfrau (yōōng'frou) 312
 Jū'ra Mountains 302
 Jūte 352
 Jut'land 295
 Kā'būl 335
 Kā'fir corn 139
 Kā-lā-hā'ri Desert 373
 Kāl-a-ma-zoo' 139
 Kam-chāt'ka 334
 Ka-na'whā River 110
 kan-ga-roo' 387
 Kan'sas 132
 products 136-145
 surface 132-135, 38
 Kansas City 149, 126, 142, 152
 Ka-rā'chī 352
 Ka-rē'li-ā 330
 Karlsbad (kärllz'bāt) 323
 Kāsh-gār' 357
 Kee-wā'tin 201
 Kēn-ne-bēc' River 56
 Ken-tuck'y 116
 products 123, 124, 104
 settlement 113
 surface 118, 119, 38
 Ken'ya 381
 Ke'o-kuk, Iowa 148
 kerosene 82
 Ke-ū'kū Lake 80
 Ke'wee-naw Peninsula 144
 Key West 104
 Khār-tūm' 380
 Khāt-mān-dū' 335
 Kiaochow (kyou'chō') 362
 Kī'fē 332
 Kiāl 290, 295
 Kil-i-mān-jā'ro 371
 Kim'ber-ley 383
 Kings'ton, Canada 208
 Kingston, Jamaica, 217
 Kingston, N.Y. 89
 Kīr-ghīz' 367
 Klon'dike region 206
 Knox'ville 125, 127, 118
 Kongo, see Congo
 Königsberg (kū'nīks-bērk) 288
 Ko-rē'a 363, 365
 Krā'kōw 298, 299
 Kuēn-lūn' 337
 Kūrdš 345
 Ku'rīl Islands 363
 Lab-ra-dōr' 202, 205, 209, 17
 Labrador Current 251
 Lack-a-wan'na (-wōn'-) 91
 Lā Crōsse' 149
 lā-goon' 245
 Lā Guā'rā 239
 Lake Plains 37, 75, 201
 lakes, formation of 56, 14, 20
 salt 39
 Lan'ca-shire 278, 279
 Lan'cas-ter, Pa. 92
 Lan'sing 147
 Lā Paz (pās) 238, 219
 Lā Sāl'lē', explorer 23
 Lās'sā 357
 Lās'sen Peak 175
 Latin nations 269, 270
 latitude 394, 16
 Lāt'vī-ā 299
 lā'va 193
 Law'rence 62
 lead 168
 Léad'ville 169, 170
 League of Nations 270
 Lēb'a-non, Mount 345
 Lē Creū-zōt' 304
 Leeds 278, 280, 281
 Leg'horn 320
 Leipzig (līp'sik) 291
 Le'na River 338
 Le'o-pōld-ville 381
 Lesser An-til'lēs 216, 217
 Lew'is-ton, Maine 62
 Lex'ing-ton, Ky. 128
 Li-be'ri-ā 376, 380
 Lib'i-ā 379
 Lib'y-an Desert 373
 Liechtenstein (līk'ten-shtīn), 321
 Liege (lē-ēzh') 293
 lig'nite 81
 Lille 304
 Lī'mā, Ohio 150
 Lī'mā, Peru 237
 Limoges (lē-mōzh') 304
 Līn'coln, Nebr. 149
 linseed oil 139
 lion 373
 Līs'bon 308
 Lith-tū-ā'ni-ā 299
 Little Rock 128
 Liv'er-pool 281, 279, 283
 Liv'ing-stone, David 375
 lū'mā 224
 lū'nōs 223
 load of a stream 12, 14
 loam 77
 Lōdz 299
 lo'ess 78, 358
 Loire (lwār) R. 266, 301, 305
 Lōn'don 282, 277
 Lōn'don-dēr-ry 281
 Long Beach, Calif. 183
 Long Branch 74
 Long Island 74, 78, 79
 longitude 394
 Lo-rain' 143
 Lōr-rāine' 302, 287-288
 Lōs An'gēl-ēs 183
 Lo-y-i-si-ān'ā 116
 climate 119, 41
 products 120-125, 104
 surface 116
 Territory, acquired 46
 Lo-yis-ville 123, 126, 128, 152
 Lōu-rēn'ço Mar'quēs 381
 Lōw'ell 57, 61
 Lower California 212
 Lu-cērne', Lake of 312
 lumbering, in Canada 203-204
 in United States 65, 124, 179
 Lu-ray' Cavern 101
 Lux'em-burg 306
 Lū-zōn' 195
 Lynch'burg, Va. 110
 Lynn 69, 62
 Lyon (lē-ōn') 304
 mac-a-ro'ni 318
 Mc-Kees'port, Pa. 94

- Mac-ken'zie R. 15, 16, 201, 207
mack'er-el 67
Mc-Kin'ley, Mt. 10, 187
Mā'con, Ga. 111
Mad-a-gas'car 383
Ma-dē'i/rā Islands 307, 383
Mad'i-son, Wis. 150
Ma-drās' 353
Ma-drid' 309
Mäg-dä-le'nä River 238, 239
Mäg'de-burg (-böörk) 291
Ma-gel'lan, Ferdinand 195
Magyars (mōd'yörz) 322
Maine 55
 climate 58
 coast 57, 67
 products 60, 63-67
mä'ize 137
Ma-lak'ka Strait 354
Ma-lay' Archipelago 355
Malay Peninsula 354
Mal'den 69
Mäl'ta 319, 278
Mam'moth Cave 119
Mā-nä/guā 211
Mā-nä'ōs 229
Man'ches-ter, England 279, 283
Manchester, N.H. 57, 61, 62
Man-chū'ri-ā 357
Man'chus, in China 360
Man'da-lay 353
Man-hat'tan Island 85, 86
Mā-nīch' River 329
Ma-nil'a 197, 195
mān'i-ōc 231
Man-i-tō'ba 201-206
manufactures in Asia 343
 in Europe 273
 in United States 60, 145, 182; see names of cities
Mä'o-ris 389
maple sugar 65, 122
Mä-rä-eai'bo 239
Maracaibo, Lake 222
marble 66, 125, 318
Mar'c'y, Mt. 74
Mä-ri'en-bad (-bät) 323
Mär'i-time Provinces 199, 202, 204, 206
Mär'mo-ra, Sea of 324
Mar-quétte', explorer 23
Marquette, Mich. 143
Marseille (mär-sä'y') 301, 305
Mar'thas Vineyard 58
Mar-ti-nique' 217
Mar'y-land (mēr'-) 99
 climate 102
 products 103-105, 107, 108
Maskat (müs-kät') 335, 348
Mas-sa-chū'setts 55
 products 60-66
 surface 55, 20
Massachusetts Bay 9
mä'té 231
Mät'tēr-horn 312
mature valley 13
Mauna (mou'nä) Lō'ä 193
Mauritius (mō-rish'i-us) 383
mean annual temperature 401
me-än'ders 14, 118
meat packing 142
Me-dī'nä 347
Med-i-ter-rā'ne-an Sea 264
Mek'ka 342, 347
Me-kōng' River 354
Mel'bourn 385, 387, 389
Mem'phis 116, 124, 126, 152
Me-nām' River 354
Men-do-cī'no, Cape 174
Me-nom'i-nee River 131
Mer-cēd' River 177
mercury 181, 308
Mēr'i-den 63
me-rid'i-an 394
Meridian, Miss. 127
Mēr'ri-mack River 56, 57
Mēr'sey River 266, 279
Mes-o-po-tā'mi-ā 347
Mēs-si'na 317
mes-ti'zōs 213, 226
Meüse River 286
Mex'i-co 25, 211-215, 19
 history and people 23, 212
 products 214, 229
Mexico, city 215
Mexico, Gulf of 9, 246
Mī-ām'i 102
mica 103
Miç'h'i-gan 132
 products 139-145, 122
 surface 132-135
Michigan, Lake 37, 146
Middle Atlantic States 71
 agriculture 79
 cities 85-95
 climate 78
 drainage 75
 manufactures 85-95
 minerals 81
 settlement 71
 surface 73
midnight sun 399
Mi-kä'do 364
Mil'an 318, 319
Mil'ford 66
Mil-wau'kee 147, 152, 153
Min-dä-nä'o 195
mining 168, 81, 181
mining camp 169
Min-ne-ap'o-lis 149, 187, 152
Min-ne-so'ta 132
 climate 135, 41
 products 136-140, 143, 145
 surface 132-135, 38
Miq-ue'lōn' 25
Mis-sis-sip'pi 116
 climate 119
 products 120-124, 127, 104
Mississippi River 15, 23, 132
 flood plains and delta 116
 jetties 118
 land waste carried by 31
 levees 117
 meanders 14, 118
 navigation on 16, 118, 126, 152-153
 water power 148, 149
Mississippi Valley, Plains of 37, 41
Mīs-sou'la 171
Mis-sou'ri 132
 products 136-145
 surface 132-135, 38
Missouri River 15, 126
Mitch'ell, Mt. 10, 101
Mo-bile' 127, 120
Mo-ham'med-an-ism 342
Mo'hawk River 77, 85, 86
Mo'kha 347
Mo-line' 145, 149
Mō-len'do 237
Möm-bä'sä 381
Mōn'a-co 306
mon'areh-ies 270
money in Europe 271
Mon-gō'li-ā 357, 337
Mongolian race 340
Mo-nog-ga-he'la River 75
Mon-ro'vi-ā 369, 380
mōn-sōōns' 258
Mon-tā'na 157
 climate 158
 products 141, 163, 166-170
 surface 157, 38
Mōnt Blānc' 302
Mōn'te Car'lo 306
Mōn-te-ne'gro 324, 325
Mon-te-vid'e-o 234
Mont-góm'ēr-y 127
Mōnt Pē-le' 217
Mont-pē'lier (-yār) 55
Mon-tre-al' 208, 204, 207
moon 396, 249
Moors 374, 309
Moose/jaw 208
mo-raines' 20, 56
Mō'rā-vā Valley 325
Mo-rā'vi-ā 322-323
Mo-roc'cō 380, 373
Mos'cōw 331-332
Mo-sēlle' River 289
mountaineers, life of 3
mountains, formation of 34
 high 10, 221, 302, 337, 371
Mt. De-sērt' Island 67
Mount Vēr'non, N.Y. 86
Mo-zam-bique' 377, 381
Mük-dēn' 357
Mül-houze' 304
Mū'nieh' 290, 291
Mūr-mānsk' 332
Mūr'ra'y River 385
Mus-ko'gee 128
Nān'sei' Islands 363
Nāntes 301
Nan-tuck-et' 58, 67
Nā'ples 316, 318, 320
Nār-ra-gan'sett Bay 57
Nash'u-ā 62
Nash'ville 127
Näs'sau, Bahamas 217
Nä-täl' 382
Nätch'ez 116
national forests 162
Natural Bridge 101
natural gas 83
navigation, history of 249
Nāz'a-reth 347
Ne-bras'ka 132
 products 136-142
 surface 132-135, 32
Nēch'ēs River 114
ne-grī'tōs 196
negroes, in Africa 374
 in South America 226
 in United States 48, 97
 in West Indies 216, 217
negro race 374
Nel'son River 15, 16, 201, 207
Ne-pal' 353
Neth'er-lands 293
 colonies 217, 239, 355
Neū-çhā-tēl' 313
Neüse River 99
Ne-vā'da 157
 products 163, 166, 169, 170
 surface 157, 39
Ne'va River 332
New'ark, N. J. 95, 87
New Bed'ford 61, 60, 67
New Britain (brīt'n) 63
New Bruns'wick 199, 203
New'burgh 89
New Cäl-e-dō'ni-ā 391
New'cas-tle, Eng. 278, 280, 281
New Castle, Pa. 94
New England 53
 cities 61-67, 69-70
 climate 41, 58
 industries 59-67
 population 58, 68
 rivers 56
 settlement 53
 shore line 57, 67
 summer resorts, 67, 68
 surface 55, 36
New'found-land 209, 255
New Guinea (gīn'i) 355, 390
New Hamp'shire 55
 climate 58
 products 60-66
New Hā'ven 63, 68, 70
New Hēb'ri-dēs 391
New Jer'sey 73
 cities and industries 95
 position and surface 73, 77
 products 79, 80, 83
New Mex'i-co 157
 climate 158
 Indians in 22
 products 141, 163, 166-170
 surface 157, 38, 39
New Or'le-an's 126, 23, 120, 152
New'port, Ky. 128
Newport, R. I. 67
Newport News 109
New Ro-çhēlle', N. Y. 86
New South Wales 387, 389
New'ton, Mass. 69
New York, City of 85-88
 history 5, 23-24, 71, 85, 86
 manufactures 87, 62, 142
 milk supply 80
 railroads 86, 87, 95, 152
 tides at 249
 water supply 84
New York, State 73
 cities 85-91
 products 79, 80, 83, 84, 140
 surface 73, 77, 20
New Zēa'land 389-390
Ni-ag'a-rā Falls 13, 75
 water power 84, 91, 208
Niagara River 37, 75
Nic-a-rā'gua 215
Ni-gē'ri-ā 380
Ni-ger River 371
night, lengths of 399
Nīle River 371, 378, 15
Nin'e-vēh 347
Ni-o-brā'rā River 26
Nish 324
nī'trate rock 235
Nizhni Novgorod (nyzh'nyē nōv'gō-rōt) 332
no-mad'ic peoples 342-343
nōm'ads 342
Nōme 187, 188, 189
Nor'folk, Va. 106, 109
Nōr-ris-town 94
north, defined 393

- North A-měr'i-că 7
 climate 16
 coast line 9
 countries 28-217
 glaciers 19
 history 21, 23
 rivers 15
 surface 10
 North Cape 261, 297
 North Căr-o-li'na 99
 products 103-107
 North Central States 129
 cities 146-150
 climate 135
 industries 136-145
 physical features 132
 settlement 129
 transportation 151-153
 North Da-kô'ta 132
 climate 135
 products 136, 138, 139
 surface 132-135, 38
 northeaster 58
 northers 120
 North Frig'id Zone 398
 North Magnetic Pole 394
 North Pole 393, 253
 North Sea 265, 272
 North Star 393, 394
 North Temperate Zone 398
 Northwest Territories 201
 Norton Sound 186
 Nor'way 296-297, 3, 269, 273
 No'va Scotia (skô'shyá) 199
 products 203-206
 Nŭ-e'ces River 114
 Nu/rem-berg 290, 291, 4
 Nyä'sä, Lake 372
 O-ä'hü 195
 Oak'land 183
 o-ä'sis 342
 oats 139, 206, 277
 Ob (ób) River 338
 ocean basins 242
 ocean currents 246, 257
 ocean highways 249
 oceanic climate 17, 18
 oceans 242-251
 currents in 246, 257
 effect on climate 17
 life in 244
 uses of 249
 water of 244
 O'der River 266
 O-des'sa 332
 Og'den, Utah 171
 Og'dens-burg 91
 O-hi'o 132
 electric railroads 153
 products 136-145
 settlement 129
 surface 132-135
 Ohio River 75, 126, 152-153
 O-khôt'sk', Sea of 334
 O-kla-hô'ma 116
 climate 119
 products 120, 123, 125, 141
 settlement 113
 surface 119, 38
 Oklahoma City 128
 "Old Northwest" 132
 Old Point Comfort 108
 old valley 13
 olives 317
 O-lym'pi-ă, Wash. 174
 O-lym'pic Mountains 40, 176
 O'ma-hă 149, 169
 O-măn' 348
 O-nei'da Lake 74
 On-tă'ri-o, Lake 37, 75
 Ontario, province 201-208
 O-pôr'to 308
 Orange Free State 381-382
 oranges 179, 307
 orbit of the earth 395
 ore 168
 Oregon (ôr'tě-gôn) 174
 climate 177, 41
 history 47, 173
 products 178-184, 163
 surface 175, 39, 40
 O-ri-no'co River 221
 Orizaba (ô-rě-să/bă), Mt. 212
 Orleans (ôr-lă-ăn') 301
 O-rô'yă 237
 O-să/kă 365
 Osh'kosh 145
 ostrich 373, 382
 Os-we'go 90
 Ot-se'go Lake 74
 Ot'ta-wă 208, 199, 203
 Oŭ-ray' 170
 oxbow loops 14
 Ox'ford, England 283
 oysters 108
 O'zărk Plateau 38, 134
 Pa-cif'ic Ocean, currents 247
 islands of 390
 Pacific States 174
 cities 182
 climate 177
 industries 178-184
 settlement 173
 surface 175
 packing centers 142
 Pa-dŭ'căt 128
 pă'gans 342
 Pago Pago (păng'ô păng'ô)
 197
 Păi'tă 237
 Pa-lăr'mo 318, 320
 Pă'l'es-tine 347
 Pă'lm Beach 102
 Pă'lo Alto (ăl'tô) 183
 Pă-mir' Plateau 337
 Păm'li-co Sound 99
 pam'pă's 223
 Pan-a-mă' 25, 215
 Panama Canal 190
 Panama hats 238
 Pan-American Union 226
 Pă-nă'y' 197
 paper 63, 84
 Pă-ră' 229
 Păr'a-guay 234
 Paraguay River 222
 Paraguay tea 231, 235
 parallel of latitude 394
 Păr-a-măr'i-bo 239
 Pă-ră-nă' River 222, 234
 Păr'is 303, 304
 parks of Colorado 39, 157
 Păr'lia-ment, British 284
 Pas-a-de'na 183
 Pas-să'ic 95
 passes 314
 Pat-a-gô'ni-ă 233
 Păt'er-son 87, 95
 Paw-tuck'et 61
 peanuts 106
 Pă'a'ry, explorer 251
 peat 81, 56, 285
 Pe'ch'i-lŭ, Gulf of 358
 Pe-chô'ră River 266
 Pe-king' 362
 Pen'nine Chain 276
 Penn-syl-vă'ni-ă 73
 cities 85, 91-94
 climate 78
 products 79-84, 104
 surface 73
 Pe-nob'seot River 56
 Pen-sa-co'la 109
 pe'ons 213
 Pe-o'ri-ă 145, 150
 Per-di'do River 115
 Pěr-năm-bŭ'co 233
 Pěr'sia (-shă) 348, 341
 Persian Gulf 348
 Përth 389
 Perth Am'boy 95
 Pe-ŕŭ' 237, 221, 222, 225
 Pe-ŕŭ'vi-an bark 237
 Peruvian Current 247
 Pe'ters-burg, Va. 110
 Petrograd (pyě-trô-grăt') 332
 Pe-tro'le-um 82-83, 125, 181,
 367, 410
 Phil-a-del'phi-ă 91-92, 85, 78
 Phil'ip-pine Islands 195, 47
 Phœnicians (fě-nish'anz) 268,
 344, 347
 Phœ'nix 172
 phos'phate rock 103, 125
 phys'i-cal geography 24
 Piěd'mont Plateau 36, 100
 Piě'rre, S. Dak. 132
 Pikes Peak 155
 Pil-co-mă'yo River 219
 Pil'sen 323
 pioneers, life of 2
 Pŭ'reus (pŭ-rě'us) 326
 Pŭ'să 319, 320
 Pitts'burgh 2, 83, 93-94
 routes of trade 85, 92, 126
 Pitts'field 70
 Pi-zăr'ro, explorer 225
 plă'c'er mining 168
 plan'ets 396
 plantations 105
 Plă'tă River 222
 Pla-teau' (-tô') States 157
 cities 171
 climate 158, 159
 industries 163-170
 settlement 155
 surface and drainage 157
 trade routes 171
 plat'i-num 239, 331
 Plătě River 26
 Plŭm'outh, England 281
 Plymouth, Mass. 23
 Po-ca-tel'lo 171
 Po'land 298, 288
 po'lar regions 251
 Poles 298
 Pole Star 393, 394
 Pôm-pe'ti 316
 Pôn'ce 192
 Pônt'chăr-train, Lake 126
 Pôn'ti-ăc 147
 Po-po-că-te'pětl 211, 212
 population, density of 49
 Po River 266, 315, 317
 Port Arthur, Asia 357, 366
 Port Arthur, Canada 208, 137
 Port au Prince (pôr-tô-prăns')
 217
 Portland, Maine 70, 67
 Portland, Oregon 183, 182
 Pôr'to Ri'co 192, 47, 216
 Port Să'id' 378
 Pôr'ts'mouth, Eng. 281
 Portsmouth, N.H. 70
 Portsmouth, Va. 109
 Pôr'tu-gal 306-309, 270, 272
 Pôr'tu-gŭeze Guinea 377
 Portuguese 307, 269, 193, 226
 Pô'sen 298
 Postal Union 270
 potatoes 22, 80, 188, 272
 Po-tô'mac River 16, 35, 100
 Po-to-si' 238
 Potts'ville 81
 Poughkeepsie (pô-kip'si) 89
 poultry 80, 140
 Prague 322, 323
 prairies 37-38, 133-135
 glacial deposits on 21, 134
 life on 3, 5
 prairie schooners 48
 Press'burg 322
 prevailing westerly winds 18,
 253, 259
 storms of 44-45
 Pri-bi-lôf' Islands 188
 prime meridian 394
 Prince Edward Island 199,
 206
 Prince Rŭ'pert 208
 Prince'ton, N.J. 95
 Proc'tor, Vt. 66
 promontories 57, 202
 Prov'i-dence 70, 60, 62, 63
 Prussia (prŭsh'ă) 290-291,
 298
 Prŭth River 325
 Pue'blă 215
 Puěb'lo, Colo. 169, 170, 172
 Pueblo Indians 22
 Puěr'to Plă'tă 217
 Pŭ'get Sound 176, 181, 10
 Pull'man, Ill. 147
 pul'que 213
 Punakha (pôo-nŭk'ă) 335
 Pyn'tă A-re'năs 219, 235
 pŭ'r'a-mids of Egypt 377
 Pŭ'r'e-nees 263, 264, 302
 quarrying in New England 66
 Quě-běc', city 208, 207, 23
 Quebec, province 201, 203
 que-bră'chô wood 234
 Queens borough, 86
 Queens'land 387, 389
 Queens'town 281
 quicksilver 181, 308, 317
 Quŭn'çy, Ill. 145, 149
 Quincy (kwŭn'zi), Mass. 66, 69
 quŭ'nine 226, 237, 355
 Quito (kě'tô) 238
 races of men 340
 Ră'cŭne' 147, 145
 railroads 152-153
 in Canada 207
 in Europe 271, 283
 in the United States 50, 52
 (maps), 69, 85, 87, 92,
 109, 110, 152, 171
 rain 11-12
 rainfall 43; maps 42 (U.S.),
 222 (S. America), 256
 (world), 267 (Europe)
 Răi-niěr', Mt. 175
 Ră'leigh, N.C. 110, 100

- ranches 141, 140
 Rân-gôn' 353
 rapids 13
 Rap-pa-hân'nock River 99
 Râr'i-tan River 95
 Rêad'ing, Pa. 94
 Reclamation Service 165
 red men 21
 Red River (of the North) 207
 Red River Valley 138
 Red Sea 348
 redwoods 180
 Reggio (rêd'jô) 317
 Re-gi'na 208
 Reichstag (rîks'tāk) 288
 Rêims 304
 reindeer 189, 339, 343
 relief maps 28-35
 religions 341; in Europe 270
 Re'no 171
 Re-ün'ion 383
 rhê'â 224
 Rhône River 265, 266, 289, 291
 Rhône Island 55
 industries 61-63, 66
 Rho-dê'sia (-zhî-â) 382
 Rhône River 265, 301, 305
 rice 122, 196, 404, 317, 352,
 355, 361
 Rich'mond, Va. 110, 104, 100
 Rich'mond borough, N.Y. 86
 Ri'gâ 299, 266
 Ri'o de Janeiro (zhâ-nâ'rô)
 231
 Ri'o Grân'de 16
 river basin 15
 river bottoms 13
 rivers 11-15
 river system 15
 Riviera (rê-vyê'râ) 267, 305
 roads 151-152
 in Europe 271
 Ro'a-noke, Va. 110
 Röch'es-ter, N.Y. 90, 79
 Rock'a-way Beach 74
 Rock'ford, Ill. 145, 150
 Rock Island 145, 149
 rock layers, formation of 31
 rocks 393; folded 34
 rock waste 12, 20, 77
 Rocky Mts. 38, 157, 201
 climate 41, 43
 Rôme, Ga. 125
 Rome, Italy 319, 268-271
 rotation of crops 78
 Rot'ter-dam 294
 Rouen (rwân) 303, 304
 Rou-mâ-ni-â 325, 272
 Roumanians 325, 269
 Royal Gorge 159
 rubber 228-229, 354, 407
 Rûr River 289
 Russia (rûsh'â) in Asia 366
 Russia in Europe 329-332,
 267, 269-273
 Russians 269, 270, 330, 333,
 366, 367
 Rut'land, Vt. 66
 Rû-wen-zô'ri Mountains 371
 rye 139, 271
 Sâ-bine' River 115
 Sac-ra-men'to 183
 Sacramento River 176, 183
 Sag'i-naw 147
 Sa-hâ'ra 338, 373, 379
 Sâi-gôn 354
 St. An'tho-ny, Falls of 137, 149
 St. Au'gus-tine 102
 St. (sân) Bêr-nârd' Pass 314
 St. (sânt) Croix 192
 St. E-l'as, Mt. 187
 St. Etienne (sân-tâ-tyên') 304
 St. (sânt) Hê-le'na 383, 278
 St. John, Island 192
 St. John, N.B. 201, 203, 207
 St. Johns, Newfoundland 209
 St. Joseph, Mo. 142, 149
 St. Lawrence, Gulf of 9
 St. Lawrence River 15, 37, 202
 navigation of 9, 16, 37, 207
 St. Lou'is 148, 126, 142, 152
 St. Lucia (lû'shî-â) 217
 St. Marys River 37, 153
 St. (sân) Nâ-zâre' 301
 St. (sânt) Paul, Minn. 149
 St. Petersburg 332
 St. Pierre (sân-pyâr'), city 217
 St. Pierre, island 25
 St. (sânt) Thomas 192
 St. Vincent 217
 Sâ-khâ-lin' (-lyên') 363
 Sâ'lem, Mass. 69
 Salem, Oregon 184
 salmon 180, 185, 188, 205
 Sâ-lo-ni'câ 326
 salt 83, 244, 299
 Salt Lake City 169, 171
 salt lakes 39
 Salt River 167
 Sâl-vâ-dôr' 215
 Sâl-wîn' River 334
 Sâ-mo'â Islands 391, 47, 197
 San An-to'ni-o 127
 sand binding 57
 San Dî-e'go 173, 183
 San Fran-cis'co 182, 195
 San Joaquin (wâ-kên') R. 176
 San Jose (hō-sâ'), Cal. 183
 San Jose, Costa Rica 211
 San Juan (hwân), P.R. 192
 San Juan Mts. 170
 Sâ'n Lû-is' Po-to-si' 215
 Sâ'n Mâ-rî'no 319
 Sâ'n Sâl-vâ-dôr' 211
 Sâ'n'ta Bar'ba-ra 183
 Sâ'n'ta Fe' 172
 Sâ'n-ti-â'gō, Chile 235
 Santiago de Cû'bâ 217
 Sâ'n'to Do-min'go 217
 Santos (sân'toōsh) 233
 São Francisco (soun frân-
 sêsh'kōō) River 231
 Saône River 301
 São Paulo (soun pou'lōō) 233
 Sâr-a-to'ga Springs 96
 Sar-dîn-i-â 315
 Sârre Basîn 306, 303
 Sas-katch'e-wan 201, 202, 206
 Saskatchewan River 201, 207
 savages, life of 1
 Sa-van'nah 109, 104, 106
 Savannah River 100
 savannas 373
 Sâve River 324
 Sax'o-ny 291, 290
 Sean-di-na'vi-an Peninsula
 263, 264, 296
 Seheldt River 293
 Sehe-nêc'ta-dy 89
 Schleswig (shlâs'vîk) 288
 scientific farming 107
 Scil'ly Islands 276
 Scot'land 276, 269, 272
 Scran'ton 94, 81
 sea 242-251; life near 3
 sea bottoms 243
 sea breeze 258
 seals 188
 Se-ât'tle 184, 173, 179, 182
 sea water 244
 Se-bâs'to-pôl 331
 Seine (sân) R. 266, 301, 249
 Sel'kirk Range 201
 Sem-it'ic people 341
 Sen'e-câ Lake 74, 80
 Sê-oul' 366
 Sêr'bi-â 325, 324
 Sevres (sâ'vr') 304
 Sew'ard Peninsula 9, 187, 189
 Shack'le-ton, explorer 253
 Shâh 349
 Shâng-hâ'i 362
 Shas'ta, Mt. 40, 175
 Shawangunk (shōn'gūm) Mts.
 74
 She-boy'gan 145
 sheep 163-164, 307, 388
 Shef'field 278, 281, 283
 shêks 348
 Shen-an-do'ah River 36, 101
 Shêr'i-dan, Wyo. 170
 ship routes 249
 shore winds 258
 Shre'v'e'port 124
 Sî-âm' 354
 Si-be'ri-â 366, 338, 343
 Si'c'ly 315-317
 Si'don, ancient city 344
 Si-êr'ra Le-o'ne 380
 Sierra Mâ'dre 6
 Sierra Ne-vâ'da, Cal. 175, 40,
 41, 43; Spain 307
 Sî-lê'si-a (-shî-â) 298, 322
 silk 304, 317, 361, 407, 87
 si'lo 80
 silt 13
 silver 168, 214, 410
 Sil'ver-ton 170
 Sim'plon tunnel 314
 Sin-ga-pôre' 354, 335
 Sinkiang (sîn-kyâng') 357
 Sioux City 142
 Sioux Falls 149
 Sit'ka 188
 Skag'way 189
 slate 66
 slaughtering 142
 Sla-vôn'ic nations 269
 Slâvs 269
 Slo-vâks' 322
 Slo-vênes' 325
 smelter 169
 Smolensk (smô-lyênsk') 329
 Smyrna (smêr'nâ) 345
 Snake River 39, 159, 160
 snow 12
 snow line 312
 Sofia (sô'fê-yâ) 326
 soils 77-78
 so'lar system 396
 Sol'o-mon Islands 390
 So-mâ'li-land 376
 Sôm'er-ville 69
 So-no'ra 214
 Soo Canals 153
 sôr'ghum 122
 south, defined 393
 South Africa 382
 South America 219
 animals 224
 climate 222, 20
 coast line 222
 countries 231-239
 forests 223
 history, government 225
 industries 226-229
 people 226
 surface and drainage 221
 South-amp'ton, Eng. 281
 South Atlantic States 99
 agriculture 104-107
 cities 109
 climate 102
 minerals and forests 103
 physical features 99
 settlement 97
 South Australia 389
 South Bend, Ind. 145, 150
 South Câr-o-li'na 99
 products 103-107, 121
 South Central States 116
 agriculture 120
 cities 126
 climate 119
 lumber and minerals 124
 physical features 116
 settlement, 113
 South Da-kô'ta 132
 products 136, 139, 145
 surface 133, 134, 38
 South Frigid Zone 398
 South Pole 393
 South Temperate Zone 398
 Southwest Africa 382
 Spain 306-309, 268-273
 Spân'iârs 307, 269, 216, 226
 Spar'tan-burg 110
 Spo-kâne' 182, 176, 169
 Spring (season) 401
 Spring'field, Ill. 150
 Springfield, Mass. 70
 Springfield, Mo. 149
 Springfield, Ohio 145
 springs 11; hot 161, 162
 sta-lac'tites 101
 standard time 397
 Stan'ley, Henry M. 375
 stars 396
 states 48, 55, 73, 99, 116, 132,
 157, 174
 steamships 251, 249
 steel 94
 steppes 330, 338; life on 1, 343
 Stettin (shî-tê-tên') 290
 Steu'ben-ville 144
 Stock'hôlm 297
 stock raising 140
 Stock'ton, Cal. 183
 Straits Settlements 354
 Strâs-bourg' 302
 strawberries 107
 streams 11-15
 Strôm'bô-lî 316
 Sû-dân' 372, 379, 380
 Sud'bûr-y 205
 Sû-êz' 378
 Suez, Isthmus of 335
 Suez Canal 378
 sugar 121-122, 404
 sugar, maple 65
 sugar beets 122, 272
 sugar cane 121-122, 195, 216
 sulphur 125, 317
 Sul'tan 326

- Su-mā'tra 355
summer 398, 399
sun 395
Su-pe'ri-or 147, 143-145
Superior, Lake 37
surf 245
Sus-que-han'na R. 16, 74, 75
swamps 56
Swē'den 297, 269, 273, 333
sweet potato 107
swine 140
Swiss people 312, 3, 4
Switz'er-land 311-314, 273
Sŷd'ney, Australia 389
Sydney, Nova Scotia 201, 205
Sŷr'a-cuse, N. Y. 90, 83
Sŷr'i-ā 345
Tā-bā'tŷn'gā 221
Tā-bā'tŷn' 334
Ta-cō'ma 179, 181, 182, 184
Taganrog (tā-gān-rōk') 332
Tā'gus River 300
Tā'i-wān' 363
Tal-la-has'see 99
Tam'pa 102, 104, 109
Tām-pi'co 215
Tā-nā-nā' River 188
Tān-gān-yi'kā 381; Lake 372
Tan-ġēr' 380
tanning 62
tapir (tā'pēr) 224
tar 104
Tā-rim' River 357
Taş-mā'ni-ā 387
Tāun'ton 62
tea 361, 365, 405
teak'wood 352
Te-gŷ-cī-gāl'pā 211
Teheran (tē'h'rān') 349
Te-huān-te-pēc', Isthmus 212
Tel'lu-ride 170
Temperate Zones 398
temperature 16, 249, 254-259, 401
Ten-nes-see' 116
 products 120, 123-125
 settlement 113
terraces of soil 78, 361
Tēr'rē Haute (hōt') 150
Teu-ton'ic nations 269, 270
Tex'as 116
 climate 119
 history 47, 113
 products 120-125, 140, 163
 surface 119
textiles, defined 61
Thames (tēnz) River 266, 282
Thes-sa-lo-ni'ca 326
thunderstorms 44
Ti'ber River 315
Tī-bēt' 357, 337
tidal rivers 57
tidal wave 249
tides 247, 249
Tide'wa-ter country 36, 99
Tī-ēn' Shān' 337
Tī-ēn'tsin' 362
tierra (tyēr'rā) cā-li-en'te 212
Tierra dēl Fue'go 239, 222
tierra frī'ā 212
Tifis (tyē-flyēs') 367
Tī'gris River 347
timber line 39
Tim-bŷk'tŷ 380
time 397
Tī-rā'nā 326
Tisza (tē'sō) River 322
Tī-ti-cā'cā, Lake 237
tobacco 104, 123, 128, 216
Tō'go 376
Tō'kŷ-ō 365
To-lē'do 148, 143, 153
Tōmsk 366
Tō'ngā Islands 391
Ton'o-pah 170
To-pe'ka 149
To-rōn'to 208, 204
Tōr'rid Zone 398
tortillas (tōr-tēl'yāz) 213
Toŷ-louŷe' 301
Tours 301
trade winds 18, 255-257, 259
transportation 151
 of rock waste by streams 12-14
Trans-vāl' 381-382
Tran-syl-vā'ni-ā 325, 326
Tran-syl-vā'ni-an Alps 325
Treb'i-zond 345
Tren-ti'nō 321
Tren'ton 95
Tri-este' 320
Trin'i-dad, Colo. 170
Trinidad, island 217
Trip'o-li 379
Trondhjem (trōn'yēm) 297
tropics 398
Troy, N.Y. 89
truck farming 79, 107
Tŷc-sōn' 172
Tŷ-cŷ-mān' 233
tun'dras 9, 187, 339
Tū'nis 379, 373
Tū'rīn 319, 318
Tur-kē-stān' 367, 337
Tūr'key 327, 345
Turks 269, 324, 341
turpentine 104
Tŷ-tŷ-i'lā 197
Twin Cities 149
Two Harbors 143
Tŷne River 266
tŷ-phōōŷ' 359
Tŷre, ancient city 344
Tŷr'ōl 321
Tŷr-rhē'nī-an Sea 260
Ugāda (ōō-gān'dā) 381
U'krāine 333
Un-cōm-pāh'grē River 166
Union of South Africa 382
United Kingdom 275
United States 28-197; see
 also names of state groups
 climate 16-18, 41-46
 foreign trade 52, 226-227
 history 24, 46-49
 industries 49, 59, 79, etc.
 people 47-49
 railroads 50, 52 (maps),
 69, 85, 87, 92, 109, 110,
 152, 171
 rainfall 43
 surface 34-40, 20
U'ral Mountains 263, 329
Urga (ōōr'gā) 357
U'ru-guay 234
Urumia (ōō-rōō-mē'ā) 334
U'tāh 157
 climate 158
 irrigation in 164-166
 products 163, 169, 170, 122
 surface 157, 39
U'ti-cā 90, 80
Vāl'dez 189
Valencia (vā-lēn'shī-ā) 307,
 308
Valladolid (vāl-yā-thō-lēth')
 307
valleys 12; drowned 58
Val-pa-ra'i'so, Chile 235
Van-coŷ'ver, city 209, 202,
 204, 207
Vancouver Island 205, 173
vanilla 214
Vār-dār' River 325
Vat'i-can 319
veins, mineral 168, 169
Ven-e-zuē'la 239, 222
Vēn'ice 320, 318, 319, 344
Vē'rā Cruz (crōōs') 215
Ver-mōnt' 55
 climate 58
 products 60, 63, 65, 66
Ve-sŷ'vi-us, Mt. 316
Vicks'burg, 116, 126, 127
Vic-to'ri-ā. B.C. 209
Victoria, Lake 372, 381
Victoria, state 387, 389
Victoria Falls 372
vicuña (vī-kōōn'yā) 224
Vi-en'na 321
Vī'kings 269
Vir-gin'i-ā 99
 climate 102
 name 97
 physical features 99
 products 103, 106-108
Virginia City, Nev. 169
Virgin Islands 192
Vis'tu-la River 266
Vlā-dī-vōs-tōk' (-dŷi-) 366
volcanic islands 243
volcanic soils 77
volcanoes 193, 316
Vōl'ga River 266, 329
Vosges (vōzh) Mountains 302
Wā'bāsh River 131
Wāleŷ 275, 278, 269
Walfisch (wōl'fish) Bay 368
Walla Walla (wōl'ā wōl'ā)
 184
Waltham (wōl'tham) 63, 69
War'saw 298
Wā'satch Mountains 158, 39,
 41
Wash'ing-ton, city 111, 226
Washington, state 174
 climate 177, 41
 products 178-182, 136
 settlement 173
 surface 175, 39, 40
Washington, Mt. 10, 55
waste of the land 12, 20, 31
watches 63
Wa'ter-bur-y (-bēr-y) 63
waterfalls 13
water power 56, 60, 84, 108,
 297
Wa'ter-town, N.Y. 91
waves 244, 245
weather 41
Weather Bureau 46
weathering 77
weather maps 46, 45
Wel'land Canal 37, 153, 207.
Wel'ing-ton 385, 390
Weser (vā'zēr) River 286
west, defined 393
West'er-ly, R.I. 66
westerly winds 18, 253, 259
 storms of 44-45
Western Australia 389
West In'dies 216, 25
West Point 89
West Virginia 99
 physical features 99
 products 103-105
wheat 136, 138, 403, 79, 178
 in Argentina 233
 in England 277
 pictures 7, 38, 129, 178, 303
Wheel'ing 110
White Horse 189
White House 111
White Mountains 55, 64
white race 341
White Sea 265
Whit'ney, Mt. 175
Wich'i-tā 142
Wilkes-Barre (bār'i) 94, 81
Wil-lām'ette River 176
Wil'liams-port 94
Wil'ming-ton, Del. 109
Wilmington, N.C. 109
windbreaks 38
winds 18, 255, 258
Win-ne-pe-sau'kee, Lake 56
Win'ni-peg 208, 206
Win'ston-Sā'lem 104
winter 398, 399, 16
Wis-con'sin 132
 products 136-140, 143, 145
 surface 132-135, 20, 38
wood 65
woodlots 64
wood pulp 63
wood 164, 388, 406
woolen manufactures 62, 280
Wōōn-sock'et 62
Worces'ter 70, 63
world winds 255, 259
Wy-o'ming 157
 climate 158, 17
 products 163, 166, 170
 surface 157, 38
Yak'i-mā 184
Yak'i-mā Valley 178
yāks 357
Yāng'tzē River 338, 358
Yār-kānd' 357
Yar'mouth 204
year, defined 397
yellow race 340
Yel'low-stone Nat'n'l Park 161
Yēm'en 347
Yē-nī-sē'i River 338
Yo'ko-hā'mā 365
Yon'kers 89
York, Pa. 94
Yo-sēm'i-tē Valley 177
Youngs'town 144
young valley 12
Yŷ-cā-tān' 212, 214
Yŷ-gō-slā'vi-ā 324-325
Yŷ'kōn River 9, 16, 187
Yukon Territory 201, 206
Zām-be'zi River 372
Zanes'ville 145
Zān-zī-bar' 381
zinc 168
zones 398, 401
Zu'i'der Zee 293, 295
Zŷ'lŷs 374
Zŷ'rēh 313

GEOGRAPHY OF KENTUCKY

By C. J. NORWOOD, DEAN

College of Mines and Metallurgy, University of Kentucky

HISTORY

Long before white men or Indians ranged the wilderness west of Cumberland Mountain and south of the Ohio River, a primitive race of mound builders inhabited what is now Kentucky. In some respects they were more civilized than the red men known to the early explorers. They built roads and forts; and they buried their dead in mounds from which relics of their life and art are still obtained.

Later, the early colonists found no Indian tribes in permanent occupation of this region. It was a land of salt licks and springs, frequented by the buffalo; and hither led the well-worn paths made by the herds who visited these places. To the Indians this was a much-prized hunting ground, where game was plentiful, and for its possession the powerful eastern nations of red men contended in savage warfare.

It is perhaps for this reason that Kentucky is said to mean "dark and bloody ground." Some historians think that the word Kentucky means prairie or meadow land. The Indians were accustomed to burn off the trees in places, which provided forage to attract game, and they called this burned-off land *kentakekowa*. "Dark and bloody ground" is, however, the generally accepted meaning.

La Salle had crossed the region from the Big Sandy River to the falls of the Ohio, near where Louisville now stands, in 1669. He and his party were probably the first white men to set foot on Kentucky soil.

About 1750, Dr. Thomas Walker crossed the eastern mountains and built a cabin on the Cumberland River. He returned to Virginia shortly after. It was the description of

this wonderful hunting ground by John Findley, who visited it in 1767, that first attracted the attention of settlers east of the mountains.


Attracted by Findley's description, Daniel Boone made an expedition to the region in 1769. The British government

had previously purchased the land between the Ohio and Tennessee rivers from the Six Nations. Boone's enthusiasm, and the purchase of the Cherokee claim by a land company in 1775, stimulated settlement. Boone was sent to blaze the trail followed later by the famous Wilderness Road through the Cumberland Gap. Harrodsburg was settled in 1774, Boonesborough in 1775, Louisville in 1778, and Lexington in 1779. Other settlements followed rapidly.

To Kentucky fell the hard task of the frontier colony. The pioneers fought and held their own against heavy odds. Indian raids were constant surprises; during the Revolu-



Boone and his companions. Mural decoration in the State Capitol



tionary War the British allied themselves with the Indians and sought to destroy the settlements. Both the Spanish and the French were eager to prevent the new colonies from obtaining trading rights in the Mississippi Valley. But Kentucky vigor won. Kentucky County, including practically the same territory as the present state

of Kentucky, was formed in 1776, as a part of Virginia. Four years later it was divided into three counties, Jefferson, Lincoln, and Lafayette.

On June 1, 1792, Kentucky became a state, with Frankfort as its capital. It was the first state in the region beyond the Allegheny Mountains to be admitted into the Union.


GEOGRAPHY OF KENTUCKY

iii



Questions and Exercises.—1. Who were the earliest known inhabitants of what is now Kentucky? 2. Why did the various tribes of Indians fight for possession of this land? 3. What is the name Kentucky supposed to mean? 4. Who were the earliest explorers to set foot on Kentucky soil? 5. Who laid down the route of the Wilderness Road? 6. Where were the earliest settlements? 7. When was Kentucky admitted as a state?

Map Study.—1. In which group of states is Kentucky situated? (See page 116.) 2. Portions of what rivers serve as boundaries of the state? 3. How does Kentucky rank in area with the other states of the South Central Group? 4. In population? (See page 116.) 5. How many states have a larger area than Kentucky? (See page 413.) 6. What is the greatest length of the state? What is the greatest width of the



Kentucky, Ohio, and West Virginia at the junction of the Ohio and Big Sandy rivers

state? (Use ruler and scale of miles.) 7. In what zone does Kentucky lie? In what part of that zone?

9. Find your county on the map. 10. How far is it in a straight line from your home to Frankfort? 11. To Louisville? 12. How far is it from Louisville to Chicago? To New York? To San Francisco? To New Orleans? (Use ruler and scale of miles.) 13. What are the three most northerly counties of the state? 14. What county extends farthest east? Farthest west?

POSITION AND SIZE

Position.—Kentucky lies between the Appalachian Mountains and the Mississippi River, midway between the Great Lakes and the Gulf of Mexico (Fig. 58). Not only has Kentucky an irregular shape, but a small part of the state, embraced within a loop of the Mississippi River, is entirely separated from the main body of its area. On the west the state is bounded mostly by the Mississippi River. Low-water mark on the north bank of the Ohio River serves as the northern boundary and a small portion of the western boundary. On the east the state is bounded by the Big Sandy River and its branch, Tug Fork, which are tributary to the Ohio River. The southeastern boundary follows an artificial line from Tug Fork to

the Breaks of Sandy, a low gap through which Russell Fork enters the state from Virginia. The boundary then follows the crest of Pine Mountain to a point southwest of Pound Gap, where it takes the crest of Little Black Mountain for a short distance, and it then follows the ridge of Cumberland Mountain to Cumberland Gap. Most of the southern boundary is a line, beginning at Cumberland Gap, 7 miles north of parallel $36^{\circ} 30'$, and extending westerly to a point in the Tennessee River 12 miles north of the same parallel. The rest of the southern boundary follows parallel $36^{\circ} 30'$ from the Tennessee River to the Mississippi.

Most of the land within these boundaries belongs to the Cumberland Plateau, the southwestern extension of the great Appalachian Plateau. The land along the Ohio River, and west of the Tennessee in Kentucky forms part of the river plains of the Ohio and Mississippi rivers.

Kentucky is the most northerly of the group of South Central States. It occupies a central position among the five groups of states forming the eastern half of the United States. If we were to draw a line on the map from Augusta, Maine, to Austin, Texas, and another from Fargo, North Dakota, to

Jacksonville, Florida, the lines would cross not far from Bowling Green.

East of Kentucky lie West Virginia and Virginia, of the South Atlantic group; to the south is Tennessee, of the South Central group; on the west and north are Missouri, Illinois, Indiana, and Ohio, of the North Central group.

This central position is of immense advantage to Kentucky. The Ohio River is a great trade route which meets the highway of the Mississippi, and so connects the state with the large markets of the Mississippi Valley and the Gulf of Mexico. In addition to these waterways, railroads connecting the large inland cities of the east and west cross the state.

Size.—Kentucky has an area of 40,598 square miles. It is the smallest of the South Central States, but ranks next to Texas, the largest state of the group, in population. It ranks thirty-sixth in size among the states of the Union, and fifteenth in population. There are thirty-five states larger than Kentucky; and twelve states smaller. Texas, the largest state, is more than six times the size of Kentucky; while Kentucky has more than thirty-two times the area of Rhode Island. Kentucky is a little more than

three fourths as large as England. Its area is about equal to that of Ireland and Wales combined.


Questions and Exercises.—1. In what part of the United States is Kentucky? 2. What rivers form part of its boundaries? 3. How is the state bounded on the east? On the south? 4. What states lie east of Kentucky? West and north? What state lies south? 5. Of what advantage is this central position? 6. What is the area of the state? 7. How many states of the Union are larger? How many are smaller? 8. Compare its area with that of the largest state. The smallest state.

SURFACE

Many thousands of years ago, during the period when most of the coal of the world was formed, a slow upward movement of the land began in what is now Kentucky. By the close of the coal period all that portion of the state lying east of the Tennessee River was above sea level. At this or a later time, a broad and relatively low fold or arch was developed, extending in a general southwesterly direction across the state from the vicinity of Cincinnati to where it enters Tennessee from Cumberland County. It is commonly called the Cincinnati Arch because Cincinnati is the largest city on this uplift. The crest or



Natural bridge, Powell County



axis of the arch, in Kentucky, begins at the Ohio River about twenty miles southeast of Cincinnati. The highest points in the crest were in Bourbon, Scott, Woodford, Garrard, Mercer, Boyle, Jessamine, and Fayette counties. This formation passed through the present site of Lexington, and to it are due the very rich soils of Fayette County and other counties to the north and south.

In time through erosion this broad and low mountain was worn down to its present surface, forming the Lexington Peneplain. This peneplain (almost a plain) is partially surrounded by knobs, which are the remnants of a former and more extensive peneplain. The various strata of rocks, which have been exposed through the wearing down of the Arch, are characteristic of the natural regions between the coal fields in eastern and western Kentucky. The diversity of soils and the wide distribution of minerals in the state are chiefly due to this uplift and its subsequent reduction by erosion.

The only elevations in the state that now have the character of true mountains are

Cumberland and Pine mountains, besides those within the region between them, comprising the conspicuous eminences of Big Black, Little Black, and Log mountains.

Kentucky slopes in a general northwesterly direction from Cumberland Mountain on the east, to the lowlands along the Ohio and Mississippi rivers on the north and west. The altitude of the eastern part of the state varies from about 650 feet at the Ohio to more than 2000 feet in the southern uplands, and to about 4000 feet on Big Black Mountain, while some of the river plains in the west are scarcely 300 feet above the sea.

The average altitude of the state is about 800 feet, but a consideration of the altitudes of the several natural regions of the state will give a more definite knowledge of the height of its surface above sea level.

There are six distinct natural regions in Kentucky: They are: (1) the *Mountains* region, or the *Eastern Coal Field*; (2) the *Knobs*; (3) the *Blue Grass* region; (4) the *Cavernous Limestone* area; (5) the *Western Coal Field*; and (6) the *Jackson Purchase*.

The Mountains or Eastern Coal Field.—This region lies to the east of an irregular line between the northern extremity of Greenup County and the point on the Tennessee line where Clinton and Wayne counties meet. It is an upland in which the streams flowing down from the mountains have cut steep-sided valleys. High hills, and in the southeast a network of sharp ridges make the surface of this region very rugged and mountainous.

There is considerable agriculture in the valleys and on the hillsides. The soil of this region generally is not so well adapted to agriculture as is that in other sections of the state. There are, however, large areas of valuable forests, and rich stores of coal, iron, and valuable clays underlie the surface. Altitudes range from less than 1000 feet above sea level, toward the Ohio River and in the valleys of the principal streams, to about 2000 feet toward Pine Mountain, and to 3500 and 4000 feet in the highlands south of this ridge.

The Knobs.—West of the Mountains region is a plateau, bordering the Central region, principally on the west and south, which is known as the Knobs. This region resembles the letter *Y* in shape, and comprises many knobs on solitary hills of hard rock, often sandstone or sandy limestone, which have resisted the leveling processes of erosion. The western arm is a wooded ridge called Muldraugh's Hill, which stands out boldly from the lower land surrounding it. Some fruit is grown in the region, but it has not been widely developed for agriculture because the soil is thin.

Blue Grass Region.—Between the arms of the *Y* of the Knobs lies the Blue Grass region, known throughout the country. It has a rolling surface, upon which the blue grass spreads like a vast carpet. This

soft, rich grass forms excellent pasturage for the fine live stock for which Kentucky is famous. The soil has been formed by the crumbling of the underlying limestone beds. Its fertility makes the Blue Grass region a most prosperous farming section.

Cavernous Limestone Area.—The Cavernous Limestone area extends along the eastern and western border of the Knobs, and westward as far as the Tennessee River. It is a region of lime sinks, and of subterranean caverns, lakes, and rivers. These were formed by the action of surface water which, collecting in a favorable location, flowed downward through open joints in the limestone, which it dissolved. Finally through solution and erosion the cavities were enlarged, forming caverns. A sinkhole in this region usually indicates the initial stage in the formation of a cave, but some of the very large sinkholes were caused by the collapse of cavern roofs. When water has dissolved all it can hold of the minerals over which it passes, it frequently deposits them again in crystalline form. The dripping ground water forms beautiful stalactites which hang like icicles from the roofs of the underground caverns; and stalagmites, which extend upward from the floors directly below the stalac-



View in the Mountains region, Pike County



Stock farm in the Blue Grass region, near Lexington

tites. Altitudes in the Cavernous Limestone area range from 350 to 600 feet above the sea toward the Ohio River, and up to 950 feet toward the southern border of the region.

Mammoth Cave.—The Mammoth Cave, in Edmonson County, is the largest underground cavern known. It is really a series of avenues, which branch and re-branch from a main gallery so as to form a network of passages and halls of various dimensions, whose aggregate length is many miles, though

not so great as is generally supposed. Several streams flow through the cave; the principal one is called Echo River. Passages connect numerous halls or chambers, the largest of which is 450 feet long and 130 feet wide. The great stalactites and stalagmites in these halls, many of them grotesque in shape, add much to the interest of the visitor in this wonderful cavern.

Other beautiful, though smaller caves in this region are Diamond, Grand Avenue, and Great Onyx caverns. From the great area that is pitted by sinkholes, it is believed that several hundred caverns of noteworthy size exist in this region. The sinkholes serve the same purpose as artificial drainage, thus promoting favorable agricultural conditions.

Western Coal Field.—The Western Coal Field covers the area of about fourteen counties in the western part of the state. The Green River in its northward course flows through the midst of it. The region is less rugged than the Eastern Coal Field, and it is therefore better adapted to agriculture. The number of its coal beds, and its total tonnage, is considerably less than that of the field farther east. For many years practically all the commercial coal produced in Kentucky was mined in this field, and its miners still produce more than a third of the total




Stalactites and stalagmites, Mammoth Cave

output of the state. Altitudes here range from 400 feet above sea level in the northwestern portion of the field to 850 feet in the southeastern part.

The Jackson Purchase.

—The Jackson Purchase includes all of Kentucky west of the Tennessee River. It differs from the rest of the state in land formation. Its soils were formed beneath the waters of an arm of the Gulf of Mexico, when that body of water extended inland many thousands of years ago. The soils vary in richness, but the region in general is very productive. In this region altitudes range from 280 to less than 500 feet above sea level.

Questions and Exercises.—1. Describe the Cincinnati Arch. 2. What is the direction of the general slope of Kentucky? 3. Where are the



Dining hall in Mammoth Cave

highest altitudes of the state? The lowest? What is the average altitude? 4. Name the six important regions of the state. 5. Locate the Eastern Coal Field. Describe it. 6. What is the shape of the Knobs region, and where is it located? Describe it. 7. Where is the Blue Grass region? For what is it famous? 8. Locate the Cavernous Limestone area. Describe it. 9. Locate and describe the Mammoth Cave. What are stalactites? Stalagmites? 10. Where is the Western Coal Field? What river flows through it? 11. What part of the state does the Jackson Purchase include? How does

it differ in land formation from the rest of the state?

DRAINAGE

Kentucky is said to have over 3000 miles of streams that are more or less navigable or may be made so, exclusive of the rivers that bound it on the north, west, and east. This



View in the Mountains region from Pound Gap

GEOGRAPHY OF KENTUCKY



Drainage map of Kentucky

is probably a greater length of navigable waterways than is found in any other state of the Union.

The main streams of Kentucky follow a general northwesterly course, chiefly owing to the slope of the land, from Cumberland Mountain toward the Mississippi and Ohio rivers. In their courses down from the highlands, the streams have cut deep trenches which often have widened into beautiful valleys; in the higher reaches their banks are

often rocky and steep, and falls are rather frequent. Deep channels, which in some stretches have developed into gorges, have been cut also in the limestone areas of the lowlands, and cliffs of this rock rise on either side of the streams.

The larger rivers are navigable from the Ohio River to a considerable distance inland, owing to their deep channels and the absence of rapids. The rivers have large loops, often many miles in circumference, with comparatively narrow "necks."

The Ohio is the main stream, into which the other rivers empty. The Big Sandy, Licking, Kentucky, and Green rivers are its chief tributaries that are entirely within the state. In the extreme western part, the Cumberland and Tennessee rivers cross Kentucky. Both flow into a southward loop



The Ohio River

of the Ohio River about forty miles above the city of Cairo, Illinois, where it enters the Mississippi.

The federal government has constructed locks and dams on the Green, Kentucky, and Big Sandy rivers. Navigation is accordingly open on these rivers the year round, with the added advantage of the regulation of the flow of these streams which prevents dangerous floods.


Kentucky is noted for its many springs both of fresh and mineral waters. In the limestone regions, in central and southwestern Kentucky, streams often sink from view. Many of these run under ground and then reappear at the surface as "big springs," often of sufficient volume to furnish water power to turn mills.

During periods when the land was submerged, sea water became imprisoned within layers of rock and in underground basins. This salt water was gradually forced up in springs. These are the mineral springs about which "salt licks" are found.





Junction of the Kentucky and Dix rivers

Questions and Exercises.—1. How many miles of navigable streams has Kentucky? 2. What is the general direction of flow of the main streams? 3. Describe the course of the rivers through the highlands; through the lowlands. 4. What are the most important rivers? Locate each one on the map. 5. What two important rivers cross Kentucky in the western part of the state? Into what river do they flow? 6. Of what advantage to the state are locks and dams in Kentucky rivers? 7. What is said of springs and underground rivers? 8. What is the source of the salt in underground basins? What are salt licks?



Lock and dam in the Kentucky River, Ravenna



CLIMATE

Latitude, altitude, nearness to the sea, and the direction of prevailing winds determine the climate of a locality (Secs. 57-60).

Kentucky lies in the temperate belt, and the climate is mild. The temperature in different sections of the state varies considerably because of the difference in altitude. The mountains are cooler than the lowlands. As no large bodies of water are near by, the climate is continental. The temperature rarely falls below zero, or rises above 100° F., so that the climate may be considered mild.

The annual rainfall ranges from about 40 inches in the most northern counties to about 53 inches in the extreme southeast. The moisture in the winds crossing the state from

the west and southwest condenses near the eastern mountains, so that the mountainous sections have more rainfall than the lowlands. The mountain regions of Kentucky have an annual rainfall of about 48 inches.

Kentucky lies in the track of storms which sweep up the Mississippi Valley from the Gulf of Mexico. It lies also in the track of storms of prevailing westerlies which cross the continent from west to east (Sec. 61).

The abundance of moisture and the mild weather conditions make it possible to raise a great variety of crops.

Questions and Exercises.—1. What kind of climate has Kentucky? 2. What is the coolest section of the state? 3. What is the range of temperature in the state? 4. What section has most rainfall? What section has least rainfall?



Cumberland Falls



Harvesting blue grass seed

FORESTS AND GAME

Forests.—Before the days of the white man, several tribes of Indians made regular trips to the land just south of the Ohio River, to hunt the buffaloes which congregated about the salt licks. There the year's supply of meat was collected, dried, and packed to carry away. Clothing and shelter were fashioned by the Indians from buffalo hides.

Kentucky was covered with forests, in the days of Indian occupation, except for a section in the central part, known as "the barrens." The unforested section occupied about ten per cent of the total area of the state. So dense was the forest growth in the forested regions that the first pioneers actually carved their way through it. The first highway, which was built over the trail laid out by Daniel Boone, was known as the Wilderness Road.

Much of the original forest area has been cleared for lumbering and farming purposes, but there is still considerable timber land in the eastern part of the state. Some of the cleared lands proved unprofitable for agriculture, and have been aban-

doned. These, in most cases, are reforesting themselves.

Kentucky lies in the heart of the region once occupied by the great central hardwood forest of the country. More than half of the original timber has been cut, to make way for settlement. Unlike the forest belts north and south of it, in which the pines predominate, this is a region favorable to the growth of hardwood trees. Walnut, oak, elm, hickory, cottonwood, basswood, chestnut, sycamore, red gum, and ash predominate.



Hauling blue grass seed to market



Apple orchard

Game.—The buffalo has gone from Kentucky. Other large game also has been practically exterminated, although occasionally a bear or deer is to be found in the mountain region. Smaller game,—the wildcat, fox, raccoon, and opossum—is plentiful in some districts; field rabbits, ground hogs, and squirrels are common throughout the state.

Birds are plentiful. Wild turkeys are found in unsettled regions at certain seasons, also wild ducks and wild geese. Many songsters

are migrants in the state; many others are permanent residents. The “Kentucky Cardinal” is famous.

The rivers yielded an abundance of fish in the early days. Persistent fishing has resulted in the extermination of some varieties, and great reduction of the stock of fish in general, in the Kentucky streams. The State Game and Fish Commission strives to destroy all nets and traps set illegally, and to punish violators of the laws protecting fish and other game. The federal government supplies fish for stocking the streams which are protected by warden services. A hatchery has been established near Louisville, to further this work.


AGRICULTURE

Nearly nine tenths of the total land area of Kentucky is in farms. The large majority of the people of the state obtain their living from farming.

In the past seventy years many of the plantations have been broken up, until now the average size of a farm is about 80 acres. The smaller acreage makes possible more care-



A Kentucky hemp field



ful farming, and the raising of a great variety of farm products.

The wide differences in soil and the mild climate allow the farmers of Kentucky to raise every kind of crop suited to the temperate zone. Stock raising is an important industry in the Blue Grass region. Tobacco is a staple product in the limestone districts, and in the Jackson Purchase region where cotton is also a crop of some importance. Corn is, however, the leading crop of the state.

Crops.—The total value of all crops raised reached about \$400,000,000 in 1919. Two fifths of this value was contributed by cereals, over two fifths by tobacco, and the rest by vegetables, hay, sugar crops, fruits, and minor products.

The average value of the corn crop is about four times that of all the other cereals combined. In 1919 about 1,000,000 acres of land were

planted to wheat. This cereal, as well as buckwheat and barley, thrives on suitable soils throughout the state.

Tobacco, in 1919, surpassed all cereals combined in market value. Kentucky produces more tobacco than any other state of the Union.



White burley tobacco



Tobacco in warehouse at Lexington

About 33 per cent of the entire crop of the country comes from this state. While more or less tobacco is grown in every county, the north-central or Blue Grass district and western Kentucky are known as especially important tobacco-raising regions. Several varieties are grown, and much of the product is exported to foreign countries.

The raising of vegetables for shipment to near-by cities is rapidly increasing. The value of the potatoes and vegetables produced in Kentucky amounts to about \$15,000,000 a year. The fruit crop is worth about \$5,000,000 annually. Apples supply more than three fourths of this value. Peaches, pears, plums, cherries, quinces, apricots, and small fruits are raised in large quantities, and find ready markets in the cities of Kentucky and the neighboring states. Large quantities of the fruits and vegetables, or about 150,000 cans, are canned each year for winter use and for sale, under the auspices of the Girls' Canning Clubs.

Hay, alfalfa, and other forage crops grown for live stock rank third in value among the farm products. Considerable blue grass seed is raised. Hemp is grown extensively in the Blue Grass region, and the amount is increasing from year to year.

Live Stock.—Kentucky horses and cattle are famous the world over. The live stock of the state is valued at about \$190,000,000. Horses and mules make up about 40 per cent of this amount, cattle 30 per cent, and swine half the remainder. Many sheep are raised.



Cutting and spreading hemp



A herd of short horn cattle

Dairying is increasing rapidly. Registered cattle are being raised more and more to improve the dairy herds. Some of the best work in improving the swine stock has been done by the Boys' Pig Club, whose members raised prize-winning pigs.

Questions and Exercises.—1. What proportion of the land area of Kentucky is in farms? 2. What is the average size of the farms? What is the advantage of the small farms? 3. What are the most important crops raised? 4. What are the most important tobacco-raising sections? 5. What kinds of fruits and vegetables are grown in your locality? What important work are the girls of the state doing to conserve these products? 6. What is the value of the live stock of the state? 7. What part have the boys of the state had in improving the live stock?

MINING

Of the total expanse of the state about 16,600 square miles are covered by coal-bearing formations, in which occur, according to locality, from nine to twelve workable seams. Coal contributes nearly four fifths of the value of all the minerals produced in Kentucky. As early as 1829, coal was shipped down the Cumberland River to Nashville from the Eastern Coal Field. It

was mined below the junction of the Laurel and Cumberland rivers. The coal was used largely in operating iron furnaces and salt works.

Kentucky has now become one of the five leading states in coal production. The Eastern Coal Field supplies more than the Western Coal Field. In 1904 the total output of commercial coal mines amounted to 7,167,324 tons, of which the Eastern Coal Field furnished only 3,045,760 tons. The growth of production in later years is illustrated by the following figures

showing the output of the respective coal fields for 1908 and 1917:

FIELD	TONS PRODUCED, 1908	TONS PRODUCED, 1917
Western Coal Field	5,634,596	9,936,538
Eastern Coal Field	4,171,181	17,770,140
Total	9,805,777	27,706,678

Thousands of men are employed in the mines. Machinery is used in drilling, breaking, and hauling the coal, and the amount produced by each miner per day has increased greatly under modern mining methods. Less than a tenth of the coal obtained is mined by



Boys' Pig Club at county fair



Exterior of coal mine, Jenkins

hand. More than three fourths is mined by machines, and a portion is shot off the solid masses in the seams with the aid of powder. Considerable coal is made into coke.

Natural gas is found in several counties. It is piped to neighboring towns and near-by cities. The gas fields of the state have not, however, proved adequate to supply the demand, and more than half the gas consumed in Kentucky is piped from West Virginia.

Oil wells in many counties produce crude petroleum. In 1829, a well sunk near Burkes-

ville yielded oil which flowed to the surface and was drained into the Cumberland River. Estill County now leads in oil production, the annual yield amounting to more than that of all the rest of the state put together.

There are great areas of limestone and sandstone, which have a high value for structural and other purposes. Limestone is used for buildings, the making of lime, and as a flux in iron and steel smelting. It is also crushed for road making, and for concrete paving and similar purposes. The onyx marble of Barren County serves for interior decoration, table tops, and like uses. Sandstone is used widely in building. Fine freestone is obtained in Rowan County, and also in Rockcastle County.

Over the whole of the Jackson Purchase, an area of about 2800 square miles, very excellent clays abound, which furnish materials for the brick, tile, and pottery industries. Here also are valuable sands, siliceous earths, and earthy lignites. Adjacent to the Western Coal Field is an area of 1000 square miles in which




Interior of coal mine

are found excellent plastic clays and some kaolinitic clays, while on the western margin of the same field and in the Eastern Coal Field are large areas of high grade clays which yield fire brick of excellent quality. There are large areas of fine clays on the rim of the central region, and superior cement materials are found both here, on the margins of both coal fields, and elsewhere in the state. Molding and glass making sand, and many other varieties of sand and gravel, are found in various parts of the state.

Asphalt rock, a sandstone high in percentage of bitumen, exists in workable deposits in the margin of the Western Coal Field, also in some sections of eastern Kentucky. It is used for paving, road making, and other purposes.

There are hundreds of square miles of iron ore favorably located with reference to coal

and limestone, besides deposits of lead and zinc. These resources are not extensively developed because they cannot compete with the larger deposits elsewhere in the country. Kentucky at one time ranked as a leading state in iron production. Deposits in other



Oil wells, Estill County



Coal barges on the Ohio River



Rafts of logs at the mouth of the Big Sandy River

states which could be more profitably worked and transported caused the industry to decline. The Kentucky iron ores are now classed as important reserves for future use.

A region of about 6000 square miles in western and central Kentucky is rich in veins of fluorspar, calcspar, and barites, with some zinc and lead. Fluorspar, used as a flux in steel, glass, and pottery manufacture, is obtained from mines in Livingston, Caldwell, and Crittenden counties. Calcspars are mined and ground in Mercer County. It is used in various manufactures, including rubber goods, paints, and putty. Barites, used in making paint and for other purposes, is mined and ground in the Blue Grass region. Phosphate rock is found also. Lithographic stone is obtained in Meade County. Among other mineral resources are salt, metallic paint and pigment earths, potash shale, and bituminous shale, which in time may be used for the production of fuel gas.

Questions and Exercises.—1. What is the most valuable mineral product of Kentucky? 2. When

and where was coal first mined in the state? 3. What are the two important coal fields? Which supplies more coal? 4. How is the coal obtained from the mines? 5. About what proportion of the natural gas used in the state is obtained from Kentucky wells? 6. When and where was the first oil well sunk? 7. What county leads in oil production? 8. For what is limestone used? 9. In what county is onyx quarried? 10. Where are sand and gravel found? Freestone? Clays? 11. Where is asphalt rock found? 12. Why is Kentucky no longer a leading state in iron production? 13. Where is fluorspar found? For what is it used? 14. Where is barytes obtained? Lithographic stone?

LUMBERING

In many counties, particularly in southeastern Kentucky, lumbering is the leading industry. Oak is the principal wood cut, followed by yellow poplar, beech, red gum, chestnut, yellow pine, and hickory. Wherever practicable, logging operations are carried on about the headwaters of streams, down which the logs may be floated to the sawmills. The same streams often supply the water power for sawing the logs into lumber.

In 1916, Kentucky produced 525,000,000 board feet of lumber. Of this, 186,126,000 board feet was soft wood, consisting mainly of yellow pine and white pine, hemlock, cedar, cypress, and spruce. The remaining 338,174,000 board feet was hardwood. Oak, yellow poplar, beech, red gum, chestnut, hickory, ash, basswood, and maple were the chief varieties cut.

Questions and Exercises.—1. In what part of the state is lumbering the leading industry? 2. Why are sawmills likely to be located near the headwaters of streams? 3. About how much lumber is sawed in the state in a year? 4. What soft woods are cut? What hardwoods?

MANUFACTURING

The first manufactures of the Kentucky pioneers were articles necessary for life in a frontier colony. Houses were built of logs from the forests. Clothing was made from the skins of animals, which for a long time served as the only source of a fresh food supply. Later, garments were fashioned of home-grown wool, which was spun, woven, and made up by hand during the winter. Shoes, furniture, and even tools were made by hand, until regular transportation connected the frontier settlements with the older colonies, making trade possible.

Manufacturing develops where there is a



Shore of the Ohio River, showing log-raft construction

bountiful supply of raw material, cheap power for operating mills and factories, markets where finished articles may be sold, and good transportation facilities. The manufactures of Kentucky use raw materials from the farms, forests, and mines of the state. Power is obtained from the coal deposits and the streams, while the rivers and railroads supply means of transportation for marketing the finished products.

Flour and cornmeal, lumber and timber products, and tobacco are the leading manufactures. The making and repairing of machinery, ironwork, and hardware, and the production of iron and steel are other important industries.

The deposits of iron ore in many parts of the state early developed the iron and steel industry. It was in Kentucky that the airblast method of converting iron into steel was first put in operation by William Kelly, on the Cumberland River in Trigg County. This was several years before the method was introduced in England by Henry Bessemer, in whose honor the process was named.

The preparation and curing of meat for market is an important industry. More people are engaged in the lumbering industry than in any



Hauling white oak logs to the railroad



Coke ovens, Ashland

other manufacturing occupation. Over 1500 establishments depending directly upon the lumber supply employ about 15,000 men. Car shops, operated by steam railway companies to build and repair cars and locomotives, also employ great numbers of men.

The printing and publishing of books, magazines, and newspapers, and the manufacture of men's clothing also employ thousands of people. Both rank among the ten leading industries of the state. There are many establishments which manufacture food products, clothing of various kinds, boots and

shoes, furniture, paints, hardware, building materials, and boats.

Questions and Exercises. — 1. What were the first manufactured products of the state? 2. What conditions cause manufacturing interests to develop in a special locality? 3. From what sources are the raw materials used in Kentucky manufactures obtained? 4. How is the power obtained? 5. How are the products transported from the factories? 6. What are the leading manufactures of the state? 7. Where and by whom was the air-blast method of converting iron into steel first used? For whom was the process named? 8. What industry employs the largest number of men? 9. Name other industries employing many workmen.

TRANSPORTATION

The first pioneers in what is now Kentucky used the buffalo paths which led from one salt lick to another through the wilderness, or the Indian trails which also often ended at a salt lick or spring. Over these roads supplies were carried on horseback, and later by wagons. Many of the old roads are still in use.

Later, settlers and supplies came in flat-boats down the Ohio River. Most of the early settlements were on or near navigable rivers, because these were an easy means of trade. Railroads later supplemented the



Iron works, Ashland

ivers. In 1835 the first locomotive and train of cars reached Frankfort from Lexington, after covering the distance of twenty-nine miles in two and a half hours. Railroad building was slow for a time, owing to the wealth of navigable waterways in the state, but by 1880 there were 1530 miles of road in operation. By 1922 this mileage had increased to about 4000.

Large areas in the mountain region of eastern Kentucky are still unreached by railroads, owing to the ruggedness of the country. Advantage has been taken of the work done by the streams in cutting valleys through the mountains, to lay the roadbeds along the rivers. Most of the railroads in the eastern part of the state, accordingly, parallel the main rivers. Over these railroads the coal and lumber of the mountain region are brought out, and the products of other sections of the state are carried in. In portions of this region there are scarcely any roads, the settlements are so few and the country is so rugged. Communications and supplies still reach these isolated districts by horseback.

Electric railways connect some of the larger cities of the state with each other and with near-by cities in the neighboring states.




Central power plant

The abundance of good roadbuilding material throughout the state encourages the construction of highways. The people of Kentucky are realizing more and more the value of good roads in furthering agriculture and commerce, and thus adding to the wealth of the state.

Questions and Exercises.—1. How did the Kentucky pioneers find their way about the state? How were supplies carried? 2. Why were most of the early settlements located near rivers? 3. When, and between what two cities, was the first railroad train run in the state? 4. How many miles of railway were in operation in 1880? What was the mileage in 1922? 5. Why were the railroads in the eastern part of the state laid out parallel to the rivers? 6. What products are brought from the mountain region over these railroads? 7. How are supplies carried to the regions where there are neither railroads nor navigable rivers? 8. What connections are provided for by the electric railways of the state? 9. What natural advantages does Kentucky possess for the construction of good roads? State the leading benefits which are derived from good roads.



River steamers at wharves on the Ohio



State capitol, Frankfort

GOVERNMENT

Like the federal government, the state government of Kentucky consists of three departments. These are the legislative or law-making department, the executive or law-enforcing department, and the judicial or law-interpreting department.

The legislative department, called the General Assembly, consists of a senate and a house of representatives. The senate has 38 members, holding office for four years. The house of representatives has 100 members, holding office for two years. The General Assembly meets at Frankfort every

two years, but the governor may call an extra session at any time.

The executive department consists of the governor, lieutenant governor, secretary of state, treasurer, auditor of public accounts, attorney-general, commissioner of agriculture, and superintendent of public instruction, all elected for a four years' term.

The judicial department consists of the Court of Appeals, and circuit, county, justice, and police courts. The

Court of Appeals has seven judges, elected for a term of eight years.

Each of the 120 counties of Kentucky has its own officers for the administration of local government. The state sends 2 senators and 11 representatives to Congress. It has, therefore, 13 votes in the electoral college.

Questions and Exercises.—1. What are the three departments of the state government? 2. What is the legislative department called? 3. How many representatives? Senators? Terms of office? 4. Who are the chief executive officers? Term of office? 5. What are the important courts? 6. How are counties governed? 7. How is Kentucky represented in Congress? In the electoral college?



The University of Kentucky, Lexington



Western State Normal School

Administration Building, University of
Kentucky

Eastern State Normal School

EDUCATION

A State Superintendent of Public Instruction, elected for a term of four years, serves as general supervisor of education in Kentucky. He is aided by the State Board of Education, of which he is a member, and which includes also the secretary of state and the attorney-general.

Each county has a county superintendent of schools, who is elected by the County Board of Education. He is the executive officer and secretary of the county board; working under his direction are the local boards of each school district. The chairman of these local boards, together with the county superintendent, form a board of education which manages the school affairs of the county.

Every child in Kentucky between the ages of six and eighteen years is entitled to free instruction in the schools of the state. Separate schools are maintained for white and for black children.

Pupils who complete the work in a grade school may enter high school and receive instruction free. Every year the accredited high schools may send graduate students to the University of Kentucky at Lexington, to enter without examination. All students here receive free instruction.

The University of Kentucky stands at the head of the public school system of the state. It has colleges of arts and science, agriculture, civil engineering, mechanical and electrical engineering, mines and metallurgy, and law, besides departments of home economics, physical education, and military science. The college of arts and science includes a department of education with a four years' course for the training of teachers.

Students who wish to prepare for the teaching profession may attend the Western State Normal School at Bowling Green, Murray Normal School at Murray, the Eastern State Normal School at Richmond, or the Morehead Normal School at Morehead, where they receive excellent training. The



Lincoln Memorial, Lincoln National Park



Fourth Avenue, Louisville

Normal and Industrial School at Frankfort fits colored students to become teachers in the colored schools of the state.

Colleges and preparatory institutions are carrying on progressive educational work throughout the state. Transylvania University at Lexington is the oldest. Central University, at Danville, is noted for the large number of its alumni who have attained prominence in public life. Berea College, at Berea, is noted for its efficient work along vocational lines.

Questions and Exercises.—1. Who is the general supervisor of education? By what board is he aided? 2. How is the education of each county managed? 3. Between what ages has a child a right to free instruction? 4. What education, beyond the elementary school, can be obtained at public expense? 5. What institution stands at the head of the public school system? 6. Of what departments does the University of Ken-

tucky consist? 7. Where are the state normal schools located? 8. What is the oldest college in the state? 9. For what is Central University noted? Berea College?

POPULATION AND CITIES


Kentucky had a population of 2,416,630 in 1920. It ranks fifteenth among the states of the Union in total population. More than three fourths of the inhabitants are classed as rural, that is, the people live in the country or in the smaller towns. Kentucky is therefore an agricultural state. There are, however, a number of large towns which are rapidly increasing in population.

About nine tenths of the inhabitants were born in the state. A large proportion of these are of English descent. Most of the others live in the larger cities, where they are engaged in manufacturing industries.

Louisville is the only city of Kentucky which ranks among the cities of the first class. That is, it is the only city with a population of more than 100,000. The inhabitants number more than 230,000. Louisville grew from a small town of log cabins, founded by settlers who had come down the Ohio River with George Rogers Clark. The pioneers settled first on an island opposite



Free Public Library, Louisville



Covington and Newport, at the mouth of the Licking River

the falls of the Ohio, which has since disappeared. In the spring of 1780 they removed to the mainland.

The town prospered from the first, because of its advantageous position on a main waterway. The rapids, having a fall of twenty-five and a fourth feet, furnish excellent water power. A canal two and a half miles long has been constructed around them, so that they do not impede navigation. Steamboats from Louisville reach more than thirty navigable rivers. Commerce and manufactures developed early, as the result of this river trade and water power. The city is now also the center of a network of railroads, which connect it with the other cities of the state and with the neighboring states. Several bridges cross the Ohio at this point, and the water frontage covers a distance of over eight miles.

Its transportation and manufacturing facilities have made Louisville the metropolis of the state. It has ready access to a region of well-developed farms, immense forests, and large coal and iron mines. It is probably the largest tobacco market in the world. Besides tobacco, machinery, flour, dressed meats, clothing, leather, lumber products, cottonseed oil, and numerous other products are manufactured. The city is a distributing market

also for commodities from other states.

Louisville is an educational center, with technical schools and colleges, and with a large library. Many public buildings, hospitals, and other institutions are situated here. Several extensive parks, and the near-by Fair Grounds are other advantages which help to make Louisville a center.

Covington is situated on the Ohio River directly opposite Cincinnati. The Licking River flows into the Ohio at this point. It is the second city of the state in population. Like

Louisville, it owes its growth to the trade facilities of the rivers, which have been supplemented by railroads and bridges connecting the city with Cincinnati and Newport.

Covington manufactures engines and machinery, tobacco, and many other products. The main county offices of Kenton County are located in Covington, and it serves as the marketing center for the surrounding districts. Several public and private institutions have made the city a prominent social center.

Lexington is the county seat of Fayette County, in the heart of the Blue Grass country. The surrounding farm region is fertile and well-populated. The city is consequently



Approach to suspension bridge, Covington



Main Street, Lexington

a large trading center for the abundant grain and tobacco crops of the region, as well as a market for the fine horses and live stock which have made this section of Kentucky famous.

Next to Louisville, Lexington is the largest tobacco market in the state. It is the largest loose leaf tobacco and re-drying market in the world. Railroads and inter-urban electric lines connect it with other centers of Kentucky, and provide means for distributing the produce marketed here.

Lexington is one of the oldest cities in the state. It is the home of the descendants of many of the original settlers from Virginia. It was founded in 1779, and named from the first battle of the American Revolution. Ashland, near by, is celebrated as the home of Henry Clay.

Transylvania University, the first school for higher education to be established west of the mountains, is located here. The University of Kentucky and other


collegiate institutions and schools have made Lexington well known as an educational center.

Newport is opposite Cincinnati on the Ohio River, and east of Covington on the Licking River. It has the same transportation facilities as Covington. The chief county offices of Campbell County are located here. Newport manufactures iron products, and is a market for the farms of the surrounding country. Near both Newport and Covington are numerous towns which are really suburbs of these cities and of Cincinnati, but which have grown to be small cities themselves. Each has its trading and manufacturing district. This group forms, with Cincinnati, a population center of nearly a million people.

Paducah is located in western Kentucky, on the Ohio River at the mouth of the Tennessee. Its advantages in the way of excellent waterways and good railroad facilities have made it develop rapidly. Great tobacco warehouses and factories are situated here, stemming and preparing tobacco for export being a specialty in Paducah. Many of the inhabitants are employed in the railroad construction and repair shops. Others are en-



Court House and Public Square, Lexington



View in the business section of Paducah

gaged in lumber manufacturing and the shipping of produce from the neighboring farm lands. Paducah is the county seat of McCracken County.

Owensboro, on the Ohio River below Louisville, is the county seat of Daviess county. The river and railroads supply transportation for the many farm and factory products. The outlying region yields large corn, tobacco, and hay crops. Tobacco and food products, and wagons are marketed here. Coal and iron are mined, and marble quarries are worked in the vicinity.

Henderson is located on the Ohio River, west of Owensboro. It is the county seat of Henderson County. It is about midway between Louisville and Cairo on the Ohio, and just south of Evansville, Indiana. The river and railroad transportation has led to commercial growth. Tobacco and fruit from neighboring farms, as well as grain and hay, are marketed in Henderson. Factories for tobacco products, wagons, and lumber products are located here.

Frankfort is the capital of the state and the county seat of Franklin County. The city is built on both sides of the Kentucky River, and thus has excellent navigation facilities.

Logs from the uplands south and east of Frankfort are easily floated down the river,


and the manufacture of lumber products is an important industry. The city is a center for the manufacture of boots and shoes. Farm products from the near-by region are marketed here. Flour and canned goods are manufactured. Other public buildings, as well as the State Capitol, are located at Frankfort.

Hopkinsville is in the western part of the state, the county seat of Christian County. It is surrounded by a region of productive farms. Coal, iron, and timber abound near by. It has factories and mills for

the manufacture of cigars, flour, building materials, and other products.

Bowling Green is located at the head of navigation on the Barren River. It is the county seat of Warren County. Besides its river transportation facilities, it is connected by railway with the principal cities in western Kentucky, and with Nashville and Clarksville in Tennessee. Live stock and tobacco raised in Warren County are shipped from here. Strawberries in their season are sent by the carload to northern markets from Bowling Green.

Natural gas and oil are found near by, as well as valuable quarries of limestone suitable for building purposes. There are tobacco factories, flour mills, and foundries. The Western State Normal School and other institutions have made Bowling Green an



Ashland House, the home of Henry Clay

educational center for the western part of Kentucky.

Ashland is on the Ohio River in eastern Kentucky. It is the largest city in north-eastern Kentucky. Coal, iron, and fire clay are mined in the vicinity. These provide material for the iron, steel, brick, pottery works, and by-product coke ovens in or near the city. Shipbuilding and car repairing are important industries. Ashland has railroad connections with Ohio and West Virginia.

Middlesboro is in eastern Kentucky, near the Virginia and Tennessee border, and northwest of the Cumberland Gap. It is the largest city of southeastern Kentucky. The steel, iron, and machine works are supplied with coal and iron mined in the district. Much coal is shipped by rail from Middlesboro for use elsewhere. The city serves as headquarters for several coal-mining companies. Its picturesque location has made it popular as a summer resort.

Winchester is the county seat of Clark County. It is a railroad junction center, located about eighteen miles southeast of Lexington. The fine live stock of the Blue Grass country, as well as tobacco and other crops, are marketed in Winchester. Lumber, building materials, engines, and foundry products are manufactured here.

Dayton, Bellevue, and Ludlow are towns opposite Cincinnati on the Ohio River. All three have developed as suburban communities and small commercial centers. *Fort Thomas*, an important United States military post, is located near by.

Maysville, the county seat of Mason County, is on the Ohio River, about sixty miles southeast of Newport. The river and railroads afford transportation facilities which have encouraged the development of the city as a shipping center. Large quantities of tobacco and grain are shipped from here. There are factories for making plows, pulleys, cotton goods, and other products.

Mayfield is in southwestern Kentucky, the county seat of Graves County. Situated on the main line of the Illinois Central Railroad, it has direct connections with Paducah to the north, and with the principal cities of northwestern Tennessee. Mayfield is surrounded by rich farming counties, which yield tobacco, hops, grain, fruit, and live stock. Tobacco warehouses, woolen and flour mills, and tobacco, pottery, carriage, and clothing factories are located here.

Paris is the county seat of Bourbon County, in northeastern Kentucky. It is connected by railroad with Lexington, nineteen miles to the southwest, and with Frankfort, Cincinnati, and Maysville. It is noted as a market for blooded live stock. Tobacco, blue grass seed, and hemp are staples of its trade.

Danville is the county seat of Boyle County, in the heart of the Blue Grass region. It is an important railroad division point, shipping center, and market, for agricultural products and horses. Several educational institutions are located in Danville.

Richmond is situated twenty-five miles southeast of Lexington. It is the county seat of Madison County. The Eastern Kentucky State Normal School is located here. Richmond is at the edge of the Blue Grass region and ships fine live stock raised in the vicinity. Lumber abounds in the district, and mills and tobacco factories are operated in the city.

Madisonville, the county seat of Hopkins County, is the center of an extensive mining industry. It is a shipping point for coal, and for the farming and stock-raising region which surrounds it. It has tobacco factories, and flour and lumber mills.

Somerset is a prominent railroad town in southeastern Kentucky. It is the county seat of Pulaski County. Coal and iron ore are abundant in the district, and petroleum is produced. Fruit, grain, and lumber are products of the locality.

TABLE I.—AREA, POPULATION, AND COUNTY SEATS OF KENTUCKY COUNTIES, 1920

COUNTY	AREA (Sq. Ml.)	POPULATION, 1920	COUNTY SEAT	COUNTY	AREA (Sq. Ml.)	POPULATION, 1920	COUNTY SEAT
Adair . . .	400	17,289	Columbia	Knox . . .	356	24,172	Barbourville
Allen . . .	394	16,761	Scottsville	Larue . . .	288	10,004	Hodgenville
Anderson . .	201	9,982	Lawrenceburg	Laurel . . .	447	19,814	London
Ballard . . .	252	12,045	Wickliffe	Lawrence . .	422	17,643	Louisia
Barren . . .	485	25,356	Glasgow	Lee . . .	199	11,918	Beattyville
Bath . . .	270	11,996	Owingsville	Leslie . . .	373	10,097	Hyden
Bell . . .	384	33,988	Pineville	Letcher . . .	355	24,467	Whitesburg
Boone . . .	251	9,572	Burlington	Lewis . . .	491	15,829	Vanceburg
Bourbon . . .	304	18,418	Paris	Lincoln . . .	338	16,481	Stanford
Boyd . . .	159	29,281	Catlettsburg	Livingston . .	392	9,732	Smithland
Boyle . . .	186	14,998	Danville	Logan . . .	643	23,633	Russellville
Bracken . . .	204	10,210	Brooksville	Lyon . . .	277	8,795	Eddyville
Breathitt . .	483	20,614	Jackson	McCracken . .	239	37,246	Paducah
Breckinridge .	568	19,652	Hardinsburg	McCreary . . .	406	11,676	Whitley City
Bullitt . . .	308	9,328	Shepherdsville	McLean . . .	253	12,502	Calhoun
Butler . . .	417	15,197	Morgantown	Madison . . .	446	26,284	Richmond
Caldwell . . .	322	13,975	Princeton	Magoffin . . .	302	13,859	Salersville
Calloway . . .	412	20,802	Murray	Marion . . .	345	15,527	Lebanon
Campbell . . .	145	61,868	Alexandria	Marshall . . .	327	15,215	Benton
Carlisle . . .	198	8,231	Bardwell	Martin . . .	227	7,654	Inez
Carroll . . .	132	8,346	Carrollton	Mason . . .	227	17,760	Maysville
Carter . . .	413	22,474	Grayson	Meade . . .	301	9,442	Brandenberg
Casey . . .	379	17,213	Liberty	Menifee . . .	203	5,779	Frenchburg
Christian . . .	725	35,883	Hopkinsville	Mercer . . .	253	14,795	Harrodsburg
Clark . . .	265	17,901	Winchester	Metcalfe . . .	303	10,075	Edmonton
Clay . . .	478	19,795	Manchester	Monroe . . .	441	14,214	Tompkinsville
Clinton . . .	233	8,589	Albany	Montgomery . .	198	12,245	Mount Sterling
Crittenden . .	391	13,125	Marion	Morgan . . .	365	16,518	West Liberty
Cumberland . .	387	10,648	Burkesville	Muhlenberg . .	472	33,353	Greenville
Daviess . . .	478	40,733	Owensboro	Nelson . . .	411	16,137	Bardstown
Edmonson . . .	308	10,894	Brownsville	Nicholas . . .	208	9,894	Carlisle
Elliott . . .	263	8,887	Sandy Hook	Ohio . . .	584	26,473	Hartford
Estill . . .	254	15,569	Irvine	Oldham . . .	180	7,689	La Grange
Fayette . . .	269	54,664	Lexington	Owen . . .	367	12,554	Owenton
Fleming . . .	325	15,614	Flemingsburg	Owsley . . .	216	7,820	Booneville
Floyd . . .	399	27,427	Prestonsburg	Pendleton . . .	279	11,719	Falmouth
Franklin . . .	199	19,357	Frankfort	Perry . . .	335	26,042	Hazard
Fulton . . .	193	15,197	Hickman	Pike . . .	779	49,477	Pikeville
Gallatin . . .	109	4,664	Warsaw	Powell . . .	181	6,745	Stanton
Garrard . . .	237	12,503	Lancaster	Pulaski . . .	628	34,010	Somerset
Grant . . .	264	10,435	Williamstown	Robertson . . .	109	3,871	Mount Olivet
Graves . . .	551	32,483	Mayfield	Rockcastle . .	310	15,406	Mount Vernon
Grayson . . .	497	19,927	Leitchfield	Rowan . . .	272	9,467	Morehead
Green . . .	279	11,391	Greensburg	Russell . . .	329	11,854	Jamestown
Greenup . . .	346	20,062	Greenup	Scott . . .	289	15,318	Georgetown
Hancock . . .	193	6,945	Hawesville	Shelby . . .	427	18,532	Shelbyville
Hardin . . .	606	24,287	Elizabethtown	Simpson . . .	216	11,150	Franklin
Harlan . . .	478	31,546	Harlan	Spencer . . .	186	7,785	Taylorsville
Harrison . . .	311	15,798	Cynthiana	Taylor . . .	279	12,236	Campbellsville
Hart . . .	430	18,544	Munfordville	Todd . . .	367	15,694	Elkton
Henderson . . .	435	27,609	Henderson	Trigg . . .	428	14,208	Cadiz
Henry . . .	303	13,411	New Castle	Trimble . . .	154	6,011	Bedford
Hickman . . .	225	10,244	Clinton	Union . . .	325	18,040	Morganfield
Hopkins . . .	546	34,133	Madisonville	Warren . . .	530	30,858	Bowling Green
Jackson . . .	333	11,687	McKee	Washington . .	299	14,773	Springfield
Jefferson . . .	387	286,369	Louisville	Wayne . . .	478	16,208	Monticello
Jessamine . . .	172	12,205	Nicholasville	Webster . . .	344	20,762	Dixon
Johnson . . .	268	19,622	Paintsville	Whitley . . .	442	27,749	Williamsburg
Kenton . . .	163	73,453	Independence	Wolfe . . .	230	8,783	Campton
Knott . . .	348	11,655	Hindman	Woodford . . .	195	11,784	Versailles

TABLE II.—CITIES AND TOWNS HAVING A POPULATION OF OVER 2000 IN 1920

CITY OR TOWN	COUNTY	POPULATION
Ashland	Boyd	14,729
Bellevue	Campbell	7,379
Bowling Green	Warren	9,638
Carrollton	Carroll	2,281
Catlettsburg	Boyd	4,183
Central City	Muhlenberg	3,108
Clifton	Campbell	2,065
Corbin	Knox	3,406
	Whitley	
Covington	Kenton	57,121
Cynthiana	Harrison	3,857
Danville	Boyle	5,099
Dayton	Campbell	7,646
Earlington	Hopkins	3,652
Elizabethtown	Hardin	2,530
Fleming	Letcher	2,069
Fort Thomas	Campbell	5,028
Frankfort	Franklin	9,805
Franklin	Simpson	3,154
Fulton	Fulton	3,415
Georgetown	Scott	3,903
Glasgow	Barren	2,559
Harlan	Harlan	2,647
Harrodsburg	Mercer	3,765
Hazard	Perry	4,348
Henderson	Henderson	12,169
Hickman	Fulton	2,633
Highland Park	Jefferson	3,979
Hopkinsville	Christian	9,696
Irvin	Estill	2,705
Jenkins	Letcher	4,707
Lancaster	Garrard	2,166
Lebanon	Marion	3,239
Lexington	Fayette	41,534
Louisville	Lawrence	2,011
Louisville	Jefferson	234,891
Ludlow	Kenton	4,582
McRoberts	Letcher	2,146
Madisonville	Hopkins	5,030
Mayfield	Graves	6,583
Maysville	Mason	6,107
Middlesborough	Bell	8,041
Morganfield	Union	2,651
Mount Sterling	Montgomery	3,995
Murray	Calloway	2,415
Newport	Campbell	29,317
Nicholasville	Jessamine	2,786
Oakdale	Jefferson	3,198
Owensboro	Daviess	17,424
Paducah	McCracken	24,735
Paris	Bourbon	6,310
Pikeville	Pike	2,110
Pineville	Bell	2,908
Princeton	Caldwell	3,689
Providence	Webster	4,151
Richmond	Madison	5,622
Russellville	Logan	3,124
Scottsville	Allen	2,179
Shelbyville	Shelby	3,760
Somerseset	Pulaski	4,672
Van Lear	Johnson	2,056
Versailles	Woodford	2,061
Winchester	Clark	8,333

TABLE III.—LEADING MINERAL PRODUCTS, 1920

PRODUCT	QUANTITY	VALUE
Coal	35,691,000 tons	\$146,576,000
Petroleum	8,738,000 barrels	34,279,000
Clay products		7,309,000
Pig iron	230,000 tons	7,307,000
Coke	740,000 tons	5,576,000
Stone	1,423,000 tons	1,756,000
Fluorspar	46,000 tons	1,247,000
Natural gas, gaso- lene	4,497,000 gallons	1,072,000
Sand and gravel	1,638,000 tons	1,048,000
Natural gas	2,000,000 M cu. ft.	690,000
Mineral waters	257,000 gallons	40,000
Lead	122 tons	20,000
Lime	2,000 tons	18,000


TABLE IV.—PRINCIPAL CROPS AND LIVE STOCK, 1919

PRODUCT	QUANTITY	VALUE
Tobacco	456,500,000 pounds	\$174,383,000
Corn	82,500,000 bushels	127,875,000
Hay	1,561,000 tons	39,649,000
Wheat	12,029,000 bushels	25,381,000
Potatoes	5,040,000 bushels	10,584,000
Oats	9,900,000 bushels	9,009,000
Cattle	1,062,000	58,469,000
Horses	439,000	45,656,000
Mules	231,000	29,337,000
Swine	1,768,000	28,288,000
Sheep	1,274,000	16,689,000

TABLE V.—LEADING MANUFACTURES, 1919

INDUSTRY	ESTABLISH- MENTS	WAGE EARNERS	VALUE OF PRODUCTS
Flour and meal	533	1,584	\$45,774,000
Lumber, timber products	1,055	10,412	35,749,000
Cars, construction, etc.	30	12,372	30,598,000
Iron and steel	27	3,017	25,208,000
Tobacco	100	3,677	24,129,000
Slaughtering, meat p'k'g	26	450	12,954,000
Castings, machinery	87	2,554	11,662,000
Printing and publishing	360	2,467	10,605,000
Carriages and wagons	71	1,977	10,510,000
Men's clothing	50	2,590	10,072,000
Leather, tanned, finished	10	661	8,748,000
Canning and preserving	18	1,046	8,223,000
Bread and bakery prod's	242	1,030	7,856,000
Brick, other clay prod's	47	2,349	5,686,000
Furniture	29	1,381	5,412,000
Confectionery, ice cream	87	798	5,255,000
Cotton goods	6	967	4,459,000
Saddlery and harness	52	479	4,444,000
Agricultural implements	8	773	4,407,000
Butter	16	140	3,655,000
Boots and shoes	7	630	3,574,000
Other manufactures	1,096	17,986	116,680,000
Total manufactures	3,957	69,340	\$395,660,000

mind.





"THE PRICES PRINTED HEREON ARE FIXED BY STATE CONTRACT
AND ANY HIGHER PRICES ARE UNLAWFUL; ANY DEVIATION
THEREFROM SHOULD BE REPORTED TO YOUR COUNTY
SUPERINTENDENT OR TO THE STATE TEXT BOOK COMMISSION
AT FRANKFORT."

BRIGHAM & McFARLANE

ESSENTIALS OF GEOGRAPHY REVISED

SECOND BOOK

with Kentucky Supplement

KENTUCKY EDITION

RETAIL PRICE
(20 PER CENT OF NET
CONTRACT PRICE
ADDED TO SAME
AS PROVIDED
BY LAW)

\$1.75

EXCHANGE PRICE
(20 PER CENT OF NET
EXCHANGE PRICE
ADDED TO SAME
AS PROVIDED
BY LAW)

\$1.60

